



# **REQUISITES**

FOR

## **BUILDING CONSTRUCTION**

COLLECTED FOR THE USE OF

**A**RCHITECTS

**B**UILDERS

**C**ONTRACTORS

**D**ECORATORS AND

**E**NGINEERS

• • • FOR SANITARY HEATING AND LIGHTING INSTALLATIONS • • •

---

## **YOUNG & MARTEN, LD.**

Manufacturers, Merchants  
Ironfounders and Shippers

---

Caledonian Works

**S T R A T F O R D**

**LONDON, England**

NEW  
1914





**REQUISITES**  
**FOR**  
**BUILDING CONSTRUCTION**

COMPILED FOR THE USE OF

**A**RCHITECTS  
**B**UILDERS  
**C**ONTRACTORS  
**D**ECORATORS AND  
**E**NGINEERS

• • • FOR SANITARY, HEATING AND LIGHTING INSTALLATIONS • • •

---

**YOUNG & MARTEN, LD.**

**Manufacturers, Merchants  
Ironfounders and Shippers**

---

**Caledonian Works  
S T R A T F O R D**

**LONDON, England**

XXXVI 151914
-----------------



DEAR SIR,

It affords us pleasure to hand you our

## New Illustrated Catalogue

the contents of which, we trust, upon perusal, will prove eminently interesting to you and induce a much-increased share of your favors.

PRECEDING  
PRICE LISTS  
CANCELLED

This issue cancels all previous editions. The basis of value set herein **dominates the prices in all our other Catalogues.**

We have endeavoured to make the work of

### Intrinsic Value to the Building and Allied Trades

UP-TO-DATE \* \* \*  
ARTISTIC DESIGNS

Extreme care has been exercised in the insertion throughout of designs, embodying the present-day **artistic taste and quite up-to-date**, whilst the prices have been kept **consistently moderate, covering every grade of value**, and in each case the point of **utility** has been studiously conserved, our desire being to place prominently before those intending to engage in the erection of any class of building, the **most advantageous mode of spending their money so as to obtain the very best results.**

SPECIAL PRICES  
FOR LARGE \*  
QUANTITIES \*

We solicit enquiries for quotations for **quantities of materials**, selected from the following pages, including **carriage and risk of breakage in transit** to buyer's nearest Railway Goods Station, irrespective of district or distance.

SHOWROOMS

We have displayed in our Showrooms at **Stratford** practically the whole of the designs shown in the following pages. Prospective purchasers intending to favor us with a visit **would by arrangement be met at a London terminus by our private motor car**, accompanied by a responsible member of our staff, and conducted to our Head Establishment, and, if necessary, conveyed back by same medium. We could make such a visit sufficiently interesting to the customer to warrant same.

PATENTS

The Company own or control several valuable patents interesting to the building trade, the most popular of which is the "**Hue**" **Adaptable Barless Grate**, which has become phenomenally, and is deservedly, successful; also, the "**Leadglass**" **Puttyless Glazing**, full particulars of which are given in these pages.

We hope to receive your enquiries and orders, to which we would give our most careful attention.

Thanking you sincerely for your past favors.

We are, DEAR SIR,

Yours faithfully,

**YOUNG & MARTEN, Ltd.**

IMPORTANT \* \* \*  
COMMUNICATIONS

**P.S.—All communications** should be addressed to the Company at Stratford; letters of complaint, or of a confidential character, if addressed to the Managing Director would receive his personal attention.

# YOUNG & MARTEN

## OF TO-DAY



Varnish & Colory Section

THE title of this brief sketch, so far as the

### Building World

is concerned, may be termed a "household phrase."

There is scarcely a city, hamlet within the zone of hours' run from London, but the Company have for a

### considerable period

possessed accounts upon their of most of the leading firms engaged in building operations.

### Name and Goods

of the Company, with increasing appreciation, are also known in all the more

### Important Commercial Centres of the Colonies,




large consignments of goods having been despatched to all parts of the civilized world.

## The Head Establishment


of the Company—a small photograph of which is given next title—is the centre of activity and the main artery infusing vitality into the whole of the

Twenty Departments  
and Branches

and from which their instructions and supplies emanate and maintained, each being connected by private wire.




*"The Baths" 1000 Deep*




area of the extensive stock of goods in ever demand by the Building and Allied Trades be them in readiness for despatch to all parts upquisition will be obtained from these illustration

The Showrooms, Wharves, Sidings, and Warehouses at Stratford are perhaps the largest of their kind in the world, reserved exclusively for stocking Builders' Goods.



*View of Nest 2000 Self Setters*



## Trade Ensign

Company has firmly i and persistently maintain the whole of their business operations embraces the following:

Modern Designs  
Sterling Quality  
Nominal Prices  
Prompt Delivery

STRATFORD, although  
beyond the City  
dary, may with con-  
vency be regarded as an  
integral part of the great  
metropolis. The Company's  
establishments are easily  
accessible from any part of  
City of London by  
Eastern Railway,  
or Omnibus, or Train  
from Aldgate, which  
the Showrooms.



Export Window Glass Department



Every obvious advantage offered to  
Town, Country, and  
Colonial Purchasers

of Building Materials of all kinds is  
the convenience of

Inspection of  
Every Article

used in the construction of any  
Building at

One Visit at the  
Stratford Premises

Main Ware-  
house alone possess  
1 floor space of  
half-a-Mile

the  
loading Dock

connecting Spur  
junction with  
is capable of  
accommodating  
full-size goods  
trains with engine.



Warehouses &  
Sidings, Stratford.


**I**N addition to the Warehouses and Railway Siding from which goods are despatched to all parts by rail daily, the Company possess

Several  
Freehold  
Wharves

the most important of these being

St. Andrews  
Millwall  
on the Thames

This is utilised as a reserve stocking area. Goods of heavy character are landed here at a much lesser cost than when of necessity same would have to be lightered to smaller wharves located upon creeks or back rivers.



The rapidly increasing Departments using this wharf have found it an enormous convenience, and a means of successfully competing for and securing orders from Contractors and Authorities requiring large consignments promptly delivered.

Roofing Slates and Tiles  
Cement, and Timber

are the staple commodities stored at St. Andrews Wharf.




*St. Andrews Wharf, Millwall,  
Thames front.*



# EXPORT

Among the consignments of goods exported recently might be mentioned those sent to the

## Private Sanatorium and Surgical Home, near Gibraltar




designed and erected by A. H. MORGAN, Esq., of New York City. Practically the whole of the materials (except bricks and timber) were supplied and shipped by the Company for this magnificent building to the architect's specification



Bungalow on the Ivory Coast, W. C. Africa, for which the whole of the goods were supplied including wrought timber



Also all the interior goods used in the private residences of Dr. Mackay and Dr. Macdonald, near Hospital described above



# General Index to Vol. I.

**Gas and Electric Lighting, Heating and Cooking Appliances, Electric Bells and Telephones, and Shop Window Fittings are indexed in Vol. II.**

Access Pipes, .....	296, 469	Automatic Drain Trap, .....	298	"Beam" Anthracite Stove, .....	128	Bossing Mallet, .....	110
Accessible Sink Traps, .....	141	Flushing Cistern, .....	215	"Beaudo" Mantel Register, .....	69	Bottom Rollers, .....	378
Acids, .....	279	Hot or Muff Hooks, .....	399	"Beaudo" Pattern Railings, .....	199	Bottoms, Fals, .....	522
"Acme" Cistern, .....	161	Latrine Range, .....	187	"Bedford" Urinals, .....	216	Boundary Wall Gutters, .....	460
"Adam" Interior, .....	86	Lavatory Locks, .....	411	Bedroom Door Cham, .....	121	Box Latch, .....	350
"Adams" Tile Grate, .....	43	Locking Coalplate, .....	529	Knocker, .....	359	Bowls Lavatory, .....	189
"Adaptable" Ball Valves, .....	153	Panic Bolts, .....	376, 377	Acet Pipe Joints, .....	143	Box Gutters, .....	159
Close, .....	172	Tanks, .....	215	Beeswax, .....	279	Box Lock, .....	352
Fires, .....	9 to 32	"Avebury" Mantel Register, .....	69	"Bellast" Sink, .....	211	Boxes for Stop Cocks, .....	529
Adjustable Blind Racks, .....	392	"Ashbridge" Mantel Register, .....	75	"Belgrave" Interior, .....	17	Boxwood Robbin, Wedge, Turnpin, .....	110
Gilding Wheel, .....	288	AXES, .....	102	"Belgravia" Urinal Range, .....	220	Rollers, .....	288
Adjusters, Gutter, .....	459	Axle Grease, .....	279	Belt, .....	(See Vol 11)	BRACKETS, .....	
Advertisement Tablets, .....	151	Oil, .....	279	Bellamy's Rollers, .....	282	Air Inlet, .....	254, 257
Adze, Carpenter's, .....	102	Pulleys, .....	391	Bell Pulls and Pushes, .....	376	Basin, .....	195
"Aetna" Brazing Lamp, .....	282			Traps, .....	150	Blind, .....	392
Air Bricks and Gratings, Earthenware, .....	299			Tulmng, .....	137	Cantilevers, .....	522
Iron, 398, 521, 526				"Belle" Looking Range, .....	99	Carved Wood, .....	325, 327
Inlet Panels, .....	256			"Belmont" Drainer and Sink, .....	209	Closet Cistern, .....	159, 167
Tubes, .....	257			Belted Cisterns, .....	155	Seat, .....	167
Valves and Brackets, .....	241, 257			Bench Oil, .....	281	Fret Cut Wood, .....	325, 327
Windows, .....	525			Screws, .....	105	Gutter, .....	157
Airers, Towel, .....	237			Standards, .....	531	Hand Rail, .....	373
Airtight Manhole Covers, .....	471			Vice, .....	105	Harness, .....	516
"Albany" Gate and Railing, .....	506			Bends, Channel, .....	296	Ladder, .....	100
"Albion" Kitchenet, .....	117			Drum, .....	291	Lavatory, .....	195
"Albion" Lavatory Basin, .....	191			Lead, .....	110	Partition, .....	523
"All night" Boiler, .....	533			Sink, .....	139, 110	Porch, .....	312
"Alma" Mantel Register, .....	91			Bent Glass, .....	471	Saddle, .....	514
"Alpertown" Mantel Register, .....	79			Benzoline, .....	279	Shelf, .....	100
"Alpha" Lawn Mower, .....	118			Lamps, .....	282	Shower, .....	216
"Alpine White" Enamel, .....	267			"Berkeley" Lavatory, .....	198	Sink, .....	211
Alum, .....	279			Berlin Black Curbs, .....	17, 19	Towel Rail, .....	121
Aluminium Bronzes, .....	273			Berlin Black, .....	265	Trivet Tables, .....	11, 16
Lead, .....	273			"Bertram" Mantel Suite, .....	18	Verandah, .....	182
Paint, .....	268			Bevelled Glass, .....	131	Bradaws, .....	101
"Amateur's" Greenhouse Boilers, .....	538			Varnish Brushes, .....	283	Brads, .....	312
American Potash, .....	281			Bib Cocks, .....	116, 118, 152	Branding Irons, .....	113
Frestles, .....	277			Bichromate Potash, .....	281	Brastown Bath, .....	231
Turps, .....	270			"Bullets" .....	182, 183	Brass Bell and Grate, .....	150
"Amesbury" Mantel Suite, .....	46			Bilt Hooks, .....	492	Chair Nails, .....	373
Ammonia, Liquid, .....	279			"Bulwell" Suite, .....	71	Cubs, .....	33
"Ancaster" Mantel Suite, .....	59			Billing's Pipe Bender, .....	110	Fernies and Sockets, .....	166
Angers' Slates, .....	297			Bins, .....	156	Furniture and Plates, .....	353
Angle Bars (Iron) .....	311			Birdfast Black, .....	281	Head Nails, .....	373
(Zinc), .....	137			Birch Closet Seat, .....	161, 166	Knockers, .....	358
Angular Basins, .....	189, 191, 194, 218			Bisset's Floor Clamp, .....	104	Lift and Force Pumps, .....	258 to 261
Sinks, .....	207			Bitumen Damp Course, .....	301	Locks, .....	315
Urinals, .....	216, 218			Blackboard Paint, .....	268	Screw Caps, .....	373
"Antarmish", .....	277			Black Beaded Frames, .....	131	Screws, .....	341
Anthracite Stoves, .....	128			Door Furniture, .....	366 to 369, 5184	Sink Grating, .....	150
Anti Corrosion Paint, .....	272			Enamel, .....	268	Ventilating Gratings, .....	398
Anti-Damp Felt, .....	301			Japan, .....	265	Brasses, Fire (see also Special Section), .....	33
Anti-D Traps, .....	138			Lead, .....	281	Brazing Lamps, .....	283
Anti-Foul Traps, .....	111			Blast Furnaces, .....	280, 282	"Brent" Range, .....	105
Antique Furniture, .....	351, 119			"Blenheim" Gate and Railings, .....	506	Brenton's Padlock Bolt, .....	386
Anvils, .....	106			Blind Bolts, .....	385	Bricks, Air, .....	299, 398
Aquariums and Stands, .....	434			Cord, .....	392	Blue and White, .....	309
Are Lamps, .....	(See Vol 11)			Furniture and Sundries, .....	392	Fire, .....	300
Arched Bath Boilers, .....	123			Blocks, Snatch, .....	110	Fletton, .....	297
Arches, Fret-cut, .....	327, 329			Blow Lamps and Pipes, .....	281	Stove, .....	11
Wire, .....	117			Pipe Solder, .....	136	Bricklayers' Tools, .....	103
"Archimedean" Flue, .....	158			Blue Bricks, .....	300	Buckle Hooks, .....	516
Screw, .....	116			Board School Hat and Coat Hooks, .....	399	Briggs' Panic Bolt, .....	377
Ventilators, .....	251, 256			Boards, Niperset, .....	5186	"Brighton" Lavatory, .....	252
Architraves, .....	330			Boat Varnish, .....	266	Brilliant Cut Glass, .....	137 to 139
"Arch" Pattern Gate and Railing, .....	504			Bobbins, .....	110	"Brilliant" Geyser, .....	210
"Arctic" Glass, .....	132			BOILERS, .....		"Brit mo" Bidets, .....	182
Ardenbrite Paint, .....	268			Bath, .....	123	Cistern, .....	161
Area Gratings, .....	526			Clothes, .....	522	Closet Suite, .....	176
Armour Bright Hue Fuses, .....	16 to 31			Heating Apparatus, .....	536 to 541	Lavatories, .....	197
Arms, Panic, .....	376			Range, .....	123, 126	British Pitch, .....	301
Art Black Garden City Furniture, .....	366 to 369			Boiler Covering, .....	301	"Briton" Check, .....	390
"Artico" Distemper, .....	289			Felt, .....	301	Bronze Door Furniture, .....	361, 363
Enamel Paints, .....	267			Safety Valves, .....	154	Bronzes, .....	208
Paint, .....	270			Screws and Unions, .....	159	Brooms, .....	284
Ready Mixed Paints, .....	269			Tops, .....	522	Brosely Roofing Tiles, .....	293
"Artese" Anthracite Stove, .....	129			Bolection Mouldings, .....	351	Brumwick Black, .....	285
Artistic Heads, .....	463			Bolt Sockets, .....	376	Bushes, .....	283 to 285, 115
Artists' Palette Knives, .....	287			Bolt and Nuts, .....	313, 155	Bush, Whalebone, .....	115
Asbestos Boiler Covering, .....	274			Bolts, Door, .....	368, 385	Buckets, Iron, .....	109
Millboard, .....	271			Lever and Spiral, .....	363	Pump, .....	259
Packing and Covering, .....	271			Panic, .....	376	"Buckingham" Bath, .....	226
Paint, .....	537			"Bombay" Native Closets, .....	181	Interior, .....	17
"Ashcroft" Boiler, .....	301			Bonnet Spring Hinges, .....	388	Lavatory, .....	143
Asphalted Felt, .....	44			Boat Boilers, .....	123	Buffers, Closet, .....	288
"Ascenden" Mantel Suite, .....	89			Scrapers, .....	134	Builder's Plant, .....	156, 109 to 113, 5180
"Aston" Mantel Suite, .....	89			Borax, .....	279	Bulhous, .....	430
"Atheistan" Tile Grate, .....	408			Borderings, Garden and Grave, .....	517 to 519	Bull's Eye Windows, .....	476
Aukers, .....	279			Border, Wrought Iron, .....	512	"Bungado" Mantel suite, .....	19
Australian Tallow, .....	408			Boring Machine, .....	113	"Buras" Interior, .....	77
				"Boscumbe" Mantel Suite, .....	35	"Burglere" Mantel Register, .....	

# General Index to Vol. I.—Continued.

Gas and Electric Lighting, Heating and Cooking Appliances, Electric Bells and Telephones, and Shop Window Fittings are indexed in Vol. II.

	PAGE		PAGE		PAGE		PAGE
Burglar-Proof Latches, ..	318	Chalk, French, ..	279	Collapsible Gates, ..	193	Cross Keys Glass, ..	126
Burning off Lamps, ..	283	"Challenge" Closet, ..	170	Collings' Hinges, ..	389	"Crown" Floor Clamp, ..	101
Butt Wall Railing, ..	198	"Champion" Chimney Pot, ..	299	Colonial Suction Pumps, ..	261	"Rim Locks, ..	345
Butt Hinges, ..	387	"Chancellor" Geyser, ..	238	Colored Glass, ..	127	"Sheet Bullions, ..	130
"Butterfly" Railings, ..	497	"Chancellor" Kitchen, ..	116	Color Washer, ..	278	"Croydon" Ball Valves, ..	152
Buttons, Iron and Brass, ..	351, 421	Channel Bricks, ..	300	Colors, ..	270	"Safety Valve, ..	151
		"Gratings, ..	171	Columns, ..	183, 530	Crystal Letters, ..	116
		"Guide, ..	378	"Colwyn" Lavatory, ..	249	Cue Holder, ..	111
		"Pipes and Fittings, ..	296	Colza Oil, ..	279	Cupboard Bolts, ..	385
		Charcoal, ..	279	Combination Baths, ..	227 to 235	"Buttons, ..	351, 421
Cabinet, Ball Catch, ..	352	"Charterhouse" Mantel Registers, ..	72	" " and Lavatory, ..	231	"Catch, ..	319, 352
"Bolts, ..	385	Chase Wedge, Boxwood, ..	140	"Iron Lavatory, ..	251	"Door Rollers, ..	383
"Coal, .. (See Special Section)		"Chatsworth" Bath, ..	231	"Gulley and Channel, ..	295	"Doors, ..	308 to 311
"Dresser, ..	313	Check Valves, ..	154	"Mantel Register, ..	50	"Fronts, ..	309
"Handles, ..	352	"Cheltenham" Bath, ..	231	"Postal Handles, ..	359	"Knobs and Buttons, ..	351
"Lavatories, ..	199	Chemicals, ..	309	"Sinks, ..	212, 214	"Locks, ..	351
"Oil, ..	285	Chequered Paviers, ..	388	"Taps, ..	216	"Turns, ..	351, 367, 422
Cabin Hooks, ..	396	Chest Hinges, ..	337	Combined Casement Stay and Fastener, ..	369	Cup Hooks, ..	372
"Caddices" Glass, ..	126	Chestnut Piling Fencing, ..	342	" " Coal and Gas Range, ..	113	"Leathers, ..	259
Cake Cover, Glass, ..	131	" " Pieces, ..	24 to 127	"Cooking Range and Interior, ..	17	Curb Leathers (see also Special Section), 20 to 70	
"Pans for Cattle, ..	547	" " Pots, ..	290	Comb and Brush Tray, ..	288	Cut Nails, ..	342
"Caledon" Fancie Mantel, ..	22	"Sweeping Machine, ..	111	Combining Rollers, ..	287	Cutting Laths, ..	287
"Caledonian" Lavatory, ..	196	China Door Furniture, ..	353	Combs, Graining, ..	287	Cycle Oils, ..	279
" " Paint Removing and	282	" " Finger Plates, ..	353	Companions, Fireside, ..	16	"Circulating, ..	156
" " Soldering Lamp, ..	171	" " Letters, ..	446	Compass, ..	401	" " Night Latch, ..	318
" " Street Gully, ..	272	Chipping Knives, ..	287	Compo Brushes, ..	283	" " Oil, ..	281
" " Vanishes, ..	285	Chisels, ..	101	Compo Pipe, ..	136		
Canal Hair Brushes, ..	91	Chloride of Lime, ..	279	Concentrated Size, ..	279		
"Camden" Hob Register, ..	385	Chubb's Locks, ..	317, 351	Cone Head Nails and Screws, ..	313		
Canadian Store Door Latches, ..	116, 185	Church Windows, ..	411 to 450	Cones, India rubber, ..	103		
Canopies, ..	211, 627	Cinder Sifter, ..	181	"Wire, ..	457	D Traps, Lead, ..	138
Canvas and Rubber Hose, ..	143	Circular Archways, ..	117	" " Anthracite Stove, ..	129	Dabbers, ..	285
Cap, Geyser, ..	241	" " Cisterns, ..	156	Continuous Flat Bar Lining, ..	515	Dado Mouldings, ..	330
" " and Lining, ..	150	" " Forges, ..	106	" " Unclimbable Railing, ..	512	" " Tiling, ..	96
" " Screw, ..	150	" " Glass Ventilators, ..	131	Contractors' Drain Machines, ..	111	Damp Course and Felt, ..	301
Capping, ..	311	" " Gratings, ..	521	" " Pumps, ..	358	" " Slates, ..	297
Caps and Bases, ..	322, 327	" " Pavement Lights, ..	179	Convex Lens, ..	178	" " Wall Preparations, ..	275
Carbolic Soap, ..	279	" " Pig Troughs, ..	517	Cooking Ranges (see also Kitcheners), ..	98	Dampers and Frames, ..	522, 523, 535
"Carlton" Lavatory Stand, ..	251	" " Sashes, ..	176	Cooper's Vacuum Pump, ..	113	Dandy Brushes, ..	284
Carpenters' Tools, ..	401	" " Stairs, ..	190, 191	Copai Varnish, ..	261	Daylight Reflectors, ..	132
Carrage Entrance Gates, Iron, 400, 500	511	Circulating Cylinder, ..	156	Coping, Iron, ..	161	Dead Lights, ..	171
" " Wood, ..	315	Circulator, "Radon," ..	210	" " Wall, ..	300	" " Locks, ..	317
" " Varnish, ..	261	Cisterns, ..	155, 156	Coppers, ..	279	" " Weight Safety Valves, ..	151
Carr's Rustfast Black, ..	279	" " Supply, ..	522	Copper Bits, ..	110	Dean's Grease Trap, ..	295
Carson's Paints and Distempers, ..	269	Cistern Brackets, ..	159, 167	" " Bound Brushes, ..	285	Deck Plange, ..	528
Cart Grease, ..	281	" " Pulls and Guides, ..	166	" " Coppers, ..	522	Decorators' Appliances, ..	283 to 289
Catland's Fanlight Openers, ..	391	" " "Clad" Door Fastener, ..	386	" " Curbs, ..	52	" " Brushes, ..	281
CARVED Wood Goods, ..		" " "Clarity" Mantel Suite, ..	58	" " Doors and Frames, ..	522	" " Stencils, ..	289
" " Brackets, ..	325	" " "Claret" Closet, ..	172	" " Grates, ..	522	" " Tub Colors, ..	273
" " Caps and Bases, ..	327	" " "Claridge" Interior, ..	19	" " Letters, ..	116	Deep Well Pumps, ..	259
" " Overdoors, ..	320	" " Clark's Hot Air Stove, ..	120	" " Lids, ..	522	Deflecting Bricks, ..	11
" " Screens, ..	328	Cleaning-down Brushes, ..	342	" " Name Plates, ..	112	" " "Delight" Cooking Ranges, ..	102, 103
Casement Bolts, ..	381	Cleaning-down Apparatus, Drain, ..	284	" " Shower Rose, ..	216	Delivery Hose, ..	113
" " Fasteners and Stays, 369 to 471	371, 375	Cleaving Apparatus, Drain, ..	111	Coppers, ..	520	" " "Delta" Interior, ..	86
" " Material, ..	333	Cleaving Wheels, ..	115	" " Portable and Galvanized, 520 to 522	520 to 522	Dentists' Furnace, ..	282
Casements, Wood, ..	309, 312	Cleat Hooks, ..	393	Corbels, ..	343	" " "Desford" Interior, ..	87
" " Wrought Iron, ..	140 to 143	" " "Clifton" Mantel Suite, ..	38	Cord Holder, ..	422	" " "Desirable" Bath Seat, ..	212
Cast Iron Baths, ..	222	" " "Clintville" Lavatory, ..	200	Corn Iron, ..	145	Desk Standards, ..	531
" " Frames, ..	178	" " "Clincher" Closet, ..	172, 177	" " "Corinthian" Mantel Suite, ..	29	Dextrine, ..	281
" " Lavatories, ..	195	" " "Close Arch" Gate and Railing, ..	152	Corn Bins, ..	156	Diamond Chequered Paviers, ..	300
" " Sashes, ..	176	Closet Basins, ..	138, 163	Corner "Comfort" Copper, ..	520	" " Wirework, ..	417
" " Star Nosing, ..	523	" " "Clos" Cisterns, ..	501	" " Mangers, ..	541	Diamonds, Glaziers', ..	430
Cast Lead Traps, ..	138	" " "Clos" Cistern Brackets, ..	159 to 167	Conices, Paper Stucco, ..	291	Diaphragm Pumps, ..	260
" " "Castle" Range, ..	118	" " "Clos" Pull Guides, ..	166	" " Steel, ..	548x	Differential Pulley Blocks, ..	110
Castor Oil, ..	279	" " "Clos" Pulls, ..	162	" " Wood, ..	334	Dirt Excluding Sockets, ..	376
Castors, ..	393, 421	" " "Clos" Divisions, ..	188	Corrugated Elbow, ..	211	Disinfectants, ..	281
Catches, Cupboard, ..	549, 551	" " "Clos" Latches, ..	166	" " Iron, ..	344	Distemper Brushes, ..	283
" " Fanlight, ..	550, 422	" " "Clos" Locks, ..	349	" " Roof Lights, ..	311, 474	Distempers, ..	269
" " Gate, ..	491	" " "Clos" Pails and Tanks, ..	181	" " Tiles, ..	298	Division Railings, ..	512
" " Sash, ..	352	" " "Clos" Pans and Traps, ..	168	" " Wirework, ..	417	" " Standards, ..	191
Cathedral Glass, ..	430	" " "Clos" Seat Buffers, ..	113	" " "Cotswold" Tile Gate, ..	90	Divisions, Stall, ..	543
" " Wirework, ..	417	" " "Clos" Hinges, ..	166	" " Cottage Baths, ..	247	" " "D. J. C." Glass, ..	426
" "Cat's Eye" Glass, ..	432	" " "Clos" Seats and Brackets, ..	161, 165, 167	" " "Laundry Stoves, ..	135	Dog Grates, ..	85
Cattle and Sheep Hurdles, ..	514	" " "Clos" Sockets, ..	166	" " "Pans and Traps, ..	168	" " "Dogs," Timber, ..	343
" " Cauldron, ..	521	Closets, ..	168 to 188	" " "Pumps, ..	258	Domestic Boilers, ..	538
" " Pans and Troughs, ..	157, 547	" " "Earth, ..	181	" " "Range, ..	98	" " "Don" Bib Cock, ..	116
Caustic Soda, ..	279	" " "Ranges, ..	181 to 187	" " "White Enamel, ..	267	Door Bolts, ..	385
" " "Ceil" Bath, ..	235	Clothes Posts and Sockets, ..	530	Cotton Waste, ..	290	" " Canopies, ..	485
" " Mantel Suite, ..	31	Cloot Nails, ..	312	Council Cauldron, ..	521	" " Chains, ..	373, 421
" " "Ceilia" Lavatory Basin, ..	103	" " "Clova" Gates and Railing, ..	601	" " Drain Machine, ..	144	" " Checks and Springs, ..	390
Ceiling Decorations, ..	279 to 291, 518x	Club Hammers, ..	402	Counter Flap Hinges, ..	387	" " Fasteners, ..	386
" " White Wash, ..	518x	Coachbuilders' Colors, ..	270	County Bath, ..	227	" " Furniture, ..	353 to 370
Ceilings, Steel, ..	278	Coach "House" Door Hinges, ..	265	" " "Stove Suites, ..	24	" " Handles and Knobs, ..	353, 370
Celm-Koto, ..	478	" " "Locking Bars, ..	306	Coupling Joint, ..	259	" " Hangers, ..	381
Cellar Flaps, ..	297	Coal Boxes and Cabinets, (See Special Section)		" " "Coverne, ..	276	" " Hinges, ..	387, 389
Cement, ..	408	" " "Plates and Rims, ..	529	" " "Covers, Manhole, ..	171 to 474	" " Hood or Porth, ..	546
" " Pavement Rollers, ..	108	" " "Shovels, ..	548x	Cougar's Ball Valve Gully, ..	295	" " Knobs, ..	351, 370
Centre Door Knobs, ..	358, 363	" " "Tar, ..	301	Cow-house Fittings, ..	524	" " Knockers, ..	358
" " Gutters, ..	460	Coat Hooks, ..	399	Cowls, ..	545	" " Latches and Locks, ..	315, 350, 385, 386
" " Pieces for Ceilings, ..	289 to 290	" " "Coburn Vemart" Door Roller, ..	379	Crabs, ..	158, 264	" " Numbers, ..	373
Chain Coil, ..	313	" " "Cochrane" Tile Gate, ..	90	Cramps, ..	410	" " Panels, ..	436
" " Hoists, ..	410	Cocks, ..	116 to 150	" " Cranes, ..	410	" " Rollers, ..	378 to 383
" " Pumps, ..	268	Coil Chain, ..	314	" " Cranked Latch Handles and Furniture, ..	367	" " Silencers, Slams and Stops, ..	372, 419
Chains, Basket and Scaffold, ..	408, 409	" " "Columbia" Spring, ..	300	Crescent Oil, ..	279	" " Springs, ..	390
" " Cistern, ..	102	" " "Columbia" s.s. Range, ..	107	" " "Crest" Kitchen, ..	536	" " Stationers, ..	419
" " Door, ..	373			" " "Crest" Boilers and Sets, ..	536	" " Step Risers, ..	526
" " Hoists, ..	410			" " "Crest" Kitchen, ..	109	Doors and Frames, Copper, ..	522
" " Spikes, ..	408			" " "Crestings, ..	480	Doors, Wood, ..	301 to 311
Chain Nails, ..	373			" " "Crosses, Iron, ..	517	" " "Dorothea" Lavatory Basin, ..	191
" " Rails, ..	330			" " "Cross Garnet Hinges, ..	389	" " Mantel Suite, ..	51

**Gas and Electric Lighting, Heating and Cooking Appliances, Electric Bells and Telephones, and Shop Window Fittings are indexed in Vol. II.**

Double Action Cisterns, .....	159	Escutcheon Pins, .....	342	Floor Sockets, .....	372, 119	Garden Rollers, .....	418
" " Pumps, .....	260	Escutcheons, .....	367	" " Springs, .....	380	" " Seats, .....	418
" " Spring Hinges, .....	388	Espagnolette Bolts, .....	368, 380	" " Filing, .....	120, 121	" " Tiles, .....	200
" " Cylinder Garden Roller, .....	418	Estate Locking Latch, .....	548a	" " " Mantel Suite, .....	53	Garnet Hinges, .....	380
" " Flap Closet Seats, .....	164	" " " Tile Gate, .....	89	" " Fine Pipes, .....	130	Gas and Coal Kitchener, .....	113
" " Gates, .....	196, 500 to 511	" " " Ever Ready" Geysier, .....	238	" " Fluoric Acid, .....	138	Gas Fittings, .....	(See Vol. 11.)
" " Hooks, .....	420	" " " Eve till Dawn" Boiler, .....	536	" " Flush Bolt, .....	281	" " Engine Oil, .....	270
" " Manhole Covers, .....	472	" " " Excelsior" Cistern, .....	161	" " " Doors and Frames, .....	385	" " Fires, .....	15
" " Oven Kitcheners, .....	113 to 119	" " " Closet, .....	171	" " " Ring Catch, .....	355	" " Heating Stoves, Fires, and Cookers, .....	(See Vol. 11.)
" " Worm Screws, .....	145	" " " Office Stove, .....	132	" " " Flushing Cisterns, .....	352	" " " Tubes and Fittings, .....	112
" " "Dover" Portable Range, .....	101	" " " Sinks, .....	212, 213	" " " Plated Glass, .....	152, 215	" " " Gasfitters' Blow Pipes, .....	281
Dr. Clark's Hot-Air Grate, .....	120	" " " Exhaust Ventilators, .....	251, 255	" " " Folding Cellar Flaps, .....	178	" " " Gates and Railings, .....	191 to 516
Drain Cleansing Apparatus, .....	111, 115	" " " Expanded Metal Lathing, .....	518, 518a, 518c	" " " Gates, .....	193	" " " Gates, Collapsible, .....	493
" " Grates, .....	471	" " " Expanding Screw Stopper, .....	533, 535	" " " Lavatories, .....	199	" " " " Wood, .....	314, 315
" " Inspection Covers, .....	528	" " " Expansion Boxes, .....	533	" " " Scaper, Drain, .....	145	" " " Gate Catch and Latch, .....	388
" " Pipes and Connections, Iron, .....	467, 470	" " " Pipes, .....	533	" " " Shelf Brackets, .....	190	" " " Hinges, .....	388
" " Rods, .....	141	" " " Extending Trolleys, .....	336	" " " Rules, .....	112	" " " Locks, .....	350
" " Stoneware, .....	294	" " " Extension Closet Seats, .....	164, 165	" " " Trestles, .....	277	" " " Spring, .....	390
" " Stopper, Tones, .....	113	" " " Ladder, .....	336	" " " Footpath Gates, .....	515	" " " Stops, .....	308, 494
" " Testers, .....	113	" " " Eye Inspection Covers, .....	528	" " " Foot Valve and Strainer, .....	259	" " " Gauge, .....	417
" " Traps, .....	528			" " " Fore Cup, .....	113	" " " Gear, Ventilating, .....	395, 397
" " Ventilators, .....	138, 251			" " " Pumps, .....	151, 259 to 262	" " " Geared Pump Motion, .....	259
Drainer and Sink, .....	209			" " " Foreign Window Glass, .....	426	" " " "Gen" Interior, .....	86
Drawback Locks, .....	350			" " " Foremost" Kitchener, .....	108	" " " Georgian" Kitcheners, .....	112, 114
Drawer Locks, .....	351			" " " Forges, .....	106	" " " Geysers, .....	238 to 240
" " Pulls and Handles, .....	372, 421			" " " Fork, Mail, .....	380	" " " Ventilating Appliances, .....	211
Draw Knives, .....	287			" " " Fork, .....	548f	" " " "Gidea" Mantel Register, .....	20
Draw-off Sinks, .....	207			" " " Foundation Felt, .....	391	" " " Gilders' Appliances, .....	271, 287
Dresser Hooks, .....	372			" " " Fourway Hooks, .....	120	" " " "Whiting, .....	271
Dresser, Plumbers, .....	110			" " " Frame and Axle Pulleys, .....	391	" " " Golding Wheel, .....	285
Dressers, Wood, .....	313			" " " Frames, Black Beaded, .....	151	" " " Glimets, .....	401
Driers, .....	270, 272			" " " "Frames" Lavatory Basin, .....	193	" " " Glacier Line, .....	392
Drilling Machines, .....	405			" " " French Casement Doors, .....	510	" " " Glacier Decoration, .....	292
Drive Screws and Washers, .....	413			" " " "Chalk, .....	287	" " " Glass Steam Cook, .....	151
Drop Gate Latches, .....	388			" " " Embossing, .....	156	" " " Aquariums, .....	474
" " " Stop, .....	398			" " " "Glue, .....	279	" " " Heading and Beveling, .....	431
" " " Scraper, .....	145			" " " Oil Varnish, .....	264	" " " Cloth, .....	279
Dry Colors, .....	271			" " " Polishes, .....	206	" " " Grinding, .....	433
" " "Dual" Coal and Gas Kitchener, .....	113			" " " Pret cut Arches, .....	328	" " " Holders, .....	446
" " "Dubois" Lead Traps, .....	110			" " " Balusters, .....	318	" " " "Paper, .....	279
Dumb Plates, .....	535			" " " Brackets, .....	325	" " " Plates, .....	373, 421
" " "Duplex" Grates, .....	120			" " " Casts, Zinc, .....	157	" " " Polishing, .....	433
Dust Bins, .....	157			" " " Front Doors, English, .....	301 to 306, 510	" " " Shelves, .....	433
Dusters, .....	283			" " " Front Door Furniture, .....	341	" " " Slates and Tiles, .....	430
				" " " "Latches, .....	153	" " " Towel Rails, .....	241
				" " " Fullway Ball Valve, .....	522	" " " Ventilators, .....	131
				" " " Lunette Bars, .....	535	" " " Glazed Bricks, .....	302
				" " " Fittings, .....	535	" " " "Cistern, .....	161
				" " " Fronts, .....	280, 282	" " " "Eclipse" Mantel, .....	22
				" " " Oil Blast, .....	522	" " " Pipes, .....	290
				" " " Pans, .....	392	" " " Sinks, .....	302
				" " " Furniture, Blind, .....	353 to 356	" " " Wall Tiles, .....	96
				" " " Lock, .....		" " " Glaziers' Diamonds, .....	430
						" " " Knives, .....	287
						" " " Laths and T Squares, .....	287
						" " " Glazing Composition, .....	129, 130
						" " " "Glenwood" Tile Grate, .....	278
						" " " Globe Bath Cocks, .....	118
						" " " Glue, .....	277 to 279
						" " " Brushes, .....	283
						" " " Pots, .....	409
						" " " Gold and Silver Bronzes and Enamels, .....	268
						" " " Lead, .....	273
						" " " Letters, .....	446
						" " " Size, .....	205
						" " " "Gotha" Boiler, .....	541
						" " " Gothic Bolts, .....	386
						" " " Handles and Latches, .....	386
						" " " Grafting Tool, .....	548e
						" " " Grain Scoops, .....	548e
						" " " Grainers' Appliances, .....	282, 287, 288
						" " " Granite Chippings, .....	197
						" " " Grant's Valve Washers, .....	143
						" " " Graphite Paint, .....	274
						" " " Grass Tablets, .....	517
						" " " Grates, Copper, .....	522
						" " " Drain, .....	474
						" " " and Frames, .....	546
						" " " Gratings, Brass, .....	150, 398
						" " " Hot Water Pipe, .....	535
						" " " Miscellaneous, .....	171, 524 to 526
						" " " Grave Borderings, .....	517
						" " " Crosses and Tablets, .....	517
						" " " Railings, .....	518, 519
						" " " Gravel Scrapers, .....	134
						" " " Sieve and Screens, .....	407
						" " " Grease Traps, .....	295
						" " " Greases, .....	281
						" " " Greenhouse Bars, .....	335
						" " " Boilers, .....	533
						" " " Brackets, .....	527
						" " " Glass, .....	426
						" " " Putty, .....	278
						" " " Stays, .....	390
						" " " Ventilating Gear, .....	395
						" " " Grinders, .....	397
						" " " Grinding and Polishing Edges (Glass), .....	133

## General Index to Vol. I.—Continued.

**Gas and Electric Lighting, Heating and Cooking Appliances, Electric Bells and Telephones, and Shop Window Fittings are indexed in Vol. II.**

PAGE		PAGE		PAGE		PAGE		PAGE	
Grindstones, .....	407	Hook Bolts, .....	343	Invisible Fanlight Openers, .....	331	Lamp Pans, .....	427		
Ground Brushes, .....	283, 286	Hooks, Brackets, .....	346	" " Roof Ventilators, .....	255	Lamps, .....	(See Vol. II)		
" " Colors, .....	270	" " Cabin, .....	392	Iron Balusters, .....	492	" " Hurricane, .....	413		
" " Glass, .....	427	" " Cleat, .....	393, 422	" " Barrows, .....	418	" " Soldering, .....	283		
Gravel Beds, .....	514	" " Cup and Dresser, .....	372	" " Casements, .....	477	" " Lancashire Tee Hinges, .....	389		
Gauges, Wire, .....	457	" " Fan, .....	403	" " Cellar Flaps, .....	478, 479	" " Lancaster" Bath, .....	225		
Guide Wheels, .....	145	" " Harness, .....	516	" " Cistings, .....	180	" " Interior, .....	181		
Guides, Pull, .....	166	" " Hat and Coat, .....	368, 399, 420	" " Curb Fenders (see also Special List), .....	15 to 70	" " Langham" Fireplace, .....	21		
Gullies, Iron, .....	470	" " Long Arm, .....	391, 422	" " Door Furniture, .....	366	" " Larbert" Range, .....	161		
" " Stoneware, .....	291, 296	" " Moulding, .....	338	" " Drain Pipes, .....	470	" " Lead Od, .....	279		
Gullies, .....	5180	" " Picture, .....	338	" " Knockers and Handles, .....	358 to 360	" " Latch Handles and Furniture, .....	403		
" " Deepeners, .....	295	" " Plasterers, .....	403	" " Lavatory Basins, .....	196, 198, 250	" " Latches, all kinds, 318 to 350, 386, 393, 518A	356		
" " Trap and Channel, .....	295	" " Sash, .....	393	" " Letters and Figures, .....	548	" " Lath, Hammer, .....	403		
Guns, .....	279	" " Shaw, .....	289	" " Mantelpieces, 24, 43, 66 to 59, 120, 127	412	" " Nails, .....	342		
Gun Metal Handles, .....	365	" " Suspending, .....	420	" " Mats, .....	494	" " Lathing, Metal, .....	113, 5180, 5186		
" " Valves, .....	154	" " Wall, .....	512	" " Pillars, .....	494	" " Laths, Glaziers', .....	287		
Gutter, Adapters, .....	455, 457	" " Wardrobe, .....	420	" " Protective Paint, .....	272	" " Plasterers', .....	301		
" " Brackets and Bolts, .....	455, 457	Hoop Iron, .....	341	" " Railings, .....	495 to 513	" " Latrine Range, .....	187		
Gutters, Iron and Connections, 155 to 400	529	Hopper Casements, .....	440	" " Sashes, .....	476, 477	" " Lattice, Wire, .....	417		
" " Pavement, .....	515	" " Pans and Traps, .....	408	" " Screws, .....	340	" " Laundry Stove, .....	133		
" " Stable, .....	137	Hoppers, Slop, .....	206	" " Sheets, .....	314	" " Landed" Mantel Register, .....	133		
" " Zinc, .....	137	Horizontal Bib Cock, .....	146	" " Sinks, .....	250, 528	" " Lavatory Basin, .....	189 to 205, 218, 250		
		" " Hornchurch" Mantel Suite, .....	64	" " Stairs, .....	489 to 491	" " Brackets and Frames, 195, 196	196		
		" " Hornsea" Stove Suite, .....	70	" " Tables, .....	134	" " Cocks, .....	149		
		Horse Nails, .....	342	" " Wash Tubs, .....	250	" " Cores, .....	240		
		" " Pots, .....	515	" " Wire, .....	341	" " Latch, .....	349		
		Horticultural Bars, .....	335	" " Irons" Closet, .....	177	" " Lock, .....	240		
		Hacking Knives, .....	287	" " Ives" Sash Fastener, .....	371	" " Rams, .....	204, 210		
		Hair Bender Telt and Fabric, .....	301	" " Ivybridge" Mantel Register, .....	68	" " Showers, .....	246		
		" " Rooms, .....	286	" " Ivyrite" Closet, .....	169, 175	" " Stands, .....	196, 198		
		" " Hooks, Plasterers, .....	403			" " Taps, Combined, .....	246		
		" " Plasterers, .....	301			" " Lavenham" Lavatory, .....	202		
		Hall round Gutters, .....	455			" " Lawn Barding, .....	517		
		Hall Fittings and Screens, Wood, .....	329			" " Mowers, .....	118		
		" " Seal Standards, .....	531						
		" " Stoves, .....	131						
		Hall's Distemper, .....	269						
		" " Hamilton" Mantel Suite, .....	23						
		Hamilton's Brushes, .....	283						
		Hammers, .....	101						
		Hand Gates, .....	501, 508, 515, 516						
		Handles, Cabinet, .....	352, 119						
		" " Door, .....	361, 365, 368						
		" " Drawer, .....	372, 118						
		" " Lift, .....	372						
		" " Lock or Latch, .....	357						
		" " Sash, .....	372						
		" " Wood Tool, .....	106						
		Hand painted Glass, .....	136						
		Handrail Bracket Tile, .....	93						
		" " Screws, .....	313						
		Handrails, Wood, .....	325						
		Hands, Iron, .....	518						
		Hanging Rollers, .....	378						
		" " Signs, .....	151						
		Hardwood Closet Seats, .....	164						
		Harland's Varnish, .....	266						
		Harness Room Fittings, .....	516						
		" " Harold" Mantel Register, .....	80						
		" " Harrington" Mantel Register, .....	81						
		" " Harrogate" Bath, .....	228						
		" " Lavatories, .....	205						
		" " Harthorn" Shade Roller, .....	392						
		Hasp Bolt, .....	386						
		Haps and Staples, .....	396						
		Hat and Coat Hooks, .....	368, 399, 420						
		Hatch Copper Bit, .....	110						
		Hatches, .....	102						
		Hatfield's Rollers, .....	378						
		Hay Racks, .....	511, 515						
		Heads, Rain Water, .....	165						
		Heath Tiles, .....	93						
		" " Heathpark" Mantel Suite, .....	63						
		Heating Apparatus, .....	513 to 541						
		" " Stoves, .....	131						
		Heavy Drain Pipes and Connections, .....	168 to 470						
		Helial Spring Hinges, .....	390						
		Hellver's Traps, .....	138						
		Helmert Chimney Cowl, .....	158						
		" " Hepburn" Hob Register, .....	91						
		" " Hercules" Lift and Force Pump, .....	262						
		" " Hero" Boiler, .....	536						
		Hexagon Body Bath Cocks, .....	119						
		" " Highgate" Stove Suite, .....	76						
		High pressure Stop and Bib Valves, .....	118						
		Hinged Manhole Covers, .....	471						
		" " Pavement Gutter, .....	529						
		Hinges, .....	166, 387						
		" " Howe Ackland" Tap, .....	151						
		Hob Register Stoves and Grates, .....	45, 91						
		Hog Han Tools, .....	283, 291						
		Holds, .....	410						
		" " Holcombe" Mantel Suite, .....	37						
		Holderbats, .....	161						
		Hole Bore, .....	413						
		" " Holland Park" Mantel Suite, .....	66						
		Hollow Columns, .....	183						
		" " Homeade" Copper, .....	520						
		Hood, Door, .....	516 and 183						

## I

" " Ideal" Domestic Boiler, .....	538	Keene's Cement, .....	297		
" " Portable Range, .....	101	" " Keep off the Grass" Tablets, .....	517		
" " Radiators, .....	539	Kemp's Drain Tester, .....	113		
" " Sectional Boiler, .....	538	" " Kensley" File Grate, .....	88		
" " Ideal" Mantel Suite, .....	41	Kenrid's Axle Pulley, .....	391		
Illuminated Signs, .....	116, 152	" " Kensington" Bath, .....	230		
" " Imperial" Washing Tubs, .....	520	Kent's Brushes, .....	283		
Implement Paint, .....	268	Kettles, Paint, .....	287		
" " Improved Farmer" Boiler, .....	521	Kicking Plates, .....	350		
Incorbed Facies, .....	416	Kimberley's Floor Gramp, .....	101		
Independent Boilers, .....	540	" " Kingsgate" Mantel Suite, .....	33		
Index Hands, .....	518	" " Kinnard" Grate, .....	92		
India rubber Beer Pipe Joints, .....	113	" " Kirkstead" Interior, .....	87		
" " Closet Butters, .....	143	Kitcheners (see also Cooking Ranges), .....	108 to 119		
" " Cones, .....	162	Kitchenier Boilers, .....	126		
" " Door Stops, .....	372	Kitchen Fenders, .....	126		
" " Plugs, .....	162	" " Mantels, .....	120		
" " Plunger, .....	115	" " Sinks, Iron, .....	528		
" " Rines, .....	113	" " Lion" Mower, .....	520		
" " Sheet, .....	143	Knives, Gliders', Glaziers', .....	280		
" " Suction Delivery Hose, .....	113	" " and Plumbers', .....	279, 290		
" " Valves, .....	740	" " Paperhangers', .....	351 to 366, 370		
Indicating Latches, .....	61	Knobs, .....	358 to 363		
" " Ingelby" Mantel Suite, .....	254	Knockers, .....	265, 272		
Inlet Valves, .....	254	" " Kosev" Heating Stove, .....	151		
" " Ventilators, .....	78	" " Krater" Sink Support, .....	211		
" " Immsbruck" Mantel Register, .....	801				
Inodorous Felt, .....	162				
Inspection Cover, .....	473, 528				
" " Pipes and Branches, .....	469				
" " Traps, .....	296				
Instantaneous Grip Vice, .....	105				
Interceptors, Iron, .....	470				
" " Stoneware, .....	295				
Interior Doors, .....	306				
Interiors, .....	17, 80, 87				
" " Invictas" Cistern, .....	160				
" " Closet, .....	171				

## J

Jack Plane, .....	401				
" " Pumps, .....	258				
Jacks, .....	409				
Jalousies, .....	312				
Japanese Glass, .....	427				
Japanned Bath, .....	222				
Japanned, .....	268				
Japan, .....	265				
Jaw Box, .....	219				
" " Jelliso, .....	276				
Joiners' Gramp, .....	101				
" " Tools, .....	101				
Joinery, .....	209				
Joints, Beer Pipe, .....	113				
" " Jones' Patent Expanding Screw Stopper, .....	113				
Juniper, Bricklayer's, .....	403				
Junctions, Lead, .....	138				
" " Stoneware, .....	295				
Juniors' Closets, .....	188				
" " Unial, .....	220				

## K

Kene's Cement, .....	297				
" " Keep off the Grass" Tablets, .....	517				
Kemp's Drain Tester, .....	113				
" " Kensley" File Grate, .....	88				
Kenrid's Axle Pulley, .....	391				
" " Kensington" Bath, .....	230				
Kent's Brushes, .....	283				
Kettles, Paint, .....	287				
Kicking Plates, .....	350				
Kimberley's Floor Gramp, .....	101				
" " Kingsgate" Mantel Suite, .....	33				
" " Kinnard" Grate, .....	92				
" " Kirkstead" Interior, .....	87				
Kitcheners (see also Cooking Ranges), .....	108 to 119				
Kitchenier Boilers, .....	126				
Kitchen Fenders, .....	126				
" " Mantels, .....	120				
" " Sinks, Iron, .....	528				
" " Lion" Mower, .....	520				
Knives, Gliders', Glaziers', .....	280				
" " and Plumbers', .....	279, 290				
" " Paperhangers', .....	351 to 366, 370				
Knobs, .....	358 to 363				
Knockers, .....	265, 272				
" " Kosev" Heating Stove, .....	151				
" " Krater" Sink Support, .....	211				

## L

Lacquers, .....	266				
Ladder Brackets, .....	400				
" " Tape, .....	392				
Ladders, .....	336				
Ladles, .....	140				
" " Laleham" Suite, .....	67				
Laminated Lead, .....	277				

## L

Lamp Pans, .....	427				
Lamps, .....	(See Vol. II)				
" " Hurricane, .....	413				
" " Soldering, .....	283				
" " Lancashire Tee Hinges, .....	389				
" " Lancaster" Bath, .....	225				
" " Interior, .....	181				
" " Langham" Fireplace, .....	21				
" " Larbert" Range, .....	161				
" " Lead Od, .....	279				
" " Latch Handles and Furniture, .....	403				
" " Latches, all kinds, 318 to 350, 386, 393, 518A	356				
" " Lath, Hammer, .....	403				
" " Nails, .....	342				
" " Lathing, Metal, .....	113, 5180, 5186				
" " Laths, Glaziers', .....	287				
" " Plasterers', .....	301				
" " Latrine Range, .....	187				
" " Lattice, Wire, .....	417				
" " Laundry Stove, .....	133				
" " Landed" Mantel Register, .....	133				
" " Lavatory Basin, .....	189 to 205, 218, 250				
" " Brackets and Frames, 195, 196	196				
" " Cocks, .....	149				
" " Cores, .....	240				
" " Latch, .....	349				
" " Lock, .....	240				
" " Rams, .....	204, 210				
" " Showers, .....	246				
" " Stands, .....	196, 198				
" " Taps, Combined, .....	246				
" " Lavenham" Lavatory, .....	202				
" " Lawn Barding, .....	517				
" " Mowers, .....	118				

## L

Lead Ad, .....	401				
" " Bell Traps, .....	150				
" " Bends, .....	139				
" " Clips, .....	138				
" " Fod, .....	277				
" " Junctions and Offsets, .....	138, 140				
" " Pipe, .....	258				
" " Pumps, .....	265				
" " Sheet, .....	219				
" " Soil Pipe, .....	276				
" " Tacks, .....	101				
" " Traps and Terminals, .....	138, 139				
" " Loaded Cathedral Light, .....	111 to 150				

## General Index to Vol. I.—Continued.

**Gas and Electric Lighting, Heating and Cooking Appliances, Electric Bells and Telephones, and Shop Window Fittings are indexed in Vol. II.**

London Tee Hinge, .....	389	Mountings for Doors, .....	381	Oress " Anthracite Stove, .....	130	"Philippe" Mantel Register, .....	76
Waste Preventer, .....	152	Mowers, .....	418	"Ornament" Mantel Suite, .....	15	Pick Axes, .....	406
Longarm Hooks, .....	393	Mud Gully, .....	297	Ornamental Archways, .....	417	Picture Rail Mouldings, .....	330, 338
Loose Box Divisions, .....	543	Muffled Glass, .....	150	Column, .....	483	Ring, .....	373
"Lotus" Mantel Register, .....	83	"Munio" Closet, .....	151	Wrought Railings, .....	513	Pig Troughs, .....	517
"Louis" Gate and Railing, .....	199	Muraine, .....	269	"Osterley" Mantel Suite, .....	67	"Plaster" Closet Suite, .....	176
"Louvre" Air Bricks, .....	524	Muranese Glass, .....	127	"Oswald" Tile Grate, .....	90	Pillar Cocks, .....	119, 151
Chimney Pots, .....	299	Muriatic Acid, .....	281	"Otium", .....	276	Crabs, .....	410
Flues, .....	158			Outlet Ventilators, .....	254	Pillars, Iron, .....	404
Ventilators, Glass, .....	131			Outside Varnish, .....	264	Pineces, .....	401
Steel Improved, .....	398			Oval Buds, .....	312	Pine Mantels, .....	28
Lubricants, .....	279			"Bushe", .....	283	Pins, Doors, .....	307
"Ludgate" Urinal, .....	219			Furniture, .....	341	Panel, Escentheon, .....	312
		Nails, .....	312	Oven Apparatus, Baker, .....	532	"Phonoe" Cistern, .....	160
		Name Tablets, .....	412, 518	Tile, .....	300	Pipe Bender, .....	110
		Naphtha, .....		Overdoors, Paper Stucco, .....	290	Bending Furnace, .....	280
		"Narbora" Interior, .....	87	Wood, .....	326	Chips, .....	138, 163
		Native Closets, .....	182	Overflows, Bath, .....	119	Fats, .....	404
		Navy Barrow, .....	403	Ox Han Winters, .....	285	Felt, .....	301
		Wheels, .....	523	Oxidised Furniture, .....	354 to 357	Nails, .....	457
		Seatsfoot Oil, .....	279			Nozzle and Dampet, .....	523
		"Needle" Bath, .....	236				
		"Nelsons" Mantel Register, .....	20				
		"Neponset" Roofing, .....	518				
		Wall Board, .....	518				
		Netting, Wire, .....	111				
		"New Automaton" Lawn Mower, .....	418				
		"New Chelmer" Lavatory, .....	196				
		"New Cottage" Bath, .....	231				
		"New Cresset" Anthracite Stove, .....	128				
		"New Devonshire" Interior, .....	87				
		"New Earlsfield" Mantel Suite, .....	12				
		"New Era" Rim Lock, .....	345				
		"New Flambeau" Anthracite Stove, .....	128				
		"New Hambleton" Suite, .....	10				
		"New Invictas" Closet Suite, .....	171				
		"New Maisonette" Stove, .....	47				
		"New Radiant" Grate, .....	90				
		"New Radiating" Anthracite Stove, .....	128				
		"New Reflex" Kitchenier, .....	110				
		"New Richmond" Suite, .....	31				
		"New River" Fittings, .....	152, 159				
		"New Seat Pad" Closet Suite, .....	171				
		"New Serena" Tile Grate, .....	89				
		Newels, Iron, .....	492				
		Wood, .....	316, 318, 320				
		Nickel-plated Showers and Sprays, .....	233 to 236				
		Sponge Holder, .....	212				
		Lowel Arms, .....	237				
		Night Latches, .....	318				
		Nitric Acid, .....	281				
		Non Concussive Garage Cock, .....	151				
		Lavatory Tap, .....	119				
		Non Conducting Coverings, .....	301				
		"Nonebetter" Door Rollers, .....	378				
		Norfolk Latches, .....	385				
		Troughs, .....	547				
		"Norton" Door Spring, .....	390				
		Nosing, Stan, .....	523				
		Whorl, .....	334				
		Numbers, Door, .....	373				
		Numerals, .....	518				
		"Nuras" Lavatory Basin, .....	192				
		Nuts and Bolts, .....	313				

# General Index to Vol. I.—Continued.

Gas and Electric Lighting, Heating and Cooking Appliances, Electric Bells and Telephones, and Shop Window Fittings are indexed in Vol. II.

	PAGE		PAGE		PAGE		PAGE
Portable Drilling Machines, . . . . .	105	"Reliance" Heating Stove, . . . . .	132	Salt Glazed Bricks, . . . . .	302	Shop Window Fittings, . . . . .	(See Vol. II.)
"Earth Closets, . . . . .	181	"Reliance" Paint Mills, . . . . .	281	"Salway" Closet Suite, . . . . .	179	Shot, . . . . .	136
Forges, . . . . .	106	"Rembrandt" Mantel Register, . . . . .	72	"Sanclaz" Closet, . . . . .	172	Showers, . . . . .	518d, 518f
Portland Cement, . . . . .	297	Resolin, . . . . .	279	Sand, . . . . .	297	Shower Baths, . . . . .	231, 235, 236
Portulacoid Slates, . . . . .	297	Restaurant Tables, . . . . .	131	Sanitary Compounds, . . . . .	279	"Lavatory, . . . . .	151
Portsmouth Pattern Ball Valves, . . . . .	153	Retaining Valve, . . . . .	259	"Dust Bins, . . . . .	151	"Rose, . . . . .	151
"Positive" Cistern, . . . . .	160	Reversible Hasp Bolt, . . . . .	386	"Paper Racks, . . . . .	213	Showers, Bath and Lavatory, . . . . .	216
Post Hole Borer, . . . . .	113	"Hinge, . . . . .	387	Sarking Felt, . . . . .	301	Shutter Hinges, . . . . .	389
Postal Handles, . . . . .	358 to 370	"Seat Standards, . . . . .	531	Sash and Angle Bars, . . . . .	332	"Screens, . . . . .	373
Posts and Sockets, . . . . .	530	Revolving Head New Smoke Conductor, . . . . .	158	"Frame Material, . . . . .	332	Shutters, Wood, . . . . .	312
Posts, Iron, . . . . .	191	"Hooks, . . . . .	129	"Cramps, . . . . .	103	Sirlian Marble Mantels, . . . . .	53
"Oak, . . . . .	303	"Rhodesian" Range, . . . . .	101	"Fasteners, . . . . .	371, 421	Sideboard Handles, . . . . .	419
Potash, . . . . .	279	"Richards" Closet, . . . . .	169	"Glazing, . . . . .	129	Side Hinges, . . . . .	166
Pot Ruby, Yellow, Blm. Glass, . . . . .	427	"Richards" Mantel Register, . . . . .	73	"Handles and Lifts, . . . . .	372, 421	"Pulleys, . . . . .	391
Pots and Covers, . . . . .	529	Ridge Capping, Iron, . . . . .	311	"Hooks, . . . . .	393	Sideroleum, . . . . .	271
"Premier" Boilers, . . . . .	528	"Tiles and Ornaments, . . . . .	298	"Lifts, . . . . .	421	Sieves, . . . . .	107
Preparations for Damp Walls, . . . . .	277	"Ventilators, . . . . .	255	"Lines, . . . . .	391	Sifter, Cinder, . . . . .	181
Prepared Sash and Frame Material, 332,	335	Ridgely Wall Paper Trimmer, . . . . .	277	"Locks, . . . . .	349	Sinks, . . . . .	416 to 451
Preservative Solution, Wood, . . . . .	271	Ridging, Iron, . . . . .	311	"Pivots, . . . . .	373	Silicate Cotton, . . . . .	271
Preserved Paste, . . . . .	271	Rim Furniture, . . . . .	313	"Roller, . . . . .	393	Soda, . . . . .	281
Presses, Bell, . . . . .	301	"Locks and Latches, . . . . .	315	"Stop, . . . . .	373	Silk Flap Ventilators, . . . . .	308
Prismatic Lens, . . . . .	178, 179	Ring Closet Seats, . . . . .	161	"Tools, . . . . .	285, 286	Sill Bricks, . . . . .	300
"Rolled Glass, . . . . .	132	Rings, Hot Water, . . . . .	113	"Weights, . . . . .	476	Sills, Wood, . . . . .	332
Propagating Glass, . . . . .	131	Ripolin, . . . . .	268	Sashes, Cast Iron, . . . . .	476	Silver and Gold Leaf, . . . . .	273
Prostate Roofing, . . . . .	518d	Rippers, Slates, . . . . .	403	"Wrought Iron, . . . . .	140, 477	Silvered Glass, . . . . .	431
Protective Paint, . . . . .	272	Rippled Glass, . . . . .	127	Sashes and Frames, Wood, . . . . .	309	Single-Action Hinges, . . . . .	388
Pull and Push Plates, . . . . .	373	"Ritz" Bath, . . . . .	233	"Saville" Boilers, . . . . .	510	"Barrel Pumps, . . . . .	258
Pull Guide, and Rod, . . . . .	163	"Lavatory Stand, . . . . .	251	"Savoy" Stove Suite, . . . . .	26	"Purchase Crabs, . . . . .	410
Pulley Blocks, . . . . .	110	"Mantel Suite, . . . . .	30	Saws, . . . . .	401	"Roller Guides, . . . . .	258
Pulleys, . . . . .	391, 392	Rivets, . . . . .	313	"Saxonia" Closet Suite, . . . . .	179	Sink Bends, . . . . .	296
Pulls, Bell, . . . . .	370	Road Gully, . . . . .	171	Scaffolding Hammer, . . . . .	403	"Brackets, . . . . .	211
"Closet Cistern, . . . . .	162, 163	"Manhole Cover, . . . . .	171	Scaffold Chain, . . . . .	108	"Plugs and Washers, . . . . .	151
Drawer, . . . . .	372	"Pick and Wedges, . . . . .	406	"Cord, . . . . .	107	"Supports, . . . . .	211
Pulpit Latch, . . . . .	350	"Robbials" Enamel, . . . . .	268	"Poles, . . . . .	303	"Traps and Grates, . . . . .	141
Pumice Stone, . . . . .	279	Rod, Well, . . . . .	259	"Lashes, Steel, . . . . .	108	Sinks, Fireclay, . . . . .	206 to 214, 302
Pump Fittings, . . . . .	259	"Rollargio" Bath, . . . . .	222	School Board Air Bricks, . . . . .	523	"Iron, . . . . .	250, 528
"Hose, . . . . .	148	Rolled Cathedral Glass, . . . . .	42	"Hat and Coat Hooks, . . . . .	399	Sirapite, . . . . .	297
Pumps, . . . . .	136, 143, 151, 268, 262	"Plate Glass, . . . . .	427	School Closets, . . . . .	188	"Sirex" Closets, . . . . .	168
Purimachos Cement, . . . . .	373	Roller Catch and Fastener, . . . . .	427	"Desk and Bench Standards, . . . . .	531	Size, . . . . .	279
Push Plates, . . . . .	361, 363	"Guides, . . . . .	382	"Seats, . . . . .	531	Skaps, Dust, . . . . .	157
Pushes, Bell, . . . . .	270	"Pump, . . . . .	359	Scissors, . . . . .	287	Skid Pans and Irons, . . . . .	523
Putty, . . . . .	270	"Stays, . . . . .	396	Scrapers, Grain, . . . . .	518d	Skirtings, . . . . .	331
"Knives, . . . . .	287	Rollers, Bellamy's, . . . . .	282	Scotch Glue, Liquid, . . . . .	277	Skylight Openers and Fittings, . . . . .	391, 395
Puttyless Glazing, . . . . .	429	"Blind, . . . . .	392	"Tee Hinges, . . . . .	589	"Stays, . . . . .	396
Petrollic Acid, . . . . .	281	"Combining, . . . . .	280	Scouting Cloth, . . . . .	281	Skylights, . . . . .	175
		"Door, . . . . .	378, 382	Scrapers, Drum, . . . . .	145	Slabbed Panels, . . . . .	95
		"Garden, . . . . .	118	"Gravel, . . . . .	134	"Tiles, . . . . .	37, 93
		"Paperhangers' . . . . .	288	"Painters' and Paperhangers', . . . . .	287	Slag Wool Coverings, . . . . .	271
		"Pavement, . . . . .	108	Screens, Lime, &c., . . . . .	107	Slam and Stop, . . . . .	372
		"Spring Blind, . . . . .	392	Screw Cups, . . . . .	373	Slate Fastener, . . . . .	140
Quadrant Levers, . . . . .	397	Roman Baths, . . . . .	223	"Drivers, . . . . .	401	"Mantel Pieces, . . . . .	51, 55, 60, 61
"Stays, . . . . .	396	"Cement, . . . . .	297	"Eyes, . . . . .	373	"Roll and Leaf, . . . . .	297
Quadruple Acting Pumps, . . . . .	260	Roofing Felt, . . . . .	301	"Pulleys, . . . . .	391	Slates' Tools, . . . . .	403
Quarry Tiles, . . . . .	299	"Paroid and Prostate, . . . . .	518e	"Stopper, . . . . .	113	Slates and Slatting, . . . . .	297
"Queen Anne" Entrance Gates, . . . . .	503	"Slate Fastener, . . . . .	140	Screwdown Cocks, . . . . .	115, 146	Slates, Glass, . . . . .	130
Railings, . . . . .	503	"Slates, . . . . .	297	Screws, . . . . .	340, 311, 313	Slatting Nails, . . . . .	312
"Queen" Office Stove, . . . . .	132	"Tiles, . . . . .	298	Screws and Washers, . . . . .	413	Sledge Hammers, . . . . .	406
Quick Flush Closet, . . . . .	170	Roof Lights, . . . . .	311, 171	Screwing Machines, . . . . .	(See Vol II)	Sliding Air Bricks, . . . . .	398, 392
"Pedestal Closet Suite, . . . . .	173	"Ventilators, . . . . .	255	Seat Brackets, . . . . .	167	"Door Rollers, . . . . .	378, 392
		"Rosalind" Mantel Register, . . . . .	82	"Buffers, . . . . .	143	"Doors and Frames, . . . . .	535
		"Rose" Hall Stove, . . . . .	131	"Seat Ped" Closet, . . . . .	171	Sash Catch, . . . . .	352
		"Nails, . . . . .	312	Seat Hinges, . . . . .	166	Ventilators, . . . . .	398
		"Shower, . . . . .	151	"Standards, . . . . .	531	Slipper Bath, . . . . .	231
		Rotary Pump Motion, . . . . .	260	Seats, Bath, . . . . .	242	"Sloane" Hob Grate, . . . . .	91
		Rough Cast Plate Glass, . . . . .	127	"Closet, . . . . .	165	Slop Hoppers, . . . . .	206 to 208
		Round Cisterns, . . . . .	156	"Garden, . . . . .	118	"Sinks, . . . . .	206 to 209
		"Corn Bins, . . . . .	156	Secret Pulleys, . . . . .	391	Slow Combustion Boilers, . . . . .	536 to 541
		"Head Screws, . . . . .	310, 311	Sectional Boilers, . . . . .	538	"Stoves, . . . . .	131, 132
		"R R" Paint Remover, . . . . .	277	Self Acting Exhaust Ventilator, . . . . .	254	Smith's Floor Springs, . . . . .	390
		Rubber, . . . . .	113	Self Closing Valves, . . . . .	150	"Forge, . . . . .	406
		"Plugs, . . . . .	162	Self Setting and Portable Ranges, 98 to	107	"Tools, . . . . .	106
		Rubbish Baskets, . . . . .	109	Self-Shutting Carriage Gate, . . . . .	510	Smoke Curing Appliances, . . . . .	158
		"Screens, . . . . .	407	Semi Rotary Pumps, . . . . .	260	"Pipes and Elbows, &c., . . . . .	126, 130
		"Wheel, . . . . .	409	Sewer Pipes and Traps, . . . . .	290, 470	"Plates, . . . . .	126
		Ruby Glass, . . . . .	127	"Ventilating Shafts, . . . . .	530	Smoothing Plane, . . . . .	401
		"Ruby" Interior, . . . . .	86	Shad-Bolt Stay, . . . . .	396	Snatch Blocks, . . . . .	410
		"Ruislip" Mantel Suite, . . . . .	63	Shade Rollers, . . . . .	392	Snow Guards, . . . . .	117
		Rules, . . . . .	112	Shampoo Spray, . . . . .	216	Soap and Sponge Holder, . . . . .	242
		"Rumford" Stove, . . . . .	126	Shanks' Rubber Bath Cones, . . . . .	113	Soaps, . . . . .	276
		Russian Tallow, . . . . .	279	Shave Hooks, . . . . .	287	Socket Pipe Rings, . . . . .	113
		Rustless Pans, . . . . .	522	"Shawford" Mantel Suite, . . . . .	50	Sockets, Closet, . . . . .	166
		"Resolite" Enamel, . . . . .	268	Sheathing Felt, . . . . .	501	"Clothes Post, . . . . .	530
		"Rede" Lavatory, . . . . .	250	Sheep and Cattle Hurdles, . . . . .	511	Soda, . . . . .	279
				"Fencing, . . . . .	337	Soft Soap, . . . . .	279
				"Marking Composition, . . . . .	268	Softeners, Badger, . . . . .	283
				"Netting, . . . . .	115	Soll Pipe Cows, . . . . .	251
				Sheet Glass, . . . . .	126	"Ferrules, . . . . .	166
				"Iron, . . . . .	344	"Guards, . . . . .	157
				"Cattle Troughs, . . . . .	157	"Lead, . . . . .	136
				"Cisterns, . . . . .	159	"Terminals, . . . . .	138
				"Lead, . . . . .	156	"Ventilators, . . . . .	254
				"Rubber, . . . . .	143	Soil Pipes and Connections, . . . . .	156 to 467
				"Zinc, . . . . .	137	Solder, . . . . .	136
				Shelt Brackets, . . . . .	100, 135	Soldering Fluid, . . . . .	279
				Shellac, . . . . .	279	"Lamps, . . . . .	284
				Shelves, Glass, . . . . .	433	"Solese" Anthracite Stove, . . . . .	130
				Sherringham's Ventilators, . . . . .	398	"Solignum" Preservative, . . . . .	274
				Ship Varnish, . . . . .	266	Solution Damp Wall, . . . . .	275
				Shoing Bars, . . . . .	344	Soot Boxes and Doors, . . . . .	522
				Shop Door Locks and Latches, . . . . .	349	"Southchurch" Mantel Suite, . . . . .	65
				"Stoves, . . . . .	132	Spandril Brackets, . . . . .	527

# General Index to Vol. I.—Continued.

Gas and Electric Lighting, Heating and Cooking Appliances, Electric Bells and Telephones, and Shop Window Fittings are indexed in Vol. II.

	PAGE		PAGE		PAGE		PAGE
"Spa" Bath, .....	222	Strainers, Paint, ..	287	Fire, .....	300	Unclimbable Gates, ..	516
Spades, .....	548	" Pump, .....	259	Garden, .....	299	" Railing, .....	512
Spike Chain, .....	408	Strand Fencing Wire, ..	116	Glass, .....	130	Underbays Ball Valve, ..	153
Spikes, .....	342	" "Strand" Urinal, ..	217	Hearth, .....	93	Undercoating, .....	267, 278
Spiral Bolts, .....	383	Strap Hinges, .....	388	Oven, .....	300	Uniform Range Sets, ..	98
" Stairs, .....	190, 491	" "Streetley" Mantel Register, ..	71	Pan, Ridge, and Wall, ..	300	Unions, .....	180
Spirit Level, .....	401	Street Grating, Heavy, ..	171	Paving Quarry, .....	299	" Steam, .....	151
Spirits, .....	279	" Gully, .....	171	Roofing, .....	298	Upight Pulleys, .....	391
Spokeshave, .....	101	" "Larthenware, ..	296	Tiles and Tile Panels, ..	93 to 96	Urinal Cisterns, .....	215
Sponge and Soap Holder, ..	212	" Name Plates, .....	518	Tiling, .....	297	" Cock, .....	150
Sponges, .....	288	" "String and Ring" Entrance Gates, ..	196	Wall, .....	96	Urinals, .....	216, 220
Spray Bath, .....	235, 236	" Railing, .....	196	Till Locks, .....	351	" Stalls, .....	217, 218
Sprays, .....	246	Suckers, Pump, .....	143	Timber, .....	343	" "Urinal Toilet Cowl, ..	150
Spring Bib Cock, .....	150	Suction Hose, .....	261	Timber, Dogs, .....	136	" "Utilities" Wall Lavatory, ..	192
" Bolts, .....	385	" Pumps, .....	385	Ingots and Plates, ..	136		
" Drain Cleaner, .....	115	Suffolk Latches, .....	158	Timmer's Mallet, .....	136		
" Hinges, .....	388	Sugar Loaf Flue, .....	276	" Solder, .....	116		
" Latches, .....	388	" Soap, .....	317	Tinned Staples, .....	215		
" Pillar Cocks, .....	392	Suite Locks, .....	279	Tip up Automatic Cistern, ..	217		
" Rollers, .....	154	" "Sulby" Tile Grate, ..	279	" Bath, .....	530		
" Safety Valve, .....	150	Sulphur Candles, .....	279	" Seats, .....	215		
" Urinal Cock, .....	290	" Dioxide, .....	279	" "Mortars, .....	212		
Springs, Door, &c., .....	529	" Roll and Flom, ..	272	" Paper Holders, ..	211		
Square Coal Plates, .....	156	Sulphuric Acid, .....	136	" Requisites, .....	215		
" Corn Bins, .....	157	" "Sun" Brand Paints, ..	283	" "Tomato" Flushing Cistern, ..	215		
" Dust Bins, .....	162	" "Solder, .....	282	Tomb Railings and Tablets, ..	517 to 519		
" Iron Pipes, .....	255	" "Vatnash Brush, ..	211	Tool Baskets, .....	100		
" Revolving Ventilator, ..	320 to 321	Supply Cisterns, .....	210	Toots, .....	103		
" Turned Wood Goods, ..	137	Supports, Sink, .....	275	Bricklayers, .....	101		
" Zinc Pipes, .....	138	" "Supreme" Geyser, ..	386	Carpenters, .....	103		
S Traps, Lead, .....	300	Surface Brushes, .....	21 to 27, 52, 93	Caulling, .....	286, 289		
Stable Bricks, .....	512, 513	" Latch, .....	106	Decorations, .....	103, 105		
" Fittings, .....	518	Surrounds, Tile, .....	111	Engineers, .....	103		
" Fork, .....	518	Swage Block, .....	115	Cashiers, .....	289		
" Grate and Frame, and Gutter, ..	515	Sweeping Machines, ..	308	Gablers, .....	289		
" Latch, .....	552	Sweep's Brush, .....	281	Gaziers, .....	290		
" Requisites, .....	516	Swedish Door, .....	301	Gainers, .....	101		
" Window, .....	525	" Lamps, .....	430 to 538	Joiner, .....	103		
Staffordshire Bricks, .....	300	" Mouldings, .....	361	Masons, .....	285, 289, 290		
Stained Glass, .....	111 to 419	" Pitch, .....	160	Painters, .....	103		
Stairs, .....	296	" "Swerve" Cistern, ..	361	Paperhangers, .....	286, 289, 290		
Stan Brackets, Wood, .....	325	Swing Door Handle, ..	151	Plasterers, .....	102		
" Nosing, Iron and Steel, ..	400, 523	Swinging Signs, .....	190	Platelayers, .....	110, 151, 289		
" Treads, Iron, Steel, and Brass, ..	100	" "Sylvia" Lavatory Basin, ..	112	Plumbers, .....	103		
Stairs, Iron, .....	489 to 491	Syphon Boxes, .....	187	Slaters, .....	106		
Stall Board, .....	478	" Cisterns, .....	295	Smiths, .....	110		
" Divisions, .....	513	Syphonic Latrine Range, ..	277	Timmen's, .....	131, 133		
" Plates, .....	446	Syphons, Diam, .....	158	Towel Alfers, .....	212, 211		
" "Standard" Bars, .....	151	Szerelney Stone Liquid, ..	112, 518	Tower Brackets, .....	119		
Standards, Divisions, .....	191	T-Fauc, .....	389	Trapped Waste, .....	150		
" School Desk and Bench, ..	551	T-Hinges, .....	311	Traps, .....	150		
" Table and Seat, .....	531	T-Irons, .....	287	Bell, .....	148		
Stands for Aquarium Glasses, ..	131	T-Squares, .....	319	Closet, .....	328		
" Umbrella, .....	116	Table Legs, .....	114	Diam, .....	296		
Staples, .....	279	Tables, Restaurant, ..	11, 16	Earthenware, .....	138		
Stauffer's Lubricant, .....	569	" Trivet, .....	295, 470	Lead, .....	138		
" "Stayfast" Casement Stay, ..	371	Tablets, Name, .....	138, 141	Sawn, .....	295, 470		
Staves, Casement, .....	396	" Park, .....	517	Shik, .....	107		
Greenhouse, .....	151	" Tomb, .....	517	Freddie Grindstone, ..	100		
Steam Cocks and Valves, ..	539	Tacks, Blue and Tinned, ..	342	Treads Stand, .....	71		
" Radiators, .....	142	" Lead, .....	138	" "Tredgale" Mantel Register, ..	336		
" Tubes and Fittings, .....	548	" "Tadworth" Tile Grate, ..	88	Trellis and Rails, .....	169		
Steel Ceilings, .....	387	Tail Door Spring, .....	396	" "Trendone" Closet, ..	588		
" Hinges, .....	344	Tail Box Flue, .....	158	Trestles, .....	518		
" Sheets, .....	408	" "Helmet Flue, .....	157	" "Trevor" Grate, ..	89		
" Wine Scaffold Lashes, ..	281, 290	Tallows, .....	155, 157	Trimmer, Paper, .....	277		
" "Louvre" Ventilators, ..	294	Tanks, .....	181	" "Triumph" Geyser, ..	238		
Stencil Brushes, .....	290	" Earth Closet, .....	215	Trivet Tables, .....	11, 16		
" Ink, .....	288, 289	" Flushing, .....	291	" "Tropic" Interior, ..	86		
" Plates, .....	336	Taper Pipes, .....	151	Trough Closet Ranges, ..	181 to 187		
Step Ladders, .....	526	" Faps, .....	116 to 151	Troughs, Feeding, ..	157, 517		
" Riser, .....	518	" Combination, .....	216	Trowels, .....	103		
" Wood, .....	316	Tar, .....	341	Truck Wheels, .....	523		
Steps for Manholes, .....	332	Tar Brushes, .....	284	Trusses, Plaster, .....	292		
Stiles, Wood, .....	283	Telephones, .....	517	Tube Colors, .....	273		
Stippling Brushes, .....	301	Telescope Harness Hook, ..	517	T Squares, .....	287		
Stockholm Tar, .....	317	Tenoning Machine, .....	105	Tubes and Fittings, ..	112		
Stock Locks, .....	537	Terebene, .....	265, 272	Tubing, Lead, .....	136		
Stoking Tools, .....	103	Terminals, Lead, .....	138	" Zinc Bell, .....	137		
Stone Breaker's Hammer, ..	296	Tessellated Tiling, .....	120	Tubular Locks, .....	314		
Stoneware Channels, .....	177	Testers, Diam, .....	113	" "Tunbridge Wells" Bath, ..	228		
" Closets, .....	301	Theatre Seat Standards, ..	166	Turned Wood Goods, ..	318		
" Damp Course, .....	296	Thimbles, Closet, .....	426	Turn Pin, .....	110		
" Gulleys, .....	301	" "Three Lances" Glass, ..	328	" Screws, .....	401		
Stomflex Roofing Felt, .....	529	Three-legged Pots, .....	400	Turns, Cupboard, .....	351		
Stop Cock Boxes, .....	152	Threshold Tread, .....	518	Turpentine, .....	165		
" Cocks, .....	117, 152	Thumb Latches, .....	343	Two-ply Seats, .....	341		
Stopping Knives, .....	491	Ties, Wall, .....	22, 25	Ivory, Iron, .....	100, 111		
Stops, Gate, .....	386	" Grates, .....	88 to 91		131		
Store Door Latches, .....	93	" Mantel Registers, ..	20, 69 to 84				
Stove Tiles, .....	168	" Pavements, .....	129				
Straight Hack Closets, .....	456	" Pegs, .....	342				
" Gutter, .....	140	Tiled Fireplaces, .....	21, 22				
" Copper Bit, .....	277	" Surrounds, .....	21 to 27, 31, 52				
" Edge, .....	489						
" Stairs, .....	416						
Strainers and Bolts, .....							



# General Index to Vol. I.—Continued.

Gas and Electric Lighting, Heating and Cooking Appliances, Electric Bells and Telephones, and Shop Window Fittings are indexed in Vol. II.

	PAGE		PAGE		PAGE		PAGE
Wall Tie Plates, . . .	523	White Glazed Bricks, . . .	302	Wire Pipe Guards, . . .	457	Wrought Iron Welded Boilers, . . .	123, 537
" Tiles, . . .	343	" Channels, . . .	296	" Snow Guard, . . .	417	" Steel Louvre Ventilators, . . .	398
" Tiling, . . .	297	" Lead, . . .	270	" Strainers, Fencing, . . .	416	Wyandott Gutter, . . .	456
" Urinals, . . .	246	" Wash, . . .	278	Wired Rolled Glass, . . .	432	Wyle's Sugar Soap, . . .	281
Walnut Mantels, . . .	26, 31, 37	" Wax, . . .	279	Wirework, . . .	417		
Wardrobe Fronts, . . .	313	" "Whitchell" Lavatory, . . .	253	Wood Balusters and Newels, . . .	317 to 324		
" Handles, . . .	367	Whitewood Mantels, . . .	28, 63	" Bench Screw, . . .	404		
" Hooks, . . .	399	Whiting, . . .	271	" Buckets, Pump, . . .	259		
Washable Distemper, . . .	269	Wicket Gates, . . .	345	" Fencing, . . .	303		
Wash-down Closets, . . .	168	"Wignone" Mantel Suite, . . .	48	" Finger Plates and Furniture, . . .	356		
Washer and Waste, . . .	151	"Wincanton" Carriage Gates, . . .	505	" Floor, Mastic, . . .	281		
" Line and Color, . . .	278	" Gate and Railing, . . .	505	" Gates, . . .	311		
Washers, . . .	343	Window Columns, . . .	530	" Handrails, . . .	325		
" Valve, . . .	413	" Decoration, . . .	291	" Letter, . . .	416		
Wash Tubs, . . .	250	" Fasteners, . . .	371	" Mantels, . . .	26 to 63		
Washing Coppers, . . .	521	" Glass, . . .	426 to 440	" Newels, . . .	316, 318, 320		
Washing-down Brushes, . . .	283	" Guards, . . .	417	" Overdoors, . . .	326		
Washerless Tap, . . .	151	" Lead, . . .	539	" Porels, . . .	312		
Waste, Cotton, . . .	290	" Radiators, . . .	300	" Preservatives, . . .	274		
Waste Not Cisterns, . . .	151 to 161	" Sill Bricks, . . .	417	" Pump Suckers, . . .	259		
Waste Sink, . . .	151	" Wirework, . . .	476	" Screws, . . .	340, 341		
Water Cart Body, . . .	589	Windows, Cast Iron, . . .	144	" Stains, . . .	266		
Water Joint Hinges, . . .	269	" Stained Glass, . . .	525	" Table Legs, . . .	319		
" Paint, . . .	275	" Ventilating, . . .	110, 177	" Workers' Vice, . . .	105		
" Proof Paper, . . .	136, 140	Wrought Iron, . . .	517	Wool Mops, . . .	281		
" Tubes and Fittings, . . .	277	" "Winsor" Pig Troughs, . . .	311	Worm Screws, . . .	115		
Waters' R.R., . . .	128	Wipe Frames, . . .	161	Writers' Pencils, . . .	285		
Watertight Glazing, . . .	279	Winn's Cistern, . . .	417	Wrought Fencing and Gates and Railings, . . .	508 to 516		
Wax, . . .	182	" Balloons, . . .	457	" Iron Casements, . . .	440 to 443		
Weather Vanes, . . .	106	" Brushes, . . .	281, 286, 288, 290	" Gratings, . . .	471		
Wedges, . . .	259	" Fencing, . . .	341, 416	" Hinges, . . .	389		
Well Pumps, . . .	259	" Gauze, . . .	107	" Hurdles, . . .	513		
" Rods, . . .	410	" Iron, . . .	344	" Nails, . . .	342		
Weston's Pulley Blocks, . . .	593	" Lattice, . . .	417	" Portable Copper, . . .	177		
Wheels, Barrow and Truck, . . .	109	" Letter Cases, . . .	412	" Sashes, . . .	342		
" Rubbish, . . .	151	" Mats, . . .	312	" Spikes, . . .	112		
Wheel Valves, . . .	279	" Nails, . . .	415	" Steam Tubes, . . .	112		
Wheen's Axle Grease, . . .	446	" Netting, . . .	415	" Tubes and Fittings, . . .	112		
White Enamelled Letters, . . .							



# The "HUE" Adaptable Barless Fire

Patent No. . . . 23223.

Regd. No. . . . 573515.

A FEW OUT OF HUNDREDS OF  
UNSOLICITED TESTIMONIALS  
ARE QUOTED AT PAGE 32 .



## Heat . . . Utility . . Economy

---

---

SHOWING THE APPLICATION OF THE  
LATEST AND MOST ECONOMICAL  
BARLESS FIRE TO EXISTING STOVES.

*Also:*

AS A COMPLETE FIREPLACE FOR PUBLIC  
INSTITUTIONS, HOTELS, MANSIONS,  
✻ ✻ BUNGALOWS AND COTTAGES. ✻ ✻

---

---

# The "HUE" Barless Fire

(REGD & PATD.)



## Its Adaptability and Special Features

Heat  
Utility  
Economy



It is now admitted generally that a fire low down on the hearth without the obstruction of bars is calculated to produce a more *healthy, natural, cheerful and economical fire* than the usual form of stove (with front bars and bottom) which holds the fuel quite near the chimney, thus allowing wastefully - a very large proportion of the heat generated to escape unused.

Barless  
Fires

¶ Many of the barless stoves on the market at the present time are admittedly fuel-savers, and practically attain the end for which they are designed, but the price in some cases is prohibitive when it is taken into consideration that in the majority of instances before they can be adopted it is necessary to remove the existing chimney piece, frequently injuring same in doing so, scrap the stove, and, in addition, entail the cost of labour and inconvenience, very often no inconsiderable item.

Special  
Feature

¶ The "HUE" Adaptable Fire is designed to give the purchaser all the advantages of a barless fire without the disadvantages mentioned in the last paragraph.

Why it  
always fits

¶ It is manufactured specially to *suit the base area of existing grates*; all that is necessary is to supply a paper template of existing bottom of gratings, with order, to ensure a perfect fit.

Cleanliness

¶ This Fire, moreover, is absolutely clean in use, any small quantity of ash finding its way into specially constructed closed pan under bottom grate. Being portable, this pan can be removed and emptied without dust or inconvenience.

Where it  
excels

¶ For Hotels, Offices, Waiting Rooms and Dwelling Houses, where a bright and economical fire is required at a minimum of expense and inconvenience, the "HUE" fills the need perfectly.

Minimum  
of attention

¶ The Fire will burn from three to four hours without attention.

## The Adaptability of the "HUE"

### Deflecting Back Bricks

¶ In instances where existing grates possess very shallow fires, *i.e.*, under 8 inches from back to front, *we very strongly recommend* that our special heavy brick backs for deflecting the heat be used. The iron backs in the majority of instances can be removed easily, and the new bricks, which are constructed in two sections, inserted quite readily, without taking out the existing stove or touching the mantel piece and surroundings. *The improvement more than warrants the extra outlay.* These remarks also apply where the Fire Brick Back and Sides of grates may be burned through and useless.

### How to Order

¶ When it is decided to fit bricks it is only necessary when ordering to state width of fire. The "HUE" is *stocked* in sizes shown on page 14, but where it is undesirable to remove the back and sides a template of the existing bottom grating should be taken and sent us, when a "HUE" Fire is specially cast to suit. Seven days are required for this operation.


### Section showing Details



- A Solid Deflecting Back Brick  
in two parts
- B Tiled Front.
- C Filling.
- D Brickwork.
- E Glazed Faience Curb.
- F Wood Mantel.
- G "HUE" Fire Basket.
- H Tile Hearth.

# The "HUE" Fire and its Adaptability

THE illustrations on this page will probably be more convincing than pages of letterpress, and the many testimonials received confirm all the advantages claimed for the "HUE" in use.




No. 1. Photograph of old style of Register Grate.

In a recent careful test for 13½ hours this type of stove burned 74 lbs. of Household Coal against 32 lbs. consumed by the "HUE" to produce equal heat.

A Booklet giving a few out of hundreds of unsolicited Testimonials received will be gladly forwarded upon application.

A 24-inch "HUE" Fire was successfully adapted to the very large Register Grate shown. The accompanying testimonial speaks for itself with regard to the alteration. (No Back Bricks were necessary here).



No. 2. The same grate (old bottom and bars shown at side) after "HUE" Fire had been placed in position.

*Fire bright with radiating heat giving full results of fuel. Warming the room and not the chimney.*

87 The Grove, Stratford, Essex.  
January 10, 1911.

Gentlemen,  
I have pleasure in testifying to the excellent results obtained from the 24 inch "Hue" Barless Hearth Fire which has been fitted for me in my private room at my office here. The room is a large one and previously to consulting you I had been unable to secure any comfort or warmth from the old-fashioned grate which existed, the heat from which, notwithstanding a huge consumption of coal, was entirely dispersed in the chimney instead of my room. Since, however, your "Hue" Barless Hearth Fire has been fixed I have obtained a considerable amount of heat and radiation therefrom with about half the consumption of coal.  
The cost of fixing the "Hue" Barless Hearth Fire, I observe from the account, is quite nominal and, when this and the benefits derived from adopting it are known, I predict for your Company a large increase of business.

Yours faithfully,


S. R. PRESTON-HILLARY.

Messrs. Young & Marten, Ltd.,  
1, 3 & 5 Romford Rd., Stratford, L.

The fire is easily kindled, but in order to stimulate same at the start it is an advantage to open the air regulator or pull forward the fret for a few minutes. There is no need to stir the fuel, which will burn steadily from three to five hours without attention, the sloping sides automatically pushing forward the unconsumed fuel until the whole becomes a glowing mass giving out an intense heat.



No. 1. An Ordinary Tile Grate.



No. 2. The same Grate modernized in less than thirty minutes, the old back being in a good state of repair.

# The "HUE" Adaptable Fire

(REGD. & PATD.)



## Modified Pattern for Grates possessing Shallow Fires

**T**HIS form of "Hue" fire, which will be found as satisfactory in working as the earlier model, enables us to supply a thoroughly efficient barless grate to the more modern tile grates and mantel registers, without the necessity or expense of special bricks; a paper pattern of existing bottom grate is all that is necessary to enable us to make a "Hue," which stands on the hearth in the space previously occupied by the bottom grating and bars.


From the price list appended it will be seen that this appliance is within the reach of all, and when it is borne in mind that a very considerable saving in fuel is effected, together with increased cheerfulness and heat in the room, a large demand is sure to result when the "Hue" becomes better known.

The ash pan we supply is a safeguard against fire and obviates the necessity of a specially prepared hearth.

As will be seen in illustration No. 1, the full depth of fire space is utilised for fuel, and the sides and back of existing stove form three sides of the fire basket as shown in Fig. 2.



**H**eat  
**U**tility  
**E**conomy



HOW TO TAKE DIMENSIONS OR TEMPLATE.

When the space C is from six to eight inches there is no need to take back away; the new pattern "Hue" answers the purpose admirably.

Fires of greater depth would be fitted with the original "Hue."

With fires less than six inches at C it is *absolutely necessary* to have our Deflecting Bricks after removing back of existing grate.

**In cases where very great heat is required we unhesitatingly advise Deflecting Bricks being used.**

# Bracket Trivet Tables to suit "HUE" Fires



No. R 6180.



No. R 6181.

	Width,	12, 14	15	16, 17, 18	20	22	24	26, 28 inches.
No. R 6180.	All Berlin Black Finish,	6 9	7 9	8 6	9 6	10 3	11 -	18/- each.
No. R 6181.	Armour Bright Finish,	8 6	9 6	10 3	12 -	12 9	13 6	21 - „
No. R 6182.	Berlin Black Legs, Brass Covered Top, . . . . .	15 -	15 9	16 6	17 3	18 -	18 9	25 6 „
No. R 6183.	Berlin Black Legs, Copper Covered Top, . . . . .	17 3	18 -	18 9	20 3	21 9	23 3	28 6 „




No. R 6182.



No. R 6183

## The "HUE" Fireside Companion

Complete with Tongs  
and Pokerette.



No. R 6161.	Price Each.
Berlin Black with Brass Mounts, . . . .	15 9
No. R 6162.	
Berlin Black with Copper Mounts, . . . .	15 9
No. R 6163.	
All Polished Brass, . . . . .	21/-
No. R 6164.	
All Polished Copper, . . . . .	24 -

# **“HUE” INTERIORS**

## **The “Belgrave”**



No. R 6187. Ground and Berlin Black Finish with Fixed Canopy, complete with 18-inch Berlin Black Finish “HUE” Fire and Solid Brick Back in two parts.

22 inches wide by 38 inches high,  
**49/6**


Berlin Black Finish Trivet Table to suit, .. .. extra **8/6**

## **The “Buckingham”**

No. R 6184. Ground and Berlin Black Finish with Adjustable Iron Canopy, complete with 18-inch Berlin Black Finish “HUE” Fire and Solid Back Brick in two parts.

22 inches wide by 38 inches high,  
**52/-**

Berlin Black Finish Trivet Table to suit, .. .. extra **8/6**





# “HUE” SUITES

## The “Nelmes”



No. R6357. Fine Cast and Painted Mantel Register with Adjustable Canopy. Double Shelf complete with Fine Cast and Blacked “HUE” Fire and Full Back Brick in two parts.

Width,	24	30 ins.
Height,	48	48 "
Shelf,	32 x 6	38 x 6 "
Fire,	12	14 "

	£	s.	d.	£	s.	d.
Hearth 3 x 3 Plain Enamelled	2	0	6	2	5	0
Tiles, .. ..	6	0		7	6	
	£2	6	6	£2	12	6

No. R2214. Fine Cast and Blacked Curb, .. 12/- each.

Bracket Trivet Tables to suit above Fires, .. 6/9 ..

## The “Gidea”

### Mantel Register

No. R6358. Fine Cast and Painted one coat. Interior Blacked. Adjustable Canopy. Double Moulded Shelf, fitted with Fine Cast and Blacked “HUE” Fire and Solid Back Brick in two parts. Plain Enamelled Tiles, any color, fitted in sides.

Width,	30	36 ins.
Height,	52	52 "
Shelf,	39 6 1/2	42 x 8 "
Fire,	12	14 "

	£	s.	d.	£	s.	d.
Hearth 3 x 3 Plain Enamelled	2	11	0	3	0	0
Tiles to match,	7	6		10	6	
Complete,	£2	18	6	£3	10	6

No. R2214. Berlin Black Finish Curb to suit, 15/9 each.

Bracket Trivet Table to suit above Fires, .. 6/9 ..



The above illustration represents 30 x 52 inch size.

# "HUE" SUITE



*Young & Rubicam  
Stratford, E.*

Tile Slabbed  
Fireplace  
Hearth

No. R 6675. 36 inches wide 49 inches high, in any plain color, with 14-inch Berlin Black "HUE"  
Fire and Back Bricks. Plain Oak Shelf with Moulded Edge, 12 x 6½ inches, .. .. £4 1


6 x 2 inch Tiles to match. .. .. 0 1

Complete, .. .. £5

Curb

No. R 2214. Fine Cast and Blacked, .. .. £0 1

# "HUE" SUITE




The above illustration represents a 36 x 48 inch size suite.

No. R 6360, Glazed Faience Mantel in loose blocks (any coloring), complete with Fine Cast and Blacked "HUE" Fire and Full Back Brick in two parts.

Width, ..	24	24	30	30	36	36 inches.
Height, ..	45	48	45	48	45	48 "
Fire, ..	12	12	15	15	18	18 "
	£4 4 0	£4 7 0	£4 16 0	£4 19 0	£5 5 0	£5 9 3
Hearth of Plain Enamelled Tiles cut to suit, ..	0 8 3	0 8 3	0 10 6	0 10 6	0 11 9	0 11 9
	£4 12 3	£4 15 3	£5 6 6	£5 9 6	£5 16 9	£6 1 0 per set.
Semi-circular Glazed Faience Curb cut to suit in sections, ..	£1 3 3	£1 3 3	£1 10 0	£1 10 0	£1 16 9	£1 16 9 each.


## “HUE” SUITE



Mantel  
Grate  
Tiles  
Hearth

No. R6667. Enamelled Slate in Fumed Oak Finish with Inlays; 9-inch jambs; width over jambs, 56 inches; height to top of shelf, 50 inches; moulded shelf, 62 x 10 inches, .. ..	£3 3 0
No. R6668. Berlin Black Finish with Adjustable Iron Canopy, complete with Berlin Black Finish “HUE” Fire and Solid Back Brick in two parts, .. .. .	2 8 0
Brickette Tiles in any color fitted, .. .. .	0 7 6
Plain Enamelled Tiles to match, 48 x 18 inches, .. .. .	0 15 0
	<hr/> £6 13 6 <hr/>
Canopy in Brass or Copper, .. .. . extra	£0 12 0
Slabbed Tile Curb up to 48 x 12 inches inside sizes, .. .. .	1 16 0
No. R6161. Black and Brass “HUE” Fireside Companion, .. .. .	0 15 9


## “HUE” SUITE



*Living + Morten Ltd  
Huddersfield, E.*

Mantel	No. R 6775. Fine Cast and Painted one coat, opening 38x38 inches; width over jambs, 54 inches; height to shelf, 54½ inches; double shelf, 60x9½ inches, .. .. .	£3 0 0
Interior	No. R 6376. Berlin Black Finish with fast Dome Canopy, complete with 18-inch Berlin Black Finish “HUE” Fire and Full Brick Back in two parts, .. .. .	2 14 0
Surround	Tile Slabbed to suit above in any plain color, .. .. .	1 10 0
Hearth	Tiles to match, .. .. .	0 12 0
		<hr/> £7 16 0
Curb	No. R 6377. B.B. Finish to suit above, .. .. .	£1 4 0
	Berlin Black Finish Bracket Trivet Table to suit above Fire, .. .. .	0 8 6

## “ HUE ” SUITE



*Young & Marten Ltd  
Chalfont, E.*

Mantel

Interior

Surround  
Hearth

Curb

No. R6188. Fumed Oak, width over jambs 41½ inches, height to centre shelf 47 inches, height to top shelf 60 inches, shelf 51×83 inches, .. .. .	£3 0 0
No. R6189. 15×24 inches, Ground and Berlin Black Finish, complete with 12-inch B.B. “HUE” Fire and Solid Back Brick in two parts, .. .. .	1 19 0
Tile Slabbed in 3×3 inches Antique Tiles, any coloring, .. .. .	1 19 0
3×3 inches Antique Tiles to match, .. .. .	0 10 6
	<u>£7 8 6</u>
No. R2187. Ground and Berlin Black Finish, .. .. .	£0 15 9
Ground and Berlin Black Finish Bracket Trivet Table to suit above Fire, .. .. .	0 6 9

## “ HUE ” SUITE



Mantel  
Fireplace  
Hearth


No. R6028. Fumed Oak Combination, with Bevelled Mirror,  $25\frac{1}{2} \times 18$  inches; width over jambs, 52 inches; height to middle shelf, 49 inches; height over all,  $72\frac{1}{2}$  inches, .. .. . £6 0 0

No. R6029. Flat Slabbed Tiled Surround, with arch opening in any plain color, complete with 16-inch Berlin Black Finish “HUE” Fire and Full Brick Back in two parts, .. .. . } 4 4 0

Plain Enamelled Tiles,  $6 \times 2$  inches to match, .. .. . }  
£10 4 0

If Mantel in Polished Walnut, .. .. . extra, £2 14 0  
“ “ Mahogany, .. .. . “ 3 0 0  
Faience Curb in loose sections to match color of Tiles,  $48 \times 12$  inches, .. .. . 1 19 0  
Polished Copper Fireside Set, complete with Tongs and Pokerette, .. .. . 1 4 0  
Berlin Black Finish Bracket Trivet Table to suit above Fire, .. .. . 0 8 6

## “HUE” SUITE



Mantel


Interior

Hearth

No. R6669. Fumed Oak with Double Columns to Jambs and with undershelf to Frieze; width over jambs, 55 inches; height to shelf, 52 inches; shelf, 63 x 11 inches, .. ..	£5 5 0
Slabbed Tile Surround, with Inset Tiles fitted with Berlin Black Finish Lift off Canopy, and complete with 16-inch Berlin Black Finish “HUE” Fire and Solid Back Brick in two parts, .. .. .	4 16 0
Tiles to match, with Insets, .. .. .	0 16 0
	<u>£10 17 0</u>
Canopy in Brass or Copper, .. .. . extra,	£1 5 6
Slabbed Tile Curb up to 48 x 12 inches inside sizes, .. .. .	1 16 0
No. R6162. Black and Copper “HUE” Fireside Companion, .. .. .	0 15 9



# “ HUE ” SUITE



The  
Valdori


The  
Valdori

Young & Co. Ltd.  
Stratford E.

Mantel  
Interior  
Panels  
Hearth

No. R6156. Pine Primed Combination with Compo Enrichments; Oval Bevelled Mirror, 23 x 17 inches; width over jambs, 58 inches; height to middle shelf, 50½ inches; height over all, 84 inches,	£4	17	6
No. R6157. 22 x 38 inches, Polished Brass Covered Frame, Brass Covered Adjustable Canopy, complete with 18-inch Armour Bright Finish “HUE” Fire and Brick Back in two parts,	5	11	0
Slabbed Tile Panels with Hand Painted Centre Ornament,	1	13	0
Cream Plain Enamelled Tiles to match,	0	12	0
	£12	13	6
No. R6158. All Brass Curb Suite, complete with Dogs, Fire Brasses and Stop,	£6	7	6
Armour Bright Bracket Trivet Table, Brass Covered Top, to suit above Fire,	0	18	0

# "HUE" SUITE



*Younger, Norton & Co.  
Stratford*

Mantel	No. R6514. Fumed Oak Combination Mantel and Overmantel, with Shaped Shelves and Bold Columns and Bevelled Mirror. Width over jambs, 60 inches; height to lower shelf, 45 inches; height to top shelf, 68 inches; height over all, 80 inches, .. .. .	£11 14
Interior Panels	No. R6515. 22 x 38 inches, Berlin Black Finish, with Antique Copper Canopy, 16-inch Berlin Black Finish "HUE" Fire, Solid Brick Back in two parts, and new pattern removable Front Bars, .. .. .	3 9
Hearth	Slabbed Tile Panels, as drawn, .. .. .	2 17
	In 6 x 2 inches Plain Enamelled Tiles to match, .. .. .	0 15
	Complete, .. .. .	£18 15
Curb Suite	No. R6516. Antique Copper Curb, with Electro-coppered Dogs and Implements, 48 x 12 inches inside, .. .. .	£3 15

# "HUE" SUITE



*Young & Marten Ltd  
Stratford, E.*

Mantel

Stove

Hearth

No. R6153. Fumed Oak Combination, width over jambs, 51½ inches; height to middle shelf, 47½ inches; height over all, 71 inches; top shelf, 58×9½ inches, .. .. .	£6 0 0
No. R6154. 42×40 inches, Rough Armour Bright hand worked, complete with 18-inch Armour Bright Finish "HUE" Fire and Full Brick Back in two parts, .. .. .	12 3 0
Antique Tiles in any color, .. .. .	1 1 0
	<u>£19 4 0</u>

If Mantel in Polished Walnut at 42/- extra. If Mantel in Polished Mahogany at 60/- extra.  
No. R6155. Armour Bright Finish Curb Suite, complete with Dogs, Fire Implements and Stop, £4 10 0  
Armour Bright Finish Bracket Trivet Table to suit above Fire, .. .. . 0 10 3

## "HUE" SUITE



Mantel

Stove

Hearth

No. R6150. Polished Walnut Combination, width over jambs, 56 inches; height to middle shelf, 48½ inches; height over all, 73 inches; top shelf, 65 x 10½ inches, .. .. .	£8	2	0
No. R6151. 42 x 40 inches, Rough Armour Bright, hand worked, complete with 18-inch Armour Bright Finish "HUE" Fire and Back Brick in two parts, .. .. .	12	3	0
Antique Tiles in any color, .. .. .	1	1	0
	£21	6	0

If Mantel in Fumed Oak at 42/- less. If Mantel in Polished Mahogany at 60/- extra.

No. R6152. Armour Bright Finish Curb Suite, complete with Dogs, Fire Implements, and Stop, .. .. .	£3	9	0
Armour Bright Finish Bracket Table to suit above Fire, .. .. .	0	10	3

# A Few Unsolicited Testimonials

FROM HUNDREDS RECEIVED IN REGARD TO THE "HUE" FIRE (Patent and Registered)  
IT WILL BE NOTED THAT THE WRITERS ARE ACTUAL USERS OR PRACTICAL MEN

9, 10, 11 Cursitor Street, Chancery Lane,  
London, E.C. December 1st, 1913

Messrs. YOUNG & MARTEN, LTD.  
DEAR SIR,—“As I have before had the opportunity of telling you, there is no doubt whatever, that when properly managed, these ‘Hue’ Fires are able to save quite 60% in the consumption of coal, and moreover I find they burn the cheaper class of coal even better than the more expensive drawing-room kind.  
I have myself had six of these stoves in my own house, and find that not only on the coal consumed, but also in the comparatively small amount of work required in connection with them, they are a very great boon and advantage.”  
Yours faithfully,  
MONTAGUE ATKINSON.

Tedstone Court, Worcester,  
May 14th, 1911.

“Mrs. Bellville is MOST pleased with the two drawing-room grates, and will now be obliged by Messrs. Young & Marten sending her the bill. Mrs. Bellville hopes to have some more grates later in hall, dining-room, smoking and school room.”

Tedstone Court, Worcester,  
February 10th, 1913.

“Mrs. Bellville begs to say in reply to Messrs. Young & Marten’s letter of the 4th, she will be delighted for them to make any use they like of her letter of May 14th, 1911. The two ‘Hue’ Fires she has in the drawing-room have given the GREATEST SATISFACTION, both as regards looks and burning.”

6 Lyndhurst Road, Hampstead, N.W.,  
November 18th, 1912.

Messrs. YOUNG & MARTEN, LTD.,  
1, 3, and 5 Romford Road, Stratford, E.  
GENTLEMEN,—“Having had five of your ‘Hue’ Fires put into my house last September, I feel I must write and tell you how thoroughly satisfied we are with them. We find they are in every way what you represent them to be; they give out much more heat than the fire-places we previously had, and are decidedly more economical in fuel consumption. The extra amount of heat we seem to get into the room is, I think, perhaps due to your fire-clay backs, and this, too, I think must be the reason why one of the chimneys in a top bedroom has ceased to smoke. It was not possible at one time to light the fire in that room if there was a high wind, but now it is quite satisfactory. I should like also to express our appreciation of the expeditious manner in which the work was carried out—the five Fires, including the Tiled Fire-place and Hearth of the Savoy Suite, being fitted and ready for use in a day and a half.” I am, Yours truly,  
R. SWINBURNE.

## FROM PRACTICAL DECORATORS:

70 Upton Lane, Forest Gate.  
DEAR SIR,—“We should like to say we have fitted nine ‘Hue’ Fires during the last fortnight, and we are thoroughly satisfied with them. There is a great future for these, and you are to be congratulated.  
We are sending for two more to day.”  
PAGE & GARDNER

Messrs. YOUNG & MARTEN, LTD.,  
1, 3, and 5 Romford Road, Stratford, E.

“Jesmond,” Theydon Bois, Essex  
October 23rd, 1912.

DEAR SIR,—“I have now given the ‘Hue’ Stove a good trial and am exceedingly pleased with it. Good heat and small consumption of coal. You can use my name in recommending it.”  
Yours faithfully,  
A. BURTON WALKER.

88 South Bank Road, Dury,  
January 4th, 1913.

DEAR SIR,—“I received your ‘Hue’ Grate on the 3rd inst., and I fixed it myself in a few minutes. I find that it gives out a lot more heat and it burns the coal right down into a dust. It makes our room look more cheerful, and I cannot speak too highly of it.”  
Yours truly,  
P. CLAYTON.

Queens Road, London, W.,  
27th November, 1913

Messrs. YOUNG & MARTEN  
Stratford, E.  
DEAR SIR,—“With reference to ‘Hue’ Fire sent on appro. to Mrs. Fred. Lee of Cheshire, you will be interested to know that same has arrived safely and is in use, giving every satisfaction.”  
We are, Dear Sirs,  
Yours faithfully,  
WM. WHITELEY, LTD.

Among the 8,000 Users  
of the “HUE” Fires are  
- - the following: - -

## RAILWAY COMPANIES

Great Western  
Great Central  
Great Eastern  
London and North Western  
North Eastern

## INSTITUTIONS

Three Counties Asylum (over 200 in use)  
Bucks County Asylum  
West Ham Hospital  
Several Colleges  
National Hospital for Paralyzed

## HOTELS

Beach, Littlehampton (over 25 in use)  
Albion, Manchester (over 15 in use)  
King’s, Brighton  
Old Ship, Brighton  
Metropole, Brighton  
Bournemouth Hydro  
Black Bull, Morpeth  
South Eastern, Deal  
Great Western, Paddington  
And Others

## LONDON STORES

Army and Navy Auxiliary, Westminster  
William Whiteley, Ltd., Westbourne Grove  
J. Storey & Co., High St., Kensington  
Shoolbred & Co., Ltd., Tottenham Court Road  
Tedeagars, 53 Victoria Street, S.W.

## PORT OF LONDON - - AUTHORITY - -

Unfortunately it is necessary  
to warn our friends against  
several imitations on the  
market. PLEASE INSIST  
UPON A “HUE” FIRE  
WITH NAME CAST ON.  
It is the Best and Cheapest.

5 Britannia Terrace, Saltburn-by-the-Sea,  
January 21st, 1913.

“Mrs. Hughes will be glad if Messrs. Young & Marten will send her another ‘Hue’ Fire. The one they made for her a few weeks ago is a great success. It was put into place with no dirt or trouble and gives twice as much heat as the old grate at from 1 to 1½ the amount of coal burnt. Mrs. Hughes has recommended the fire to several people, with every confidence that they will give the greatest satisfaction. The one that Mrs. Hughes now requires is a 22-inch one of the same relative dimensions and shape as the template of the 20-inch fire, which was sent as a guide to Mrs. Hughes some time ago. As this is a stock pattern, Mrs. Hughes hopes to receive it without delay. She encloses 21s. in payment.”

## AN ARCHITECT STATES:

101 Evering Road, Stoke Newington, N  
Messrs. YOUNG & MARTEN, January 10th, 1913  
DEAR SIR,—“The ‘Hue’ Fire you recently delivered to 16 Kelross Road, Highbury, was fixed with very little trouble. I have since seen it in operation, and can speak well of its warming capacity and cheerful appearance. It has in this case entirely removed the floor-draught which previously was painfully apparent. I have introduced it to the notice of many of my clients, and shall be ordering some more directly.” Yours faithfully,  
WILLIAM S. WILSON.

14 Union Court, Old Broad Street, E.C.  
November 11th, 1913.

“I am quite satisfied with the work and the increased heat it gives with very moderate consumption of fuel.”  
Yours faithfully,  
J. R. MOORE-SMITH.

## A BUILDER STATES:

“Roseville,” High Road, Ilford.  
GENTLEMEN,—“The two ‘Hue’ Fire Baskets with solid brick backs have not only modernized our old stoves, which in itself is a fact worthy of consideration in these days of advanced fashion, but we find as you stated, that we get a great deal more heat at considerably less cost. We have now had them in three weeks and are delighted with them and consequently shall be able to recommend them to our friends with the greatest confidence.”  
Yours truly,  
J. H. LANCE.

YOUNG & MARTEN, LTD.,  
1, 3, and 5 Romford Rd., Stratford, E.

Chapel Lane, Stockton Heath, Warrington.  
DEAR SIR,—“In consequence of the increased cost of coal, I felt it necessary to look round to discover a method of reducing the consumption of fuel in my own house. The adoption of a ‘Hue’ Fire has proved a wonderful economiser at a very little cost in conversion of an old-fashioned grate. Although I have only had one a few weeks, it has saved the initial cost, and its heating capabilities are wonderful.”  
Yours faithfully,  
FRANK WARBURTON.

Greenhow Hill Vicarage, Pateley Bridge,  
N. E. Railway, Yorks, Dec. 4th, 1912.

DEAR SIR,—“Your enclosures to hand with many thanks. The width of the ‘Hue’ Grate (front) is 16 inches, or a trifle over. We want you to send us Bracket Trivet Table for this ‘Hue’ Grate—‘All Herlin Black Finish.’ Will remit on receipt of account. I should also say how satisfied we are with the ‘Hue’ Grates in the two important things of much more heat in the room, and a quite appreciable saving of fuel.”  
Yours faithfully,  
S. B. PORRITT

## FROM A DECORATOR:

235 Lewisham High Road, London, S.E.  
Messrs. YOUNG & MARTEN, Sept. 25, 1913.  
Stratford

DEAR SIR,—“Enclosed please find order for 2 ‘Hue’ Fire Baskets. I am pleased to inform you I have now fitted 21 of these Stoves in the neighbourhood, and in every case they are giving entire satisfaction. My customers are recommending them to their friends, and I look forward to having a good season with these Fires. Can you supply me with another hundred Booklets?”  
I remain Yours truly,  
A. W. OUNSTED.


Black Bull Hotel, Morpeth,  
February 6th, 1913.

GENTLEMEN,—“Re yours of 4th. You are at liberty to print my remarks re your ‘Hue’ Fire. It has given every satisfaction—a great saver in fuel and throws out the heat INTO the room. Without a doubt it is decidedly in front of the ordinary Bar Grate Fire.”  
Yours faithfully,  
J. CLARK.

166 Broomhall Street,  
Sheffield, October 1, 1913.

“I have fixed one of your fires in my own home, and the result has been highly satisfactory; in fact in the first six months it has saved itself in coal; so I can do nothing else but recommend them.”  
Yours truly,  
GEORGE A. SIMPSON

Sunny Corner, Hornsea, E. Yorks.  
DEAR SIR,—“Certainly you may use my remarks praising your Grate which is a little treasure. I have told many people of it, and have been the means of their getting them, and only last month my mother put two in for a tenant in one house.”  
Yours truly,  
M. WALLIS.



The  
Combination  
Suite

## Wood Mantel


## Interior

## Slabs

## Hearth

## Curb Suite

No. R 6672. White Primed Combination Mantel and Overmantel, with Circular Bevelled Mirror 18 inches diameter; width over jambs, 54 inches; height to top shelf, 50 inches; height over all, 76 inches, .. .. .	£11 14 0
No. R 6665. 21 inches wide x 38 inches high x 16 inches fire. Ground and Berlin Black Superior Finish, Full Brass Adjustable Canopy, Solid Brick Back, Convertible Fall Bar Fire, with Brass Vase Knobs and Ashes Fret, .. .. .	2 2 9
No. RP 253. Dull surface, with Hand-painted Decoration, .. .. .	2 2 0
Tiles to match, .. .. .	1 2 6
Complete, .. .. .	£17 1 3
No. R 6528. Polished Brass, complete, with Dogs, Implements, and Stop, .. .. .	£5 11 0



# Mantel Interior Surround Hearth

No. R 5592. Pine Primed ; width over jambs, 54 inches ; height over all, 84 $\frac{1}{2}$ inches ; height to shelf, 54 $\frac{1}{2}$ inches ; Shelf, 64 inches, .. .. .	£2 5 0
No. R 5582. Ground and Berlin Blacked, Movable Canopy, Brass Ornaments, Full Brick Back in sections, .. .. .	3 15 0
Tile Surround, with Hobs Slabbed, .. .. .	7 4 0
To match Tile Surround, .. .. .	1 7 0
Complete, .. .. .	£14 11 0
Overmantel, as shown, Pine Primed, .. .. . extra	£1 19 0
" " Polished Walnut, .. .. .	1 19 0
If Mantel in Polished Walnut, .. .. .	2 2 0
No. R 5917. Black and Copper, 48 x 12 inches inside, .. .. .	3 15 0

## Curb Suite



The  
"Boscombe"  
Suite

Mantel  
Interior  
Panels  
Hearth

Curb Suite

No. R5955. Pine Primed Combination, with Overmantel fitted with Shaped Bevelled Mirror; width over jambs, 54½ inches; height to centre shelf, 50 inches; height over all, 78½ inches, ..	£9 15 0
No. R6370. 22 x 38 inches, Ground and Berlin Black Finish, with Full Brass Adjustable Canopy, Section Brick Back, Barless Fire, with Brick Front, Ashes Pan fitted to Fret, 17-inch Fire, ..	2 2 1
Slabbed Tiles, as drawn, with Hand-decorated Centre, .. .. .	1 17 6
Plain Enamelled Tiles to match, .. .. .	1 1 0
Complete, .. .. .	£14 15 7
No. R6172. All Polished Brass, complete, with Implements; 48 x 12 inches inside size, .. ..	£5 15 6





The  
Hearth  
Suite

The  
Hearth  
Suite

Mantel

No. R 6065. Pine Primed Combination Mantel and Overmantel, fitted with Three Bevelled Mirrors—  
centre, 25 x 14½ inches; two sides, 14½ x 8½ inches—with Enrichments and Mouldings; width  
over all, 55½ inches; height to shelf, 49 inches; height over all, 78 inches, .. .. £7 5 6

Grate

No. R 6066. 38 x 38 inches; Ground and Berlin Black Finish, with Full Brass Adjustable Canopy;  
Section Brick Back; Barless Fire, with Knobs and Brick to front, and Ashes Fret, .. .. 2 11 9

Tiles

Tiles fitted as drawn, .. .. 0 7 6


Hearth

Plain Enamelled Tiles, to match, .. .. 0 15 0

Complete, .. .. £10 19 9

Curb Suite

No. R 6045. Polished Brass, complete with Implements, 48 x 12 inches inside, .. .. £2 11 0



The  
Curb Suite

Mantel  
Interior


Panels  
Hearth

Overmantel

Curb Suite

No. R6550. Polished Walnut: width over jambs, 54 inches: height to shelf, 52½ inches: shelf, 61 x 11½ inches, .. .. .	£5 5 0
No. R6551. 22 inches wide x 38 inches high. Superior Finish Ground and Berlin Black; Antique Copper Adjustable Canopy; Barless Fire, with Brick at Front, and Ashes Fret; Stool Bottom Grating; Solid Brick Back, .. .. .	2 5 0
No. R6552. Slabbed Tile Hobs. in any plain color, .. .. .	3 15 0
6 x 2 inches Plain Enamelled Tiles to match, .. .. .	0 15 0
Complete, .. .. .	£12 0 0
54 inches wide x 30 inches high, with 24 x 21 inches Bevelled Mirror as drawn, in Polished Walnut, 101/- extra. If Mantel in Fumed Oak, at 21/- less. If Overmantel in Fumed Oak, at 12/- less.	
No. R6067. Antique Copper, with Dogs, Stop and Fire Irons in Armour Bright, 48 x 12 inches inside, .. .. .	£3 15 0

The  
Clifton  
Suite



Mantel

Interior

Surround  
Hearth

Overmantel

Curb

No. R6197. Pine Primed, with Bold Carved Trusses; width over jambs, 58 inches; height to top of shelf, 53 inches; shelf, 63½ × 10 inches, .. .. .	£3 9 0
No. R6370. 19 × 30 inches, Ground and Berlin Black Super Finish, Fixed Brass Canopy, Barless Fire, with Ashes Pan and Trivet Table on Brass Spindles, 15-inch Fire, Section Brick Back, .. .. .	2 11 0
Slabbed in one piece of 3 × 3 inch Dull Surface Tiles, any color, .. .. .	2 8 0
Tiles to match in 3 × 3 inches, .. .. .	1 1 0
Complete, .. .. .	£9 9 0
Pine Primed Overmantel, with Carved Ornaments and Brackets; Circle Bevelled Mirror, 24½ inches diameter, .. .. .	£4 10 0
No. R5981. All Brass Curb Suite, 48 × 12 inches inside, .. .. .	6 10 6

The  
"Fitzjohn"  
Suite



The  
"Fitzjohn"  
Suite

## Mantel

No. R6026. Pine Primed Combination Mantel and Overmantel, with Columns and Compo Enrichments; Oval Bevelled Mirror, 20 x 15 inches; width over jambs, 52½ inches; height to middle shelf, 45 inches; height over all, 78 inches, .. .. . £3 15 0

## Interior

No. R6027. 22 inches wide by 38 inches high. Ground and Berlin Black Finish Interior, with Full Brass Adjustable Canopy, Barless Fire, Section Brick Back, .. .. . 2 5 0

## Panels

Slabbed Tile Panels, Hand-painted design on cream ground, .. .. . 1 19 0

## Hearth

Tile Hearth, 48 x 18 inches; Cream Plain Enamel Tiles, .. .. . 0 13 6

Complete, .. .. . £8 12 6

## Curb

No. R6040. Brass Curb Suite, 48 x 12 inches inside, .. .. . £3 12 0



Mantel


Interior

Panels

Hearth

Curb Suite

No. R 6674. Combination Mantel and Overmantel. White Primed, with $34\frac{1}{2} \times 15$ inches shaped Bevelled Mirror; width over jambs, 50 inches; height to mantel shelf, 55 inches; height over all, 84 inches; Shelf, $59 \times 10$ inches, .. .. .										£3	9	0
No. R 6664. 21 inches wide $\times$ 38 inches high. Ground and Berlin Black Finish, Section Brick Back, Vertical Steel Bars, Full Brass or Copper Adjustable Canopy, Vase Knobs on Bars, .. .. .										1	17	10½
Slabbed Tiles with Decorated Centre, as drawn, .. .. .										0	18	9
6 $\times$ 6 inch Decorated Tiles to match, .. .. .										0	15	0
Complete, .. .. .										£7	0	7½
No. R 6700. Ground and Berlin Black Finish, with Cast Brass or Copper Ornaments, $48 \times 12$ inches inside, .. .. .										£2	11	9



Mantel  
Interior  
Panels  
Hearth

Overmantel  
Curb Suite

No. R 5338. Pine Primed ; width over jambs, 51 inches ; height to shelf, 51½ inches ; shelf, 60 inches,	£2 5 0
No. R 5380. 22 38 inches. Ground and Berlin Black Finish. Adjustable Canopy, fitted with Brass or Copper Panel, Section Brick Back, Barless Fire, with Ashes Prett, .. .. .	1 14 0
Slabbed Panels, with Decorated Centre, as drawn, .. .. .	1 10 0
6 x 3 inch Plain Enamelled Tiles to match. .. .. .	0 15 0
Complete, .. .. .	£6 4 0
Pine Primed, 52 inches wide x 32 inches high, with 25 18 inch beveled Mirror, .. .. .	£1 16 0
No. R 6711. Berlin Black, with Brass or Copper Ornaments, 48 x 12 inches inside size, .. .. .	2 5 0
EXTRAS—Mantel in Fumed Oak, .. £1 7 0	EXTRAS—Overmantel in Fumed Oak, .. £0 15 0
„ „ Polished Walnut, .. 2 15 0	„ „ Polished Walnut, 1 10 0
„ „ „ Mahogany, 3 3 0	„ „ „ Mahogany, 1 12 0



Mantel

No. R 5945. Pine Primed Combination Mantel and Overmantel, with Bevelled Mirror; width over jambs, 52 inches; height to centre shelf, 44 inches; height over all, 65 inches, .. .. £2 2 0

Grate

No. R 6379. 38 x 38 inches; Ground and Berlin Black Finish; Adjustable Canopy, fitted with Brass or Copper Panel; Convertible Fall Bar Fire, with Ashes Fret; Section Brick Back, .. 1 16 9

Tiles

Panel Tiles, fitted as drawn, .. .. . 0 6 0

Hearth

48 x 18 inches, in 6 x 6 inch Decorated Tiles to match, .. .. . 0 12 0

Complete, .. .. . £4 16 9

If Mantel and Overmantel in Fumed Oak, .. .. . extra, £0 13 6

Curb

No. R 6045. Curb Suite in Polished Brass. 48 x 12 inches inside, .. .. . 2 11 0



Mantel

Interior

Panels

Hearth

Overmantel

Curb

No. R5548. Iron. Fine Cast and Painted one coat; width over jambs, 53 inches; height to shelf, 56 inches; double moulded shelf, 59 9 inches, .. .. . £2 6 6

No. R5900. 21 x 38 inches Berlin Black Finish; Adjustable Canopy Full Brass; Section Back; Heavy Convertible Fall Bar Fire. and Ashes Eject. .. .. . 1 18 7½

Slabbed Tile Panels, as drawn, .. .. . 0 18 9

48 x 18 inches, in 6 x 6 inch Decorated Tiles to match, .. .. . 0 15 0

Complete, .. .. . £5 18 10½

Fine Cast and Painted as drawn, 46½ inches wide, 21 inches high, with Bevelled Mirror, 24 x 12 inches, .. .. . £1 10 0

No. R6722. Curb Suite in Polished Brass, 48 x 12 inches inside, .. .. . 3 7 6





Mantel

Grate

Panels

Hearth

Overmantel  
Curb

No. R 5549. Fine Cast-iron Mantel: jambs, 8 inches wide; lintel, 15½ inches deep; opening 37½ x 37½ inches; double shelf, 60 x 9 inches, .. .. .	£2 0 6
No. R 6030. 38 x 38 inches, Ground and Berlin Black Finish, with Full Brass Adjustable Canopy, Barless Fire, with Brick at Front, Ashes Fret, fitted with Sliding Vent, and Ashes Pan, 17-inch Fire, Section Brick Back, .. .. .	1 18 3
30 x 6 inches, Hand-painted Green and Gold Decoration, as drawn, .. .. .	0 10 6
Plain Cream Tiles to match, 48 x 18 inches, .. .. .	0 13 6
Complete, .. .. .	£5 2 9
Fine Cast Iron, 57 inches wide by 33 inches high, with Oval Bevelled Mirror, 26 x 15 inches, ..	£1 19 0
No. R 6040. All Brass Curb Suite, 48 x 12 inches inside, .. .. .	3 12 0




Mantel  
Grate  
Tiles  
Hearth

No. R5591. Pine Primed, with Leaded Glass Door to Cupboard, and with Pediment. Width over jambs, 50 inches; height over all, 62½ inches; shelf, 53 inches, .. .. .	£2 11 0
No. R6068. Pine Cast and Blacked Hob Register, with Adjustable Canopy; Section Brick Back; Vertical Bars and Ash Fret, .. .. .	2 0 6
Panel Tiles as drawn, .. .. .	0 7 6
6 x 6 inch Decorated Tiles to match, .. .. .	0 15 0
Complete, .. .. .	£5 14 0
Mantel in Fumed Oak, .. .. .	18/- extra.
.. Polished Walnut, .. .. .	27/- ..
Grate in Berlin Black Finish, .. .. .	7/6 ..
No. R5920. Berlin Black Finish, .. .. .	15/- each.

Curb

## The "Amesbury" Suite



### Mantel

No. R6199 Pine Primed, with elaborate Compo Enrichments; width over jambs, 59 inches; height to top of shelf, 53 inches; shelf, 66 x 10 $\frac{1}{2}$  inches, .. .. . £2 17 0

### Interior

No. R6371. 22 x 38 inches, Ground and Berlin Black Finish, Brass Adjustable Canopy, Fall Bar Fire with Brass Knobs, Section Brick Back, 16-inch Fire, .. .. . 2 0 1 $\frac{1}{2}$

### Panels

Slabbed Tiles, Green and Gold Decoration on Cream Ground, .. .. . 1 1 0

### Hearth

6 x 6 inch Tiles, decorated to match, 48 x 18 inches, .. .. . 0 15 0

Complete, .. .. . £6 13 1 $\frac{1}{2}$

### Curb

No. R6043. All Brass Curb Suite, 48 x 12 inches inside, .. .. . £2 17 0

# The "New Maisonette" Suite

COMBINED COOKING RANGE AND INTERIOR STOVE.



Mantel  
Grate  
Hearth

No. R6364. Fine Cast Iron, 46 inches wide over jambs, 57 inches high to top of shelf; shelf, 56½ x 9 inches; ground on top; opening, 36 or 38 inches wide x 38 inches high, .. ..	£2 3 6
No. R6365. Fine Cast and Blacked, with Adjustable Canopy; Full Brick Back; wrought-iron oven, 15 inches wide x 17 inches high 16 inches deep; hot closet, with swing door over oven, 17 inches wide 9 inches high x 12 inches deep. Bright Polished Dish Rest to oven and fire, .. ..	5 3 6
6x3 inch White Glazed Tiles, .. ..	0 9 0
Complete, .. ..	£7 16 0

Curb

If Wrought Welded Bath Boiler fitted in Cast-iron Flue in place of Brick Back, .. .. extra,	£2 2 0
No. R2214. Fine Cast and Blacked, .. ..	0 12 0



## The "Bertram" Suite

### Mantel

No. R 6892. Fine Cast, with Opening  
30 inches wide 42 inches high.  
Width over jambs, 38 inches.  
Height over all, 54 inches. Moulded  
Wood Shell, 45 x 8 inches. .. £1 5 0

### Interior

No. R 6898. Fine Cast and Blacked.  
18 inches wide 27 inches high, with  
Lift-off Canopy. Solid Brick Back.  
Barless Fire, with Table Front, .. 1 7 0

### Surround

Slabbed in 4 1/2 2 1/2 Plain Enamelled  
Tiles, any color, .. .. 1 10 0

### Hearth

4 1/2 2 1/2 Tiles to match, .. .. 0 10 6  
Complete, .. .. £4 12 6

### Curb

No. R 2214. Fine Cast and Blacked, £0 12 0



## The "Wigmore" Suite

### Mantel

No. R 6893. Fine Cast, with Opening  
30 inches wide x 42 inches high.  
Width over jambs, 38 inches.  
Height over all, 54 inches. Moulded  
Wood Shell, 45 x 8 inches. .. £1 5 0

### Interior

No. R 6899. Rough Bright Finish.  
18 inches wide x 30 inches high.  
Adjustable Canopy. Section Brick  
Back. Horizontal Bars and Ash  
Fret, .. .. 1 9 3

### Surround


Slabbed in 6 2 Enamelled Tiles, any  
color, .. .. 1 10 0

### Hearth

6 x 2 Tiles to match, .. .. 0 10 6  
Complete, .. .. £4 14 9

### Curb

No. R 5919. Fine Cast and Blacked, £0 9 0



*Young & Marten Ltd  
Shropshire, E*

## The "St. Margarets" Suite

### Mantel

No. R 6890. Fumed Oak, with shaped under-shelf. Width over jambs, 30 inches. Height to top shelf, 63 inches. Top Shelf, 45 inches. Opening, 29½ inches. 41½ inches. £3 9 0

### Interior

No. R 6807. Ground and Berlin Black Finish. 18 inches wide 30 inches high. Antique Copper Adjustable Canopy. Section Brick Back. Barless Fire with Brick Front. Ashes Pan fitted to Fire. 15 inch Fire. 2 2 1½

### Surround

Slabbed Tiles in any color. Plain Enamels. 1 10 0

### Hearth

Tiles to match. 0 10 6  
Complete. £7 11 7½

### Curb

No. R 5019. Berlin Black Finish. £0 15 9

## The "St. Hilda" Suite

### Mantel

No. R 6801. Pine primed with Oval Bevelled Mirror, 22 inches. Width over jambs, 37 inches. Height over all, 72 inches. Opening, 29½ inches. 41½ inches. Top Shelf, 41 inches. 5½ inches. £2 15 6

### Interior

No. R 6918. Ground and Berlin Black Finish. 18 inches wide 30 inches high. Adjustable Iron Canopy. Section Brick back. Barless Fire with Trivet Table. 15 inch Fire. 1 9 3

### Surround


Slabbed Tiles in any color. Plain Enamels. 1 10 0

### Hearth

Tiles to match. 0 10 6  
Complete. £6 5 3

### Curb

No. R 2214. Berlin Black Finish. 0 15 9



*Young & Marten Ltd  
Shropshire, E*



## Combination Mantel Register

Tiles  
Hearth

Curb

No. R6356. Fine Cast and Painted one coat. Interior Ground and Berlin Black Finish. Adjustable Canopy. Barless Fire and Ashes Fret. Section Brick Back. Two Heavy Moulded Wood Shelves. Width over jambs, 42 inches; height to middle shelf, 41 inches; height over all, 66½ inches; top shelf, 50½ x 8½ x 2½ inches; 16-inch Fire, .. .. .										£5 5 0
Set Tiles, fitted as drawn, any color, .. .. .										0 7 6
4½ x 2½ inch Plain Enamelled Tiles to match, .. .. .										0 12 0
Complete, .. .. .										£6 4 6
No. R2214. Cast Iron, Ground and Berlin Black Finish, .. .. .										each, £0 15 9



## Combination Mantel Register with Mirror


Tiles  
Hearth

Curb

No. R6385. Fine Cast and Painted one coat. Interior Ground and Berlin Black Finish. Adjustable Canopy. Convertible Fall Bar Fire and Ashes Fret. Section Brick Back. Two Heavy Moulded Wood Shelves. Shaped Bevelled Mirror in Lintel. Width over jambs, 42 inches; height to middle shelf, 48 inches; height over all, 68 inches; top shelf, 51 x 8½ inches; 16-inch Fire,		£6	4	6
Set Tiles fitted as drawn, any color, .. .. .		0	7	6
6 x 6 inch Plain Enamelled Tiles to match. .. .. .		0	12	0
Complete, .. .. .		£7	4	0
No. R2187. Cast Iron, Berlin Black Finish, .. .. .		£0	15	9



## The "Glasbury" Suite



### Mantel

No. R6198. Fumed Oak: width over jambs, 48 inches: height to centre shelf, 42 inches: height to top shelf, 56 inches: shelf, 56x10 inches, .. .. . £3 0 0

### Interior

No. R6372. 18 inches wide by 30 inches high, Ground and Berlin Black Finish, with Adjustable Canopy in Antique Copper, Barless Fire with Copper Knobs, Section Brick Back, .. .. 1 17 9

### Surround

Files Slabbed up of 3x3 inch Antique Tiles, any coloring, .. .. . 1 19 0

### Hearth

3x3 inch Antique Tiles to match, .. .. . 0 13 6

Complete, .. .. . £7 10 3

### Curb

No. R6044. Antique Copper Curb Suite, 43x12 inches inside, .. .. . £3 6 0

## The "Florence" Suite

### Mantel

No. R 502. Sicilian  
Marble; Square  
Shelf; 8 inch  
Jambs; width  
over jambs, 54  
inches; height to  
shelf, 45 inches;  
shell, 58 84  
inches, .. £1 16 0

### Grate

No. R 6003. Fine  
Cast and Blacked,  
Adjustable Can-  
opy, Solid Brick  
Back, Barless  
Fire and Ashes  
Fret, .. 1 5 10

### Tiles

Tiles and Slips as  
drawn, .. 0 7 6

### Hearth

6 6 inch Decorated  
Tiles to match, .. 0 15 0



Complete, .. £4 4 4

If Mantel with 9 inch  
Jambs, .. extra £0 3 0

If Mantel with O.G.  
Shelf, .. extra 0 3 0

### Curb

No. R 561. Sicilian  
Marble, 48 12  
inches inside, .. 1 10 0



## The "Venetian" Suite

### Mantel

No. R 481. Sicilian  
Marble, with Flutes  
and Buttons.  
O.G. Moulded Shelf.  
9 inch Jambs; width  
over jambs, 56 inches;  
height to shelf, 46  
inches; shell, 60  
94 inches, .. £2 11 0

### Grate

No. R 6508. Ground  
and Berlin Black  
Finish. Full Brass  
or Copper Adjustable  
Canopy. Convertible  
Fall Bar to Fire and  
Ashes Fret. Section  
Brick Back, .. 2 6 6

### Tiles

Panel Tiles as drawn, .. 0 7 6

### Hearth

6 6 inch Decorated  
Tiles to match, .. 0 15 0

Complete, .. £6 0 0

### Curb

If Square Edge to  
Mantel Shelf, .. less 0 3 0

No. R 562. Sicilian  
Marble, 48 12  
inches inside, .. 1 8 6

## The "Aston" Suite



### Mantel

No. R6559, Enamelled Slate, Imitation Walnut and Adams Decoration and Double Black Moulded Trusses, Moulded Shelf, 9-inch jambs, Width over jambs, 54 inches. Height to shelf, 47 inches. Shelf, 60 x 10 inches .. .. . **£2 9 6**

### Grate

No. R5540, Ground and Berlin Black Finish with Side Hobs, Adjustable Canopy, Fire Brick Cheeks, with Arch Flue Bath Boiler fitted in, Cast-iron Self-contained Flue with Patent Damper worked by single action of Canopy, .. .. . **3 9 0**

### Tiles

Decorated Panels, fitted as drawn, .. .. . **0 6 0**

### Hearth

48 x 18 inches in 6 x 6 inch Decorated Tiles, .. .. . **0 12 0**

Complete, .. .. . **£6 16 6**

Grate in Fine Cast and Blacked, .. .. . **2/6 less.**

If without Cast-iron Flue, .. .. . **8/3 ..**

### Curb

No. R6526, Ground and Berlin Black Finish Iron Curb, .. .. . **10/6 each.**

N/1002  
1375

016.621-7085-RED

# The "Bath" Suite



BALANCE SHEET	
...	...
...	...
...	...
...	...

Mantel

No. R6558. Enamelled Slate. Imitation Pollard Oak, with Gilt Incised Lines, Floral Decoration and Double Black Moulded Trusses. Moulded Shelf. 9-inch jambs. Width over jambs, 54 inches. Height to shelf, 47 inches. Shelf 60 x 10 inches. £2 11 0

Grate

No. R6380. Fine Cast and Blacked "Bath" Grate. Adjustable Canopy. Fire Buck Cheeks with Arch Flue Bath Boiler. Long Rod Damper and Frame. 36 or 38 inches wide x 30 inches high, 2 10 0

Tiles

Embossed Panels, fitted as drawn .. 0 7 6

Hearth

48 x 18 inches in 6 x 6 inch Decorated Tiles to match, .. 0 15 0  
Complete, .. £6 3 6

Grate in Berlin Black Finish, .. 2/6 extra.  
Cast-iron Self-contained Flue for Bath Boiler, .. 8/3 ..

Curb

No. R2214. Fine Cast and Blacked, .. 12/- each.

## The "Letchworth" Suite



Mantel

No. R 5542. Fine Cast; width over jambs, 52 inches; height to shelf, 54 inches; opening, 38 x 38 inches; double shelf, 62 x 9½ inches, .. .. . £1 14 0

Grate

No. R 6525. Fine Cast and Blacked; Adjustable Iron Canopy; Vertical Bars and Ashes Fret, .. .. . 1 0 5½

Tiles

Panel Tiles as drawn, .. .. . 0 7 6

Hearth


6 x 6 inch Decorated Tiles to match, .. .. . 0 15 0

Complete, .. .. . £3 16 11½


Curb

No. R 6526. Fine Cast and Blacked, .. .. . 8/3

## The "Olympic" Suite



Mantel	No. R 6670. Fine Cast Iron. Width over jambs, 53 inches. Height to shelf, 56 inches. Double shelf, 60 x 10 inches. Opening, 38 x 38 inches, ..	£1 18 3
Register	No. R 6662. 38 inches wide x 38 inches high. Ground and Berlin Black. Superior Finish. Adjustable Iron Canopy. Section Brick Back. Projecting Barless Fire. Sliding Vent and knob fitted to Fret, ..	2 1 3
Panels	Hand Decorated Panel Tiles, as drawn, ..	0 10 6
Hearth	Plain Enameled Tiles to match, ..	0 15 0
	Complete, ..	£5 5 0
Curb	No. R 6526. Ground and Berlin Black Finish, ..	16 6



Width, 42 inches; Height, 53 inches; Fire, 16 inches; Shelf, 51 x 8½ inches.

Mantel Register	No. R6344. Fine Cast and Painted one coat; Interior Blacked; Adjustable Canopy, with Brass or Copper Bead; Barless Fire, with Brick at front; Ash Fret; Solid Brick Back; Double Shelf, .. .. .	£3 7 6
Tiles Hearth	Panel Tiles, fitted as drawn, .. .. .	0 7 6
	6 x 6 inch Decorated Tiles to match, .. .. .	0 13 0
	Complete, .. .. .	£4 8 0
Curb	No. R2214. Fine Cast and Blacked, .. .. .	12/- each.



*Young, Martin & Co.  
Stratford*

Mantel  
Register  
Tiles  
Hearth  
Curb

Width, .. .. .	36	42 inches.
Height, .. .. .	54	54 ..
Fire, .. .. .	14	16 ..
Shelf, .. .. .	44 x 8	50 x 8 ..
No. R643. Fine Cast and Painted one coat; Interior Blacked; Adjustable Canopy; Convertible Fall Bar Fire, with Brass Vase Knobs; Ashes Fret; Section Brick Back: Double Shelf, .. .. .		
	£2 11 9	£3 0 0
Panel Tiles fitted as drawn, .. .. .	0 7 6	0 7 6
6 6 inch Decorated Tiles to match, .. .. .	0 11 3	0 13 0
Complete, .. .. .	£3 10 6	£4 0 6
No. R2187. Fine Cast and Blacked, .. .. .		
	12 - each.	



## The "Rayleigh" Suite



### Mantel

No. R5940. Enamelled Slate. Black Ground. Colored Panels. Incised Gilt Lines. Moulded Trusses. O.G. Moulded Shelf. 9-inch jambs. Width over jambs, 56 inches. Height to shelf, 46 inches. Shelf, 60 x 10 inches. .. .. . **£1 19 0**

### Grate

No. R5891. Ground and Berlin Black Finish. Adjustable Canopy. Section Brick Back. Barless Fire, **1 16 0**

### Tiles

30 x 6 inch Embossed Panels as drawn. .. .. . **0 7 6**

### Hearth

48 x 18 inches, in 6 x 6 inch Decorated Tiles to match, .. .. . **0 15 0**

Complete, .. .. . **£4 17 6**

It Mantel with 8-inch Jambs, .. .. . less, **2/3**

.. without gilt lines, .. .. . **2/3**

.. with Square Shelf, .. .. . **2/3**

### Curb Suite

No. R6171. Ground and Berlin Black Finish, with Brass or Copper Ornaments, .. .. . **£2 5 0**

# The "Eastwood" Suite



## Mantel

No. R 2309. Enamelled Slate. Black Ground. Colored Panels and Neckings. Square Shelf. 8-inch jambs. Width over jambs, 52 inches. Height to shelf, 46 inches. Shelf, 58 x 9 inches, .. £1 7 9

## Grate

No. R 6095. Fine Cast and Blacked. Fixed Canopy. Vertical Bars and Ashes Fret, .. 0 19 3

## Tiles

Panel Tiles as drawn, .. .. . 0 6 0

## Hearth

6 x 6 inch Decorated Tiles to match, .. .. . 0 12 0

Complete .. .. . £3 5 0


If Mantel with 9-inch Jambs, .. .. . extra, 4/6

.. .. Gold Lines, .. .. . 2 3

.. .. O.G. Shelf, .. .. . 4/6

## Curb

No. R 2175. Fine Cast and Blacked, .. .. . 6/9



## The "Bungalow" Suite

Wood  
Mantel

No. R 6673. White Primed, with  
Compo enrichments, fitted  
with Under Shelf; width over  
jambs, 52 inches; height to  
top shelf, 48½ inches; shelf,  
58 × 8 inches, .. .. £1 5 6

Grate

No. R 6361. Fine Cast and  
Blacked, with Adjustable  
Canopy and Solid Brick Back.  
38 × 38 inches, .. .. 1 5 6

Hearth

Plain Enamelled Tiles, any color, 0 12 0  
Complete, .. .. £3 3 0

Curb

Grate in Ground and Berlin  
Black Finish, .. .. extra. 7 6  
Vertical Fire Bars, .. .. 2 -  
No. R 2177. Fine Cast and  
Blacked, .. .. 6 9  
Curb Ground and Berlin Black  
Finish, .. .. extra, 2 -

## The "Barnes" Suite

Wood  
Mantel

No. R 5331. White  
Primed; width over  
jambs, 50 inches;  
height to shelf, 50½  
inches; shelf, 55½  
inches, .. .. £1 8 6

Grate

No. R 5383. 38 × 38  
inches; Berlin  
Blacked; "New  
Haverling" Grate, .. 1 6 1½

Tiles

Floral Panels as drawn, 0 6 0


Hearth

To match above, .. 0 12 0  
Complete, .. £3 12 7½

Curb Suite

No. R 5188. Black and  
Brass, 48 × 42 inches, £1 10 0





## The "Ruislip" Suite

### Mantel

No. R 6076. Pine Primed ;  
width over jambs, 47½  
inches ; height to shelf,  
50 inches ; opening,  
37½ 37½ inches ;  
shelf, 54 8½ inches, **£1 10 0**

### Grate

No. R 6077. Ground and  
Berlin Black Finish.  
Adjustable Canopy.  
Section Brick Back.  
Convertible Fall Bar  
Fire with Ashes Fret, ... **2 2 0**

### Tiles

Fitted as drawn, any color, **0 7 6**

### Hearth

To match above, 48 x 48  
inches, ... **0 15 0**

Complete, ... **£4 14 6**

Mantel in Fumed Oak at **19 6** extra

### Curb

No. 5919 Berlin Black Finish, **15 9**

## The "Heath Park" Suite

### Mantel

No. R 6078. Pine Primed,  
with Compo enrich-  
ments ; width over  
jambs, 53 inches ;  
height to shelf, 52  
inches ; shelf 57 10  
inches, ... **£1 13 0**

### Grate

No. R 5894. Berlin Black  
Finish, 38 38 inches.  
Adjustable Canopy.  
Solid Brick Back.  
Semi-Barless Fire, and  
Ashes Fret, ... **1 13 0**

### Tiles

30 x 6 inch Panel Tiles, as  
drawn, ... **0 7 6**


### Hearth


6 x 6 inch Decorated Tiles to  
match, ... **0 15 0**

Complete, ... **£4 8 6**

### Curb Suite

No. R 5884. Berlin Black  
Finish, complete with  
Dogs and Implements,  
48 12 inches inside  
size, ... **£1 7 0**





## The "Ingleby" Suite

### Mantel Register

No. R 6345. Fine Cast and Painted  
one coat. Interior Blacked.  
Section Brick Back. Adjustable  
Canopy. Barless Fire, with  
Trivet Table. Double Moulded  
Shell. 38 inches wide  
53 inches high, .. .. £2 17 9

### Tiles Hearth

Tiles fitted as drawn, .. .. 0 7 6  
To match above, .. .. 0 12 0  
Complete, .. .. £3 17 3

### Curb

No. R 2214. Fine Cast and  
Blacked, .. .. 12 - each.

## The "Hornchurch" Suite

### Mantel Register


No. R 6346. Fine Cast and Painted  
one coat. Interior Berlin Black  
Finish. Adjustable Canopy.  
Barless Fire and Ashes Fret.  
Section Brick Back. Heavy  
Moulded Shell. 36 inches wide x  
54 inches high; Fire, 16 inches;  
Shell, 42 x 7 inches. .. .. £2 15 1½


### Tiles Hearth

Tiles fitted as drawn, .. .. 0 6 0  
To match above, .. .. 0 9 0  
Complete, .. .. £3 10 1½

### Curb

No. R 2214. Berlin Black Finish, 15 9 each.





## The "Olympia" Suite

### Mantel Register

No. R6367. Fine Cast. Adjustable Canopy, Vertical Bars, and Ashes Fret. Section Brick Back. Moulded Shelf. 42 inches wide x 50 inches high; Fire 16 inches; Shelf, 49 x 8 inches, .. .. £2 9 0

### Tiles Hearth

Tile Panels, fitted as drawn, .. 0 7 6  
42 x 18 inches, in 6 x 6 inch Decorative Tiles to match above .. 0 11 3  
Complete, .. £3 7 9

### Curb

No. R2214. Iron, Fine Cast and Blacked, .. .. 12 - each.

## The "Southchurch" Suite

### Mantel Register

No. R6368. Fine Cast and Painted one coat. Interior Blacked. Adjustable Canopy. Horizontal Bars and Ashes Fret. Section Brick Back. Double Shelf. 38 inches wide x 53 inches high; Fire, 16 inches; Shelf, 47 x 6½ inches, .. .. £2 11 0

### Tiles


Plain Enamelled Tiles fitted as drawn, any color, .. .. 0 7 6

### Hearth

To match above, 42 x 18 inches, 0 11 3  
Complete, .. .. £3 9 9

### Curb

No. R2187. Iron, Fine Cast and Blacked, .. .. 12 - each.





## The "Holland Park" Suite

### Mantel Register

No. R6386. Fine Cast and Painted one coat. Interior Blacked. Adjustable Canopy. Barless Fire, with Brass or Copper Knobs, and Ashes Fret Section Brick Back. Double Moulded Shelf. 34 inches wide x 56 inches high; 15-inch Fire Shelf, 43 x 7 inches, .. .. £2 17 0

### Tiles

3 x 3 inch Plain Enamelled Tiles fitted, any color, .. .. 0 5 3

### Hearth

To match above, .. .. 0 9 0

Complete, .. .. £3 11 3

### Curb

No. R2187. Cast Iron, Berlin Black Finish, .. .. 13 6

## The "Ravenscourt" Suite

### Mantel Register

No. R6387. Fine Cast and Painted one coat. Interior Blacked. Adjustable Canopy. Barless Fire, with Ashes Fret and Trivet Table. Section Brick Back. Double Moulded Shelf. 34 inches wide x 56 inches high; 15-inch Fire Shelf, 43 x 7 inches, .. .. £3 6 0

### Tiles

3 x 3 inch Plain Enamelled Tiles fitted, any color, .. .. 0 5 3

### Hearth

To match above, .. .. 0 9 0

Complete, .. .. £4 0 3

### Curb

No. R2214. Cast Iron, Berlin Black Finish, .. .. 15 9





## The "Osterley" Suite

### Mantel Register

No. R 6069. Fine Cast and Painted one coat. Interior Blacked. Adjustable Canopy. Section Brick Back. Barless Fire and Ashes Fret. Heavy Moulded Shelf, 30 inches wide 51 inches high; 16-inch Fire; Shelf, 38 x 7 inches, .. .. £1 18 9

### Hearth

Plain Enamelled Tiles, .. .. 0 7 6  
Complete, .. .. £2 6 3

### Curb

No. R 2214. Fine Cast and Blacked, .. .. 12 - each.

## The "Laleham" Suite

### Mantel Register

No. R 6075. Fine Cast and Painted one coat. Interior Blacked. Adjustable Canopy. Solid Brick Back. Barless Fire and Ashes Fret. Moulded Shelf, 31 inches wide x 53½ inches high; 12-inch Fire; Shelf, 38 x 7 inches, .. .. £2 9 6

### Tiles

Plain Enamelled Tiles, fitted as drawn, .. .. 0 6 0

### Hearth

Plain Enamelled Tiles, .. .. 0 7 6  
Complete, .. .. £3 3 0

### Curb

No. R 2187. Fine Cast and Blacked, .. .. 12 - each.





## Artistic Tiled Mantel Registers



No. R 6900. **THE "MILNER"**

Section Brick Back. Adjustable Iron Canopy.  
Barless Fire, with Trivet Table and Ash Fret.  
Double Shelf. Profile, 4 inches. Painted one  
coat.

Width,	..	..	43 inches.
Height,	..	..	57 ..
Fire	..	..	15 ..
Double Shelf,	..	..	49½ x 7 ..

Price, without Tiles,	..	..	<b>76/6</b> each.
Set Tiles fitted,	..	..	<b>7/6</b>

Complete, .. .. **84/** each.


No. R 6911. **THE "IVYBRIDGE"**

Section Brick Back. Polished Satin or Antique  
Brass or Copper Frieze Hood. Barless Fire,  
with Trivet Table and Ash Fret. Double Shelf.  
Painted one coat.


Width,	..	..	43 inches.
Height,	..	..	55 ..
Fire,	..	..	15 ..
Double Shelf,	..	..	53 x 7½ ..

Price, without Tiles,	..	..	<b>81/-</b> each.
Set Tiles fitted,	..	..	<b>4/6</b>

Complete, .. .. **85/6** each.



## Artistic Tile Mantel Registers



No. R 6523. **THE "BEAUFOY"**

Painted one coat and Interior Blacked. Adjustable Canopy.  
Full Brick Back. New Pattern Barless Fire and  
Ashes Fret. Double Shelf.

Width, .. .. .	35 1/2 inches.
Height, .. .. .	51 ..
Shelf, .. .. .	12 0 1/2 ..
Fire, .. .. .	14 ..


Price, fitted with Buckette Tiles, as drawn,  
any color, .. .. . **60 9** each.

No. R 6524. **THE "AVEBURY"**


Painted one coat and Interior Berlin Blacked. Adjustable  
Canopy. Section Brick Back. New Pattern Barless  
Fire and Ashes Fret. Double Shelf.

Width, .. .. .	36 inches.
Height, .. .. .	50 ..
Shelf, .. .. .	44 7 1/2 ..
Fire, .. .. .	16 ..

Price, fitted with Plain Enamelled Tiles, as  
drawn, any color, .. .. . **62 3** each.



## The "Hornsea" Suite



**Mantel Register** No. R 5930. Fine Cast and Painted one coat. Interior Blacked. Brick Back in Sections. Barless Fire. Ashes Pan attached to Fret.

Width,	24	30 ins.
Height,	48	48 "
Fire,	14	16 "
Shelf,	34 x 6	36 x 6 "

Prices, .. **£2 6 6** **£2 9 6**

**Hearth** 41 x 21 in. Plain Enamelled Tiles, in any color, **0 7 6** **0 9 0**

Complete, **£2 14 0** **£2 18 6**

**Curb** No. R 2214. Fine Cast and Blacked, **12** - each.


## The "Highgate" Suite

**Mantel Register** No. R 5931. 36 inches wide, 56 inches high, 16 inches fire; shelf, 42½ x 8½ inches; Fine Cast, Painted one coat, Interior Blacked, full Brick Back, Movable Canopy, Low Fire, Ashes Pan attached to Fret, .. **£3 5 3**


**Hearth** 41 x 21 inches Plain Enamelled Tiles, in any color, .. .. **0 10 6**

Complete, **£3 15 9**

**Curb** No. R 2214. Fine Cast and Blacked, **12/-** each.



## Artistic Tile Mantel Registers



No. R 6557. **THE "OLIVIA"**


Fine Cast. Adjustable Canopy. Section Brick Back. New Pattern Bars and Ashes Fret. Double Shelf.

Width.	..	..	..	34 inches.
Height.	..	..	..	52 "
Double Shelf,	..	..	..	42 x 6 "
Fire,	..	..	..	15 "
Price, without Tiles,	..	..	..	<b>37/9½</b> each.
Set Tiles fitted,	..	..	..	<b>5/3</b>
				<hr/>
Complete,	..	..	..	<b>43/0½</b> each.


No. R 6902. **THE "TREDEGAR"**

Section Brick Back. Polished Satin or Antique Brass or Copper Frieze Hood. Barless Fire, with Trivet Table. Double Shelf. Painted one coat.

Width.	..	..	..	31 inches.
Height,	..	..	..	52 "
Double Shelf,	..	..	..	43 x 6½ "
Price, without Tiles,	..	..	..	<b>67/6</b> each.
Set Tiles fitted,	..	..	..	<b>4/6</b>
				<hr/>
Complete,	..	..	..	<b>72/-</b> each.



## Artistic Tile Mantel Registers



No. R 6903. **THE "CHARTERHOUSE"**


Section Brick Back. Adjustable Iron Canopy.  
New Pattern Bars and Ash Fret. Double Shelf.  
Painted one coat.

Width,	..	..	..	30 inches.
Height,	..	..	..	50 ..
Fire,	..	..	..	15 ..
Double Shelf,	..	..	..	39½ × 6¼ ..
Price, without Tiles,	..	..	..	<b>36/-</b> each.
Set Tiles fitted,	..	..	..	<b>5/3</b>
Complete,	..	..	..	<b>41/3</b> each.


No. R 6904. **THE "REMBRANDT"**

Section Brick Back. Adjustable Iron Canopy.  
Barless Fire, with Trivet Table. Double  
Shelf. Painted one coat.

Width,	..	..	..	30 inches.
Height,	..	..	..	50 ..
Fire,	..	..	..	15 ..
Double Shelf,	..	..	..	39½ × 6¼ ..
Price, without Tiles,	..	..	..	<b>42/-</b> each.
Set Tiles fitted,	..	..	..	<b>5/3</b>
Complete,	..	..	..	<b>47/3</b> each.



## Artistic Mantel Registers



No. R 6905. **THE "MANDEVILLE"**

Section Brick Back. Adjustable Iron Canopy.  
Cast-iron Beaded Side Panels. Barless Fire  
and Ash Fret. Double Shelf. Painted one  
coat.

Width,	..	..	..	34 inches.
Height,	..	..	..	50 "
Fire,	..	..	..	15 "
Double Shelf,	..	..	..	42×7 "
Price,	..	..	..	<b>37/1½</b> each.

No. R 6906. **THE "RICHELIEU"**

Section Brick Back. Adjustable Iron Canopy.  
Barless Fire and Ash Fret. Double Shelf.  
Painted one coat.

Width,	..	..	..	34 inches.
Height,	..	..	..	50 "
Fire,	..	..	..	15 "
Double Shelf,	..	..	..	42×7 "
Price, without Tiles,	..	..	..	<b>37/1½</b> each.
Set 4½×2½ Tiles fitted,	..	..	..	<b>5/3</b>
Complete,	..	..	..	<b>42/4½</b> each.



## The "Streatley" Suite

Mantel  
Register

No. R 6924. Fine Cast, with Adjustable Canopy. 36 inches wide 48 inches high. Fire, 16 inches. Single Shelf, 42 7 inches, .. £1 8 1½

Tiles  
Hearth

Embossed Panels as drawn, .. 0 6 0  
Tiles to match, .. 0 9 0  
Complete, .. £2 3 1½

Curb

No. R 2187. Fine Cast and Blacked Iron, .. £0 12 0



## The "Bidwell" Suite

Mantel  
Register

No. R 5959. Fine Cast, with Adjustable Canopy. Section Brick Back. 16-inch Barless Fire, with Brick Front and Ash Prol. 34 inches wide 50 inches high. Double Shelf, 42 inches 7 inches, .. £2 5 0

Tiles

3 : 3 Plain Enamelled Tiles in any shade, .. 0 6 0

Hearth

Tiles to match, .. 0 9 0  
Complete, .. £3 0 0

Curb

No. R 2214. Fine Cast and Blacked Iron, .. £0 12 0

## Artistic Tile Mantel Registers



No. R 8255. **THE "PLYMPTON"**

Fixed Canopy, with Ashes Fret.

Width, .. ..	30	36	36	inches.
Height, .. ..	44	44	46	..
Fire, .. ..	14	16	16	..
Shelf, .. ..	17 x 6	43 x 6	43 x 6	..
Prepared for Tiles, ..	<b>21/6</b>	<b>24/6</b>	<b>25/7½</b>	each.
Set Tiles fitted, ..	<b>5/3</b>	<b>5/3</b>	<b>5/3</b>	set.

Complete, .. **26/9** **29/9** **30/10½**

Adjustable Canopy, 1/6 extra.

No. R 6894. **THE "AXBRIDGE"**

Adjustable Canopy, with Ashes Fret.

Width, .. ..	30	36	42	inches.
Height, .. ..	46	46	48	..
Fire, .. ..	12	14	16	..
Shelf, .. ..	35 x 6½	43½ x 6½	50 x 7	..


Prepared for Tiles, **24/-** **27/1½** **34/10½** each.  
Set Tiles fitted, .. **5/3** **5/3** **5/3** set.

Complete, .. **29/3** **32/4½** **40/1½** each.





## Artistic Mantel Registers



No. R 6907. **THE "PHILIPPE"**

Section Brick Back. Double Shelf. New Pattern  
Barless Fire, with Ashes Fret. Painted one  
coat, and Surround Blackleaded.

Width, .. .. 34 inches.  
Height, .. .. 52 ..  
Double Shelf, .. .. 43 x 6 $\frac{1}{4}$  ..

Price, .. .. **52/9** each.


Trivet Table to Fire, .. .. **5/10 $\frac{1}{2}$**  extra.

No. R 6908. **THE "MANOEL"**

Section Brick Back. Double Shelf. Barless Fire,  
with Trivet Table and Ashes Fret. Painted  
one coat, and Frieze and Concaves Black-  
leaded.

Width, .. .. 34 inches.  
Height, .. .. 52 ..  
Double Shelf, .. .. 43 x 6 $\frac{1}{4}$  ..

Price, .. .. **60/-** each.



# Artistic Mantel Registers



No. R 6353. **THE "BURGHCLERE"**


Fine Cast and Painted one coat. Interior Blacked.  
Fixed Canopy. Solid Brick Back. Vertical Bars and  
Ashes Fret. Double Shelf.

Width,	..	..	..	..	30	36	inches.
Height,	..	..	..	..	50	52	"
Fire, ..	..	..	..	..	14	16	"
Shelf, ..	..	..	..	..	40x7	46x7	"
Prices, ..	..	..	..	..	<b>40/6</b>	<b>45</b>	each.


No. R 6513. **THE "PORCHESTER"**

Fine Cast and Painted one coat. Interior Blacked.  
Adjustable Canopy. Solid Brick Back. New Pattern  
Barless Fire, with Ashes Fret. Double Shelf.

Width,	..	..	..	..	31	inches.
Height,	..	..	..	..	53½	"
Fire, ..	..	..	..	..	14	"
Shelf, ..	..	..	..	..	38x6½	"
Price, ..	..	..	..	..	<b>49 6</b>	each.



## Artistic Mantel Registers



No. R 6909. **THE "INNSBRUCK"**


Solid Deep Brick Back. Double Shelf. Barless Fire, with  
Ashes Fret. Painted one coat.

Width,	..	..	..	25	29 inches.
Height,	..	..	..	46	51 ..
Fire,	..	..	..	12	15 ..
Double Shelf,	..	..	..	32×5 $\frac{3}{4}$	39 $\frac{1}{2}$ ×6 $\frac{1}{4}$ ..
Prices,	..	..	..	30/4 $\frac{1}{2}$	45/- each.


No. R 6910. **THE "MADISON"**

Section Brick Back. Double Shelf.  
New Pattern Barless Fire, with Ashes Fret.  
Painted one coat.

Width,	..	..	..	..	29 inches.
Height,	..	..	..	..	51 ..
Fire,	..	..	..	..	15 ..
Double Shelf,	..	..	..	..	39×6 $\frac{1}{4}$ ..
Price,	..	..	..	..	40/6 each.
Trivet Table to Fire,	..	..	..	..	5/10 $\frac{1}{2}$ extra.



# Artistic Mantel Registers



No. R 6096. **THE "ALPERTON"**

Iron Back. Double Shelf. Horizontal Bars and Ashes Fret. Painted one coat.

Width, .. .. .	25 inches.
Height, .. .. .	46 ..
Fire, .. .. .	12 ..
Double Shelf, .. .. .	32 x 5 $\frac{3}{4}$ ..
Price, .. .. .	<b>24</b> - each.

Section Brick Back. Double Shelf. Horizontal Bars and Ashes Fret.


Width, .. .. .	29 inches.
Height, .. .. .	51 ..
Fire, .. .. .	15 ..
Double Shelf, .. .. .	39 $\frac{1}{2}$ x 6 $\frac{1}{4}$ ..
Price, .. .. .	<b>36</b> / each.




No. R 6511. **THE "ONSLow"**

Solid Brick Back. Adjustable Canopy. New Pattern Bars and Ashes Fret.

Width, .. .. .	24 inches.
Height, .. .. .	46 ..
Fire, .. .. .	14 ..
Price, .. .. .	<b>27/9</b> each.



## Artistic Mantel Registers



No. R 6190. **THE "VALE"**

Adjustable Canopy, Barless Fire and Ashes Fret.

Width,	..	..	24	30	36 inches.
Height,	..	..	46	47	49 ..
Shelf,	..	..	30×5	36×6	41×7 ..
Fire,	..	..	12	15	17 ..
Prices,	..	..	19 -	22 9	27 - each.

Double Shelf, increasing  
height by 2½ inches, **2 6 3 3 3 9** extra.


Section Brick Back, **5,7½** extra.

No. R 6553. **THE "HAROLD"**


Fitted with Vertical Steel Bars, Single Shelf, and  
Brick Back.

Width,	..	..	..	24	30	36 inches.
Height,	..	..	..	41	43	46 ..
Shelf,	..	..	..	28×6	33½×6	42½×6½ ..
Fire,	..	..	..	12	14	16 ..

Prices, complete with  
Ashes Fret, .. **15 10½ 19,7½ 25,1½** each.



## Artistic Mantel Registers



No. R 6911. **THE "MORDEN"**

Iron Back. Double Shelf. Horizontal Bars and Ashes Fret.

Width,	..	..	..	24 inches.
Height,	..	..	..	43 ..
Fire,	..	..	..	12 ..
Double Shelf,	..	..	..	29½ × 4½ ..

Price, .. .. . **17/4½** each.

No. R 6512. **THE "HARRINGTON"**

Iron Back. Single Shelf. Horizontal Bars and Ashes Fret.


Width,	..	..	..	27 inches.
Height,	..	..	..	48 ..
Fire,	..	..	..	14 ..
Shelf,	..	..	..	33½ × 6 ..

Price, .. .. . **24/9** each.


If fitted with Solid Brick Back and

Barless Fire, .. .. . **9/9** extra.

Double Shelf, .. .. . **3/-** ..




## Artistic Mantel Registers



No. R 6912. **THE "ROSALIND"**

Width,	..	..	24	30	36 inches.
Height,	..	..	40	42	44 ..
Fire,	..	..	12	14	16 ..
Shelf,	..	..	31 x 5½	37 x 5½	43 x 5½ ..
Prices,	..	..	<b>13/3</b>	<b>17/-</b>	<b>21/9</b> each.

Ashes Fret, 1/1½ extra.




No. R 6168. **THE "PAULINE"**

Width,	..	..	..	24	30 inches.
Height,	..	..	..	41	42 ..
Fire,	..	..	..	12	14 ..
Shelf,	..	..	..	28 x 6	33½ x 6½ ..
Prices,	..	..	..	<b>13/6</b>	<b>17/-</b> each.

Ashes Fret, 1/1½ extra.

## Artistic Mantel Registers



No. R 5356. **THE "LOTUS"**

Width,	..	..	24	30	36 inches.
Height,	..	..	38	40	42 ..
Fire,	..	..	12	14	16 ..
Shelf,	..	..	32 x 6	38 x 6½	44 x 7 ..
Prices,	..	..	13/1½	16/6	21/4½ each.

Ashes Fret, 1/1½ extra.




No. R 6350. **THE "BARTON"**

Width,	..	24	30	36 inches.
Height,	..	39	40	42 ,
Fire,	..	12	14	16 ..
Shelf,	..	28½ x 5½	34½ x 5½	40½ x 5½ ..
Prices,	..	13/3	16/6	21/- each.

Ashes Fret, 1/3 extra.



## Artistic Mantel Registers



No. R 6912. **THE "LAUREL"**


Width at Base,	18	20	24	30	36 inches.
Height, ..	36	36	38	42	43 „
Fire, ..	10	10	12	14	14 „
Shelf, ..	24 × 4½	24 × 4½	29 × 5½	36 × 5½	41 × 6½ „
Prices, ..	<b>8/3</b>	<b>9/4½</b>	<b>11/1½</b>	<b>14/7½</b>	<b>18/7½</b> each.

No. R 5958. **THE "OAKLEAF"**

EXCELLENT VALUE.


Width, .. ..	24	30	36 inches.
Height, .. ..	40	40	42 „
Shelf, .. ..	30 × 6½	36 × 6½	42 × 7 „
Fire, .. ..	12	16	18 „
Prices, .. ..	<b>13/1½</b>	<b>16/6</b>	<b>21/4½</b> each.

Ashes Fret, **1/1½** each extra.



# Dog Grates


No. R 2295.



Brick Back to Fire. 21 ins. high × 18 ins. wide.  
Fire, 16 ins. wide × 7½ ins. deep, back.

Fine Cast, .. .. .	20/3 each.
Berlin Black, Second Finish, .. .. .	26/3 "
" " Best " .. .. .	29/6 "


No. R 6914.



Brick Back to Fire. 19½ ins. high × 19½ ins. wide. Fire, 16½ ins. wide × 7 ins. deep, back. Fitted with Brass Fret and Knobs

Fine Cast, .. .. .	51/- each.
Berlin Black, Third Finish, .. .. .	60/- "
" " Second " .. .. .	66/9 "
" " Best " .. .. .	78/- "


No. R 6915.



Brick Back to Fire. 26 ins. high × 20 ins. wide. Fire, 17 ins. wide.  
Fitted with Brass Knobs on Bars, and Brass Drop Legs.

Berlin Black, Best Finish, .. .. .	97/6 each.
Armour Bright Finish, .. .. .	120/- "

No. R 6913.




Brick Back and Sides to Fire.  
28 ins. high. Fire, 11½ ins. deep.

Width over all, .. .. .	19½	21½	23 inches.
Width of Fire, .. .. .	16	18	20 "
Berlin Black, Second Finish, .. .. .	61/6	67/6	75/- each.
" " Best " .. .. .	73/6	79/6	85/6 "
Brass Knob on top of Bars, .. .. .			3/9 extra.
Fitted with Gas Burner and Ball Asbestos Fuel, .. .. .			18/9 "

## Dwarf Interiors

No. R 6916. **THE "DELTA"**




18 ins. wide x 30 ins. high.

Adjustable Iron Canopy. Section Brick Back.  
Basket Bars and Ashes Fret.

Fine Cast and Blacked, .. .. 27/3 each.  
Ground and Berlin Black Finish, 2/- extra.  
Brass or Copper Canopy, .. .. 9/- ..

No. R 6917. **THE "EMERALD"**




18 ins. wide x 30 ins. high.

Adjustable Iron Canopy. Section Brick Back.  
Semi-barless Fire with Ashes Fret.

Fine Cast and Blacked, .. .. 23/4 each.  
Ground and Berlin Black Finish, 4/1 1/2 extra.  
Brass or Copper Canopy, .. .. 9/- ..

No. R 6918. **THE "TROPIC"**



18 ins. wide x 30 ins. high.

Adjustable Iron Canopy. Section Brick Back.  
Barless Fire with Trivet Table and Ashes  
Fret.

Ground and Berlin Black Finish, 29/3 each.  
Brass or Copper Canopy, .. .. 9/- extra.

No. R 6919. **THE "GEM"**




18 ins. wide x 30 ins. high.

Adjustable Iron Canopy. Section Brick Back.  
Convertible Fall Bar Fire and Ashes Fret.

Ground and Berlin Black Finish, 28/6 each.  
Brass or Copper Canopy, .. .. 9/- extra.  
Brass or Copper Knobs to Fire-front, 2/- ..

No. R 6920. **THE "ADAM"**



19 ins. wide x 30 ins. high.

Fixed Brass or Copper Hood Canopy, with  
Cast Ornament in centre. Section Brick  
Back. Barless Fire with Trivet Table with  
Brass or Copper Legs and with Ash Fret.

Ground and Berlin Black Finish, 56/9 each.

No. R 6921. **THE "RUBY"**




21 ins. wide x 30 ins. high

Lift-off Canopy. Section Brick Back. Barless  
Fire with Trivet Table and Ash Fret.

Black-lead Finish, .. .. 49/6 each.  
Armour-bright Finish, .. .. 4/6 extra.

# Interiors

No. R 5546. **THE "NEW DEVONSHIRE"**



Fine Cast. Adjustable Iron Canopy. Solid Brick Back. Cast Spindle Bars and Ashes Fret.

22 ins. wide x 38 ins. high x 16 ins. fire.

Price, .. 18 10½ each.


Brass Knobs, as drawn, .. 1/6 extra.

Section Brick Back, .. 2 6 ..

Steel Spindle Bars, .. 1 1½ ..

Ground and Berlin Black Finish, 4 1½ ..

No. R 6506. **THE "MARTON"**




Ground and Berlin Black Finish. Antique Copper Adjustable Canopy. Convertible Fall Bar Fire and Ashes Fret.

22 ins. wide x 38 ins. high x 18 ins. fire.

Price, .. 39 6 each.

No. R 6504 **THE "NARBORO"**




Ground and Berlin Black Finish. Adjustable Iron Canopy. Section Brick Back. Barless Fire, Ashes Fret, and Ashpan.

22 ins. wide x 38 ins. high x 16 ins. fire.

Price, .. 32 - each.

Full Brass or Copper Canopy, .. 9 - extra.

No. R 6507. **THE "KIRKSTEAD"**




Ground and Berlin Black Finish. Full Brass or Copper Canopy. Section Brick Back, Barless Fire with Ashes Pan and Trivet Table.

20 ins. wide x 38 ins. high x 16 ins. fire.

Price, .. 49 6 each.

No. R 6505. **THE "DESFORD"**




Ground and Berlin Black Finish. Adjustable Iron Canopy. Full Brick Back. Barless Fire with Brick to front, and Ashes Fret.

21 ins. wide x 38 ins. high x 16 ins. fire.

Price, .. 32 - each.

Brass or Copper Bead to Canopy, 3 9 extra.

No. R 6370. **THE "LEIGHAM"**




Ground and Berlin Black Finish. Full Brass or Copper Adjustable Canopy. Section Brick Back. Barless Fire with Brick to front. Ashes Pan and Vent fitted to Fret.

22 ins. wide x 38 ins. high x 17 ins. fire.

Price, .. 42 1½ each.

# Superior Finished Tile Registers

No. R 6508. THE "KEMSLEY"



Ground and Berlin Black Finish. Full Brass or Copper Adjustable Canopy. Section Brick Back. Convertible Fall Bar and Ashes Fret.

Width, .. .. .	36	38	40 inches.
Height, .. .. .	38	38	38 "
Fire, .. .. .	16	16	16 "

Prices, without Tiles, .. .. . **46/6** **47/7½** each.  
 Tiles fitted as drawn, .. .. . **7/6** **7/6** set.

Complete, **54/-** **55/1½**  
 Black Canopy, at 9/- less.

No. R 6066. THE "GLENWOOD"




Ground and Berlin Black Finish. Full Brass or Copper Adjustable Canopy. Section Brick Back. Barless Fire, with Brick Front fitted with Knobs and Ashes Fret.

Width, .. .. .	36	38	40 inches.
Height, .. .. .	38	38	38 "
Fire, .. .. .	17	17	17 "

Price, without Tiles, .. .. . **51/9** each.  
 Tiles fitted as drawn, .. .. . **7/6** set.

Complete, **59/3**

No. R 6509. THE "TADWORTH"



Ground and Berlin Black Finish. Full Brass or Copper Adjustable Canopy. Section Brick Back. Vertical Steel Standard Bars, with Knobs and Ashes Fret.

Width, .. .. .	36	38	40 inches.
Height, .. .. .	38	38	38 "
Fire, .. .. .	16	16	16 "

Prices, without Tiles, .. .. . **46/6** **47/7½** each.  
 Tiles fitted as drawn, .. .. . **7/6** **7/6** set.

Complete, **54/-** **55/1½**  
 Black Canopy, at 9/- less.

No. R 6510. THE "SULBY"



Ground and Berlin Black Finish. Full Brass or Copper Adjustable Canopy. Section Brick Back. Vase Knobs and Ashes Fret.


Width, .. .. .	36	38	40 inches.
Height, .. .. .	38	38	40 "
Fire, .. .. .	16	16	16 "

Prices, without Tiles, .. .. . **58/1½** **60/4½** each.  
 Tiles fitted as drawn, .. .. . **7/6** **7/6** set.

Complete, **65/7½** **67/10½**  
 Black Canopy, at 9/- less.

# Tiled Grates

No. R 6660. THE "ETHELBERT"



Fine Cast and Blacked, with Iron Adjustable Canopy, Solid Brick Back, Barless Fire, and Ashes Fret.


Width, 38 ins.; Height, 38 ins.; Fire, 16 ins.

Price, without Tiles, .. .. . 25/10½ each.  
Set Tiles fitted, as drawn. .. .. . 5/3

Complete, .. .. . 31/1½ each.

Grate Ground and Berlin Black Finish, .. .. . 10/9 extra.  
Full Brass or Copper Canopy, design as drawn. .. 9/- "

No. R 6661. THE "ATHELSTAN"




Ground and Berlin Black Finish, Iron Adjustable Canopy, Section Brick Back, Convertible Fall Bar Fire, with Ashes Fret.

Width, .. .. .	30	32	34	36	38 ins.
Height, .. .. .	36	36	36	38	38 "
Fire, .. .. .	14	14	14	17	17 "

Price, without Tiles, .. .. . 41/- each.  
Set Tiles fitted, .. .. . 7/6

Complete, .. .. . 48/6 each.

No. R 5890. THE "TREVOIR"




Ground and Berlin Black Finish, Iron Adjustable Canopy, Solid Brick Back, Convertible Fall Bar Fire, with Ashes Fret.

Width, .. .. .	36	38 ins.
Height, .. .. .	38	38 "
Fire, .. .. .	16	16 "

Price, without Tiles, .. .. . 32/3 each.  
Set Tiles fitted, .. .. . 6/-

Complete, .. .. . 38/3 each.

No. R 5891. THE "NEW SERENA"



Ground and Berlin Black Finish, Iron Adjustable Canopy, Section Brick Back, Barless Fire with Ashes Pan and Ashes Fret.

Width, .. .. .	30	32	34	36	38 ins.
Height, .. .. .	36	36	36	38	38 "
Fire, .. .. .	14½	14	16	16	16 "


Prices, without Tiles, 34/6 35/3 36/- each.  
Set Tiles fitted, .. 5/3 5/3 5/3

Complete, .. 39/9 40/6 41/3 each.

Brass or Copper Canopy, .. .. . 9/- extra.

# Tile Registers


No. R 6517. THE "OSWALD"



Fine Cast and Blacked, Fixed Canopy, Vertical Bars and Ashes Fret.


Width, .. .. .	30	32	34	36	38	ins.
Height, .. .. .	36	36	36	38	38	..
Fires, .. .. .	13	13	16	16	16	..
Prices, without Tiles,	17/7½	18/4½	18/4½	19/3	19/3	each.
Tiles, fitted as drawn,	5/3	5/3	5/3	5/3	5/3	
Complete,	22/10½	23/7½	23/7½	24/6	24/6	each.
Ground and Berlin Black Finish, ..	3/- extra.					
Adjustable Canopy, .. .. .	1/6 ..					

No. R 6519. THE "COCHRANE"



Ground and Berlin Black Finish, Adjustable Canopy, Solid Brick Back, Vertical Bars and Ashes Fret.				
Width, .. .. .	..	..	36	38 ins.
Height, .. .. .	..	..	38	38 ..
Fires, .. .. .	..	..	16	16 ..
Prices, without Tiles...	..	..	26/9 each.	
Tiles, fitted as drawn,	..	..	6 -	
Complete,			32/9 each.	
Brass or Copper Knobs fitted to Bars, 1/9 extra.				

No. R 6518. THE "COTSWOLD"



Fine Cast and Blacked, Adjustable Canopy, Vertical Bars and Ashes Fret.							
Width, .. .. .	28	30	32	34	36	38	ins.
Height, .. .. .	36	36	36	36	38	38	..
Fires, .. .. .	12	12	15	15	17	17	..
Prices, without Tiles,	19 1½	19 10½	20/9		each.		
Tiles, fitted as drawn,	5/3	5/3	5/3				
Complete,	24 4½	25 1½	26/-		each.		
Ground and Berlin Black Finish, 3/- extra.							


No. R 5384. THE "NEW RADIANT"



Ground and Berlin Black; Adjustable Canopy, fitted with Brass or Copper Panel; Section Brick Back; Vertical Bars and Ashes Fret.						
Width, .. .. .	30	32	34	36	38	Ins.
Height, .. .. .	36	36	36	38	38	..
Fires, .. .. .	14	14	16	16	16	..
Prices, without Tiles, 29 7½	30 4½			31 3		each.
Tiles, fitted as drawn, 7 6	7 6			7 6		
Complete, 37 1½	37 10½			38 9		each.
Brass or Copper Knobs fitted to Bars, 1 9 extra.						


# Hob Registers and Mantel Hob Registers

No. R 651. THE "CAMDEN"




Width, .. .. .	24	26	28	30	32	34	36 ins.
Height, .. .. .	36	36	36	36	36	36	38 "
Fires, .. .. .	10	10	10	10	12	12	12 "
Prices, Fine Cast, ..	13 1½	14 3	15 3	16 4½	17 6	18 6	19 7½ each.

No. R 3891. THE "ALMA"



Width, .. .. .	24	30	36 ins.
Height, .. .. .	41	44	45 "
Fires, .. .. .	10	10	12 "
Prices, .. .. .	21 9	27 4½	32 7½ each.


No. R 6520. THE "SLOANE"



Width, .. .. .	36	38 ins.
Height, .. .. .	48	38 "
Fires, .. .. .	17	17 "
Prices, Fine Cast, without Tiles, ..	34 7½	each.
Set Tiles fitted, .. .. .	4 6	
Complete, .. .. .	39 1½	each.

Ground and Berlin Black Finish, 6 9 extra.

No. R 6521. THE "HEPBURN"




Width, .. .. .	36	42 ins.
Height, .. .. .	46	49 "
Shelves, .. .. .	42 x 6	48 x 8 "
Fires, .. .. .	15	17 "
Prices, Fine Cast, without Tiles, ..	40 10½	50 7½ each.
Set Tiles fitted, .. .. .	4 6	
Complete, .. .. .	45 4½	55 1½ each.

If fitted with H.P. Back Boiler, no Flue, .. 23 9 extra.  
" " " and Cast-Iron Flue, 30 "



# Parsons and Kinnaird Grates

No. R 2293. PARSON GRATE



With Blower.				
Width,	18	20	22	24 inches.
Height,	36	36	36	36 "
Fire,	14	16	18	20 "
Prices, Fine Cast,	23 9	24	25 10	27 9 each.
" Berlin Black,	34 1	35 3	36 9	39 "

If with Solid Milner Brick Back, 9 9 each extra.


No. R 2390. SQUARE KINNAIRD GRATE



Very strong and heavy make of Stove, with fitted Mouldings, fitted Frame, Slow Combustion, Ashpan, Steel Spindle Bars, with Brick Back. Suitable for station waiting rooms, board schools, public offices, municipal buildings, &c.

Width,	34	36	38	40 inches.
Height,	36	38	38	40 "
Fire,	17	17	17	18 "
Price, Fine Cast,	76 6 each.			
" Berlin Black, 3rd Finish,	105 3 "			
" " " 2nd "	116 3 "			

No. R 2294. PARSON GRATE




For Tiles, at sides, "Slow Combustion," with Blower.				
Width,	33	36	38	40 inches.
Height,	36	36	36	36 "
Fire,	15	16	18	20 "
Prices, Fine Cast,	28 6	29 7	30 9	34 6 each.
" Berlin Black,	41 7	42 9	44 3	48 "

Self-colored Tiles fitted, 7 6 per set extra.

If with Solid Milner Brick Back, 9 9 each extra.

No. R 2370. SQUARE KINNAIRD GRATE




Strong Pattern, suitable for schools, public offices, &c., fitted with Brick Back, Damper, and Stool.


Width,	30	32	34	36	38	40	42 inches.
Height,	36	36	36	38	38	40	42 "
Fire,	13	15	15	17	17	19	19 "
Prices, Fine Cast,	40 6	42 9	44 3	45 9	47 3	48 6	each.
" Berlin Black, 3rd Finish,	51 7	52 6	53 3	54 9	56 3	57 9	58 6 "
" " " 2nd "	60 9	62 3	63	64 6	66 6	67 6	68 3 "

LONDON


# Dado Wall Tiling.




Price 21/- per square yard.




Price 22/6 per square yard.




Price 21/- per square yard.



Price 22/6 per square yard.



Price 21/- per square yard.




Price 22/6 per square yard.

ALL ABOVE DESIGNS IN STOCK.



# Plain Register Stoves

No. R 602. Register Stove




Width,	18	20	22	24	26	28	30	32	34	36 ins.
Height,	36	36	36	36	36	36	36	36	36	38 "
Fires,	8	10	10	12	12	14	14	14	16	16 "
Prices,	7/7½	8/6	9/3	10/1½	11/-	11/10½	12/7½	13/6	14/4½	15/3 ea.

No. R 602. Strong Register Stove



Width,	24	26	28	30	32	34	36 ins.
Height,	36	36	36	36	36	36	38 "
Fires,	12	12	14	14	16	16	16 "
Prices,	13/6	14/9	16/-	17/3	18/4½	19/6	20/3 ca.


No. R 606. Extra Strong Register Stove



Width,	30	32	34	36 ins.
Height,	36	36	36	38 "
Fires,	14	16	16	16 "
Prices,	18/-	19/6	21/-	21/9 ea.

Ashes Fret to suit, 2/- extra.

No. R 6361. Heavy Plain Register Stove  
With Solid Brick Back and Adjustable Canopy.




Width,	24	26	28	30	32	34	36	38 ins.
Height,	36	36	36	36	36	36	38	38 "
Fires,	14	14	14	14	16	16	16	16 "
Fine Cast,	14/3	15/6	16/7½	17/10½	19/-	20/3	21/4½	22/7½ ea.
Berlin Black,	21/-	22/3	23/4½	24/7½	25/9	27/-	28/1½	29/4½ "

Ashes Fret included. Vertical Fire Bars, 1/6 extra.

## "S.A.C." Ranges and Uniform Sets

No. R 701.

### New Pattern Improved "London" Cottage Range




Hob in two parts, solid round fire bars, oven on either right or left hand.

Sizes, .. ..	24	26	28	30	32	34	36 ins. wide.
Oven, inside, ..	10	10	12	12	14	14	..
Fire, .. ..	9	10	10	10	10	12	12 ..
Oven and Sham, 21/-	22/1	23/3	24/4	25/6	26/7	27/9	each.
Sizes, .. ..	28	30	32	34	36 ins. wide.		
Oven, inside, ..	10	12	14	14	14	14	..
Fire, .. ..	10	10	10	12	12	12	..
Oven and Boiler, with 1/2-in. Y.M. Tap, as drawn, }	29/3	30/4	31/6	32/7	33/9	each.	

1 in. Cast-iron Fire Pads fitted to any size Range to order only, at 3/9 extra.

No. R 702.

### Medium-weight "London" Cottage Range



Hob in two parts, bright latch and knob, bright draw fret and knob, oven on either right or left hand.


Sizes, .. ..	24	26	28	30	32	34	36 ins. wide.
Oven, inside, ..	10	10	12	12	14	14	..
Fire, .. ..	9	10	10	10	10	12	12 ..
Oven and Sham, 25/6	26/3	27/9	28/6	30/-	30/9	32/3	each.
Sizes, .. ..	28	30	32	34	36 ins. wide.		
Oven, inside, ..	10	12	14	14	14	14	..
Fire, .. ..	10	10	10	12	12	12	..
Oven and Boiler, with 1/2-in. Y.M. Tap, as drawn, }	33/9	34/6	36/-	36/9	38/3	each.	

2 in. Cast-iron Fire Pads fitted to any size Range to order only, at 3/9 extra.

No. R 703.

### New Pattern Strong "London" Cottage Range

With Bright Dish Rest to Oven and Draw Fret to Fire.




Sizes, .. ..	24	26	28	30	32	34	36 ins. wide.
Oven, inside, ..	10	12	12	14	14	16	16 ..
Fire, .. ..	8	8	10	10	10	10	10 ..
Oven and Sham, ..	30/9	34/6	35/3	37/6	39/-	40/3	42/- each.
Sizes, .. ..	28	30	32	34	36	38	40 42 ins. wide.
Oven, inside, ..	10	12	14	14	16	16	16 ..
Fire, .. ..	9	9	9	10	10	12	12 ..
Oven and Boiler, with 1/2-in. G.M. Tap, as drawn, }	39/9	42/-	45/-	48/-	49/6	51/-	52/6 54/- each.

1 in. Cast-iron Fire Pads fitted to any size Range to order only, at 3/9 extra.

No. R 6378.

### Uniform Sets



Oven on right or left hand.


Sizes, ..	30	32	33	34	36	38	42	44	45 ins. wide.
Oven, ..	10	11	12	12	13	14	15	16	17 ..
Boiler, ..	10	11	11	12	13	14	15	16	16 ..
Fire, ..	10	10	10	10	10	11	12	12	12 ..
Oven and Sham, }	24/-	24/9	26/3	27/-	28/6	32/3	36/9	46/6	48/- each.
Oven and Boiler, }	31/6	33/-	34/6	35/3	36/9	44/3	52/6	63/-	65/3, ..
Cheeks to Oven, 1/6 each.									
Trivet, 1/6 each.									
Top Dampers and Frames, 1/1 1/2 each.									

# Self-Setting Cooking Range

## THE "BELLE"

This is one of the very best self-setting and self-contained Cooking Ranges. Every part is interchangeable and easily replaced. Sliding damper in nozzle regulating fire flue and the heating of oven.

Soot plug in nozzle for cleaning purposes. Vertical lift-out fire bars. Bright dish rest to oven and fire part, the latter constructed to convey the cinders to ashes pan.



Hot Plate  
17 inches deep.

Hot Plate  
27 inches high.

Right or Left Hand Oven.

Ovens measure 12 ins. deep by 12½ ins. high by widths as under:

Width, .. ..	20	22	24	26	28	30	32	33	34	36	38	40	42 inches.
Width of Oven...	9	10	10	12	12	14	16	16	18	18	18	18	18 "
Width of Fire, ..	5	5	6	6	6	8	6	8	8	8	8	8	8 "
No. R 5538. Oven and Sham, Close Fire, .. ..	44/1½	46/3	47/3	49 10½	52 6	55 1½	56 9	57 9	58 9	60 4½	68 3	73 6	76 1½ each.
Width, .. ..					28	30	32	33	34	36	38	40	42 inches.
Width of Oven...					10	12	12	12	14	16	18	18	18 "
Width of Fire, ..					6	6	6	6	8	8	8	8	8 "
No. R 5539. Oven and Boiler with Tap. Close Fire, .. ..					60/4½	63/-	65 7½	68 3	70 10½	73 6	81 4½	86 7½	89 3 each.

Extras:—2-ft. length Sheet-iron Smoke Pipe and Smoke Plate, .. .. 20 to 30 ins., 3/- ; 32 to 42 ins., 3/9 per set.  
Open and Close Fire, .. .. .. .. .. 2/7½

											20 to 30 ins.	32 to 42 ins.
Under-front, .. .. .											3 1½	3/9
Iron Skirting all round, .. .. .											8 4½	10/6
2-ft. length Cast-iron Smoke Pipe, with Cleaning Door. .. .. .											4/3	4/3
Raising and Lowering Fire, to 8-in. fire only, .. .. .											6/3	6/3
Cast-iron Back and Ends, .. .. .											20 to 30 ins., 2/7½ ; 32 to 36 ins., 5/3 ; 38 to 42 ins., 7/10½	
Cast-iron Plate Rack and Standards, .. .. .											20 to 28 ins., 10/6 ; 30 to 36 ins., 13/1½ ; 38 to 42 ins., 15/9	
Hot Closets, .. .. .											20 to 28 ins., 13/1½ ; 30 to 36 ins., 15/9 ; 38 to 42 ins., 18/4½	


# Self-Setting Cooking Range

## THE "LARBERT"

The genuine "Larbert" Self-setting Range is so thoroughly well known as to require no description.

Great Fuel Saver.

Simple and Easy of Management.



Hot Plate  
16½ inches deep.

Hot Plate  
25 inches high.

Right or Left Hand Oven.

Ovens measure 12 ins. deep by 12 ins. high by widths as under :—

Width, .. .. .	20	22	24	26	28	30	32	33	34	36	38	42 inches.
Width of Oven, .. ..	9	10	10	12	12	14	14	14	14	16	16	16 "
Width of Fire, .. ..	5	5½	5½	5½	5½	6½	6½	6½	6½	8½	8½	8½ "
No. R 1757. Oven and Sham, Close Fire,	47/3	49/6	50/7½	53/4½	56/3	59/-	60/9	61/10½	63/-	64/7½	73/1½	81/6 each.

Width, .. .. .	28	30	32	33	34	36	38	42 inches.
Width of Oven, .. ..	10	12	12	14	14	14	16	16 "
Width of Fire, .. ..	5½	5½	5½	6½	6½	6½	8½	8½ "
No. R 1758. Oven and Boiler with Tap. Close fire, as drawn,	64/7½	67/6	70/3	73/1½	75/10½	78/9	87/1½	95/7½ each.

Extras : — 2-ft. length Sheet-Iron Smoke Pipe and Smoke Plate, .. .. 20 to 30 ins., 3/- ; 32 to 42 ins., 3/9 per set.  
Open and Close Fire. .. .. 2/7½

	20 to 30 ins.	32 to 42 ins.
Under-front, .. .. .	3/1½	3/9
Iron Skirting all round, .. .. .	8/4½	10/6
2-ft. length Cast-Iron Smoke Pipe, with Cleaning Door, Raising and Lowering Fire, .. .. .	4/3	4/3
	—	6/3
Cast-iron Back and Sides, .. .. .	20 to 30 ins., 2/7½ ; 32 to 36 ins., 5/3 :	38 to 42 ins., 7/10½
Cast-iron Plate Rack and Standards, .. .. .	20 to 28 ins., 10/6 ; 30 to 36 ins., 13/1½ ; 38 to 42 ins., 15/9	
Hot Closets, .. .. .	20 to 28 ins., 13/1½ ; 30 to 36 ins., 15/9 ; 38 to 42 ins., 18/4½	

# Self-Setting Cooking Ranges

FOR HOME AND COLONIAL USE.



## THE "DOVER"

Latest and most improved Stove in the market.

Fitted with extension hob attachable to either end of stove. Drop-down front bars and iron linings for wood, angle bars and brick linings for coal. Oven door can be opened by means of foot catch; ornamental fret under oven door lifts automatically when oven door is released to level of oven bottom. Nickel-plated nameplate and air-cooled door knobs. Feet, doors, cups, and fittings so constructed that if replacements are wanted the parts fall readily into place without any fitting. Poker, raker, and litter with each stove.

Nos.	Sizes of Hot Plate in Inches.	Sizes of Oven in Inches.	Price, each.
R 5550A	28 x 17½	13 x 12 x 8½	45/-
R 5551B	30 x 19½	15 x 14 x 8½	53 3
R 5552C	32 x 21½	17 x 16 x 9	63/-

2 feet lengths of stove pipe to suit above,  
1/6 each.

Cast-iron Side Boiler with wrought-iron U tube and draw-off tap to

No. R 5551B, 27/6 extra.

No. R 5552C, 33/- ..

When ordering say if for wood or coal fire.

## THE "RHODESIAN"

The fire is extra large and suitable for burning turf and the breast is arranged to fold, and may be used for resting fire logs. The hob is extended beyond the usual depth to suit Colonial requirements, and the fret as represented at end is interchangeable, and may be set at front or other end. Range stands 25 inches high; body, 18 inches high; hot plate, 20 inches deep; ovens, 12½ inches high by 15 inches deep by widths as specified.

### No. R 5378. Oven and Sham.

Width in Inches.	Oven in Inches.	Price, each.
30	14	85 6
36	14	93 -
42	18	114/-


### No. R 5379. Oven and Boiler.

Width in Inches.	Oven in Inches.	Price, each.
36	14	109 6
42	18	131 3

Smoke Pipe and Plate for 30 and 36 inch, 3 9:  
42 inch, 4/6 per set extra.

2-foot Cast-iron Pipe, with Cleaning Door, 4/10½ extra.  
Boilers Galvanized, .. .. 4/10½ ..  
Copper Boiler, tinned inside, .. .. 36/- ..  
Cast-iron Back and Ends, 30 and 36 inch, 13/6 ..  
Ditto for 42 inch, .. .. 15/- ..

WITH IRON-LINED FLUES.






# Self-Setting Cooking Range

OUR "DELIGHT" OPEN AND CLOSE FIRE

(REGISTERED 64477.)



Hot Plate  
16 ins. deep.

Hot Plate  
27 ins. high.

Left Hand Oven.

Ovens measure 15 inches deep by 12 inches high by widths as under:

Width, .. .. .	24	26	28	30	32	34	36	38	42 inches.
Width of Oven, .. .. .	10	12	12	14	14	14	14	16	16 "
Width of Fire, .. .. .	5½	5½	5½	6½	6½	6½	8½	8½	8½ "
No. R 1294. Oven and Sham, Open and Close Fire, ..	60/-	63/-	66/-	69/-	71/3	74/3	77/3	86/3	95/3 each.
Width, .. .. .			28	30	32	34	36	38	42 inches.
Width of Oven, .. .. .			10	12	12	14	14	16	16 "
Width of Fire, .. .. .			5½	5½	5½	6½	6½	8½	8½ "
No. R 1295. Oven and Boiler with Tap, Open and Close Fire, .. .. .			75/-	78/-	80/3	89/3	92/3	101/3	113/3 each.


Extras: -2-ft. length Sheet-iron Smoke Pipe and Smoke Plate, 24 to 30 ins., 3/-; 32 to 42 ins., 3/9 per set.

Oven right hand to order only, .. .. . 3/9

Raising and Lowering Fire, fitted to order only, from 30 ins. upwards, .. .. . 7/6

# Self-Setting Cooking Range

OUR "DELIGHT" OPEN AND CLOSE FIRE  
AND WITH HOT CLOSET FITTED.



Hot Plate  
16 ins. deep.

Hot Plate  
27 ins. high.

Left Hand Oven.

Ovens measure 15 inches deep by 12 inches high by widths as under :

Width, .. .. .	24	26	28	30	32	34	36	38	42 inches.
Width of Oven, .. .. .	10	12	12	14	14	14	14	16	16 "
Width of Fire, .. .. .	5½	5½	5½	6½	6½	6½	6½	8½	8½ "

No. R 1296. Oven and Sham, Open and Close Fire, and Hot Closet fitted, **85/6 88/6 91/6 91/10½ 94/1½ 98/1½ 100/1½ 106/6 115/6** each.

Width, .. .. .	28	30	32	34	36	38	42 inches.
Width of Oven, .. .. .	10	12	12	14	14	16	16 "
Width of Fire, .. .. .	5½	5½	5½	6½	6½	8½	8½ "

No. R 1297. Oven and Side Boiler with Brass Tap, Open and Close Fire, and Hot Closet fitted, **97/10½ 100/10½ 103/1½ 113/1½ 115/1½ 121/6 133/6** each.


Extras: --2-ft. length Sheet-iron Smoke Pipe and Smoke Plate, .. 24 to 30 ins., **3/-**; 32 to 42 ins., **3/9** per set.  
Oven, right hand, to order only, .. .. **3/9**  
Raising and Lowering Fire, fitted to order only, from 30 ins. upwards, .. .. **7/6**  
Cast-iron Plate Rack and Standards, .. ..  
fitted as drawn, .. .. 24 to 28 ins., **10/6**; 30 to 36 ins., **13/1½**; 38 to 42 ins., **15/9**

# Self-Setting Cooking Range

## THE "IDEAL" (Heavy Pattern)

This is a greatly improved form of Portable Cooking Range. It is constructed of much heavier metal than the ordinary type, and both oven and hot plate are very capacious. The latter is 19 inches deep; the former 18 inches high by 17 inches deep by widths as under. The oven is fitted with five slides and two stout shelves. Open or close fire by single action. "Eagle" raising bottom grate, upright bars, fall bar, sifter to ashes pan, oven dish rest, and dish rest to fire conveying ashes from fire to sifter, large side boiler and tap, down draught to oven, complete control ventilator to oven, cup lifter, and grate raiser.

Hot Plate  
19 inches deep.



Hot Plate  
27 inches high.

Oven on either right or left hand, and double the capacity of the cheaper kinds.

Drawing shows the fire raised about midway.

Width, .. .. .	36	39	42 inches.
Width of Oven, .. .. .	15	15	17 „
Width of Fire, .. .. .	8	8	10 „
Capacity of Side Boiler, .. .. .	8	8	12 quarts.
No. R 2982. Oven and Sham, .. .. .	114/-	132/-	150/- each.
No. R 2983. Oven and Side Boiler, with Brass Tap, .. .. .	132/-	150/-	168/- „
No. R 2984. Oven and High-pressure Bath Boiler, .. .. .	171/-	189/-	207/- „

"Eagle" Lifting Fire fitted to all Ranges, excepting those with High-pressure Bath Boiler. .. .. .

13/6 extra.

2-ft. length strong Smoke Pipe and Smoke Plate to suit above,

4/6 per set.


# Self-Setting Cooking Range

FITTED WITH H.P. BATH BOILER.

## THE "BRENT"

A reliable Cooker and Hot-water producer.

Hot Plate  
25 inches high.



Hot Plate  
17 inches deep.


A 20 to 25 gallon Circulating Cistern will be found most suitable for this Range. Two 1-in. connections fitted either on top or at side. Oven left hand. Open and close fire.

Width, .. .. .	30	32	33	34	36	38	42 inches.
Width of Oven, .. .. .	15	15	15	15	15	16	16 ..
Width of Fire, .. .. .	6½	6½	6½	6½	6½	6½	7½ ..
No. R 4343. Oven and H.P. Boiler,							
Open and Close Fire, .. ..	115/6	117/1½	118/1½	119/3	120/9	131/3	136/6 each.
2-ft. length Sheet-iron Smoke Pipe and Plate, .. .. .						3/9 extra.	

Oven, right hand, to 30 in. and 36 in. only, no extra.

# Self-Setting Cooking Range

## THE "ELYSIAN" (Extra Heavy Pattern)



Hot Plate  
22 inches deep.

Hot Plate  
28 inches high.

All ovens measure 17 inches high by 18 inches deep by widths as under:—

Widths of Range,	..	..	..	..	..	..	..	42	48	54 inches.
Ovens measure in Oven and Sham Ranges,	..	..	..	..	..	..	..	18	18	— inches wide.
Oven and Side Boiler,	..	..	..	..	..	..	..	—	18	— " "
Double Oven,	..	..	..	..	..	..	..	—	16 and 12	18 and 14 " "
No. R 6165. Oven and Sham,	..	..	..	..	..	..	..	273/-	296/3	— each.
High Pressure Boiler fitted,	..	..	..	..	..	..	..	88/3	88/3	— extra.
No. R 6166. Oven and Side Boiler, with Brass Tap,	..	..	..	..	..	..	..	—	321/-	— each.
No. R 6167. Double Oven,	..	..	..	..	..	..	..	—	321/-	400/6 " "
High Pressure Boiler fitted,	..	..	..	..	..	..	..	—	88/3	88/3 extra.


Single Oven Ranges made with left-hand oven only. All smoke nozzles, 7 inches diameter.

If fitted with strong Bottom Plate and mounted on Wheels for camp use, 80/3 extra.

# Self-Setting Cooking Range

FITTED WITH H.P. BATH BOILER.

## THE "COLINDA"



Hot Plate  
17 inches deep.

Hot Plate  
25 inches high.

A 20 to 25 gallon Circulating Cistern will be found most suitable for this Range.

Two 1-inch connections as drawn.

Oven right or left hand.



Width,	..	..	..	..	..	30	33	36	39	42 inches.
Width of Oven,	..	..	..	..	..	14	16	16	16	"
Width of Fire,	..	..	..	..	..	6½	6½	8½	8½	"
No. R 5315. Oven and H.P. Bath Boiler, Close										
Fire,	..	..	..	..	..	112/10½	115/6	118/1½	128/7½	133/10½ each.
Open and Close Fire fitted,	..	..	..	..	..	..	..	..	..	at 2/7½ extra.
2-ft. length Sheet-iron Smoke Pipe and Plate,	..	..	..	..	..	..	..	..	..	at 3/9 "

[illegible]

**OVENS** are 15 inches high by 13 inches deep by widths as under.

With Oven and Boiler and Covings.

With Oven and Boiler and Skirtings, with Damper  
Flue Plates.



Width of Range, .. .. .	24	27	30	33	36	39	42 inches.
Ovens measure in Oven and Sham Ranges, .. .. .	11	12	15	17	18½	18½	18½ inches wide.
" " " Boiler Ranges, .. .. .	—	—	12	15½	15½	17	17 "


No. R 721.	Oven and Sham, with Skirtings and Flue Plates, .. .. .	43/1½	44/7½	45/9	47/3	48/4½	54/4½	58/6	each.
No. R 722.	Oven and Boiler, with Tap, Skirtings and Flue Plates, .. .. .	53/7½	55/1½	56/3	57/9	58/10½	64/10½	69/-	..
No. R 723.	Oven and Sham, with Covings, Plate Rack and Smoke Plate, .. .. .	62/7½	64/1½	65/3	66/9	67/10½	73/10½	78/-	..
No. R 724.	Oven and Boiler, with Tap, Covings, Plate Rack and Smoke Plate, .. .. .	73/1½	74/7½	75/9	77/3	78/4½	84/4½	88/6	..
	Wrought Welded Arch Flue Bath Boiler to suit, .. .. .	21/-	21/-	21/-	21/-	21/-	22/6	22/6	..

108

# The "Crest" Kitchener

This is one of the most serviceable low-priced Kitcheners in our series. It is well made throughout. Hot plate, 27 inches high, 16 inches deep  $\times$   $\frac{3}{4}$  inch thick. Covings, 27 inches high (total height, 54 inches), with ventilator and bright O.G. mouldings to sides and lintel bar. Sliding cover, fall bar, and removable lower solid bars to fire part. Bright dish rests to oven and fire. The latter conveys falling cinders to the ashes pan. Well and fully bright fitted.

Oven  
on either  
Right or Left  
Hand.



Ovens  
16 inches high.  
15 inches deep.


Width of Range, .. .. .	30	33	36	39	42	48 inches.
Ovens measure inside Oven and Sham, .. .. .	14	15	18	18	20	20 inches wide.
" " Oven and Boiler, .. .. .	—	15	18	18	20	20 "
Fires measure .. .. .	8	8	8	8	10	10 "
No. R 5372. Close Fire, with Iron Covings, Oven and Sham, ..	71/7½	73/6	74/3	80/3	84/9	98/7½ each.
Wrought Welded Arch Flue Bath Boiler to suit, ..	21/-	21/-	21/-	21/-	22/6	22/6 "
No. R 5373. Close Fire, with Iron Covings, Oven and Side Boiler, complete, with Brass Tap. .. .. .	82/1½	84/-	84/9	90/9	95/3	109/1½ "
Open and Close Fire Arrangement fitted, .. .. .	6/-	6/-	6/-	6/-	6/-	6/- extra.
"Eagle" Lifting Fire fitted, .. .. .	8/7½	8/7½	8/7½	8/7½	8/7½	8/7½ "
Ashpit Linings fitted to "Eagle" Fire, .. .. .	3/4½	3/4½	3/4½	3/4½	3/4½	3/4½ "
Tiled Covings extra on price of Iron Covings, .. .. .	23/7½	25/10½	28/1½	30/4½	32/7½	37/6 "
No. R 480½. Cast-iron Mantel to suit above; 8-inch Jambs, 10-inch Lintel, 7-inch Shelf, .. .. .	18/9	19/9	20/9	21/9	22/9	25/9 each.



# The "New Reflex" Kitchener

With 2-inch Round Corners and 2-inch Bright O.G. Jamb Mouldings all round.

**HOT PLATE.**  
16 inches deep,  
 $\frac{3}{4}$  inch thick,  
26 inches high.




**COVINGS.**  
28 inches high.  
Total height, 54 inches.

Width of Range, . . . . .	30	33	36	39	42	45	48 inches.
Ovens measure inside Oven and Sham Ranges, . . . . .	12	14	18	18	18	18	20 inches wide.
" " Oven and Boiler Ranges, . . . . .		14	16	18	18	18	20 "
" " Double Oven Ranges, Roaster, . . . . .		—	—	—	12	14	16 "
" " " Baker, . . . . .		—	—	—	12	12	12 "
No. R 5374. "Close Fire, with Iron Covings, Oven and Sham, Wrought Welded Arch Flue Bath Boiler to suit; $\frac{1}{4}$ -in. plate, . . . . .	78 4 $\frac{1}{2}$	80 3 $\frac{1}{2}$	81 -	87 -	91 6	100 1 $\frac{1}{2}$	107 3 each."
No. R 5375. "Close Fire, with Iron Covings, Oven, and Side Boiler, complete with Brass Tap, . . . . .	21 -	21 -	21 -	22 6	22 6	22 6	22 6 "
No. R 6381. "Close Fire, with Iron Covings, Double Oven. Open and Close Fire Arrangement, fitted as drawn, . . . . .	88 10 $\frac{1}{2}$	90 9	91 6	97 6	102 -	110 7 $\frac{1}{2}$	117 9 "
"Eagle" Lifting Fire, fitted as drawn, . . . . .	—	—	—	—	126 -	139 7 $\frac{1}{2}$	141 4 $\frac{1}{2}$ "
Ashpit Linings fitted to "Eagle" Fire, . . . . .	6 -	6 -	6 -	6 -	6 -	6 -	6 - extra.
Tiled Covings extra on price of Iron Covings, . . . . .	8 7 $\frac{1}{2}$	8 7 $\frac{1}{2}$	8 7 $\frac{1}{2}$	8 7 $\frac{1}{2}$	8 7 $\frac{1}{2}$	8 7 $\frac{1}{2}$	8 7 $\frac{1}{2}$ "
Sliding Hot Closet, fitted above Plate Rack, as drawn, . . . . .	3 4 $\frac{1}{2}$	3 4 $\frac{1}{2}$	3 4 $\frac{1}{2}$	3 4 $\frac{1}{2}$	3 4 $\frac{1}{2}$	3 4 $\frac{1}{2}$	3 4 $\frac{1}{2}$ "
If fitted with Gas Burner to Oven and Swing Gas Grill, and Boiling Burner to Oven Hob of Single Oven Ranges, . . . . .	23 7 $\frac{1}{2}$	25 10 $\frac{1}{2}$	28 1 $\frac{1}{2}$	30 4 $\frac{1}{2}$	32 7 $\frac{1}{2}$	35 3	37 6 "
	17 3	17 3	17 3	17 3	17 3	21 9	21 9 "
	47 3	47 3	47 3	47 3	47 3	47 3	47 3 "

# The "Major" Kitchener

This pattern has been specially designed to meet the demand for a first-class Kitchener at a moderate price. It embodies all the latest ideas and improvements, and is substantially built and well fitted. Bright polished dish rests to both oven and fire, sliding fire cover, extra broad polished mouldings to end covings, and polished lintel bar to smoke plate.



## HOT PLATE.

27 inches high,  
18 inches deep,  
 $\frac{1}{2}$  inch thick.

## COVINGS.

27 inches high,  
54 inches high over all.

Sizes, .. .. .	36	39 2	42	45	48 inches wide.
Ovens measure in Oven and Sham Ranges, .. .. .	18	18	20	20	20 "
" " Oven and Boiler Ranges, .. .. .	16	16	18	18	20 "
" " Double Oven Ranges, .. .. .	-	-	12 & 12	14 & 12	16 & 12 "
Fire, .. .. .	8	10	10	10	10 "
No. R 6362. Oven and Sham, Close Fire, Iron Covings, ..	88 9	98 3	102 9	111/-	117 9 each.
Wrought Welded Arch Flue Bath Boiler to suit, ..	21/-	22 6	22 6	22 6	22 6 "
No. R 6363. Oven and Side Boiler, with Brass Tap, Close Fire, Iron Covings, .. .. .	99 3	108 9	113 3	121 6	128 3 "
No. R 6359. Double Oven, Close Fire, Iron Covings, .. .. .			137 6	145 9	153 - "
Open and Close Fire, fitted as drawn, .. .. .	6/-	6/-	6/-	6 -	6/- extra.
"Eagle" Lifting Fire, fitted as drawn, with Ashpit Linings, ..	12/-	12/-	12/-	12 -	12/- "
Tiled Covings extra on price of Iron Covings, .. .. .	28 1 1/2	30 4 1/2	32 7 1/2	35 3	37 6 "
Descending Flue to Oven to all sizes, .. .. .					5 3 "

# The "Georgian" Leamington Kitchener

Made with large wrought-iron oven, with cast-iron top ventilated for roasting, bright malleable fitted-on hinges and latch, bright dish rest, upright wrought fire bars, draw fret, heavy hot plate, with ground surface, fall bar to fire, O.G. hob mouldings, sliding cover to fire, plate rack, with bright O.G. front, bright front edges to covings and smoke plate, ashes pan, with cinder sifter, bottom grate, false bottom, cup lifters and raker complete.

HOT PLATE, 28½ inches high by 18½ inches deep at fire, and 20 inches deep at oven by ½ inch thick.

COVINGS, 25½ inches high, giving total height 54 inches.

OVENS, 18 inches high by 17½ inches deep by widths as under.


SUBSTANTIALLY  
CONSTRUCTED.



FULLY BRIGHT  
FITTED.

Width of Range, .. .. .	36	42	48 inches.
Ovens measure in Oven and Sham Ranges, .. .. .	17	19	21 inches wide.
" " Oven and Boiler Ranges, .. .. .	15	17	19 "
No. R2971. Oven and Sham, Close Fire, Iron Covings, .. .. .	117 -	132/-	150/- each.
3-inch Wrought Welded Arch Flue Bath Boiler to suit, .. .. .	24 -	25 6	27/- "
No. R2972. Oven and Nozzle Side Boiler, with Brass Tap, Close Fire, Iron Covings, .. .. .	134 3	149 3	167 3 "
Open and Close Fire fitted, .. .. .	7 6	7 6	7 6 extra.
"Eagle" Lifting Fire fitted, with Ashpit Linings and Patent Steel Bars, .. .. .	22 6	22 6	22 6 "
Tiled Covings extra on price of Iron Covings, .. .. .	27 -	31 6	36 - "
Sliding Hot Closet, with Iron Doors above Plate Rack, .. .. .	22 6	24 -	25/6 "
Glass Panels fitted to Hot Closet Doors, .. .. .	4 6	6/-	7/6 "
No. R5536. Iron Kitchen Mantel, as drawn, .. .. .	27/-	30/-	33/- "

# OUR NEW PATTERN Dual Gas and Coal Kitchener



Hot Plate  
26 inches high,  
16 inches deep,  
 $\frac{3}{8}$  inch thick.

Covings  
28 inches high.  
Total height,  
54 inches.

Fitted with 4 × 2 inch Round Corners, and 3-inch Bright O.G. Jamb Mouldings. Oven fitted with Atmospheric Gas Burners and Swing-back Gas Hot Plate to hob.

Width of Range,	.. .. .	36	42 inches.
Ovens measure ..	.. .. .	18	18 ..
Fires ..	.. .. .	8	10 ..
No. R5537. Oven and Sham, Close Fire, Iron Covings,	.. .. .	132/-	144/- each.
Wrought Welded Arch Flue Bath Boiler. ..	.. .. .	21/-	22/6 ..
Open and Close Fire fitted, as drawn, ..	.. .. .	6/-	6/- extra.
"Eagle" Lifting Fire, with Ashpit Linings, ..	.. .. .	12/-	12/- ..
Tiled Covings extra to price of Iron Covings. ..	.. .. .	28/1½	33/- ..
Hot Closet above Plate Rack, with Iron Sliding Doors. ..	.. .. .	17/3	17/3 ..

# The "Georgian" Double-Oven Leamington Kitchener

Made with large wrought-iron ovens, with cast-iron top ventilated for roasting, bright malleable fitted-on hinges and latches, bright dish rests to oven and fire, upright steel fire bars, heavy hot plate with ground surface, fall bar to fire, O.G. hob mouldings, sliding cover to fire, plate rack with bright O.G. front, bright front edges to covings and smoke plate, ashes pan with cinder sifter, bottom grate, false bottom, cup lifters and raker complete.

HOT PLATE, 28½ inches high by 18½ inches deep at fire, and 20 inches deep at oven by ½ inch thick.

COVINGS, 25½ inches high, giving total height 54 inches.

OVENS, 18 inches high by 17½ inches deep by widths as under.

FIRE BARS are now supplied loose and replaceable from the front to close fire kitcheners, the operation occupying a few seconds only.

SUBSTANTIALLY  
CONSTRUCTED.

FULLY BRIGHT  
FITTED.



Width of Range, .. .. .	42	48	54 inches.
Ovens measure inside Roaster, .. .. .	14	16	18 "
" " Baker, .. .. .	10	12	15 "
No. R 2973, Close Fire, with Iron Covings, .. .. .	177/-	195/-	219/- "
Wrought Welded Arch Flue Bath Boiler, to suit ¾-inch plate, .. .. .	24/-	25/6	27/- "
Open and Close Fire Arrangement, fitted as drawn, .. .. .	7/6	7/6	7/6 extra.
"Eagle" Lifting Fire, fitted as drawn, with Patent Wrought Bars, .. .. .	22/6	22/6	22/6 "
Tiled Covings, as drawn, extra on price of Iron Covings, .. .. .	31/6	36/-	40/6 "
Sliding Hot Closet, fitted above Plate Rack, with Glass Door, as drawn, .. .. .	30/-	33/-	36/- "
No. R 5536. Iron Kitchen Mantel, as drawn, .. .. .	30/-	33/-	36/ "


# The "Regal" Leamington Kitchener

EXTRA HEAVY.

HOT PLATE, 20 inches deep,  $\frac{1}{2}$  inch thick, 28 inches high. COVINGS, 28 inches high.

Total height, 56 inches. Long rods and knobs fitted to dampers.

SUBSTANTIALLY  
BUILT.



PERFECTLY  
FITTED.

Width of Range, .. .. .	36	42	48	54	60 inches.
Ovens measure in Oven and Sham Ranges, .. .. .	16	18	20	20	inches wide.
" " Oven and Boiler Ranges, .. .. .	14	16	18	18	"
" " Double Oven Ranges, Roaster, .. .. .	—	—	12	14	"
" " " " Baker, .. .. .	—	—	—	—	"
No. R 5310. Oven and Sham, Close Fire, Iron Covings, ..	183/-	225/-	246/-	—	each.
8-Inch Wrought Welded Arch Flue Bath Boiler to suit, .. .. .	24/-	25/6	27/9	29/3	30/- "
No. R 5311. Oven and Nozzle Side Boiler with Brass Tap, Close Fire, Iron Covings, .. .. .	198.-	240/-	270/-	300/-	"
No. R 5312. Double Oven, Close Fire, Iron Covings, ..	—	—	279/-	312/-	348/- "
Open and Close Fire, fitted as drawn, .. .. .	14/3	14/3	14/3	14/3	14/3 extra.
"Eagle" Lifting Fire, fitted as drawn, .. .. .	21/-	21/-	21/-	21/-	21/- "
Tiled Covings, extra on price of Iron Covings, .. ..	60/-	66/-	72/-	90/-	105/- "


# The "Chancellor" Open and Close Fire Kitchener

BEST FINISH. HEAVY METAL. WELL FITTED.

HOT PLATE, 28 inches high, 18 inches deep,  $\frac{1}{2}$  inch thick, return corners.

OVENS, large wrought iron, ventilated, cast-iron saddle cover.

COVINGS, 26 inches high, panelled tiled, ventilator, bold jamb mouldings.



Width of Ranges, .. .. .	48	54	60 inches.
Ovens measure inside Roaster, .. .. .	21	23	25 inches wide.
" " " Baker, .. .. .	17	20	23 "
Fire, .. .. .	10	11	12 "
No. R 5880. Double Oven, with Close Fire and Iron Covings, .. ..	226 6	249/-	270/- each.
No. R 5881. " " Open and Close Fire and Iron Covings, .. ..	234 -	256 6	277 6 "
No. R 5882. " " Open and Close and "Eagle" Fire and Iron Covings, .. .. .	256 6	279/-	300/- "
Tiled Covings, extra on price with Iron Covings, .. .. .	43 6	48 9	54/- extra.
Wrought Welded Arch Flue Bath Boiler to suit, .. .. .	25 6	27 9	29 3 "


Black parts Ground and Berlin Blacked, .. .. 39 - extra each Range.

All bright parts Nickel-plated, .. .. 57/- " "

# The "Alberta" Extra Heavy and Best Finish Leamington Open and Close Fire Kitchener

WITH "EAGLE" PATENT ADJUSTABLE FIRE.

The "Alberta" is a range of the very best class and style, embodying all the latest improvements in Open and Close Fire Leamington Kitcheners. The "Eagle" Fire Arrangement is acknowledged on all sides to be far and beyond anything of the same character. The Range is 30 inches to hot plate, 22 inches deep, with 30-inch covings, with open and close fire, bright polished plate rack, hot plate ground, and oven doors ground, glazed and berlin blacked, fitted with loose malleable bands.



The Ovens in  
SINGLE OVEN  
RANGES  
measure

22 inches deep by  
18 inches high by  
widths, in inches,  
as under:

Range.	Oven and Sham.	Oven and Boiler.
42	18	16
45	19	17
48	20	18
51	21	19
54	22	20
57	23	21
60	25	23

The Ovens in  
DOUBLE OVEN  
RANGES  
measure

22 inches deep by  
18 inches high by  
widths, in inches,  
as under:

Range.	Left- hand Oven.	Right- hand Roaster.
48	12	16
51	14	16
54	15	18
57	16	19
60	18	20
66	21	22
72	23	25

A description of the "Eagle" Patent Adjustable Fire is given on page 119.

Sizes, ..	42	45	48	51	54	57	60	66	72 inches wide.
Oven and Sham, with Iron Covings, and Open and Close and "Eagle" Patent Fire, ..	222/-	240/-	252/-	270/-	291/-	303/-	318/-	-	each.
Oven and Boiler, with Iron Covings, and Open and Close and "Eagle" Patent Fire, ..	240/-	255/-	267/-	288/-	306/-	321/-	336/-	-	..
Double Oven, with Iron Covings, and Open and Close and "Eagle" Patent Fire, ..			300/-	315/-	330/-	342/-	354/-	379/6	406/- ..
If without Open and Close Fire, deduct, ..	7/6	7/6	7/6	7/6	7/6	7/6	7/6	7/6	7/6 ..
" " "Eagle" Patent Adjustable Fire, deduct, ..	22/6	22/6	22/6	22/6	22/6	22/6	22/6	22/6	22/6 ..
Tiled Covings, extra on price with Iron Covings, ..	37/6	40/6	43/6	45/9	48/9	51/-	54/-	59/3	64/6 ..
Jamb Mouldings and Bright Face, extra, ..	28/3	28/6	29/3	31/6	32/3	34/6	35/3	37/6	38/3 ..



## The "Castle" Cooking Range

Is the acme of refinement and utility. Substantially constructed throughout. Flues self-contained, bisecting the ovens, ensuring complete results from fuel consumed. Economical in use—large or small fire at will by raising grate arrangement. Vertical steel fire bars, replaceable in a few seconds. Removable grill over fire box. Asbestos-lined oven doors enamelled inside face. Woodite heat-resisting knobs to doors. Indicating long rod dampers. Upper hot closet with glass inspection slide. Foot pedal opener to oven doors. "Phoolproof" or self contained flues to ovens. Requires no specially skilled labour to set same.




Fig. 1  
Pedal  
Oven  
Door  
Opener.

Fig. 2  
Pedal  
Oven  
Door  
Opener.

Width of Range, ..	42	45	48	51	54	60	ins.
Ovens measure: Roaster, ..	14	15	17	18	18	21	ins. wide x 18 ins. high x 18 ins. deep.
Baker, ..	10	12	12	15	15	17	18
Fire measures, ..	8	8	10	11	11	12	ins. wide.
No. R6389. Double Oven Range, with Grill, Tiled Covings and Jambs, Hot Air Closet, Pedal Oven Door Opener, as illustration, ..	456 -	468 -	480 -	510 -	540 -	570 -	each.
No. R6340. Wrought Welded Arch Flue Bath Boiler, 8-in. Plate and Flue Box, ..	33 -	33 -	34 6	34 6	36 -	36 -	per set.
No. R838. Wrought Welded Plain Boot Boiler, 8-in. Plate and Flue Box, ..	78 -	78 -	84 -	84 -	90 -	105 -	..
Ironwork, Berlin Black, Best Finish, ..	30 -	33 -	36 -	39 -	42 -	45 -	extra.
All Bright Parts Nickel Plated, ..	54 -	57 -	60 -	63 -	66 -	69 -	..
Length of Shelf, ..	48	54	60	66	72	78	84
Facia, ..	42	48	54	60	66	72	78
Best Quality Pine Shelf, with Facia and Brackets, ..	6 -	7 6	9 -	10 6	12 -	13 6	15 - 16 6 each.

# Kitcheners

## Instructions for Building-in or Setting our CLOSE, and OPEN and CLOSE FIRE KITCHENERS

### DESCRIPTION OF DIAGRAMS

Diagram 1 shows in perspective the brickwork necessary for a left-hand oven and boiler "Crest," "Foremost," "New Reflex," "Georgian," "Major," "New Dual," "Alberta," "Chancellor," or similar Range when completed, presuming the ironwork were removed. DDD are dampers, OF is oven flue, FF is fire flue, BF is boiler flue, RPPRRPPR are rests for hot plate, PPP are brick piers, OC is oven hot chamber, SBW is solid brickwork, MF is mid-feather under oven, A is brickwork under oven, IB is inlet to boiler flue, BR is rest for side boiler.

Diagram 2 shows the Range in its position, with portions removed to show the purpose of the flues, indicated by the heat travelling from fire over top of oven, down outer side, under oven, round mid-feather to flue; also in same manner over boiler, down outer side, under boiler to flue. O is oven, FB FB are fire-brick cheeks, NB is nozzle side boiler. RBG is brickwork for resting the cast-iron bottom grate.

Diagram 3 is section of Open and Close Fire Arrangement and "Eagle" Patent Adjustable Fire. V is ventilator, D is damper, H is hood, BB is bath boiler, DB is drop bar, BBF is bath boiler flue, RB is patent raising bottom grate (the dotted lines indicate the bottom grate in its raised position), R is special poker for lifting bottom grate, CS is cinder sifter, AP is ashes pan.



Diagram 1.



Diagram 2.




Diagram 3.

The above diagrams and description indicate the arrangement of flues, and show the brickwork necessary in building-in our Close Fire or Open and Close Fire Ranges. The following hints should be carefully noted: Fit the Range in its proposed opening temporarily, and ascertain that it is complete, and that all the parts are at hand, and note their respective purpose.

Prepare brickwork as shown in Diagram 1. This is best done in connection with setting the ironwork. Commence with the oven first. A must be the exact level with bottom of soot plug under oven; the same applies to boiler side. Build up piers PPP to level of hot plate. Leave flues about 4 inches deep, and above hot plate these should be increased to 6 inches deep, and all flues carried at least 2 feet above the height of top of iron coverings, then turned into the main flue or chimney. Build up as follows: two projections BR for boiler to rest upon. RP should project slightly for the hot plate to rest upon. IB shows the inlet to boiler flue. Build up brickwork RBG for rest for bottom grate, and SBW solid brickwork with fire-tile front. In the case of a high pressure bath boiler being used, the latter occupies this space (see Diagram 3), but built up quite close to the fire and to the hot plate. The space OC at back of oven should be as large as possible consistent with the size of oven, so as to give as much heating surface as possible. The flues must not be cramped, but may taper slightly towards the dampers DDD and these should regulate minimum size. In the case of using the open and close fire, as shown in No. 1323, "Alberta," and Diagram 3, the most advantageous method of constructing flue to bath boiler is by arranging heat to pass under boiler into direct flue. With double oven ranges the same process is applied to both ovens as indicated above to the one. The covering-in plate must be perfectly air-tight. In fact, no air should be allowed to pass into the flues but by means of the fire box. Finish off all flues quite smooth and smoke tight, and separate from each other. Give time to allow the mortar to set before lighting the fire, and then only a small fire should be kindled. Before doing this, loosen all screws.

### Instructions for Using our CLOSE, and OPEN and CLOSE FIRE RANGES

To kindle the fire, shut the Range down to a close fire and open the damper to fire flue only. In a few minutes the fire will have burned bright, and the Range will be ready for cooking operations; in the case of the "Eagle" Patent Adjustable Fire, for small service, it will not be found necessary to add fuel after the fire has been once made up, but by raising the bottom grate at intervals one notch on ratchet, an even and equable heat will be maintained, and be an immense saving in fuel, as at end of cooking operations only a very small amount of unconsumed fuel will remain in fire box this also can be used for further necessary culinary purposes.

To heat oven, open damper of oven flue only; the same applies to boiler when specially needed. The small soot plugs, arranged for the purpose of cleaning the flues, must in every case be placed tight in their respective positions. All the flues must be thoroughly cleaned by sweeping with the flue brush and soot raker at least once in every week.


### ADVANTAGES OF THE RAISING FIRE ARRANGEMENT

Which can be applied to our "Crest," "Foremost," "New Reflex," "Georgian," "Major," "New Dual," "Alberta," "Regal," and "Chancellor" Kitcheners. See pages 108 to 117.

It is usual to have the Open Fire Arrangement when the "Eagle" Fire is required; we can, however, apply the latter to Close Fire Ranges. The immense advantage of having a fire of the size required must be obvious to every one. For instance, a fairly large fire is required at first to heat the oven, hot plate, &c., but when hot a very small fire (if in the right place) will keep it so; but with ranges which have the fire box always of one size, the fire must be kept full up, close to the hot plate, or the air will pass over the top of the fire into the flues, instead of through the fire, and in consequence the ovens are cooled down. Now, with the Raising Fire, when the Range is thoroughly heated, the fire can be raised close to the hot plate, so that, with only a handful of coal burning, no air can possibly pass into the flues except through the fires.

The adjustment of the bottom grate is very simple, and is instantly raised or lowered (when in use) with an ordinary kitchen poker. We can guarantee an enormous saving both in time and fuel by the use of this arrangement of fire box: the fire is lighted very rapidly, burns small coal and of a very inferior quality, and the combustion is so perfect that very little soot is found in the flues.

## Hot Air Stoves




EXTRAS to No. R 5204.

Brass or Copper Repousse Panel, 17 3  
With Raised Top, 5 3

EXTRAS to Nos. R 5204 and R 5205.

Cast Curved Blower for quick Firing, 3 9  
With Tiles in Canopy, 7 6  
Register Door to close throat of vent, 10 6  
Cast iron Back Plate with Soot Door at bottom,  
and with hole to suit Nozzle of Grate, 10 6



### No. R 5204. Dr. CLARK'S DUPLEX GRATE

With Berlin Blacked Panel, Brass or Copper Knobs, Teale Back Brick, Ashpan with Ventilated Front, Damper at top to regulate draught, and fitted on four wheels for easy removal.


Sizes, ..	Wide High Deep Fire	Wide High Deep Fire
	16 1/2 x 21 1/2 x 16 x 12 ins.	19 1/2 x 21 1/2 x 16 x 15 ins.
Fine Cast and Stove Blacked, ..	£5 4 3 each.	£5 11 0 each.
Ground and Berlin Blacked ..	6 3 0 ..	6 10 6 ..
Best Finish Berlin Blacked, ..	6 12 0 ..	7 1 0 ..

### No. R 5205. Dr. CLARK'S DUPLEX GRATE

With Brass or Copper Repousse Panel, Brass or Copper Rail and Knobs, Teale Back Brick, Ashpan with Ventilated Front, Damper at top to regulate draught, and fitted on four wheels for easy removal.

Sizes, ..	Wide High Deep Fire	Wide High Deep Fire
	16 1/2 x 24 1/2 x 16 x 12 ins.	19 1/2 x 24 1/2 x 16 x 15 ins.
Fine Cast and Stove Blacked, ..	£6 10 6 each.	£6 18 0 each.
Ground and Berlin Blacked, ..	7 10 0 ..	7 16 0 ..
Best Finish Berlin Blacked, ..	8 1 3 ..	8 8 0 ..

## Iron Kitchen Mantels



No. R 4801.

Iron Kitchen Mantel.

6 inch Jambs. 8 inch Lintel. 7 inch Shelf.

No. R 4802.


Iron Kitchen Mantel.

8 inch Jambs. 10 inch Lintel. 7 inch Shelf.

No. R 480.

Iron Kitchen Mantel.

10 inch Jambs. 12 inch Lintel. 9 inch Shelf.



No. R 6388.

Iron Kitchen Mantel.

9 inch Jambs. 12 inch Lintel.  
7 inch Shelf.

Openings	FINE CAST.											
Width,	24	30	33	36	42	48	36	42	48	54	60	ins.
Height,	48	48	48	54	54	54	54	60	60	60	60	ins.
No. R 4801,	15 6	16 4 1/2	17 10 1/2	19 10 1/2	20 9	23 9						each.
.. R 4802,		16 9	18 9	20 9	22 9	25 9						
.. R 480,							27	32	35	39	45	..

Openings	FINE CAST.					
Width,	36	42	48	54	54	60
Height,	54	54	54	54	60	60
Prices,	23 10 1/2	25 10 1/2	28 10 1/2	32 10 1/2	35 10 1/2	41 10 1/2

## Tesselated and Mosaic Floor Tiling

AS SHOWN ON OPPOSITE PAGE. DETAILED PLAN FOR LAYING SENT WITH ALL ORDERS.


Design Nos., ..	RT 237	RT 238	RT 239	RT 240	RT 241	RT 242
Unselected Quality, ..	10 6	9	9	12 9	12 9	13
Best Quality, ..	12	10 6	10 6	15	15	15

Design Nos., ..	RT 243	RT 244	RT 245	RT 246	RT 247	RT 248
Unselected Quality, ..	9 9	12	10 6			
Best Quality, ..	10 6	12 9	12	25 6	25 6	52 6

The above prices are for Tiles laid to plan, packed, and free on rail, London, for quantities of six yards and upwards.  
Packing for export charged extra according to quantities.

# Wrought Welded Bath Boilers


FITTED WITH ROUND STEEL COVERS.



No. R837. Flat Bottom for Close Fire and Open and Close Fire Kitchens.

Sizes in Inches.				Prices, Each.	
A	B	C	D	3/4 in. Plate.	1/2 in. Plate.
10	7	8	10	20 -	22 3
12	8	8	10	21 9	24 -
14	8	8	10	23 3	26 3
14	10	8	10	25 6	28 6

No. R838. Wrought Welded Plain Boot Boilers, fitted with Two Round Steel Covers.




Sizes in Inches.		Prices, Each.	
Wide.	High.	3/4 in. Plate.	1/2 in. Plate.
10	18	56 9	67 3
12	18	61 9	73 3
14	18	66 9	79 3
12	21	65 3	77 3
14	21	70 9	84 3
12	24	68 9	81 9
14	24	74 9	88 9
16	24	80 9	95 9

Other Sizes as shown on drawing.

Arch Flue fitted to above Boilers.


First five sizes, 15 - extra; other sizes, 16 - 6 extra.



No. R836. Arched Flue for Close Fire and Open and Close Fire Kitchens.


Sizes in Inches.				Prices, Each.	
A	B	C	D	3/4 in. Plate.	1/2 in. Plate.
10	7	7	9	21 -	23 3
10	8	8	10	21 9	24 -
12	7	7	9	22 6	24 9
12	8	8	10	23 3	25 6
12	10	8	10	25 6	28 6
14	10	8	10	27 -	30 -

No. R2143. Wrought Welded Arch and Intersecting Flue Boot Boilers, fitted with Two Round Steel Covers.



Sizes in Inches.		Prices, Each.	
Wide.	High.	3/4 in. Plate.	1/2 in. Plate.
12	18	98 9	108 9
14	18	102 3	115 3
12	21	103 3	115 9
14	21	109 3	122 9
12	22	105 3	117 9
14	22	111 9	125 9
16	22	117 3	132 3
12	24	110 3	123 3
14	24	116 3	130 9


Other Sizes as shown on Drawing.



No. R6310. Arched Flue for Lifting Fire Kitchens and Register Stoves.

Sizes in Inches.				Prices, Each.	
A	B	C	D	3/4 in. Plate.	1/2 in. Plate.
10	6	8	8	21 -	23 3
10	6	11	12	21 9	24 -
11	8	5	5	21 9	24 -
12	6	8	8	22 6	24 9
12	7	9	9	23 -	25 3
12	6	11	12	23 3	25 6
14	6	11	12	24 9	27 9
16	6	11	12	26 3	29 3

No. R6341. Wrought Welded Arch and Oval Vertical Flue Boot Boilers, fitted with Two Round Steel Covers.



Sizes in Inches.			Prices, Each.	
Wide.	High.	Deep.	3/4 in. Plate.	1/2 in. Plate.
12	22	19	121 6	135 -
14	22	19	127 6	142 -
16	22	19	133 6	149 -

Other Sizes as shown on drawing.


If without Manlids, 1/6 per manlid less.

Holes drilled and tapped up to 1 in., 9d.; 1 1/2 and 1 3/4 ins., 1/-; 2 ins., 1/3 per hole.

# **"Yorkshire" Kitchen Range**

No. R 6366.

Substantially built and exceedingly well fitted. Solid or sectional oven (the latter with corrugated or plain bottom). Bold raised panel oven door. Ground and Berlin Black finish with brass ventilator. Polished dish-rest to oven. Projecting plate rack and boiler top. Slanting arch plate. Swing smoke slip. Cast fire bars screwed on from front, with fall bar. Fall crow and side boiler with hook lid.



Oven on either right or left hand.

Width, .. .. .	36	39	42	45	48	51	54	ins.
Height, .. .. .	48	48	51	51	51	54	54	"
Oven, inside	Width, ..	14	14	16	16	16	18	"
	Height, ..	17	17	19	19	19	20	"
	Depth, ..	16	16	16	16	16	16	"
Oven Front, .. .	18	18	20	20	20	22	22	"
Fire, .. .. .	9	12	12	13	14	15	16	"
Boiler Front, .. .	9	9	10	12	14	14	16	"
Prices, .. .. .	<b>69 3</b>	<b>72 3</b>	<b>76 3</b>	<b>83 -</b>	<b>87 9</b>	<b>104 -</b>	<b>110/-</b>	each.

#### ADDITIONS.

If made 51 ins. high where shown 48 ins., ..	<b>2 -</b>	extra.	Bright Wrought Horizontal Bars and Fall Bar, <b>19/10½</b>	extra.
Copper Hinged Lid to Boiler, .. .. .	<b>3 -</b>	"	Black Wrought Fall Crow, .. .. .	<b>3/-</b> "
Cast Cover Plate up to 48 ins., .. .. .	<b>4 1½</b>	"	Berlin Blacked, Second Finish, .. .. .	<b>21/9</b> "
" " over 48 " .. .. .	<b>4 10½</b>	"	Nickel-plating all bright parts up to	
Sheet Iron Oven instead of Cast Iron, ..	<b>8 3</b>	"	48 ins., <b>30/-</b> ; 51 and 54 ins., ..	<b>35/3</b> "
Draw Fret, .. .. .	<b>4 1½</b>	"	Brass Tap to Boiler, ½ in., .. .. .	<b>4/1½</b> "
Black Wrought Horizontal Bars and Fall Bar, <b>12 9</b>		"	Steel Vertical Fire Bars, .. .. .	<b>2/-</b> "

#### DEDUCTIONS.

Hot Hob, .. .. .	36	39	42	45	48	51	54	ins.
	<b>4/3</b>			<b>6/-</b>		<b>8/-</b>		less.
Plain Hob, .. .. .	36	39	42	45	48	51	54	ins.
				<b>7/3</b>	<b>9/-</b>	<b>11/-</b>		less.

## Special Cheap "Yorkshire" Kitchen Range

Sizes made in Nos. R 1352,  
R 1353, and R 1354.

36 ins. wide x 48 ins. high.

39 " " x 48 " "

42 " " x 48 " "

45 " " x 48 " "

48 " " x 48 " "

or 45 inches high if  
required.



Sizes of Ovens in  
Nos. R 1351, R 1352, R 1353,  
and R 1354.

13 ins. wide x 13 ins. high.

14 " " x 14 " "

14 " " x 14 " "

15 " " x 15 " "

16 " " x 16 " "

Oven on either right  
or left hand.

No. R 1353. This is a strong, well-fitted Kitchen Range, with hollow top, coves, and arch-plate, cast fall-bar range; hob boiler, with copper hinged lid; bright disc latch, and loose fitted bright bands to oven door.

Nos. R 1351 and R 1352 are the same Range as No. R 1353, but in a form specially suited for sculleries and cottage property.

Sizes made,	..	..	..	..	..	..	..	..	36	39	42	45	48 ins. wide,
Height to Top of Oven,	..	..	..	..	..	..	..	..	35½	37	37	38½	38½ " "
Oven, Inside,	..	..	..	..	..	..	..	..	13	14	14	15	16 " "
Fire,	..	..	..	..	..	..	..	..	11	12	13	14	15 " "
Boiler Front,	..	..	..	..	..	..	..	..	8	9	11	12	13 " "

Prices	No. R 1351. Extra Special Cheap form of No. R 1353 Range, viz.: Plain Range, consisting of Oven, fitted with Knob Catch, Vent, Fall Bar, Plain Hob and Hollow Top (but neither coves, arch-plate, nor boiler); size of Ovens as above,	39/-	41/3	43/6	48/-	52/9	each.
"	No. R 1352. Special Cheap form of No. R 1353 Range, viz.: Range, Fitted Oven, with Knob Catch, Vent, Cast Fall Bar, Hob Boiler, Coves, and Arch-plate; all dimensions as given to No. R 1353,	57/4½	60/4½	62/6	70/6	75/3	"
"	No. R 1353. As drawn and described above,	61/1½	64/1½	66/3	74/3	79/-	"
"	No. R 1354. As drawn and described to No. R 1353, but with Continuous Plate Rack, Swing Smoke Slip, Cast Fall Crow and Bright Bracket Shelf; dimensions as given to No. R 1353; see also No. R 6366 on opposite page,	76/3	76/3	80/6	87/3	90/6	"

### DEDUCTIONS.

Any of the following items, when not required, may be deducted from inclusive prices:

If without Hob Boiler,	..	..	4/6 less.
" Cast Fall Crow,	..	..	3/- "
" Bright Bracket Shelf,	..	..	3/- "


### ADDITIONS.

The following, when needed, are extra to any size Range:—

If with Cast Fall Crow,	..	..	3/- extra.
" Bright Bracket Shelf,	..	..	3/- "
" Draw-out Fret,	..	..	4/1½ "
" Brass Tap to Boiler, ½ inch,	..	..	4/1½ "
If No. R 1351 has Hob Boiler,	..	..	12/- "


# Stoves, Range Fittings, Smoke Pipes and Elbows, &c.

No. R 683. ELLIPTIC STOVE




Sizes, 14 16 18 20 22 24 26 28 30 32 34 36 ins. wide.  
Light Pattern, 3½¢ per inch.  
Strong " 61. "

No. R 687. MASON STOVE




Sizes, 9 10 11 12 ins. wide.  
Prices, 2 9 3 36 3 9 each.

No. R 684. FALL BAR RUMFORD STOVE



Sizes, 18 20 22 24 26 28 30 32 34 36 ins. wide.  
Price, 7½¢ per inch.

No. R 1150. CAST-IRON KITCHENER SIDE BOILER  
With Neck.



Width	Length	Height	Price
5½ ins.	12½ ins.	9½ ins.	12 6 each.
7½ "	13 "	10 "	15 "
6 "	14 "	11 "	15 "
9½ "	14 "	10½ "	16 6 "
10 "	14 "	11 "	18 "
8 "	16 "	13 "	18 "
11 "	16 "	13 "	20 "
14 "	16 "	13½ "	18 9 "
10 "	16 "	13 "	21 9 "

No. R 1154. S.A.C. RANGE BARS  
With Pinned Fall Bar.




Sizes, 9 10 12 ins. wide.  
Prices, 2 3 3 39 per set.

No. R 1155. CLOSE FIRE RANGE BARS  
With 2 inch Wrought iron Pins up to 9 inches.  
Above 9 inches, ½-inch Pins.



Sizes	6	6½	7	7½ ins.
Prices	3 9	4 3	4 9	5 3 per doz.
Sizes	8	8½	9	9½ ins.
Prices	5 9	6 3	6 9	8 3 per doz.
Sizes	10	10½	11	11½ 12 ins.
Prices	9 -	10 6	12	13 6 15 per doz.

No. R 1075. SHEET-IRON SMOKE PLATE  
With Sliding Cleaning Door.



Stock Sizes, 24 to 30 32 to 36 38 to 42 44 to 48 ins. wide.  
Prices, 1 6 2 3 3 - 3 9 each


No. R 1014. PLATE RACK  
Bright Half-round Front and Prongs for building in



Sizes, 24 30 36 42 48 ins.  
Prices, 6 6 9 7 - 7 6 9 each.


WROUGHT-IRON SMOKE PIPES, ELBOWS AND CAPS

Sizes	2½	3	3½	3½	3½	4	4½	4½	4½	5	5½	5½	6 ins.
Plain Pipes, Black, 2 feet lengths,	3d.	4d.	5d.	5d.	5d.	6d.	6d.	6d.	7d.	7d.	7d.	8d.	9d. per ft.
" Galvanized, "	6d.	10d.	1½	1 -	1 -	1½	1½	1½	1½	1½	1½	1½	1½
Plain Elbows, Square or Obtuse, Black, "	9d.	10d.	1 -	1½	1½	1½	1½	1½	1½	1½	1½	1½	1½
" " Galvanized, "	1 7½	1 10½	2 3	2 6	2 9	2 9	3 -	3 -	3 -	3 3	3 3	3 3	3 10½
Elbows, with Doors, Square or Obtuse, Black, "	1 1½	1 3	1 6	1 9	1 10½	1 10½	2 -	2 -	2 -	2 3	2 3	2 3	2 9
" " Galvanized, "	2 6	2 9	3 3	3 10½	4 1½	4 1½	4 6	4 6	4 6	4 10½	4 10½	4 10½	5 6
Cone Caps, Black, "	1	1 1½	1 3	1 6	1 9	1 9	1 10½	1 10½	1 10½	2 -	2 -	2 -	2 3
" Galvanized, "	2 3	2 6	2 9	3 3	3 10½	3 10½	4 1½	4 1½	4 1½	4 6	4 6	4 10½	4 10½



No. R 1800. KITCHEN FENDER


6 inches high.



Sizes, 3 ft. 3 ft. 6 ins. 4 ft. 4 ft. 6 ins. 5 ft.  
Prices, 11 3 12 - 13 6 14 3 15 - each.


# Iron Mantels

No. R 5542.




Jambs, 7½ inches wide. Lintel, 14 inches deep. Double Shelf.  
 Openings, .. 30 x 36 34 x 36 36 x 38 38 x 38 ins.  
 Shelf, .. 54 x 9½ 58 x 9½ 60 x 9½ 62 x 9½ ..  
 Prices, Fine Cast, 28/9 30/4½ 34 - each.

No. R 4218.




Jambs, 7 inches wide. Lintel, 14 inches deep. Double Shelf.  
 Openings, .. 30 x 36 34 x 36 36 x 38 38 x 38 ins.  
 Shelf, .. 54½ x 9½ 59½ x 9½ 60½ x 9½ 63½ x 9½ ..  
 Prices, Fine Cast, 28/9 30/4½ 34 - each.

No. R 6670.



Jambs, 7½ inches wide. Lintel, 16 inches deep.  
 Double Shelf, 60 x 10 inches. Opening, 38 x 38 inches.  
 Price, Fine Cast, .. 38/3 each.

No. R 6671.



Jambs, 5½ inches wide. Lintel, 14 inches deep.  
 Wood Moulded Shelf, 54 x 9 inches. Opening, 38 x 38 inches.  
 Price, Fine Cast, .. 40/6 each.



# Anthracite Coal Stoves

No. R 6060. THE "BEAM"



Nos.,	1	2
Width,	18	24 ins.
Height,	23½	29½ "
Depth over Base Plate,	14½	15½ "
Heating Capacity,	2500	3500 cub. ft.
Fine Cast and Black Leaded, with Nickel Fittings,	66/9	85/6 each.
Enamelled in Colors, Crimson excepted, with Nickel Fittings,	99/9	123/9 "
Enamelled Crimson,	17/3	17/3 extra.

Back Extension similar to that shown to No. R 6062.


Fine Cast and Black Leaded, 9/9 each extra.

Enamelled in Colors, 16/6 " " " " Each Extra.

Cast-iron Flue Pipe, 3 ft. long, with Elbow Bend, Black Leaded, 9/-

" Oval Bend, with Socket to take 4½-in. Pipe, 3/10½

No. R 6062. THE "NEW RADIATING"  
WITH BACK EXTENSION.



Width, 24 ins.; height, 29 ins.; depth over base plate, 15½ ins.	
Heating Capacity,	3500 cub. ft.
Fine Cast and Black Leaded, with Nickel Fittings,	85/6 each.
Enamelled in Colors, Crimson excepted, with Nickel Fittings,	123/9 "
Enamelled Crimson,	17/3 extra.

Back Extension, as shown in above drawing—


Fine Cast and Black Leaded, 9/9 each extra.

Enamelled in Colors, 16/6 " " " " Each Extra.

Cast-iron Flue Pipe, 3 ft. long, with Elbow Bend, Black Leaded, 9/-

" Oval Bend, with Socket to take 4½-in. Pipe, 3/10½

No. R 6061. THE "NEW CRESSET"



Width, 24 ins.; height, 30 ins.; depth over base plate, 15½ ins.

Heating Capacity,	3500 cub. ft.
Fine Cast and Black Leaded, with Nickel Fittings,	85/6 each.
Enamelled in Colors, Crimson excepted, with Nickel Fittings,	123/9 "
Enamelled Crimson,	17/3 extra.

Back Extension, similar to that shown to No. R 6062.


Fine Cast and Black Leaded, 9/9 each extra.

Enamelled in Colors, 16/6 " " " " Each Extra.


Cast-iron Flue Pipe, 3 ft. long, with Elbow Bend, Black Leaded, 9/-

" Oval Bend, with Socket to take 4½-in. Pipe, 3/10½

No. R 6063. THE "NEW FLAMBEAU"



Nos.,	2	3
Height,	29	31 ins.
Width,	16½	18½ "
Depth,	12½	14 "
Heating Capacity,	2000	3000 cub. ft.
Fine Cast and Black Leaded, with Nickel Fittings,	76/6	90/9 each.
Enamelled in Colors, Crimson excepted, with Nickel Fittings,	109/6	133/6 "
Enamelled Crimson,	16/6	19/6 extra.



## Anthracite Coal Stoves

### The "CONTESSE"

REGISTERED TRADE MARK.

All sizes of "Contesse" Stoves are now fitted with a Patent Automatic Check Valve which equalises the draught in the chimney and increases ventilation.

Fittings of hopper door, fire door and ashpan are nickel-plated.


\* NOTE. Where space is limited, Tray in front can be removed, thus reducing depth required by  $\frac{1}{2}$  ins. for Nos. 1, 1s, 2s, and 2s; and by  $\frac{5}{8}$  ins. for Nos. 3 and 3s.



Without Surround—Nos. 1, 2, and 3.

No.	Average Heating Capacity.	Width over all.	Depth over Movable Tray.	Height over all.	Height to top of Flue Collar.	Blacklead.	Black Vitreous Enamel.	Majolica Enamel in Various Colors.	Ruby Red Majolica Enamel.
1	1500 C.F.	17 $\frac{1}{2}$ ins.	15 $\frac{1}{2}$ ins.	26 ins.	15 $\frac{1}{2}$ ins.	£3 3 0	£4 4 0	£4 14 6	£5 5 0
1s	1500 "	17 $\frac{1}{2}$ "	15 $\frac{1}{2}$ "	26 "	15 $\frac{1}{2}$ "	3 14 6	5 2 6	5 15 6	6 7 0
2	2000 "	20 "	15 $\frac{1}{2}$ "	27 "	16 $\frac{1}{2}$ "	3 13 6	4 14 6	5 5 0	5 18 0
2s	2000 "	20 "	15 $\frac{1}{2}$ "	27 "	16 $\frac{1}{2}$ "	4 5 0	5 13 0	6 6 0	7 0 0
3	3500 "	23 "	16 $\frac{1}{2}$ "	29 "	17 $\frac{1}{2}$ "	4 7 6	5 8 6	5 18 6	6 13 6
3s	3500 "	23 "	16 $\frac{1}{2}$ "	29 "	17 $\frac{1}{2}$ "	5 0 0	6 8 6	7 1 0	7 16 0

With Surround—Nos. 1s, 2s, and 3s.




### The "ARTESSE"

REGISTERED TRADE MARK.

All sizes of "Artesse" Stoves are now fitted with a Patent Automatic Check Valve which equalises the draught in the chimney and increases ventilation.

Handles and fittings of hopper door, fire door, and ashpan are nickel-plated.

Prices of "Artesse" Stoves in Full Armour Bright Finish quoted on application.



Without Surround—Nos. 2, 3, and 4.

No.	Average Heating Capacity.	Width over all.	Depth over Base Plate.	Height over all.	Height to top of Flue Collar.	Blacklead.	Black Vitreous Enamel.	Various Colors of Majolica Enamel.	Ruby Red Majolica Enamel.
2	2500 C.F.	22 $\frac{1}{2}$ ins.	14 $\frac{1}{2}$ ins.	28 ins.	16 $\frac{1}{2}$ ins.	£4 4 0	£5 5 0	£5 15 6	£6 8 6
2s	2500 "	22 $\frac{1}{2}$ "	14 $\frac{1}{2}$ "	28 "	16 $\frac{1}{2}$ "	4 15 6	6 3 6	6 16 6	7 10 6
3	4500 "	25 $\frac{1}{2}$ "	15 "	30 "	18 $\frac{1}{2}$ "	4 14 6	5 15 6	6 6 0	7 2 0
3s	4500 "	25 $\frac{1}{2}$ "	15 "	30 "	18 $\frac{1}{2}$ "	5 6 0	6 15 0	7 8 0	8 5 0
4	8500 "	28 $\frac{1}{2}$ "	17 $\frac{1}{2}$ "	33 $\frac{1}{2}$ "	20 $\frac{1}{2}$ "	5 15 6	7 2 0	7 17 6	8 18 6
4s	8500 "	28 $\frac{1}{2}$ "	17 $\frac{1}{2}$ "	33 $\frac{1}{2}$ "	20 $\frac{1}{2}$ "	6 12 6	8 8 0	9 6 0	10 8 0

With Surround—Nos. 2s, 3s, and 4s.

### PATENT "ESSE" STOVES with PRESSURE BOILERS, for Heating Hot-water Pipes or Radiators.

Nos. 3 and 4 "ARTESSE" STOVES can be supplied with Wrought-Iron or Cast-Iron High Pressure Boilers fitted at the back of the Fire-chamber.

This arrangement is most convenient for heating a room adjacent to the one in which the Stove is placed—the hot water circulating through radiating pipes or a Hot-water Radiator. It may also be used in conjunction with a small cylinder (about 20 gallons) for giving a supply of Hot Water for Bath or other purposes.

The Boiler in a No. 3 size Stove is powerful enough to heat radiating pipes or a radiator large enough to keep a room of 2000 cubic feet nicely warm, and the No. 4 size to warm an adjacent room of 3000 cubic feet.

#### TWO ROOMS HEATED WITH ONE FIRE.

The cost of fitting any of the above Stoves with a Wrought-Iron Boiler is £3 8 6 extra to Price Do., do., with a Cast-Iron Boiler is 2 2 0 of Stove. Quotations for Copper Boilers on application.

# Anthracite Coal Stoves


## The "SOLESSE"

REGISTERED TRADE MARK.

An Improved Circular Continuous Burning Stove, fitted with a swinging ornamental top. The upper portion of the body acts as a hopper for the fuel, and the ashpan being fitted with the "Esse" Patent Regulator, it can be kept alight for 8 to 12 hours. Though this type of Stove is not so suitable for sitting-rooms and bedrooms as those shaped like the "Contesse," it will be found very convenient for small Halls and Offices. The body of the "Solesse" is made of Polished Blue Steel Plate, and the inside is lined with fire-brick. It is fitted with Hinged Fire Bars, Fire Door with Mica Panels, Removable Ash Tray, Asbestos jointed Feed Door on top, and has all the mountings nickel-plated. A Key for the Door and a Coal Chute are supplied with all "Solesse" Stoves.

No.	Average Heating Capacity	Width over Feet.	Depth over Movable Tray.	Height over all.	Height to top of Blue Collar.	Plain Finish.	Black Vitreous Enamel.	Majolica Enamel in Various Colors.	Ruby Red Majolica Enamel.
1	1500 C.F.	14 ins.	18 ins.	28 ins.	18½ ins.	£1 19 0	£3 0 0	£3 4 0	£3 18 0
2	1750 "	14 "	18 "	30 "	20½ "	2 1 6	3 2 6	3 6 6	4 0 6
3	2000 "	14 "	18 "	32 "	22½ "	2 4 0	3 5 0	3 9 0	4 3 0

\* Without Tray, Depth is reduced by 4½ inches in all cases.



## The "ORESSE"


REGISTERED TRADE MARK.

A handsome Cylindrical Hall Stove with Embossed Steel Body. It is fitted with an improved Fire-grate arrangement, and is suitable for use with Anthracite Coal or Coke. "Oresse" Stoves (except No. 10 size) are supplied with the following parts nickel-plated: Top ornament, steel moulding round bottom edge of dome, foot rests at sides, and all handles. No. 10 has smaller nickel-plated top ornament and handles, but is not fitted with steel moulding and foot rests, and is without reversible flue at back.

	No. 10.	No. 12.	No. 14.	No. 16.
Approximate Heating Capacity, ..	7,000	10,000	15,000	20,000 cubic feet.
SIZES. Width at Base, ..	19½	21½	23½	25½ ins.
Height over all, ..	54½	57½	60½	61½ "
Depth ..	22½	24½	26½	28½ "
Diameter of Cylinder, ..	10	12	14	16 "

	Blacklead.	Black Vitreous Enamel.	Majolica Enamelled in Various Colors.	Ruby Red Majolica Enamel.
No. 10, ..	£4 0 0	£6 0 0	£6 14 0	£8 4 0
No. 12, ..	5 5 0	7 7 0	8 3 0	9 15 0
No. 14, ..	6 6 0	8 8 0	9 4 0	11 0 0
No. 16, ..	7 7 0	10 0 0	10 16 0	12 15 0

It with Top Ornament in Plain Finish, and without Nickel-plated Steel Moulding and Foot Rests, 11 less for Nos. 14 and 16, and 6 less for No. 12.



Oval to Round Cast iron Bend, with Socket.

Oval to Round cast-iron Nozzle, with Socket.

	For No. 1.	Nos. 2 and 3 (4 in. pipe).	No. 4 (5 in. pipe).
Black leaded, ..	3 3	3 6	4 3
Enamelled, ..	5 6	5 9	6 6

NOTE.—Suitable for "Contesse" and "Artesse" only, shown on page 129.


Strong Cast-iron Flue Pipe, 36 ins. long, and Elbow, to fit on nozzle at back of Stove and enter tight-fitting top closure plate.

Black-leaded, 7 6  
Enamelled, 12 6

NOTE. Not suitable for "Oresse" or "Solesse."



Square Steel Elbow.



Obtuse Steel Elbow.

Suitable for connecting Stove to chimney when ordinary grate is not disturbed.


The tops of these Elbows, which are intended to pass through a hole in a sheet-iron top closure plate, are fitted with a dust cap.

Elbows, as above, 18 ins. long, .. 4 6


# Heating Stoves

## No. R4319. THE "TORTOISE" RADIATING STOVE

Perfect Combustion Assured.  
No Unpleasant Fumes.



Inlet for fresh air can be underneath the bottom, or on either side, in any position, instead of at back as shown.



PURE AIR FROM OUTSIDE BUILDING


With Horizontal or Vertical Nozzles and Fire Tile Lining and Hearth. Stoves sent Horizontal Nozzles unless otherwise ordered.

It will be seen by the illustrations that this Stove is so constructed that the fresh air enters the Stove at the base through the inlet tube, which is connected to the outside grating by a pipe. The air ascends through the tubes of corrugations, getting warmed as it passes over the cylinder, till it finally passes out at the top, through holes and slots especially constructed for the purpose, into the room as Heated Fresh Air.

Each Stove is fitted with a valve by which the cold air may be excluded when Stove is not in use.

The Stove is adapted in every way to meet the requirements of the Education Authorities.

	Height	External Diam.	Heating Capacity.	Size of Nozzles.	Price, including Ashes.
R 4319/2. ..	23½ ins.	14 ins.	9,000 cub. ft.	4½ ins.	£3 10 6 each.
R 4319/3. ..	31 "	14 "	12,000 "	4½ "	4 4 0 "
R 4319/4. ..	33 "	16 "	18,000 "	4½ "	5 12 6 "
R 4319/5. ..	36 "	18 "	30,000 "	5½ "	7 0 3 "
R 4319/6. ..	41 "	20 "	50,000 "	6½ "	9 3 0 "
Nos. ..	2	3	4	5	6
Ashes Tray. ..	6 -	7 6	10 6	15 -	42 -
Air Inlet Connector, Straight or Elbow, ..	7 6	7 6	9 -	10 6	15 -



## No. R6170. THE "KOSEY" Fire Brick Lined.

Slow Combustion, with Cast-iron Panels in front and sides.



Height, 34 ins.  
Body, 12½ ins. square.  
Sole Plate, 20 ins. wide x 22 ins. deep.  
4 in. Smoke Nozzle.  
Heating capacity, 15,000 cub. ft.

Fine Cast and Blacked,  
54 - each.

Berlin Black Finish,  
64 6 each.

Tiles fitted in Front and Sides,  
13 6 extra.

## No. R815. THE "TORTOISE" Horizontal or Vertical Nozzles.



RENEAULT

Fitted with fire tile lining and including ashes pan.

No.	Height.	Diam.	Heating Capacity.	Diam. of Nozzle.	Price.
0.	16	8 ins.	1,000 cubic ft.	3½ ins.	16 10½ each.
1.	20 x 9	2,000	3½	22 6	"
2.	25 x 10	6,000	3½	33 9	"
3.	30 x 12	10,000	4½	49 6	"
4.	32 x 14	15,000	4½	70 6	"
5.	35 x 16	25,000	5½	112 6	"
6.	40 x 18	40,000	6½	147 -	"
7.	45 x 21	70,000	7½	224 3	"
8.	50 x 21	120,000	8½	336 -	"


Nos.	0	1	2	3	4	5	6	7	8
Ashes Trays, ..	2 3 3 -	4 6 6 -	7 1½	10 6	15 -	42 -	52 6	each.	
Extra Fire Brick Linings, ..	4 6 4 6 6 -	9 9	13 6	16 10½	21 -	28 6	49 6	p. set.	

## No. R812. THE "ROSE" HALL STOVE

Always sent with back flue unless specially ordered otherwise.

The drawing represents No. 2 Stove.

No. 1 has one fire door only.




This is a handsomely designed Warming Stove, well adapted for placing in dining halls, schools, offices, &c. It is constructed of strong cast-iron plates; fire chamber is fitted with a flue deflector and brick linings, furnished with draw-out ashpan.

No.	Height.	Depth from Front to Back.	Width across Sole Plate.	Nozzle.	Price.
1.	25 ins.	20 ins.	18 ins.	5 ins.	40 6 each.
2.	30 "	25 "	21 "	6 "	54 -
3.	35 "	25 "	24 "	6 "	76 6 "

# Heating Stoves

## No. R 813. IMPROVED SHOP STOVE

Suitable for heating small shops and workrooms.




Nos., ..	R 813AA.	R 813A.	R 813B.
Width, ..	7½	8½	9½ ins.
Depth, ..	7½	8½	9½ "
Height, ..	12½	17½	19½ "
Diameter of Smoke Nozzle, ..	2½	3	3½ "
Prices, ..	10 1½	11 9	13 4½ ea.

Nos., ..	R 813C.	R 813D.	R 813E.
Width, ..	10½	11½	12½ ins.
Depth, ..	10½	11½	12½ "
Height, ..	22½	23½	26 "
Diameter of Smoke Nozzle, ..	3½	4	4 "
Prices, ..	16 3	20 9	26/- ea.

Brick linings fitted to No. R 813B, 1 7½; No. R 813C, 1 9;  
No. R 813D, 3; No. R 813E, 3 7½ each extra.

## No. R 808. THE "QUEEN" OFFICE STOVE

The "Queen" pattern is a general favourite, and is highly commended for bedroom, office, shop, or cabin, as, in addition to its use as a warming Stove, it may be transformed into a Cooking Stove by simply removing the elegant ornamental top, which stands directly over the two fire covers. This Stove is fitted with fire-brick lining, and the sliding doors in front assist in kindling or deadening the fire as required. It is supplied with cup-lifter and poker.



Nos., ..	R 808A.	R 808B.
Extreme Sizes—		
Width, ..	17	18½ ins.
Height, ..	23½	25 "
Depth, ..	12	13 "
Prices, ..	17 10½	21 7½ ea.

Bottom Plate projects 5 inches.


2-foot lengths Sheet-Iron Pipe to suit, at .. 1 1½ each.  
Cast-iron Knee Elbows to suit, at .. 4 6 "

## No. R 814. THE "RELIABLE"

Round. Fire Brick Lined.  
Slow Combustion.  
New Design, Registered.

Prices, including Ashes Pan.			
Nos., ..	R 814A.	R 814B.	R 814C.
Height, ..	23	27	30 ins.
Diameter, ..	9	10	12 "
Diameter of Nozzle, ..	3	3½	3½ "
Heating Power, ..	2,000	6,000	10,000 cub. ft.
Prices, ..	24/-	28 6	36/- each.

Nos., ..	R 814D.	R 814E.
Height, ..	32	34 ins.
Diameter, ..	14	16 "
Diam. of Nozzle, ..	4	4 "
Heating Power, ..	15,000	25,000 cub. ft.
Prices, ..	60.-	84 - each.



## No. R 820.

### THE "RELIABLE"

Square. Fire Brick Lined.  
Slow Combustion.  
New Design, Registered.

Prices, including Ashes Pan.			
Nos., ..	R 820A.	R 820B.	
Height, ..	23	29 ins.	
Diameter, ..	9	12 "	
Diameter of Nozzle, ..	3	3½ "	
Heating Power, ..	5,000	8,000 cub. ft.	
Prices, ..	31 6	51 9 each.	
Nos., ..	R 820C.		
Height, ..	32	ins.	
Diameter, ..	15	"	
Diam. of Nozzle, ..	4	"	
Heating Power, ..	12,000	cub. ft.	
Price, ..	77 3	each.	

## No. R 810. THE "EXCELSIOR" OFFICE STOVE

Fire Brick Lined.

A very suitable  
Stove for the office,  
shop, parlour, or  
bedroom.

By the arrangement  
of the front blowers  
it is easily and  
quickly kindled,  
and, by removing  
the blowers, a  
nice, cheerful fire  
is presented.

Nos., ..	1	2
Width, ..	24	27 ins.
Height, ..	30	32
Nozzle, ..	5	6 "
Prices, ..	30/-	39 6 ea.

Nos., ..	3
Width, ..	30 ins.
Height, ..	34 "
Nozzle, ..	6 "
Price, ..	48/- ea.



## No. R 5292. THE "EQUATOR"


Fire Brick Lined.

Slow Combustion, with Vertical or  
Horizontal Smoke Nozzle.

Prices, including Ashes Pan.


Nos., ..	1	2	3
Height, ..	16	20	25 ins.
Diameter, ..	8	9	10 "
Diam. of Nozzle, ..	4	4	4 "
Prices, ..	14 9	16 10½	20 1½ ea.

Nos., ..	4	5
Height, ..	30	32 ins.
Diameter, ..	12	14 "
Diam. of Nozzle, ..	4	5 "
Prices, ..	27 9	38 7½ ea.



# Plumbers' and Laundry Stoves


No. R1836.  
THE "MODEL" LAUNDRY STOVE



Can be placed on Range Hobs.

	Wide.	Deep.	High.	Nozzle.
No. 1.	10 ins.	12 ins.	9 ins.	3 ins.
.. 2.	12 ..	13 ..	9 1/2 ..	3 ..


No. R986. THE "VILLA" LAUNDRY STOVE



With Loose Ashpan and Wrought Latch.

	Wide.	Deep.	High.	Nozzle.
No. 1.	10 ins.	12 ins.	18 ins.	4 ins.
.. 2.	11 ..	13 1/2 ..	20 ..	4 ..


No. R1837.  
THE "COTTAGE" LAUNDRY STOVE




	Wide.	Deep.	High.	Nozzle.
No. 1.	7 ins.	8 1/2 ins.	13 ins.	3 ins.
.. 2.	8 1/2 ..	10 1/2 ..	15 ..	3 ..

No. R965  
PLUMBER'S STOVE, with Lead Pot

Price, complete,  
as drawn,  
43 6 each.



No. R4224. THE "LAUNDRESS" SQUARE LAUNDRY STOVE





No. 1 (3 sections) —			
Size at Base.	Height.		
16 x 16 ins.	27 ins.	75	each.
No. 2 (4 sections)			
Size at Base.	Height.		
16 x 16 ins.	35 ins.	99	each.

No. R817. "TORTOISE" LAUNDRY STOVES

New cheap Laundry Stoves, for burning coke or anthracite coal; fire tile lining and hearth, constructed for domestic uses as well as laundries in large establishments, with or without loose lid.


Ashes Pans supplied with  
Nos. 1, 2, and 3 only.



No.	Nos. 00 and 0.	No. 1.	No. 2.	No. 3.	No. 4.
00.	heats 5 flat irons, 3 in. nozzles,	7 6 each.			
0.	7	3	3, 28 ins. high x 15 ins. diam., heats 14 flat irons, 4 in. nozzles,	59 3 each.	
1,	18 1/2 ins. high x 10 ins. diam.,	5	4, 31 .., .. x 12 ..	22	4 .. 70 6 ..
2,	26 .., .. x 12 ..	10	5, as No. 4, but one tier more,	28	4 .. 84 ..

Ash Trays to suit No. 1, 4 6; No. 2, 6 -; No. 3, 7 5 each extra.

No. P 2121. **CAST-IRON TABLE**




Complete, with  
Round Top.

Height, 27 ins.  
Diam. of Top,  
20 ins.

Fine Cast and Painted, 18 each.  
Painted and Bronzed, 21 "  
If with 21 in. diam. Sicilian Marble Top, 10 6 extra  
" " Rouge or St. Ann's Marble Top, 12 9 "

No. P 2123. **CAST-IRON TABLE**  
Oblong Top.




Height, 28 ins.

Fine cast and painted one coat,  
with bearing frame to receive  
top.

Sizes, 36 x 20 42 x 20 48 x 20 ins.  
Ironwork only, 18 9 19 6 22 6 p. set.  
Sicilian Marble Top, 15 18 21 extra.  
Rouge or St. Ann's Marble Top, 17 3 19 6 22 6 "  
Ironwork Bronzed, 7 6 extra.

No. P 2123. **CAST-IRON TABLE**  
Round Top.




Height, 30 inches.

Fine cast and painted one coat.  
Ironwork only, without Top, 16 6 p. set.  
" " Bronzed, 6 9 extra.  
" " Diam., 25 27 ins.  
Sicilian Marble Top, 12 9 15 9 extra.  
Rouge or St. Ann's Marble Top, 20 3 23 3 "


### UMBRELLA STANDS

No. R 5181.  
All Brass.




7 1/2 ins. deep.  
25 ins. high.  
Price, 24 each.

No. R 5182.  
All Brass.




9 ins. deep. 23 ins. high.  
Price, 26 3 each.

No. R 5183.  
All Brass, with Cast Iron Pans.



8 ins. deep. 25 ins. high.  
4 hole, 22 6; 6 hole, 24; 8 hole, 25 6;  
10 hole, 28 6; 12 hole, 31 6 each.

No. R 5184  
Wrought Iron



8 1/2 ins. deep. 26 ins. high.  
Price, 52 6 each.


No. R 5185.



9 ins. deep. 21 1/2 ins. high.  
No. R 5185. Wrought Iron, 51 each.  
No. R 5186. Wrought Iron and  
Copper, 67 6 each.


### SCRAPERS

No. R 3323



Price, 10 6 per doz.

No. R 3324



Plain, 15 p. doz.  
Ornamental, 17 6 "

No. R 3326.



Pan, 16 x 12 ins. Blacked, 4 each.

No. R 3325.


To drive,  
21 - per doz.  
For Stone,  
12 9 per doz.  
With Pan,  
13 1/2 x 10 ins.  
3 each.




No. R 1152.

To drive,  
21 - per doz.  
For Stone,  
12 9 each.  
With Pan,  
3 each.

No. R 3327.



Scraper, with Brushes, as drawn. Blacked.  
12 x 12 ins., 13 6 each. 12 x 15 ins., 17 3 each.



No. R 1228.  
Gravel Scraper

Sizes, 24 x 14 30 x 16 36 x 18 42 x 18 48 x 18 ins.  
Prices, 7 6 9 9 12 12 9 17 3 each.

# **PLUMBERS' AND SANITARY ENGINEERS' REQUISITES SECTION**

LEAD, ZINC, SOLDER, TIN, AND COPPER

ZINC GUTTERS      ▲ ▲ ▲      PIPES

**TUBES AND FITTINGS FOR STEAM, WATER, AND GAS**

**TOOLS FOR PLUMBERS   ▲ ▲   DRAIN CLEANSING APPARATUS**

**VENTILATORS · AND · SMOKE · CURING · APPLIANCES**

LEAD TRAPS AND BRASSWORK

▲ ▲ ▲ ▲ ▲ **PUMPS** ▲ ▲ ▲ ▲ ▲

DUST BINS, CORN BINS, AND SHEET

▲ ▲ ▲      IRON GOODS      ▲ ▲ ▲

CISTERNS, TANKS, AND CYLINDERS

**CLOSETS   ▲ ▲   URINALS   ▲ ▲   LAVATORIES**

**BATHS of all Grades**

GEYSERS



## Lead, Solder, Tin, and Zinc

The prices of Lead and Zinc vary daily according to the Market value of the crude materials which form the bases of their manufacture. Prices quoted on receipt of particulars and quantities required.

**LEAD**

Sheet Lead, in sheets, about $32 \times 7$ ft.	...	...	per cwt.
or half sheets, about $16 \times 7$ ft.	...	...	
(Kept in stock in 3, 4, 5, or 6 lbs. per ft.)			
Sheets $40 \times 8$ ft., and other sizes and substances rolled to order.			
Sheets measuring $32 \times 7$ ft. weigh approximately :—			
Substance ...	3	$3\frac{1}{2}$	4    5    6    7 lbs. to the foot.
	6	7	8    10    12    14 cwt. per sheet.
Lead Pipe, in Coils up to $1\frac{1}{2}$ ins. ...	...	...	per cwt.
" in Lengths 2 ins. and upwards ...	...	...	"
Lead Soil Pipe, 10-ft. lengths, 2 to 4 ins. round ...	...	...	"
" " " $4\frac{1}{2}$ to 6 ins. round ...	...	...	"
" " " $3\frac{1}{2} \times 3\frac{1}{2}$ ins., and $4 \times 3$ ins. square ..	...	...	"
Pump Barrels, Heads and Nozzles ...	...	...	"
Composition Gas Tubing, in $\frac{1}{2}$ -cwt. Coils ...	...	...	"
London Patent Shot, in 14 or 28 lb. bags ...	...	...	"
Window Lead, in $\frac{1}{2}$ -cwt. bundles ...	...	...	"
Laminated Lead, for Damp Walls, in $\frac{1}{2}$ -cwt. rolls ...	...	...	"

## SOLDER

Plumbers', ordinary quality	...	...	...	...	per lb.
" best	"	(branded " Sun Brand ")	...	...	"
Tinman's, best	"	...	...	...	"
Blowpipe, best	"	...	...	...	"
Rushes, best	"	...	...	...	"

**TIN**

"Lamb and Flag," in Ingots	...	...	...	...	per lb.
" " in Strips	...	...	...	...	"
Tin Pipe, in Coils	...	...	...	...	"
Tin Encased Pipe, in Coils	...	...	...	...	per cwt.
Lead Pipe, tinned inside	...	...	...	...	"
Tin Plates	...	...	...	...	per box.

Complete List of Sizes and Weights of Lead Pipe manufactured. Those kept in our Stock are indicated by larger letterpress—any of the remainder supplied promptly.

		Inch.	Lbs.																
Weight per 15 ft.	A	...	25																
	1	...	15																
	2	...	10	15	20														
	3	...	10	15	<b>20</b>	<b>25</b>	30												
	4	...	11	14	<b>15</b>	16	<b>18</b>	20	<b>22</b>	<b>25</b>	28	<b>30</b>	35	40					
	5	...	16	<b>18</b>	20	<b>22</b>													
	6	...	<b>17</b>	<b>21</b>	25	30	35	<b>40</b>	<b>45</b>	50									
	7	...	<b>22</b>	<b>24</b>	<b>26</b>	<b>28</b>	<b>30</b>	<b>32</b>	<b>36</b>	40	<b>45</b>	50	55	60					
	8	...	28	<b>36</b>	45														
	1	...	<b>30</b>	<b>36</b>	<b>42</b>	<b>45</b>	48	52	56	<b>60</b>	64	70	80						
Weight per 12 ft.	1	...	42	52	60	68	76												
	1	...	28	30	<b>36</b>	<b>42</b>	<b>48</b>	52	<b>56</b>	60	64	72	80						
	1	...	28	36	<b>42</b>	<b>48</b>	<b>56</b>	60	<b>63</b>	68	72	84	96						
	1	...	60	72	84	96													
	2	...	40	48	<b>56</b>	60	<b>72</b>	<b>84</b>	96	112	120	144							
Weight per 10 ft.	2	...	100	132															
	2	...	70	84	96	112	120												
	2	...	100	125															
	3	...	100	112	120	130	140	150											
	3	...	112	130	150	160	180												
	4	...	140	160	170	200	220	300											
	4	...	140	170	220														
	5	...	150	220	250														
Weight per 10 ft.	5	...	220																
	6	...	220																

## SOIL PIPE

	Ins.	Lbs.					
Weight per 10 ft.	2	...	36				
	2½	...	36	45	50	60	
	3	...	45	53	60	68	74 80
	3½	...	52	60	70	80	90
	4	...	56	60	70	80	100 112
	4½	...	70	80	90	100	112
	5	...	75	88	100	112	
	5½	...	90	106			
6	...	90	106	120			

## SQUARE SOIL PIPE

**3½ × 3½ ins.      4 × 3 ins.**

## COMPOSITION PIPE

$\frac{1}{8}$   $\frac{11}{16}$   $\frac{1}{4}$   $\frac{1}{16}$   $\frac{1}{8}$   $\frac{1}{16}$   $\frac{1}{8}$   $\frac{1}{16}$   $\frac{1}{8}$   $\frac{1}{16}$   $\frac{1}{8}$   $\frac{1}{16}$  ins.

OLD LEAD allowed for as Cash at per cwt., at our Stratford Depots. Trade Draft, 4 lbs. per cwt.

01.D METALS can only be received, irrespective of mode of transit, and credited by us at the actual scaleweight at our Works or Mills—subject to the usual Trade Draft. Freight must be prepaid by consignor, who possesses the privilege of electing a representative to inspect the weighings in.

## ZINC

Lipini Sheet Zinc, Nos. 9 to 16 Gauge...	...	...	...	per cwt.					
Vieille Montagne Sheet Zinc, Nos. 9 to 16 Gauge	...			„					
Gauges Stocked, Nos.	6	9	10	11	12	13	14	15	16
Approximate weight of	1	10 15½	17½	20	22½	25½	28½	32½	37½ lbs.
8 x 3 ft. Sheet	...								

No. 6 is per cwt. extra.

Perforated Sheet Zinc, 8 x 3 ft. (small hole) ... ..		per sheet.
Zinc Slating Nails, 1½ in. and upwards ... ..		per cwt.
Zinc Bell Tubing ... ..	¾      1      1½ in.	"
		per cwt. extra.
Zinc Capping, Round or Square ... ..		per cwt.
Old Zinc allowed for as cash at ... ..	cwt.	
Old Brass " "	"	} at our Stratford Depots.
Old Brazieri Copper " "	"	
Old Clean do. " "	"	

# Zinc Gutters, Pipes and Fittings

We guarantee these to be strong and well made. The O.G.'s are of No. 10 Gauge.



No. P 353.  
Round Pipe.

Sizes, ...	1 1/2	1 3/4	2	2 1/2	3	3 1/2	4	4 1/2 inches.
P 351. Half-round Gutter,	-	-	-	-	1 6	1 8	1 10 1/2	2 3 per 7-ft. length.
P 352. O.G. Gutter,	-	-	1 7 1/2	1 9	2 -	2 4 1/2	2 9	3 - .. ..
P 353. Round Pipe,	1 4 1/2	1 6	1 9	2 3	2 6	2 10 1/2	3 3	.. ..
P 1489. Elbow,	7 1/2 d.	7 1/2 d.	9 d.	10 1/2 d.	1 -	1 6	1 9	each.
P 1490. Bend,	9 d.	9 d.	1 -	1 3	1 6	1 9	2 3	..
P 1491. Shoe,	9 d.	9 d.	1 -	1 3	1 6	1 9	2 3	..
P 355. Square Head,	1 6	1 6	1 9	2 -	2 3			..
P 356. Bell Head,	1 6	1 6	1 9	2 -	2 3			..

Sizes, ...	1 1/2 x 1	2 x 1 1/2	2 1/2 x 2	3 x 2 1/2	4 x 3 inches.
P 354. Square Pipe,	3 6	4 -	4 3	4 10 1/2	5 9 per 7-ft. length.

Sizes, ...	1 1/2	2 inches.
No. 12 Gauge Square Capping,	1 9	2 4 1/2 per 8-ft. length.




No. P 354.  
Square Pipe,  
with  
Ornamental  
Mountings.

O.G. Gutters can be supplied in Nos. 11, 12, or 14 Gauge, to order.

## PERFORATED SHEET ZINC


No. 9 Gauge. In Sheets, 8 x 3 feet.

Meat Safe Hole




Perforation No. 8.  
Price, 6 6 each.

Bird Cage Pattern




Perforation No. 15 G.  
Price, 7 6 each.

Fancy Pattern



Perforation No. 16 G.  
Price, 7 6 each.

Diamond Pattern




Perforation No. 21 D.  
Price, 7 6 each.

Any pattern cut to sizes, price, 6d. per foot super.


The designs shown are those mostly in demand, but we can supply any other pattern upon receipt of particulars.

## No. P 70. ZINC FRETS



Fret Nos.,	56	70	35	34	28	29
Width, ...	1 1/2	1 1/2	2 1/2	2 1/2	2 1/2	4 1/2 inches.
Prices, ...	1 3	1 9	2 3	2 3	3 4 1/2	3 9 per 8-ft. length.


## ZINC BELL TUBING



Prices, ...	4 1/2 d.	5 1/2 d.	6 1/2 d.	8 1/2 d.	10 1/2 d.	1 3 per 8 ft. length.
-------------	----------	----------	----------	----------	-----------	-----------------------


## Lead Traps and Sundries

No. P 1916. Cast Lead P Trap




Sizes, 1 1/4 1 1/2 2 ins.  
With Brass Access Screw, 2/6 3/- 4 - each.

No. P 1917. Cast Lead S Trap



Sizes, 1 1/4 1 1/2 2 ins.  
With Brass Access Screw, 2/9 3/3 4/9 each.


No. P 2199. Cast Lead Junction  
8 lbs. Lead.



With Arm, 9 12 15 18 24 ins.  
Prices, 12/6 13/6 14/9 15/- 18/- each.


### Hellyer's Patent Cast Lead "Anti-D" Traps

No. P 343.



4 1/2 to 4 inches.  
8 lbs. lead, for water-closets,  
slop-sinks, &c.  
Price, 10 - each.

No. P 344.




3 1/2 to 2 inches.  
9 lbs. lead, for sinks,  
baths, &c.  
Price, 5 6 each.

No. P 345.



1 1/2 inches.  
9 lbs. lead, for lavatories,  
&c.  
Price, 3 - each.


No. P 346.



1 1/2 inches.  
With enlarged mouth, for  
sinks, baths, &c.  
Price, 3/3 each.

If with Brass Screw-cap to Traps Nos. P 344, P 345 and P 346, 1/6 extra.  
Nos. P 344, P 345, and P 346 will be sent with Brass Screw-cap unless otherwise ordered.

No. P 1640. Lead Pipe Clip




Bore of Pipe,	1	1 1/2 ins.
Prices, ..	2 - 2 9	3 3 per doz.
Bore of Pipe, ..	1 1/2	2 ins.
Prices, ..	4 6	7 6 per doz.

Clips are made to fit external diameter of pipes of the bore given above.

No. P 1630.


#### Single Cast Lead Tack

Equal to 10 lbs. lead.



For Pipes	1 1/2	2	2 1/2 ins.
Prices, ..	3 - 3 3	5 -	per doz.
For Pipes	3	3 1/2	4 ins.
Prices, ..	7 - 8 3	10 6	per doz.

No. P 3729.  
Patent Lead Soil Pipe Terminal









Sizes,	2	2 1/2	3	3 1/2	4 ins.
Prices,	2/9	3/6	4/6	5/-	5/6 each.

# Hydraulic Drawn Lead Traps

MADE FROM PURE PIG LEAD BY HYDRAULIC MACHINERY.

Special Shapes to Order at Short Notice.

No. P 1901. Full S Trap		No. P 1902. Open S Trap		No. P 1903. P Trap		No. P 1904. Bath Trap		No. P 1905. Short Bend		No. P 1906. Long Bend	
											
Size.	Weights.			P 1901. With Screw.	P 1902. With Screw.	P 1903. With Screw.	P 1904. With Screw.		P 1905. SHORT BEND. without Screw.		P 1906. LONG BEND. without Screw.
1 1/4 ins.,	4 1/2 lbs.,	..	..	1/6	..	1/5	..	1/3	6d.	..	8d. each.
	6 "	..	..	1/10	..	1/9	..	1/4	8d.	..	10d.
	7 "	..	..	2/-	..	1/10	..	1/6	9d.	..	1/-
	8 "	..	..	2/4	..	2/3	..	1/9	10d.	..	1/1
1 1/2 ins.,	5 "	..	..	1/11	..	1/10	..	1/6	8d.	..	10d.
	6 "	..	..	2/4	..	2/1	..	1/9	10d.	..	1/-
	7 "	..	..	2/7	..	2/5	..	1/11	11d.	..	1/3
	8 "	..	..	3/-	..	2/9	..	2/3	1/1	..	1/5
1 3/4 ins.,	5 1/2 "	..	..	2/9	..	2/6	..	2/3	11d.	..	1/3
	7 "	..	..	3/3	..	3/-	..	2/4	1/2	..	1/7
2 ins.,	5 "	..	..	2/10	..	2/7	..	2/2	11d.	..	1/2
	6 "	..	..	3/2	..	3/1	..	2/5	1/1	..	1/6
	7 "	..	..	3/8	..	3/6	..	2/8	1/3	..	1/8
	8 "	..	..	4/4	..	4/2	..	3/4	1/7	..	2/1
2 1/4 ins.,	5 "	..	..	3/11	..	3/7	..	2/11	1/3	..	1/8
	6 "	..	..	4/4	..	4/2	..	3/4	1/5	..	1/11
	7 "	..	..	4/11	..	4/10	..	3/10	1/8	..	2/4
	8 "	..	..	5/5	..	5/4	..	4/1	1/11	..	2/6
3 ins.,	5 "	..	..	4/11	..	4/8	..	3/7	1/7	..	2/-
	6 "	..	..	5/8	..	5/6	..	4/3	1/10	..	2/5
	7 "	..	..	6/5	..	6/5	..	5/-	2/1	..	2/6
	8 "	..	..	7/6	..	7/2	..	5/6	2/5	..	3/2
3 1/2 ins.,	5 "	..	..	6/3	..	6/1	..	4/11	1/11	..	2/6
	6 "	..	..	6/9	..	6/7	..	5/3	2/3	..	3/-
	7 "	..	..	8/-	..	7/6	..	6/1	2/8	..	3/6
	8 "	..	..	9/2	..	8/11	..	7/1	3/2	..	4/2
4 ins.,	5 "	..	..	7/2	..	7/2	..	6/6	3/-	..	3/3
	6 "	..	..	8/6	..	8/1	..	6/11	3/3	..	4/-
	7 "	..	..	10/2	..	10/-	..	7/8	4/-	..	5/-
	8 "	..	..	10/9	..	10/7	..	8/2	5/-	..	5/9
4 1/2 ins.,	6 "	..	..	10/2	..	9/7	..	7/3	4/-	..	5/3
	8 "	..	..	12/9	..	12/2	..	9/2	5/3	..	6/9

For Cast Lead Traps, Lead Junctions, and "Anti-D" Traps, see page 138.  
Special shape Lead Bends and Offsets, see page 140.

## Lead Bends, Offsets, and Traps

SPECIAL SHAPES.

Nos. P 1909 and P 1910.



No. P 1909. 4 x 26 1/2 ins.  
6 lbs., .. 8/- each.  
8 " .. 10/6 "

Nos. P 1911 and P 1912.



No. P 1911. 4 x 28 ins.  
6 lbs., .. 10/- each.  
8 " .. 13/- "

Nos. P 1913 and P 1914.



No. P 1913. 4 x 28 ins.  
6 lbs., .. 9/- each.  
8 " .. 11/3 "


No. P 1915.



	6 lbs.	8 lbs.
4 x 8 x 12 ins., ..	5/-	6/6
4 x 8 x 18 " ..	6/6	8/6
4 x 8 x 21 " ..	7/3	9/6
4 x 8 x 24 " ..	8/-	10/6
4 x 9 x 30 " ..	9/9	12/6
4 x 9 x 36 " ..	11/3	14/3
4 x 9 x 40 " ..	12/6	15/9

## Plumbers' and Tinmen's Tools

No. P 1304. Bossing Mallet



Small Medium Large  
Boxwood, 1/9 2/3 2/9 each.

No. P 1395. Tinman's Mallet



Sizes, .. 2 1/2 3 3 1/2 ins.  
Boxwood, 1/3 1/9 2/- each.

No. P 1392. Plumber's Dresser



Small Medium Large.  
Boxwood, 2/3 3/- 3/3 each.


No. P 1396.

Boxwood Chase Wedge



2 2 1/2 3 3 1/2 4 ins.  
1/- 1/1 1/6 1/9 2/- each.

No. P 1389. Straight Copper Bit



Price, .. 1/9 per lb.

No. P 1397.  
Boxwood Turnpin



1 in., .. 3/9 doz.  
1 1/2 " .. 4/6 "  
2 " .. 6/- "  
2 1/2 " .. 9/- "  
3 " .. 12/- "

No. P 1526.  
Boxwood Bobbin

1 in., .. 2/6 doz.  
1 1/2 " .. 3/9 "  
2 " .. 6/- "  
2 1/2 " .. 9/- "  
3 " .. 15/- "  
3 1/2 " .. 21/- "  
4 " .. 30/- "


No. P 1385.

Plumbers' Metal Pots  
With Wrought Ball Handles.



4 5 6 7 8 ins.  
1/3 1/9 2/- 2/6 3/6 each.

No. P 1383. Hatchet Copper Bit



Price, .. 1/10 1/2 per lb.

No. P 1387. Plumbers' Ladles



Sizes, .. 2 1/2 3 3 1/2 4 4 1/2 5 6 ins.  
Prices, .. 6d. 7 1/2 d. 9d. 1/- 1/1 1/2 1/6 2/- each.

No. P 4618. Billing's Patent Pipe Bender



Sizes, 1 1 1/2 1 3/4 ins. diam.  
Prices, 2/6 3 6 5/- each.

Sizes, .. 2 3 ins. diam.  
Prices, .. 7/- 16/9 each.

## The "Perfik" Roof Slate Fastener

No. P 6329.


Packed in one gross boxes, complete with Galvanized Wedges.

Price, .. 11/3 per gross.

Not less than Gross Lots supplied.

DIRECTIONS FOR FIXING PATENT FASTENER.


Remove damaged Slate. Replace with new one X. Slip the flanges A B of Strap under the old slates Y Z, the part C standing up between the same. Push the strap upwards until the notch in part C retains the bottom edge of the new slate X. Insert the wedge D into the hole in Fastener, and drive it until sufficiently wedged to secure the slate from slipping.



# Barron's Patent "Anti-Foul" and Accessible Sink Traps

MADE TO L.C.C. REQUIREMENTS AND SUITABLE FOR ALL SINKS.  
AS SUPPLIED TO H.M. GOVERNMENT WORKS.


No. P 6570.



Galv. C.I. Trap with S.P. or Q Plain  
Outlet and Brass Grate, .. 5/-  
Galv. C.I. Trap with S.P. or Q Screwed  
Outlet and Brass Grate, .. 6/3  
Grates are made 2½, 3, 3½, and 4 ins.  
diameter.  
3-in. Grates sent out unless other  
size ordered.

WATER SEAL, 2 Inches.


No. P 6570. Cross Section



None genuine without this  
Trade Mark.




No. P 6571.




Galv. C.I. Trap with S.P. or Q Plain  
Outlet and Brass Plug and Grate, .. 6/9  
Galv. C.I. Trap with S.P. or Q Screwed  
Outlet and Brass Plug and Grate, .. 8/-

No. P 6572.



Galv. C.I. Trap with S.P. or Q Plain  
Outlet and Brass Waste Plug  
and Washer, .. 12/6  
Galv. C.I. Trap with S.P. or Q  
Screwed Outlet and Brass Waste,  
Plug and Washer, .. 13/-  
Brass Trap with S.P. or Q Plain  
Outlet and Brass Waste, Plug  
and Washer, .. 24/6  
Brass Trap with S.P. or Q Screwed  
Outlet and Brass Waste, Plug  
and Washer, .. 25/6


No. P 6572.  
Longitudinal Section



Observe on Section P 6572, the  
advantages of these Accessible  
and Self-cleansing Traps with  
Grate **below** not above Over-  
flow as hitherto made, ensuring  
a sound connection between the  
2½ to 2 in. tapered Brass Waste  
and Sink at Overflow, also  
access for sweeping.

All Clearing Caps are made  
thoroughly watertight, with  
specially prepared greased hemp,  
forming a perfect seating. Each  
Trap is tested before being sent  
out to customers.

# Wrought-Iron Gas, Steam, and Water Tubes and Fittings, PAINTED OR GALVANIZED.



**STANDARD  
LIST**

**STANDARD  
LIST**

Nominal Internal Diameter in Ins.,	1/4	1/2	3/4	1	1 1/4	1 1/2	1 3/4	2	2 1/4	2 1/2	2 3/4	3	3 1/4	4	4 1/2	5	5 1/2	6
<b>TUBES.</b>																		
1 Tubes, 2 ft. long and over, per ft.,	3/4	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
2 Pieces, 12 to 2 1/2 ins. long, each,	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
3 " 4 to 11 1/2 " " "	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
4 Long Screws, 12 to 2 1/2 ins., " "	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
5 " 3 to 11 1/2 " " "	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
23 Barrel Nipples, " " " "	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
6 Bends, " " " "	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
7, 8, 9, Springs, not socketed, " "	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
<b>FITTINGS.</b>																		
10, 11, Socket or Pipe Union, each, 2/	2/6	3/	4/	5/6	6/9	8/	9/	10/	15/	17/6	20/	22/6	27/6	35/	48/	66/	84/	105/
12 Elbows, Square, " " "	8/	9/	10/	1/	1/10	2/5	3/	3/10	6/3	9/	11/6	14/	22/	28/	35/	45/	55/	65/
13 " Round, " " "	9/	11/	1/	1/3	1/6	2/1	2/7	3/6	6/9	10/	13/	17/	25/	32/	40/	50/	60/	70/
14 Tees, " " " "	9	10	11	1/2	1/5	2/	2/6	3/2	6/6	9/6	12/6	16/6	24/	30/	38/	48/	58/	68/
15 Crosses, " " " "	1 4	1/6	1/11	2/4	3/	4/	4/10	6/	14/	21/4	28/	40/	56/	72/	90/	110/	130/	150/
16 Sockets, Plain, " " "	2	2/	3/	3/4	4/	5/	5/8	6/	1/9	2/6	3/	3/6	5/	6/	7/	8/	9/	10/
17 " Diminished, " " "	3	4	5	6	7	8	9	10	2/3	3/3	4/	5/	7/	9/	11/	13/	15/	17/
18 Flanges, " " " "	9	10	11	1/2	1/4	1/9	2/	2/3	4/	5/	6/9	8/6	10/	11/6	13/	15/	17/	19/
19 Caps, " " " "	3	3/	4/	5/6	7/8	1/	1/3	1/7	3/	4/4	5/3	6/	9/9	10/6	12/	14/	16/	18/
20 Plugs, " " " "	3	3/	4/	5/6	7/8	1/	1/3	1/7	2/	2/6	3/6	4/9	7/	10/	12/	14/	16/	18/
21 Backnuts, " " " "	2	2/	3/	3/4	5/6	7/8	1/	1/3	1/9	2/3	3/	3/6	4/6	5/6	7/	8/	9/	10/
22 Nipples, " " " "	2	2/	3/	3/4	5/6	7/8	1/	1/3	1/9	2/3	3/	3/6	4/6	5/6	7/	8/	9/	10/
24 Union Bends, " " " "	2 6	3/	3/9	5/	6/3	8/6	10/	11/6	21/	27/	32/	37/	49/	58/	72/	88/	105/	120/
25 Main Cocks, " " " "	2 3	2/9	3/6	4 6	6/6	8/6	11/	14/	27/	40/	50/	60/	85/	110/	140/	170/	210/	250/
26 " with Brass Plugs, " " "	7/	8/9	11 6	16/	21/6	28/	35/	45/	68/	100/	125/	150/	212/	250/	300/	360/	420/	480/
27 Roundway Cocks, " " "	3 6	4/	5 6	7/6	10/	13/	17 6	22/	38/	60/	75/	90/	120/	160/	200/	240/	280/	320/
28 " with Brass Plugs, " " "	10 6	12/	16/6	22 6	30/	39/	52/6	66/	114/	180/	225/	270/	360/	480/	600/	720/	840/	960/
29 Cock Spanners, Wrought, " " "	1/6	1/8	2/2	2/8	3/2	3/6	4/	4/3	4 9	6/	7/6	9/	12/	14/	16/	19/	22/	24/
30 " Malleable Cast, " " "	1	1/4	1/8	2/	2/4	3/	3/6	4/	4 9	6/	7/6	9/	12/	14/	16/	19/	22/	24/
31 Syphon Boxes, 1 quart, " " "	22/9	23/	23/4	24/	24/6	25/2	26/3	28/6	32/6	35/6	38/6	42/6	55/6	61/6	70/	80/	90/	100/
32 " " 2 " " "	27/	27/4	28/	28/6	29/2	30/3	32/6	35/6	37/6	40/6	43/6	47/6	55/6	61/6	70/	80/	90/	100/
33 " " 3 " " "	32	32/4	33/	33/6	34/2	35/3	37/6	40/6	43/6	46/6	49/6	53/6	61/6	67/6	78/	90/	100/	110/
34 " " 4 " " "	38/	38/4	39/	39/6	40/2	41/3	43/6	46/6	49/6	53/6	57/6	61/6	70/	80/	90/	100/	110/	120/

Current Discounts from Standard List, as above, quoted specially to enquiry giving particulars and quantity required.

## NOTES.

TUBES SCREWED AND SOCKETED, supplied in random or exact lengths from 2 to 12 feet, and all exact lengths over 12 feet are charged at 2 1/2 per cent. less gross discount.

TUBES, NOT SCREWED OR SOCKETED, supplied in random lengths of any length are charged at the current discount, with an extra allowance of 2 1/2 per cent. off the nett.

TUBES, NOT SCREWED OR SOCKETED, cut to exact lengths of any length, are charged at the same discount as Tubes screwed and socketed in random lengths.

TUBES, SCREWED, AND SENT WITHOUT SOCKETS, are charged at the current discount, with an extra allowance of 1 1/2 per cent. off the nett.

TUBES AND FITTINGS coated inside and outside [with Dr. Angus Smith's Solution, are charged at 2 1/2 per cent. less gross discount.

TUBES AND FITTINGS painted red will be charged at STEAM DISCOUNTS.

TUBES AND FITTINGS painted blue will be charged at WATER DISCOUNTS.


ALL SHORT LENGTHS, 4 inches to 2 feet, whether random or exact, to be considered pieces, and sold at gross prices of pieces, less same discounts as Tubes of random lengths.

TUBES OF INTERMEDIATE DIAMETERS are charged at the list price of the next larger size.

SPRINGS, IF SOCKETED, will be charged extra for the Sockets at list prices.


# Drain Plugs, Testers, Vacuum Pumps, and Rubber Goods

(No. P 4623. **Jones' Patent Expanding Screw Stopper**  
For Testing Drains with Water.



Sizes, ...	4	6	9	12 ins.
Prices, Galvanized Iron, with Centre Outlet,	10 6	14 9	27 -	42 - each.
" " " without " "	10 6	14 9		" "

In ordering, please state with or without centre outlet.




No. P2164.  
**Cooper's Patent Vacuum Pump**

This special sanitary appliance is for removing obstructions in closet traps, drains, soil pipes, baths, sinks, stack pipes, &c.


Price, 7/6 each.

No. P 4662.  
**Banner's Patent Rapid Drain Tester**



Price, ... 1/- each.


No. P 4663.  
**Kemp's Patent Drain Tester**



Full size.


Price, ... 10½d. each.

No. P 4620.  
**Force Cup**



Small, 1 6; Medium, 3 9  
Large, 6- each.

No. P 4185.  
**Cooper's Patent Vacuum Pumps**



No. 2, 27 - each.

No. 3, 13 6 each.

No. 2 is a 9-inch Pump with angle, and is suitable for closet traps and 4 and 6 inch gullies and 4 and 6 inch pipes, and always to be used on the surface of the same.

No. 3 represents the 5½-inch Pump with new junctions for lengthening or shortening, as may be required by the user. This is adapted for all classes of work up to a radius of 5 inches.

## India Rubber and Canvas Delivery Hose for Pumps

Three Ply.

Internal Diameter,	½	¾	1	1½	2 ins.
Prices, per foot, ...	10½d.	1/3	1/6	1/9	2/- 2 7½

## India Rubber and Canvas Suction Hose for Pumps, with Spiral Wire

Three Ply.

Internal Diameter,	1	1½	2	2½	3 ins.
Prices, per foot, ...	1/9	2 3	2 7½	3-	3 4½

## India Rubber Hot-water Rings for Socket Pipes

Price, ... 6- per lb.

## Rubber Valves for Water Waste Preventers

Best Quality- 2 ins; Thin, 1/6; Thick, 2- per dozen.

" 2½ " " 2/3; " 4- "

Thick always sent unless otherwise ordered.

Any other sizes or qualities, or Plumbers' Rubber Goods not enumerated in the above list, quoted for specially upon receipt of details.

## Sheet Rubber

Quality No. 1, 6/9; No. 2, 5/3; No. 3, 3/9 per lb.

## Shanks' Rubber Bath Cones

Sizes, ...	1½	1¾	ins.
Prices, ...	7½d.	9d.	10½d. 1/1½ each.

## Closet Seat Buffers

Best, ... 1 3 per doz.; Common, ... 10½d. per doz.

## Beer Pipe Joints

No. 1 quality, 2 ins., 6/-; No. 2 quality, 2 ins., 4/6 per doz.


## Grant's Valve Washers

Large, 3½ ins. diameter, with 1 in. hole, ...	7½d. each.
" 3½ " " " 1½ " " ...	7½d. "
Medium, 3 " " " 1 " " ...	6d. "
Small, 2½ " " " 1 " " ...	6d. "



# Drain Cleansing and Chimney Sweeping Apparatus and Accessories

No. P 3000. **Drain Cleansing Apparatus**




Complete set with 3-foot rods, roller guide, worm screw, and plunger.

Sizes, 30 40 60 80 100 feet.  
Prices, **22/6 30/ 45/ 57/- 75/-** per set.

Sweep's Head Brush, **4/6** extra.  
6-inch Drain Brush, **3/9** „


No. P 4419. **Chimney Sweeping Machine**



A very complete and useful Chimney Sweeping Machine at a low price, suitable for builders, farms, hotels, &c., of excellent quality and guaranteed to give satisfaction. Each Machine consists of specially-tested red malacca canes fitted with interchangeable brass screws, steel-riveted 16 or 18 inch chimney brush, hand brush, soot shovel, best hair flue brush, chimney cloth to cover fire-place, with cloth slide stretcher for same, and straps.

Prices 40 feet, **57/6**; 60 feet, **75/6**; 80 feet, **96/-**; 100 feet, **111/-** per set.

No. P 6328. **The Contractor's Machine**




Consisting of red malacca canes, brass clearing wheel, double worm screw, 4-inch water-closet stout rubber plunger in brass fittings, for unstopping water-closets. Drain brush and straps.

Sizes, .. 30 40 50 60 70 feet.  
Prices, .. **33/- 39. 45- 54 - 60/-** per set.

Sizes, .. 80 90 100 150 200 feet.  
Prices, .. **69/- 75 - 81 - 117/- 150/-** per set.

No P 6135. **The "Council" Machine**

Fitted with Interchangeable Brass Screws.



This is a high-class machine, the canes used being a special tough and sound malacca. Only best whalebone, iron forgings and best brass castings used. Supplied in 36-inch lengths, including 4 or 6 inch whalebone head, double worm screw, 4-inch drop scraper, 4-inch rubber plunger, and brass clearing wheel.

Sizes, 30 40 50 60 70 feet.  
Prices, **42/- 49/6 60 - 66/9 75/9** per set.

Sizes, 80 90 100 150 200 feet.  
Prices, **84 - 92/3 100/6 144/- 183/9** per set.

No. P 5118. **Patent Swivel Collar Locking Joint Set, Extra Strong Pattern**

For Drains, Sweeps, Electrical and Telephone Work.

With 6-inch Whalebone Head, Double Worm Screw, 4-inch Drop Scraper, Rubber Plunger and Brass Wheel.




The Joint is made of cast brass and is the simplest and most satisfactory locking joint yet produced, being simpler than the ordinary pattern, but at the same time a perfect locking joint. The locking is accomplished by the square head engaging in a slot in the ferrule. Particular attention is drawn to the fact that there is nothing to get out of order. No springs. No loose ferrules to get lost. No pins. No projections on the outside of ferrules. No space where dirt can collect. Only the best malacca canes used, which are specially selected to fit ferrules without paring down and are free from dry rot.

Sizes, .. 30 40 50 60 70 80 90 100 150 200 feet.  
Prices, .. **51- 60 - 72 - 84/- 96- 104 - 120/- 130/- 180/- 228/-** per set.


## Fittings for Drain Machines

No. P4656.  
Indiarubber Plunger  
With Brass Cup.



Sizes, 4 5 6 ins.  
Prices, 3/- 3/9 4/6 each.

No. P4657.  
Plain Scraper



Size, 4 ins.  
Price, 2/9 each.

No. P4658.  
Folding Scraper



Sizes, 4 6 ins.  
Prices, 3 - 3 9 each.

No. P4659.  
Gun-metal  
Clearing Wheel



Price, 3 9 each.

No. P4660.  
Universal  
Clearing Wheel



Price, 4 6 each.

No. P4661.  
Brass  
Clearing Wheel



Price, 2 9 each.

No. P5817.  
Whalebone Brush  
In Brass Fittings,  
as Illustrated.



Sizes, 4 6 9 ins.  
Prices, 8/- 9/- 10/1½ each.

**Brass Heads**  
With Brass Sockets.  
Sizes, 4 6 9 ins.  
Prices, 4/- 4/6 5/3 each.

No. P5747.  
Drop Scraper  
With Guide Wheel.



Price, 7/6 each.

No. P5748.  
Steel Tipped Coring  
Iron  
With Guide Wheel.



Price, 7/6 each.

No. P5749.  
Double Worm Screw  
With Guide Wheel.



Price, 7 6 each.

No. P4654.  
Double Worm Screw




Price, 2 9 each.

No. P5750.  
Archimedean Screw.




Price, 2/6 each.

## The "Ferret" Flexible Spring Drain Cleaner



(Showing section of Water-closet Pan  
and Trap with Cleaner passing through.)

No. P6136.



Showing Cleaner passing through  
Gully Trap.



HANDLE.



JOINT.

The Flexible Drain Cleaner is formed of the finest steel wire, closely coiled to transmit the thrust of the handle throughout the whole length.

It is still so flexible that, as will be seen from the illustration, the Cleaner may be passed through such abrupt bends as occur in a gully or water-closet trap - an impossibility with ordinary cane rods.

Any number of lengths may be added as required, and, owing to its spiral formation, the Cleaner can be twisted and turned to right or left in the drain, whereby the screw point can get a grip of and disintegrate an obstruction.

Obstructions can usually be removed by applying the Cleaner at a gully, water-closet, or any other inlet, thus obviating the frequent necessity of opening up the ground and breaking into a drain.


The Cleaner may be applied with advantage to ordinary cane rods, and an adapter joint is supplied with each set for this purpose.

Price per set, 6 feet long (in two 3 feet lengths), including Handle, Adapter Joint for cane rods, and Tool for unscrewing the Joints, without which the Joints cannot be unfasted under any circumstances, ... 15/9

Extra 3 feet Jointed Lengths, 6/- each.


# Plumbers' Brass Work

No. P 26B.  
**Light Bib Cock**  
Screw Boss.




Diam., ... 1/2 in.  
Price, ... 2 1/4 each.

No. P 28 1/2.  
**Screw-down Bib Cock**  
Heavy. "School Board" Pattern.




Diam., ... 1/2 3/4 1 in.  
Prices, with Key, 4 3 6 6 9 9 each.

No. P 31.  
**Screw-down Bib Cock**  
With Union on Nose for Hose.



Diam., ... 1/2 3/4 1 in.  
Prices, ... 4 6 9 6 each.

No. P 26.  
**The "Don"**  
Special Value.



Diam., ... 1/2 3/4 in.  
Prices, ... 2 9 4 6 each.

No. P 35 1/2.  
**Horizontal Screw-down Bib Cock**  
Right or Left Hand.




Diam., ... 1/2 3/4 in.  
Prices, ... 3 9 5 9 each.

No. P 262.  
**Capstan Head Bib Cock**  
Lettered Hot or Cold.




Diam., ... 1/2 3/4 1 in.  
Yellow Metal, Light, 3 4 5 each.

No. P 35. **Bib Cock**  
Extra Strong.




Diam., 1/2 3/4 1 1 1/2 1 3/4 in.  
Prices, 3 3 5 3 9 18 25 6 each.

No. P 6490.  
**China Disc Crutch Cock**  
Hot or Cold.



Diam., ... 1/2 in. (Light). 3/4 in. (Medium).  
Prices, 2 6 5 - each.


No. P 6491.  
**Capstan Head Bib Cock**  
Heavier Pattern. Gun Metal.



Diam., ... 1/2 3/4 1 in.  
Prices, ... 3 6 4 6 7 6 10 6 each.


# Plumbers' Brass Work

No. P 24. **Stop Cock**  
Light Pattern. For Lead.




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
Prices, 2/3 3/9 5/6 10/6 13/6 each.

No. P 29. **Screw-down Stop Cock**  
Tinned and Screwed.




Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$  1 in.  
Prices, ... 2/9 3/9 6/9 each.

**Screw-down Stop Cock**  
Male Ends.




Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$  1  $1\frac{1}{4}$  ins.  
No. P 30. Light, 2/6 4/- 5/9 11/6 each.  
,, P 705. Strong, 3/6 5/6 8/- 18/- ..

No. P 6575. **Double Union Stop Cock**  
Polished Body. Medium Weight




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
Prices, 4/- 6/- 8/9 17/- 20/- each.

No. P 33. **Stop Cock**  
Heavy Pattern. For Lead.



Diam.,  $\frac{1}{2}$   $\frac{3}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
Prices, 3/6 5/- 7/6 13/6 17/3 each.

No. P 23. **Stop Cock**  
Union both ends. "East London" Pattern.




Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$  1 in.  
Prices, ... 4/- 6/3 each.

**Screw-down Stop Cock**  
Male and Female Ends.




Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$  1  $1\frac{1}{4}$  ins.  
No. P 6493. Light, 2/6 4/- 5/9 11/6 each.  
,, P 6494. Strong, 3/6 5/6 8/- 18/- ..

No. P 5482. **Bar Basin Cock**  
With Union.




Diam., ...  $\frac{1}{2}$  in.  
Price, ... 3/6 each.

No. P 6492. **Stop Cock**  
Male Inlet. Union Outlet. Medium Weight.




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
Prices, 3/6 5/3 7/6 15/9 18/- each.

No. P 26 $\frac{1}{2}$ . **Heavy Stop Cock**  
"School Board" Pattern. With Loose Key.



Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$  1 in.  
Ends for Lead, ... 4/- 6/- 9/- each.  
Ends Screwed for Iron, 4/3 6/6 9/6 ..  
Union Ends, ... 5/9 8/- 11/6 ..

**Screw-down Stop Cocks**  
Female Ends.



Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$  1  $1\frac{1}{4}$  ins.  
No. P 4508. Light, 2/6 4/- 5/9 11/6 each.  
,, P 6495. Strong, 3/6 5/6 8/- 18/- ..

No. P 21. **Bent Main, Ferrule**




Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$  1 in.  
Prices, ... 1/7 $\frac{1}{2}$  2/3 3/6 each.

# Plumbers' Brass Work


## Plug Pattern and Full-way Bib and Stop Cocks

No. P 38. Plug Bib Cock  
Screw Boss.




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$   $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
Prices, 3 3 4 3 5 - 9 6 16/3 25/- each.

No. P 36. Plug Stop Cock  
Tinned Ends.




Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$   $1$  in.  
Prices, ... 3 3 4 9 8/- each.

No. P 281.  
Round-way Plug Bib Cock  
With Square Head and Iron Spanner.




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$   $1\frac{1}{4}$   $1\frac{1}{2}$   $2$  ins.  
Prices, 5/9 8/- 12/6 20/9 29/- 54/- each.

No. P 40. Plug Bib Cock  
With Union on Nose. Screw Boss.




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$  in.  
Prices, 4 6 6 - 7 6 12 - each.

No. P 39. Plug Stop Cock  
Screwed Ends.



Sizes,  $\frac{1}{2}$   $\frac{3}{4}$   $1$   $1\frac{1}{4}$  ins.  
Prices, 3/9 5 3 9 - 15/- each.


No. P 286.  
Round-way Plug Stop Cock  
With Square Head and Iron Spanner.



Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$   $1\frac{1}{4}$   $1\frac{1}{2}$   $2$  ins.  
Prices, 4/6 6/4 10/6 17/3 24/- 46/6 each.


## Range and Hot-water Cocks

No. P 70 $\frac{1}{2}$ . Range Cock




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$  in.  
Prices, 2 6 3 6 4 - 6 - each

No. P 71 $\frac{1}{2}$ . Range Cock  
With Ebony Handle.




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$  in.  
Prices, ... 3 3 4 3 5 6 each.

No. P 72. Globe Range Cock  
Ebony Handle.




3 $\frac{1}{2}$ -in. Tail.  
Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$  in.  
Prices, 4 6 5 6 6 6 10 - each.

No. P 73.  
Best Gland Gun-metal Bib Cock  
Ebony Handle.




Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$  in.  
Prices, 6 - 8 - 10 12 6 each.

No. P 291. Hot-water Cock  
Gun Metal, Ebony Handle.



Diam.,  $\frac{1}{2}$   $\frac{3}{4}$   $1$  in.  
Prices, 4/- 5/6 12/6 each.

No. P 461. Hot-water Cock



Diam., ...  $\frac{1}{2}$   $\frac{3}{4}$   $1$  in.  
Prices, ... 6/9 8/6 13/6 each


# Plumbers' Brass Work

No. P 277. Pillar Cock



Sizes, ... 1 in.  
 Yellow Metal, 3/3 3/9 each.  
 Gun Metal, 3/9 4/3 6/9 10/- ..  
 Nickel Plated, 4/3 4/9 7/10 12/6 ..


No. P 275. Globe Bath Cock



Size, ... 1 in.  
 Yellow Metal, ... 4 - each.  
 Gun Metal, ... 5 - ..  
 Nickel Plated, ... 6 - ..


No. P 65. Bath Plug

With  
Fly Nut  
and  
Union.




Sizes, ... 1 1/2 1 1/4 ins.  
 Yellow Metal, ... 2/9 4/6 each.  
 Nickel Plated, ... 3/6 5/6 ..

No. P 6498. Quarter-turn Pillar Cock  
 Fitted with Ebony Handle.




Sizes, ... 1 in.  
 Gun Metal, 6 - 8/9 12 - each.  
 Nickel Plated, ... 7/- 10/- 13/6 ..

No. P 6496.  
 Hexagon Body Globe Bath Cock



Size, ... 1 in.  
 Gun Metal, ... 6 - each.  
 Nickel Plated, ... 7 - ..


No. P 420. Trapped Bath Waste  
 With Fly Nut and Union.



Sizes, ... 1 1/2 1 1/4 ins.  
 Yellow Metal, ... 4/3 6/9 each.  
 Nickel Plated, ... 5/- 8/- ..

No. P 5480.


Non-concussive Pillar Lavatory Tap  
 Heavy Pattern.



Size, ... 1 in.  
 Gun Metal, ... 11/6 each.  
 Nickel Plated, ... 12/9 ..


No. P 6497.

Hexagon Body Globe Bath Cock  
 Quick Turn. Fitted with Ebony Handle.



Size, ... 1 in.  
 Gun Metal, ... 8/- each.  
 Nickel Plated, ... 9/- ..

No. P 66. Bath Overflow



Size, ... 1 1/2 in.  
 Yellow Metal, ... 2/3 each.  
 Nickel Plated, ... 3/- ..

# Plumbers' Brass Work

No. P 53.  
**Short Boiler Screw**



$\frac{1}{8}$   $\frac{3}{8}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  2 ins.  
7½d. 9d. 13 29 46 each.

No. P 54.  
**Long Boiler Screw**



$\frac{1}{8}$   $\frac{3}{8}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
1- 1/6 29 4/ 5/- each.

No. P 55.  
**Short Boiler Screw  
Double Nut.**



$\frac{1}{8}$   $\frac{3}{8}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
8d. 1/- 1/9 3/- 4/3 each.

No. P 302.  
**Cap and Lining for Water  
Strong.**



$\frac{1}{8}$   $\frac{1}{2}$   $\frac{3}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
4½d. 5d. 9d. 1 1½ 1/6 2/- each.

No. P 295.  
**Union<sup>o</sup>  
Tinned and Screwed.**



$\frac{1}{8}$   $\frac{1}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
1 16 23 39 56 each.

No. P 296. **Heavy Union  
Tinned and Screwed.**



$\frac{1}{8}$   $\frac{1}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
13 110 26 4 59 each.

No. P 298.  
**Plumbers' Union  
For Lead.**




$\frac{1}{8}$   $\frac{1}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
10½d. 1/4 2/1½ 3/6 5/- each.

No. P 301.  
**Strong Barrel Union**




$\frac{1}{8}$   $\frac{1}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  2 ins.  
1- 1/6 2/3 3 4 9 7/6 each.

No. P 4456. **Copper Flap Valve**



To fit  $\frac{1}{8}$  1  $1\frac{1}{4}$  1½ 2 in. Pipe.  
2 29 4 5 66 per doz.


No. P 381. **Brass Flap Valve**




$\frac{1}{8}$  in., 7½d. each.  
1 " 10½d. "  
1½ " 1/ " "  
1½ " 1/3 " "  
2 " 16 " "  
2½ " 23 " "

No. P 68. **Brass Cap and Screw**

$\frac{1}{8}$  in., 4d. each.  
1 " 4½d. "  
1½ " 6d. "  
1½ " 9d. "  
2 " 13 " "  
2½ " 23 " "  
3 " 33 " "  
3½ " 46 " "  
4 " 56 " "




No. P 77. **Urn Pattern Toilet Cock**



Yellow Metal,  $\frac{1}{8}$  in. 6 66 each.  
Nickel Plated,  $\frac{1}{8}$  in. 69 73 "


No. P 5481. **Spring Urinal Cock**



With Shield.

Price,  
80/- per doz.

No. P 80.  
**Self-closing Spring Bib Valve**



Plain Tail,  $\frac{1}{8}$  in. 39 53 each.  
Screwed for Iron,  $\frac{1}{8}$  in. 43 59 "

No. P 62. **Basin Plug  
With Fly Nut and Union.**



$\frac{1}{8}$   $\frac{1}{4}$  1  $1\frac{1}{4}$   $1\frac{1}{2}$  ins.  
1/6 1/9 1 10 27 4 1½ each.

No. P 51. **Lead Bell Trap  
With Brass Bell and Grate.**



Sizes over Brass—  
2 2½ 3 3½ 4 ins.  
14½ 16 23 29 33 each.

No. P 52.  
**Brass Grating**



2 2½ 3 3½ 4 ins.  
3d. 4½d. 5d. 6d. 9d. each.


No. P 50.  
**Brass Bell and Grate**



2 2½ 3 3½ 4 ins.  
6d. 9d. 1 1½ 1/6 2/- each.

# Plumbers' Brass Work

No. P 6503,  
**Strong Plug and Washer**  
Slotted for Overflow. Brass.




$\frac{3}{4}$ in.,	...	2/6	each.
1 "	...	2 9	"
$1\frac{1}{4}$ "	...	3 6	"
$1\frac{1}{2}$ "	...	5 3	"
2 "	...	8 3	"

No. P 1616,  
**Copper Shower Rose**  
With Female Inlet.




Sizes,	4	5	6	7	Ins.
Prices,	2 3	2 9	3 3	3 9	each.
Sizes,	8	9	10	12	ins.
Prices,	4 6	5 3	6 6	8 9	each.

No. P 4837,  
**Brass Waste**  
For Belfast Pattern Sinks.




Stamped Brass,	...	1/10 $\frac{1}{2}$	each.
Cast Brass,	...	2/6	"

No. P 6499,  
**Non-convulsive Garage Cock**  
Heavy Pattern.  
As approved by the Metropolitan Water Board.




Suitable for  $\frac{1}{4}$ ,  $\frac{3}{8}$ ,  $\frac{1}{2}$ , or 1 inch hose pipes.  
Price, ... .. 21 - each.  
These Waste-not Cocks will pay for themselves very quickly.

No. P 6489,  
**The "Hoare-Ackland" Washerless Tap**  
A RELIABLE ARTICLE.




Sizes,	...	$\frac{1}{4}$	$\frac{3}{8}$	1 in.
Prices,	...	6 -	10/6	18/9 each.

No. P 6501,  
**The "Standard" Tap**  
(Strongly made and well finished.)




Sizes,	...	$\frac{1}{4}$	$\frac{3}{8}$	1 in.
Prices,	...	4/-	6 3	9/9 each.

No. P 6502,  
**Brass Waste**  
With Overflow and India Rubber Plug for Belfast Sinks.



3 $\frac{1}{2}$ -inch Flange.	
$1\frac{1}{4}$ Ins.,	... 6 - each.
2 "	... 8 3 "

No. P 4619,  
**Plumbers' Brass Force Pump**  
With 3 feet of Hose, and Nozzle.



Price,	...	37/6	each.
--------	-----	------	-------

No. P 6488,  
**High-grade Pillar Tap**  
New Pattern.




Gun Metal, $\frac{1}{4}$ in.,	8/- each.
Nickel Plated,	9/6 each.



# Plumbers' Brass Work


BEST QUALITY, APPROVED AND STAMPED "NEW RIVER" FITTINGS.

No. P 4455.  
**Stop Cock Ferrule**




$\frac{1}{2}$  inch, 4/- each.  $\frac{3}{4}$  inch, 6/- each.

No. P 251.  
**High Pressure Stop Valve, with Two Unions**




$\frac{1}{4}$	$\frac{1}{2}$	1	$1\frac{1}{2}$	$1\frac{1}{2}$	2 ins.
4/9	7/-	10/6	22/6	33/-	64/6 each.

No. P 252.  
**High Pressure Bib Valve, S.B.**




Sizes,	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{2}$	$1\frac{1}{2}$	2	ins.
Prices,	3/6	5/6	9/-	19/-	27/-	51/-	each.

No. P 254. **Croydon Ball Valve, S.B., Copper Ball**



$\frac{1}{2}$	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{2}$	$1\frac{1}{2}$	2	ins.
13/7	4/3	6/4	10/6	20/3	27/9	51/-	each.


No. P <sup>N.R.</sup><sub>249</sub>.  
**Screw-down Bib Cock**  
S.B., Lettered.



Gun Metal.


Sizes,	$\frac{1}{2}$	$\frac{3}{4}$	inch.
Prices,	4/6	6/6	each.

No. P 259. **Bath Cock**



$\frac{1}{2}$  inch, ... 7/6 each.


No. P <sup>N.R.</sup><sub>292</sub>. **Screw-down Pillar Cock**  
Lettered.



Gun Metal, Best Quality.

Sizes,	...	$\frac{1}{2}$	$\frac{3}{4}$	1	inch.
Prices,	...	4/3	6/-	9/-	18/6 each.
Nickel-plated,	1/-	$1\frac{1}{2}$	$1\frac{1}{4}$	$1\frac{1}{8}$	extra.


No. P 6117.  
**The "Clincher" Waste Preventer**  
With Stamped Cover.



2	Gallon, Cast-iron, Painted,)	23/- each.
	Stamped "New River," ...)	
Galvanized,	...	30/- ..

Hardwood Pull and Chain, as shown  
Price, ... 7 $\frac{1}{2}$ d. each extra.

No. P 5827.  
**The "London" Waste Preventer.**  
With Cast-iron Cover.



2	Gallon, Cast-iron, Painted,)	21/9 each.
	Stamped "New River," ...)	
Galvanized,	...	28/9 ..


This Cistern gives a powerful sharp flush.

Hardwood Pull and Chain, as shown.  
Price, ... 7 $\frac{1}{2}$ d. each extra.

# Plumbers' Brass Work—Ball Valves

## "ADAPTABLE" PATENT FULL-WAY BALL VALVE

CROYDON PATTERN.



Has no Cup Leathers. Height of water regulated without bending ball lever.  
Re-rubbed without removing Ball Lever.

Sizes, ..  $\frac{1}{2}$   $\frac{3}{4}$  1 1 $\frac{1}{2}$  2 2 $\frac{1}{2}$  3 ins.  
No. P 6880. Screw Boss, 3/9 5/- 7/- 9/9 21/9 36/- 73/- 86/- 105/- each.  
,, P 6881. Fly Nut and Union, 4/6 5/9 8/- 11/6 — — — — „

## CROYDON BALL VALVES


STRONGEST PATTERN.



Sizes, ..  $\frac{1}{2}$   $\frac{3}{4}$  1 1 $\frac{1}{2}$  2 ins.  
No. P 254. Screw Boss, .. 3/7 $\frac{1}{2}$  4/3 6/4 $\frac{1}{2}$  10/6 20/3 27/9 51/- each.  
Stamped "New River."  
No. P 6884. Fly Nut and Union, .. 4/6 5/- 7/6 13/6 — — — — „  
Stamped "New River."  
If Unstamped, deduct .. 4d. 4d. 4d. 6d. 1/- 1/- 2/- „

## CROYDON BALL VALVES


ORDINARY AND MEDIUM PATTERNS.



Sizes, ..  $\frac{1}{2}$   $\frac{3}{4}$  1 1 $\frac{1}{2}$  2 ins.  
No. P 43. Ordinary Pattern, Screw Boss, .. 2/1 $\frac{1}{2}$  2/3 3/9 6/6 14/3 21/- 37/6 each.  
No. P 1965. Ordinary Pattern, Fly Nut and Union, .. 2/6 2/9 4/6 7/6 — — — — „  
No. P 6886. Medium Pattern, Screw Boss, .. 2/9 3/- 4/6 7/6 — — — — „  
No. P 6887. Medium Pattern, Fly Nut and Union, .. 3/- 3/6 5/6 — — — — „

## "ADAPTABLE" PATENT FULL-WAY BALL VALVES


PORTSMOUTH PATTERN.



For High or Low Pressure. Has no Cup Leathers.


Sizes, ..  $\frac{1}{2}$   $\frac{3}{4}$  1 in.  
No. P 6882. Screw Boss, .. 4/- 5/- 7/- 9/9 each.  
,, P 6883. Fly Nut and Union, .. 5/- 6/- 8/- 11/6 „

## PORTSMOUTH PATTERN BALL VALVE



Sizes, ..  $\frac{1}{2}$   $\frac{3}{4}$  1 in.  
No. P 6116. Strong Pattern, Detachable Seating Screw Boss, .. 3/- 3/4 $\frac{1}{2}$  5/6 8/- each.  
No. P 6885. Fly Nut and Union, .. 3/4 $\frac{1}{2}$  3/9 6/- 10/6 „


## UNDERHAYS PATTERN BALL VALVE



Sizes, ..  $\frac{1}{2}$   $\frac{3}{4}$  1 1 $\frac{1}{2}$  2 3 ins.  
No. P 6888. Screw Boss, 5/3 5/9 8/- 12/- 22/- 33/9 75/- 160/- each.  
For Lead Pipe.  
No. P 6889. Fly Nut and Union, .. 6/- 7/- 10/6 13/6 — — — — „


# Standard Weight Steam Fittings and Safety Valves

No. P 76. **Steam Wheel Valve**




$\frac{1}{2}$	$\frac{3}{4}$	$\frac{1}{2}$	$\frac{3}{4}$	$\frac{1}{2}$ in.
2/6	3/-	3 9	5/-	7/6 each.
$\frac{1}{4}$	$\frac{1}{2}$	2	3	ins.
11/6	15/-	21 -	66	' each.

No. P 70. **Steam Stop Cock**




$\frac{1}{2}$	$\frac{3}{4}$	$\frac{1}{2}$	1	$\frac{1}{2}$	$\frac{1}{2}$	2 ins.
3 6	4 -	6 6	8 9	12 9	17 -	27/- each.

No. P 4523. **Gun-metal Steam Union**




$\frac{1}{2}$	$\frac{3}{4}$	1	$\frac{1}{2}$	$\frac{1}{2}$	2 ins.
2 9	3 9	5 3	8 -	10 -	14 3 each.

No. P 5496. **Radiator Valve**  
With Union and Wood Wheel.




$\frac{1}{2}$	$\frac{3}{4}$	1	$\frac{1}{2}$	$\frac{1}{2}$	2 ins.
6 3	7/6	10/-	12/6	16 6	31/6 each.

No. P 4522. **Gun-metal Check Valve**




$\frac{1}{2}$	$\frac{3}{4}$	$\frac{1}{2}$	1	$\frac{1}{2}$	$\frac{1}{2}$	2 ins.
3 -	3 9	5 6	7/-	10 6	13 6	19 6 each.

No. P 839.  
**Spring Safety Valve**




$\frac{1}{2}$	1 in.
5 3	7/6 each.

No. P 4528.  
**Dead-weight Safety Valve**




$\frac{1}{2}$	$\frac{3}{4}$	1 in.
5 -	6 -	7/6 each.

No. P 4524 **Gun-metal Full-way Valve**  
(Peet's Pattern).




$\frac{1}{2}$	$\frac{3}{4}$	1	$\frac{1}{2}$	$\frac{1}{2}$	2 ins.
6 6	8 -	10 -	14 3	18 -	24 - each.

No. P 5497.  
**Gland Steam Stop Cock**



$\frac{1}{2}$	$\frac{3}{4}$	1	$\frac{1}{2}$	$\frac{1}{2}$	2 ins.
4 6	7 6	9 9	14 3	18 9	28 6 each.

No. P 4454.  
**"Croydon" Safety Valve**



$\frac{1}{2}$  in., 6 6 each.  
1 " 7 6 ..  
Lead Cones,  
6d. each extra.

# Best London Made Cisterns and Tanks


No. P 231. GALVANIZED IRON OPEN CISTERN. Best quality and make. Stock sizes.



Galls.	Length	Width	Depth	18 gauge	16 gauge	14 gauge	12 gauge or 1 plate bare.	11 gauge or 1 plate full.	Galls.	Length	Width	Depth	16 gauge	14 gauge	12 gauge or 1 plate bare.	11 gauge or 1 plate full.
20	22	16	16	14/3	15/9	20/3	25/6	28/-	150	42	31	32	52/6	63/-	82/-	90/-
25	24	17	17	15/9	17/3	22/6	28/6	30/6	175	44	33	33	61/6	75/-	92/-	100/-
30	24	18	19	17/6	19/6	25/6	31/-	35/-	200	46	35	35	63/6	78/9	95/-	110/-
40	27	20	20	19/6	22/6	28/6	36/-	39/-	250	50	39	36	77/6	95/-	115/-	130/-
50	29	22	22	22/-	26/-	33/-	42/-	45/-	300	54	43	36	95/-	110/-	140/-	150/-
60	30	23	24	25/-	28/-	37/6	45/-	51/-	350	66	42	36	115/-	120/-	150/-	165/-
70	32	26	24	—	32/-	42/-	51/-	56/-	400	72	42	38	120/-	130/-	160/-	175/-
80	34	27	24	—	34/6	45/-	53/-	60/-	500	78	44	42	—	155/-	186/-	200/-
90	36	26	26	—	37/6	48/-	58/-	65/-	600	84	48	42	—	195/-	215/-	240/-
100	38	27	27	—	39/-	49/6	60/-	69/-	800	97	55	43	—	—	300/-	310/-
125	40	31	28	—	47/-	60/-	72/-	82/-	1000	109	61	43	—	—	335/-	350/-

No. P 5476.

HYDRAULIC BELTED  
GALVANIZED CISTERN.




REGISTERED  
DESIGN.  
—  
NEW  
PATTERN.

## SIZES IN STOCK.

Gallons, ..	20	25	30	40	50	60	80	100	120	150	200	250	300	Inches.
Length, ..	24	24	26	26	27	32	36	36	40	40	54	68	80	"
Width, ..	16	17	18	18	23	23	26	26	32	32	32	32	32	"
Depth, ..	15	17	17	21	23	23	24	29	27	32	32	32	32	each.
Prices, 18 Gauge, ..	12/6	14/3	15/9	18/-	20/9	22/6	27/-	31/6	—	—	59/-	75/-	90/-	"
" 16 " ..	15/9	17/3	19/6	21/9	25/6	27/-	32/-	36/-	45/-	50/-	72/6	95/-	110/-	"
" 14 " ..	19/6	22/-	25/-	27/-	32/-	35/-	42/-	48/-	52/6	60/-	—	—	—	"


No. P 232. GALVANIZED IRON HOT-WATER TANK

Made same dimensions as No. P 231 Open Cistern.



Galls.	14 gauge	12 gauge or 1 plate bare.	11 gauge or 1 plate full.
20	25/-	32/-	35/-
25	26/-	35/6	38/-
30	29/6	39/6	42/-
40	37/6	46/-	50/-
50	43/-	53/-	59/-
60	46/-	57/-	64/6
80	—	68/-	76/-
100	—	82/-	92/-

With  
Improved  
Corners  
and



New  
Pattern  
Manhole  
Covers.

All our Cisterns, Tanks and Cylinders are Galvanized after they are made and TESTED before coming out of Works.


RUBBER RINGS TO MANHOLES.—Up to 30 gallons, .. 2/- extra.  
Above 30 " .. 3/- "

14 Gauge not recommended above 40 gallons.

Designed to save the time of Plumbers and Fitters, and to make an effective joint to Manhole Covers in two minutes. The Covers can be removed from time to time to clean or inspect Tanks and replaced quickly, no fresh jointing material being required. The Tanks are supplied with good India Rubber Ring for joint and are ready for fixing, no red lead or other jointing material necessary.

Capacity, ..	20	25	30	40 gallons.
14 Gauge, ..	25/6	27/-	31/6	39/- each.
1/2 In. Plate, ..	36/-	39/-	45/-	52/6 "

## Cisterns and Bins



No. P 6573. **PORTABLE BUILDER'S CISTERN**


Also suitable for conveying Water or Liquid Manure.  
Any size can be supplied.

With Internal Angle Iron at top dropped down to receive Cover.

(Cover not included). Size, 38 × 27 × 27 inches deep.

16 Gauge, Galvanized, .. .. .	84/- each.
14 " Painted, .. .. .	80/- "


No. P 6574. **GALVANIZED OR PAINTED WATER CART BODY**



Gallons, about	100	125	150	175	200	250	300
Length, ..	51	52	54	57	60	66	72 ins.
Width, ..	41	42	43	43	43	45	45 "
Depth, ..	16	18	19	22	22	24	27 "
Plate, ..	1	1	1	1	1	1	1 "
Painted, ..	105/-	112/-	123/-	140/-	150/-	225/-	263/- each.
Galvanized, ..	142/-	153/-	168/-	190/-	205/-	310/-	360/- "

With one Manhole only. If two Manholes as illustration, 11/- extra.


No. P 1230. **GALVANIZED CORN BIN**



Capacity, ..	2	4	6	8	10	12	16 bushels.
Prices, ..	21/-	25/6	31/6	36/6	49/6	56/-	75/9 each.

No. P 260.

**GALVANIZED ROUND CISTERN**




16 Gauge.  
For Oil or Water.

Gls.	Ht.	Diam.	Price.
Ins.	Ins.	Each	
15	22	16	19/6
20	24	18	21/-
30	30	19	25/6
40	33	21	30/-
50	35	23	33/-
60	36	25	36/-
80	42	27	40/-
100	48	28	45/-

No. P 1234.

**GALVANIZED ROUND CORN BIN**




2 Bushels, Price, 22/6 each.	
4 " " " 27/- "	
6 " " " 33/- "	
8 " " " 37/6 "	
10 " " " 49/6 "	
12 " " " 57/- "	
14 " " " 69/- "	

No. P 233.

**GALVANIZED ROUND HOT WATER CIRCULATING CYLINDER**

Fitted with 4 Flanges, as required.

Galls.	Height.	Diam.	16 Gauge.	14 Gauge.	1/2 plate.
Ins.	Ins.	Ins.			
20	30	15	28/6	33/-	42/-
23	36	15	30/-	36/-	45/-
27	42	15	32/-	37/6	48/-
31	33	18	34/6	40/-	52/-
34	36	18	36/-	42/-	54/-
37	39	18	38/-	44/-	57/-
40	42	18	40/-	46/-	60/-
45	48	18	-	-	66/-
52	45	20	-	-	70/-
56	48	20	-	-	75/-




Coupling Joints, as shown, are extra, according to size.

Manhole Covers, .. .. .	5/- each extra.
Rubber Rings, .. .. .	3/- .. ..

# Dust Bins, Tanks and Troughs


## No. P 1231. GALVANIZED ROUND PORTABLE DUST BIN

And Cover to fit outside. Strong, Galvanized after made.



30 x 18 inches,	..	Price, 9/9 each.
24 x 18 "	..	" 7/6 "
20 x 16 "	..	" 6/- "
16 x 14 "	..	" 5/3 "

## No P 1230½. DUST SKEP



14 inches diameter at top.  
12 " " " bottom,  
16 " deep.


With Cover,	..	4/6 each.
Without Cover,	..	3/9 "

## No P 5477. GALVANIZED OIL TANKS

Inverted Top or Bottom.  
Manhole and Bolted Cover.

2-inch Brass Filling Bung,  
and Flange for Tap.


And including a ½-inch  
Draw-off Tap.



Gauge,	..	18	18	18	18	18	18	18	16
Gallons, about	20	30	40	50	60	80	100	200	
Length,	..	15	20	20	21	22	22	24	33 ins.
Width,	..	15	20	20	21	22	22	24	33 "
Height,	..	27	27	33	34	39	48	48	51 "
Prices,	..	33/-	37/6	42/-	49/6	60/-	66/-	75/-	105/- each.

## No. P 1233. GALVANIZED SANITARY DUST BIN

With Hinged Cover.



Width of Front.	Front to Back.	Height at Back.	Price.
20 ins.	20 ins.	35 ins.	14/3 each.
22 "	22 "	37 "	17/3 "
24 "	24 "	38 "	21/- "
28 "	24 "	38 "	27/- "
32 "	24 "	38 "	30/- "
36 "	28 "	40 "	37/6 "


Other sizes quoted for specially to enquiry.

ALL GOODS GALVANIZED AFTER MADE.

## No. P 5478.

## GALVANIZED SHEET-IRON CATTLE TROUGHS

Fitted with Safety-edge Iron round Top. 14 Gauge.




Length,	..	36	48	60	72	84	96	108	120 ins.
Width,	..	18	18	18	18	18	18	18	18 "
Depth,	..	16	16	16	16	16	16	16	16 "
Prices,	..	38/-	42/-	52/-	63/-	69/-	75/-	82/6	94/6 each.

Other sizes quoted for upon receipt of Specification.


# Smoke-Curing Appliances, Cowls and Flues

No. P373.  
The "Louvre"



Strong Galvanized Iron,  
3/- each. 33/- per doz.  
With Extra Top Cap,  
4/6 each. 51/- per doz.

No. P361.  
Vertical Cowl



In Galvanized Iron,  
8/- each

No. P362.  
Malt House Cowl




In Galvanized Iron,  
8/- each.

No. P363.  
Lobster Back Cowl




In Galvanized Iron,  
7/6 each.

No. P364.  
Sugar Loaf Head  
With Round Bottom.



In Galvanized Iron,  
8/6 each.


No. P360.  
"Helmet"  
Chimney Cowl



In Galvanized Iron,  
8/3 each.


Extra strong pattern,  
made of galvanized iron  
and painted,  
13/6 each.

No. P371.  
Tallboy Flue




6 ft. high. Base, 12x9 ins.  
No. P371, Zinc, ... 10/6 each.  
" P372, Galvd. Iron, 7/6 "

No. P375.  
Elbow Flue




6 ft. high. Base, 12x9 ins.  
No. 375, Zinc, ... 15/- each.  
" 375, Galvd. Iron, 10/6 "

No. P387.  
Tee Flue




6 ft. high. Base, 12x9 ins.  
In Zinc, ... 15/- each.  
In Galvanized Iron, 12/9 "

No. P540.  
"Louvre" Top Flue



6 ft. high. Base, 12x9 ins.  
In Galvanized Iron, 11/3 each.

No. P365.  
Sugar Loaf Flue




6 ft. high. Base, 12x9 ins.  
Zinc, 15/-; Galvd. Iron, 12/- each.



No. P6106.  
The  
Tall Helmet


Made of strong  
galvanized iron  
and afterwards  
painted 2 coats.  
Diam of Tube,  
10 ins.  
Height under  
Helmet, 3 ft  
24/- each.

No. P524.  
Elbow  
Tee Flue




8 ft. high.  
Base, 12x9 ins.  
Zinc, ... 15/- each.  
Galvd. Iron, 10/6 "

No. P369.  
Revolving Head  
New Smoke Conductor



This new Revol-  
ving Cowl is re-  
commended for  
its adaptability  
to the purpose  
intended.  
It is strong,  
being made of  
galvanized iron,  
and is ornamen-  
tally japanned.  
It is fitted with-  
out the usual  
screw, but with  
open vanes  
which project to  
catch the wind.  
It cannot pos-  
sibly choke or be  
damaged by fire,  
or injured by the  
sweep's brush.  
The Hood is  
fitted with great  
nicety and turns  
on a steel centre  
in oil, whilst the  
central shaft  
works in gun-  
metal bearings.  
Height, 4 ft.  
Diameter, 11 ins.  
42/- each.




No. P368  
The  
"Archimedeian"

Height.	Diam.	
3 ft. 0 ins. x 10 ins.		44/3
3 " 6 " x 10 "		52/6
4 " 0 " x 10 "		56/6
3 " 0 " x 12 "		60/-
3 " 6 " x 12 "		67/6
4 " 0 " x 12 "		70/-
	Oil, ...	1/3
3 ft. 0 ins. x 14 ins.		70/-
3 " 6 " x 14 "		75/-
4 " 0 " x 14 "		82/6
	Oil, ...	1/10 1/2


# Galvanized Sheet-Iron Waste Preventing Cisterns

No. P 85. **DOUBLE-ACTION CISTERN**  
LIGHT PATTERN.




Price, .. .. 7/6 each.

No. P 85½. **DOUBLE-ACTION CISTERN**  
THE "KINT."




Price, .. .. 10/6 each.

No. P 085. **"NEW RIVER" STAMPED WASTE PREVENTER**



Price, .. .. 22/6 each.


No. P 6794. **DOUBLE-ACTION CISTERN**  
STRONG PATTERN.



Price, .. .. 8/9 each.


No. P 6795. **GALVANIZED SHEET-IRON WASTE PREVENTER**

Of the Valveless Syphon type.  
Easy Action. Certain Flush.



Price, .. .. 15/- each.

No. P 6796. **CISTERN BRACKETS TO DRIVE**  
Suitable for Cisterns illustrated on this page.




Painted, .. .. Price, 9d. per pair.  
Galvanized, .. .. " 1/3 "




# Cast-Iron Syphon Waste Preventing Cisterns

No. P 240. THE "SWERGE" VALVE SYPHON



With 1 1/2 in. Iron Syphon,	..	..	..	2 Gallons.	3 Gallons.
" 1 1/2 " Brass "	..	..	..	16/6	20/- each.
" 1 1/2 " Iron "	..	..	..	22/6	24/- "
" 1 1/2 " Brass "	..	..	..	18/-	22/6 "
" 1 1/2 " Brass "	..	..	..	24/-	30/6 "


No. P 4501. THE "MAIL"



2 Gallon,	..	..	..	..	Painted	Galvanized.
3	"	..	..	..	Price, 19/6	23/6 each.
					24/-	33/- "


No. P 6755. THE "INVICTAS"

Fitted with Rubber Stops, Silencing Tube to Dome, and Silent Ball Valve.




2 Gallon,	..	..	..	..	Painted.	Galvanized.
3	"	..	..	..	Price, 23/3	32/9 each.
					27/-	37/6 "

No. P 1989. THE "PIONEER" VALVELESS SYPHON




2 Gallon,	..	..	..	..	Painted.	Galvanized.
3	"	..	..	..	Price, 15/-	22/6 each.
					18/-	27/- "
					Beech Handle Pull	and Chain, 7 1/2d. each.

No. P 5260. THE "FAVOURITE"  
Cast Iron Painted.



2 Gallon,	..	..	..	..	Price, 18/- each.
3	"	..	..	..	21/- "

No. P 2165. THE "POSITIVE"  
Cast Iron Painted.




2	Gallon, .. .. .	Price, 20/3 each.
3	" .. .. .	25/- "
	China" Handle Pull and Brass Chain, .. .. .	1/3 "

# High-Class Waste Preventing Cisterns

## No. P 6754. THE "EXCELSIOR"

Delightful Easy Action.  
Certain Flush




	2 Gallons.	3 Gallons.
Cast Iron Painted, .. .. .	Price, 40/-	45/-
" " " Stamped " New River," ..	45/-	—
Fireclay, .. .. .	48/-	54/-

### EXTRAS :—

Galvanizing, .. .. .	8/6	10/6
Enamelled Inside, .. .. .	10/6	12/6
Enamelled Outside and Inside, .. .. .	16/-	20/-
Silencing Tube to Syphon, .. .. .	3/-	3/-
Brass Chain and China Pull, .. .. .	Price, 1/6 each.	
Superior Celluloid Handle Pull and Plated Chain, ..	5/3	

## No. P 89. WINN'S ACME CISTERN

The Popular Pattern.





2 Gallon.

Cast Iron Painted, .. .. .	Price, 28/6 each.
Beech Handle, Pull and Chain, .. .. .	7 1/2d. "

## No. P 6121. THE "BRITANO"

Made in the new Hygeian Ware.



The "Britano" Cistern has been designed to afford a perfectly incorrodible waste preventing cistern of excellent quality, and at a price hitherto unapproached.

Iron cisterns, whether painted, galvanized, or glass enamelled, when subject to the action of water soon rust, causing a red streak which disfigures and ruins the glaze of closet pan and urinal stall. This is impossible with the "Britano" Cistern. It is made of "Hygeian ware" which is highly glazed, it is hard as iron, and when knocked rings like a bell.

Every cistern is warranted not to "Craze" or "Dunt."

The patent combination valveless syphon fittings, which are made of white metal and brass, are quite simple and strong.


Syphonic action is set up by a delightfully easy pull, and the flush, though rapid, is singularly quiet.

White Glazed outside, .. .. .	Per 2 Gallon, 40/6 each.	Per 3 Gallon, 45/- each.
Cast-iron Painted Cistern Brackets, .. .. .	3/-	per pair.
Best Celluloid Handle Pull and Nickel-plated Chain, ..	5/3	each.

# Cistern Pulls, Rubber Plugs, and Closet Cones

No. P 318.


**GALVANIZED CHAIN  
AND PULL**



Price, .. 4½d. each.

No. P 319.

**GALVANIZED CHAIN,  
BEECH HANDLE**



Price, .. 6d. each.

No. P 320.

**BRASS CHAIN,  
PLAIN CHINA PULL**



Price, .. 10½d. each.

No. P 311.

**BRASS CHAIN,  
REEDED CHINA PULL**



Price, .. 1/9 each.


No. P 374.  
**BRASS CHAIN,  
HAND-PAINTED  
HANDLE**



Price, .. 4/6 each.

No. P 4329.

**CISTERN PULL**




Stained Walnut, Mahogany,  
or Ebonized Handle.  
Brass Chain.

Price, .. 1.10½ each.

No. P 4484.

**RUBBER BASIN AND BATH PLUGS WITH METAL RINGS**




Brass Mounts.

Size over top, .. ..	2	2	1	1½	1½	1½ ins.
Prices, .. ..	4½d.	5½d.	1 6d.	7½d.	8½d.	9d. each.
Size over top, .. ..	1½	1½	2	2½	2½	2½ ins.
Prices, .. ..	10½d.	11½d.	1/-	1/1½	1/6	1/9 each.

No. P 4321.

**INSERTION LINED CONE**



1½ inches, .. Price, 9d. each.  
1½ .. .. 1/- ..

No. P 4322.


**ELBOW INDIA RUBBER  
CONE**



Price, .. 1/6 each.

No. P 4483.

**CISTERN PULL**




Heavy Pull with Copper Chain  
and Fitting.

Price, .. 4/3 each.


# Cistern Pulls and Chains and Pipe Clips

No. P 6789.  
**CISTERN PULL**



Horn Handle with Brass Chain.  
Price, .. 3/9 each.

No. P 6790.  
**CISTERN PULL**




Celluloid Handle, Nickel-plated Chain.  
Price, .. 5/3 each.

No. P 382.  
**PULL, GUIDE AND ROD**




Imitation Mahogany Block, with China Pull and Brass Chain  
Price, .. 4/6 each.  
If with Real Mahogany Block.  
Price, .. 5/3 each.

No. P 6791.  
**PULL, GUIDE AND ROD**



Brass Plate, with China Pull and Brass Chain.  
Price, .. 5/6 each.

No. P 6792.  
**STAMPED BRASS PIPE CLIP**



1 1/2 inch, .. Price, 8d. each.  
1 1/4 " .. 7 1/2 d. "

No. P 386.  
**CAST BRASS PIPE CLIP**




1 1/2 inch, .. Price, 9d. each.  
1 1/4 " .. 10 1/2 d. "

If with Rubber Buffer.

1 1/2 inch, .. Price, 10 1/2 d. each.  
1 1/4 " .. 1/- "

No. P 6793.  
**STAMPED BRASS PIPE CLIP**  
With Rubber Buffer.



1 1/2 inch, .. Price, 7 1/2 d. each.  
1 1/4 " .. 9d. "

# Pedestal Closet Seats

RING PATTERN.

Each Seat is sent out with Pillar Hinges as described.

BRITISH MANUFACTURE.

No. P 6137. **Single Ring Seat**



	Ex. 1	1½ ins.
Hardwood, Unpolished, with Galvanized Hinges, .. .. .	3/-	-
Hardwood, Polished Mahogany Color, with Plated Malleable Hinges, .. .. .	4/9	—
Oak, Unpolished, with Galvanized Hinges, .. .. .	4/6	—
Polished Birch, with Brass Hinges, .. .. .	6/-	—
Polished Mahogany, with Nickel-plated Brass Hinges, .. .. .	8/3	—

No. P 6138. **Double Ring Seat**




	Ex. 1	1½ ins.
Hardwood, Polished Mahogany Color, with Plated Malleable Hinges, .. .. .	8/-	—
Polished Birch, with Brass Hinges, .. .. .	—	10/-
Polished Mahogany, with Nickel-plated Brass Hinges, .. .. .	—	13/6

## EXTENSION PATTERN

Each Seat is sent out with Bolts and Nuts as described.

No. P 5819. **Extension Seat**

SINGLE FLAP.



	Ex. 1	1½ ins.
Hardwood, Unpolished, with Iron Bolts, Brass-covered Heads, .. .. .	4/6	—
Hardwood, Stained Mahogany, with Iron Bolts, Brass-covered Heads, .. .. .	5/9	—
Polished Oak, with Brass Bolts, .. .. .	—	7/6
Polished Mahogany, with Brass Bolts, .. .. .	—	8/3

No. P 6139. **Extension Seat**

DOUBLE FLAP.



	Ex. 1	1½ ins.
Hardwood, Stained Mahogany, with Iron Bolts, Brass-covered Heads, .. .. .	9/6	—
Polished Oak, with Brass Bolts and Nuts, .. .. .	—	12/6
Polished Mahogany, with Brass Bolts and Nuts, .. .. .	—	13/6

# Pedestal Closet Seats

BRITISH MANUFACTURE.

## No. P 397. Standard Pattern

SINGLE FLAP, WITH SIDE HINGES.



	Ex. 1	1 1/4 ins.	
Hardwood, Unpolished, .. .. .	Price, —	5/3	
Hardwood, Polished Mahogany Color, ..	6/	—	
Polished Birch, .. .. .	7/6		
Polished Oak, .. .. .	8/3		
Real Mahogany, .. .. .	9/-		

## No. P 398. Standard Pattern

DOUBLE FLAP, WITH SIDE HINGES.



	Ex. 1	1 1/4 ins.	
Hardwood, Polished Mahogany Color, ..	Price, 12/6	—	
Real Mahogany, .. .. .	—	18/-	

## DOUBLE THICKNESS TWO-PLY SEATS

STRONG AND SPLENDIDLY FINISHED.

## No. P 6764. Double-thickness Two-ply Seat

SINGLE FLAP.



	Ex. 1 1/4 ins.	
Polished Birch, .. .. .	Price, 10/6 each.	
Polished Mahogany, .. .. .	13/6 ..	

## No. P 6765. Double-thickness Two-ply Seat

DOUBLE FLAP.




	Ex. 1 1/4 ins.	
Polished Birch, .. .. .	Price, 17/3 each.	
Polished Mahogany, .. .. .	22/6 ..	

Our Seats are all guaranteed British made, and will be found much superior in Make and Finish to the many grades of Foreign Seats now on the Market.

# Plumbers' Brass Work, Soil-Pipe Ferrules, Sockets and Seat Hinges

No. P 6123. **FERRULE.**




The above illustration shows the most perfect form known for connecting the Lead Pipe and the Brass Ferrule together, and emphasizes the value and importance of the concave head.

The Brass Ferrule, as shown, has a concave head formed upon one end. The Lead Pipe passes through the Brass Ferrule, and it is turned over and staved into the concavity of the head, thus forming a perfectly sound and reliable junction without the aid of solder. The Lead Pipe passing through the Brass Ferrule thoroughly protects it from the deteriorating effects of acids, &c. It is jointed to the Iron Pipe in the usual way by means of Rope Yarn and Molten Lead.

Length, ...	3½	4	4½	5 ins.
Bore, ...	1½	2½	3½	4½
Prices, ...	11/3	13/-	15/9	19/6

## CAST BRASS SOCKETS AND FERRULES

No. P 2937. **BRASS SOCKET.** No. P 2938. **BRASS FERRULE.**



Diam.	Price.	Diam.	Price.
1½ ins. ...	1/1½ each.	1½ ins. ...	9d. each.
2 " ...	1/4½ "	2 " ...	1/- "
3 " ...	2/- "	3 " ...	2/- "
3½ " ...	2/9 "	3½ " ...	2/4½ "
4 " ...	3/1½ "	4 " ...	3/- "


## CLOSET SEAT HINGES

No. P 6104. **SINGLE.**



Prices, per dozen sets.  
 Iron, Galvanized, ... 9/-  
 Nickel-plated, ... 13/6  
 Brass, Polished, ... 27/-  
 Brass, Nickel-plated, ... 33/-  
 A Set consists of 2 Pillars and Nuts and 2 Flaps.


No. P 6105. **DOUBLE.**



Prices, per dozen sets.  
 Iron, Galvanized, ... 15/9  
 Nickel-plated, ... 21/-  
 Brass, Polished, ... 39/-  
 Brass, Nickel-plated, ... 48/-  
 A Set consists of 2 Pillars and Nuts and 4 Flaps.

No. P 6122.


## MACHINE-MADE SOLID DRAWN BRASS SOCKETS



The illustration below shows the Lead Pipe connected to the Earthenware horn of the closet by means of the brass socket and cement. This form of socket enables the plumber to make with Portland cement a firm joint absolutely gas and water tight without the aid of solder. The concave head forms a key which ensures the efficiency of the joint.

The advantages which the Patent Socket possesses over the ordinary cast socket are highly appreciated by sanitary experts.

These Sockets are made of solid drawn brass of high quality, and are free from pores and flaws so often found in cast ones.




Sizes,	3 x 2	3 x 2½	4½ x 3½	5 x 3½ ins.
Prices,	19/6	19/6	31/6	33/- doz.

Sizes,	...	5 x 4½	5½ x 4½	5½ x 4½ ins.
Prices,	...	33/-	39/-	48/- doz.

No. P 6103.

## SIDE BRASS HINGE FOR CLOSET SEAT



Price, ... 13/6 per dozen pairs.

No. P 6109.

## CISTERN PULL GUIDE



Prevents the handle having free play to swing about on the wall, damaging paper and plaster.

Price, 1/- each.

# Cistern and Pedestal Seat Brackets

## CISTERN BRACKETS

No. P 4407.




7, 8, and 9 ins.  
Price, 9d. per pair.

No. P 4400.



7, 8, and 9 ins.  
Price, 1/1½ per pair.

No. P 1457.



10½ ins., Price, 2/3 per pair.

No. P 1458.



10½ ins., Price, 2/3 per pair.

## SEAT BRACKETS

No. P 1460.




16 ins., Price, 4/6 per pair.

No. P 1464.



16 ins., Price, 5/3 per pair.


No. P 1465.




15 ins., Price, 6/9 per pair.

## PEDESTAL SEAT BRACKETS

No. P 4437. ADJUSTABLE.




REGISTERED  
DESIGN.



Will adjust to six different sizes, viz., 15, 15½, 16, 16½, 17, 17½ inches.  
This pattern stands clear of the wall 2 inches, leaving ample room for pipes, &c.  
Price, .. .. 4/6 per pair.


No. P 4408.



16½ ins. high, Price, 2/9 per pair.


## FANCY PATTERNS.

No. P 4403.




16½ ins. high, Price, 4/- per pair.

No. P 6846.



17 ins. high, Price, 5/3 per pair.

No. P 6847.




16½ ins. high, Price, 6/- per pair.



# Closet Pans and Traps

No. P 5261. The "Vidonite" Straight-back Wash-down Closet  
In Two Pieces, with Deep Socket Trap.




This design of cheap Wash down Closet is approved by County Council.  
The high trap gives a deep water seat.  
Basin, 16½ ins. diam. 15½ ins. high.  
Cane and White, .. .. Price, 7 6 each.

No. P 3397. The "Sirez" Straight-back Wash-down Closet  
In Two Pieces, Flushing Rim.




Made with S or P Trap. Basin, 15×14½×17½ inches high.  
Cane and White, .. .. Price, 5/9 each.

No. P 97. Cottage Pan and Trap  
With Ordinary Flushing Rim.




Cane and White, with S or P Trap.  
Price, .. 5/9 each.



No. P 98.  
Hopper Pan  
and Trap  
With  
Ordinary  
Flushing Rim.

Cane and White, with S or P Trap, Price, 4/6 each.

No. P 6782. Short Hopper Pan and Trap  
With Flushing Rim.



Cane and White, with S or P Trap.  
Price, .. 4/6 each.


## VALVE CLOSET BASINS

No. P 1594.  
Valve Basin, Flushing Rim  
Right Hand Overflow (Sitting).



Height, 11 ins.; diameter, 16×14 ins.;  
diameter of Outlet, 4 ins.  
White, .. .. Price, 12/6 each.  
White and Printed, .. 13 6 ..

No. P 1594½.  
Valve Basin, Flushing Rim  
Left Hand Overflow (Sitting).




Height, 11 ins.; diameter, 16×14 ins.;  
diameter of Outlet, 4 ins.  
White, .. .. Price, 12 6 each.  
White and Printed, .. 13 6 ..

No. P 1598.  
Valve Basin, Flushing Rim  
Side Arm Supply, Right Hand Over-  
flow (Sitting).



Height, 11 ins.; diameter, 16×14 ins.;  
diameter of Outlet, 4 ins.  
White, .. .. Price, 12/6 each.  
White and Printed, .. 13, 6 ..

No. P 1598½.  
Valve Basin, Flushing Rim  
Side Arm Supply, Left Hand Over-  
flow (Sitting).



Height, 11 ins.; diameter, 16×14 ins.;  
diameter of Outlet, 4 ins.  
White, .. .. Price, 12/6 each.  
White and Printed, .. 13/6 ..

# High Class Pedestal Closets

No. P 4451. **THE "IVYLITE"**



With **S** or **P** Trap.

Cane and White, .. .. .	Price, <b>23/3</b> each.
All White, .. .. .	" <b>27/-</b> "
White and Printed, .. .. .	" <b>33/6</b> "

No. P 4409. **THE "TRENDONE"**



With **S** or **P** Trap.

Cane and White, .. .. .	Price, <b>24/-</b> each.
All White, .. .. .	" <b>25/6</b> "
White and Printed, .. .. .	" <b>31/6</b> "

No. P 393. **THE "RAPIDUS"**



With Front Outlet.

Cane and White, .. .. .	Price, <b>25/6</b> each.
All White, .. .. .	" <b>33/-</b> "
White and Printed, .. .. .	" <b>39/-</b> "

No. P 6826. **THE "RICARDIA"**



With Back Outlet.


Cane and White, .. .. .	Price, <b>18/-</b> each.
All White, .. .. .	" <b>19/6</b> "
White and Printed, .. .. .	" <b>25/6</b> "

Standard Pattern Seats, suitable for the above Closets, are illustrated and described on page 165.

## Pedestal Closets and Seats

No. P 6756.

### THE "CHALLENGE"



With Back Extension Whitewood Seat, Bolts and Nuts.  
Cane and White Closet, with Whitewood Seat, and  
Bolts and Nuts, .. .. . Price, **16/6** each.  
Closet only, .. .. . " **11/3** "

No. P 6757.

### THE "QUICK FLUSH"



With Ring Seat and Pillar Hinges.  
All White Closet, with Real Mahogany Ring Seat,  
and Plated Malleable Hinges, .. .. . Price, **19/6** each.  
If with Imitation Mahogany Seat, .. .. . " **16/6** "  
Closet only, .. .. . " **12/-** "

No. P 5992.

### THE "CHALLENGE"




With Back Extension Mahogany Seat, Bolts and Nuts.

All White Closet, with Real Mahogany Polished Seat,  
and Bolts and Nuts, .. .. . Price, **22/6** each.  
If with Imitation Mahogany Seat, .. .. . " **20/3** "  
Double Flap Seats, .. .. . " **4/6** extra.  
Closet only, .. .. . " **13/6** each.

No. P 6758.

### THE "HUMBER"



With Back Extension Seat, Bolts and Nuts.

All White Closet, Real Mahogany Polished Seat,  
and Bolts and Nuts, .. .. . Price, **23/3** each.  
If with Imitation Mahogany Seat, .. .. . " **20/9** "  
If in Cane and White, with Whitewood Seat, .. .. . " **17/3** "  
Double Flap Seat, .. .. . " **4/6** extra.  
Closet only, White, .. .. . " **15/-** each.  
" " Cane and White, .. .. . " **12/9** "

When ordering, please state whether S or P Trap.

# Pedestal Closets and Seats

No. P 6759.

## THE "SEAT PED"



With Back Extension Seat, Bolts and Nuts

Cane and White Closet, and Whitewood Seat, Bolts and Nuts, ..	Price, 17/3 each.
All White, with Real Mahogany Polished Seat, ..	" 23/3 "
" " Imitation Mahogany Seat, ..	" 21/- "
Double Flap Seat, ..	4/6 extra.
Closet only, Cane and White, ..	Price, 13/- each.
" " All White, ..	" 15/- "

No. P 6784.

## THE "INVICTAS"



With Back Extension Seat, Bolts and Nuts.  
Centre Outlet.

All White Closet, Double Flap Real Mahogany Seat, Bolts and Nuts, ..	Price, 30/- each.
If with Imitation Mahogany Seat, ..	" 26/3 "
" " Single Seat, Real Mahogany, ..	" 26/3 "
" " " " Imitation Mahogany, ..	" 23/3 "
Closet only, Cane and White, ..	Price, 15/9 each.
" " All White, ..	" 18/- "

When ordering please state whether S or P Trap.

No. P 6783.

## THE "EXCELSIOR"



With Back Extension Seat, Bolts and Nuts.

All White Closet, with Real Mahogany Double Flap Seat, Bolts and Nuts, ..	Price, 33/- each.
If Imitation Mahogany, ..	" 28/6 "
If Single Flap Seat, Real Mahogany, ..	" 28/6 "
" " " Imitation Mahogany, ..	" 25/- "
Closet only, Cane and White, ..	Price, 16/6 each.
" " All White, ..	" 20/3 "

No. P 6785.

## THE "INVICTAS"



With Back Extension Seat, Bolts and Nuts.

All White Closet, Double Flap Real Mahogany Seat, Bolts and Nuts, ..	Price, 30/- each.
If with Imitation Mahogany Seat, ..	" 26/3 "
" " Single Seat, Real Mahogany, ..	" 26/3 "
" " " " Imitation Mahogany, ..	" 23/3 "
Closet only, Cane and White, ..	Price, 15/9 each.
" " All White, ..	" 18/- "

## Pedestal Closets and Seats

No. P 6785.

### THE "CLINCHER"



Strong Vitrified Stoneware Pedestal Closet.  
S or P Trap.

All White Closet, with Polished Oak Seat, ..	Price, 27/- each.
Cane and White Closet, with Hardwood Unpolished Seat, .. .. .	" 21/- "
Closet only, Cane and White, .. .. .	Price, 16/6 each.
" " All White, .. .. .	" 19/6 "

No. P 5991.

### THE "ADAPTABLE"



Two-piece Pedestal Closet.  
Trap can be adjusted to any angle.

All White Earthenware Closet, with Mahogany Seat, .. .. .	Price, 22/6 each.
Cane and White Closet, with Whitewood Seat, .. .. .	" 17/3 "
Closet only, Cane and White, .. .. .	Price, 13/6 each.
" " All White, .. .. .	" 15/- "

No. P 6786.

### THE "SANCLOZ"



Heavy Fireclay Pedestal Closet, with Bold Roll Rim.  
S or P Trap.

In White, with Superior Two-ply Double Flap Real Mahogany Seat and Brass Bolts and Nuts, ..	Price, 42/- each.
With Single Flap Seat, .. .. .	" 34/6 "
Closet only, .. .. .	Price, 22/6 each.

No. P 1597.

### THE "CLANZER"

Trapless Closet.




This Closet is designed as a substitute for the Pan Closet, the outlet being arranged in the same position.

Cane and White, .. .. .	Price, 18/- each.
All White, .. .. .	" 24/- "

# New Series of Pedestal Closet Suites

No. P 6113.

## THE QUICK FLUSH SUITE



Comprising All White Pedestal Closet, S or P Trap, Polished Oak Seat with Back Extension Piece bolted to Pan with Brass Bolts; 2 gallon Cast-iron Painted Quick Flush Waste Preventer and Brackets, China Pull and Brass Chain, Galvanized Telescopic Flush Pipe and Clip, .. Price, **46/6** per set.

If with Lead Fall Pipe and Wiped Joint to Cistern Union, .. .. . **6/6** extra.

No. P 6324.

## THE "LONDON" SUITE



Comprising All White Pedestal Closet, S or P Trap, Double Flap Real Mahogany Seat with Back Extension bolted to Pan with Brass Bolts; 2-gallon Tested and Stamped Painted Cast-iron Waste Preventer and Brackets, Brass Chain and Imitation Mahogany Pull, Galvanized Telescopic Flush Pipe and Clip, .. .. . Price, **58/6** per set.

If with Single Flap Seat, .. .. . **52/-** ..

If with Lead Fall Pipe and Wiped Joint to Cistern Union, .. .. . **6/6** extra.

When ordering please state whether **S** or **P** Trap.

# New Series of Pedestal Closet Suites


No. P 5492.

## THE NEW "SEAT-PED"



No. P 5846.

## THE NEW "INVICTAS"



Comprising Cane and White Pedestal Closet, S or P Trap, Whitewood Seat with Back Extension Piece bolted to Pan, 2-gallon Cast-iron Painted "Pioneer" Cistern and Brackets, Brass Chain and China Pull, Galvanized Telescopic Flush Pipe and Clip. . . . . Price, **39/9** per set.

If with All White Closet and Real Mahogany Seat, . . . . . **45/-** ..

If with 1 1/2-in. Lead Fall Pipe and Wiped Joint to Cistern Union, . . . . . **6/6** extra.

Comprising All White Pedestal Closet, S or P Trap, Double Flap Real Mahogany Polished Seat bolted to Pan, 2-gallon Cast-iron Painted "Invictas" Syphon Cistern, fitted with Rubber Stops, Silencing Tube to Dome and Silent Ball Valve, Cistern Brackets, Brass Chain and Horn Handle, Galvanized Telescopic Flush Pipe and Clip, . . . . . Price, **63/-** per set.

If with Single Flap Seat, . . . . . **57/-** ..

If with Lead Fall Pipe and Wiped Joint to Cistern Union, . . . . . **6/6** extra.

When ordering, please state whether S or P Trap.

# Pedestal Closet Suites

No. P 6752.

## THE "HUMBER" SUITE




Comprising All White "Humber" Closet, S or P Trap, Stained Mahogany Seat, Cast-iron Pedestal Brackets, 2-gallon "Pioneer" Cistern and Brackets, Brass Chain with Imitation Mahogany Pull, Galvanized Telescopic Flush Pipe and Clip.

With Cane and White Closet,	..	..	..	Price, 46/6 each.
" All White Closet,	..	..	..	" 49/6 "
" White and Printed Closet,	..	..	..	" 58/6 "
If with Double Flap Seat,	..	..	..	6/6 extra.

No. P 6753

## THE "IVYLITE" SUITE



Comprising All White "Ivylite" Closet, S or P Trap, with Solid Mahogany Polished Seat, Cast-iron Pedestal Brackets, 2-gallon "Pioneer" Cistern and Brackets, Copper Chain with Real Mahogany Pull. Galvanized Telescopic Flush Pipe and Clip.

With Cane and White Closet,	..	..	..	Price, 63/- each.
" All White Closet,	..	..	..	" 69/- "
" White and Printed Closet,	..	..	..	" 75/- "
If with Double Flap Seat,	..	..	..	8/6 extra.

When ordering please state whether S or P Trap.




# Superior Pedestal Closet Suites

No. P 6824. **THE "BRITANO"**



No. P 6131. **THE "PILASTER"**



Comprising: Two-gallon White-glazed Valveless Syphon Cistern, Painted Iron Brackets, Strong Pull and Eye, 1½-inch Galvanized Steel Flush Pipe and Clip, All White Closet, Polished Birch Seat.

Price, .. 100/- per set.

Comprising: Two-gallon White-glazed Valveless Syphon Cistern, Painted Iron Brackets, Superior Celluloid Handle Pull, with Strong Nickel-plated Chain, Nickel-plated Copper Flush Pipe and Clip; White Pedestal Closet, with Double-flap Walnut Seat, Brass Bolts and Nuts.

Price, .. 120/- per set.

If Closet is White with Gilt Lines, 10/- extra.

When ordering please state whether **S** or **P** Trap.

# Strong Fireclay and Stoneware Closet Suites

SUITABLE FOR PUBLIC BUILDINGS, CLUBS, &C.

No. P 6120. THE "CLINCHER"



Comprising: Strong Vitrified Stoneware White Pedestal Closet, S or P Trap; Polished Oak Seat, with back Extension Piece, bolted to Pan with Brass Bolts; Two-gallon Tested and Stamped Painted Cast-Iron Waste Preventer and Brackets; Brass Chain and Hardwood Pull; Galvanized Telescopic Flush Pipe and Clip.

Price, .. .. 57/- per set.


If with Cane and White Closet and Hardwood Unpolished Seat.

Price, .. .. 52/- per set.

If with Lead Fall Pipe, with Wiped Joint to Cistern Union,

6/6 per set extra.

No. P 6825. THE "IRONA"



Comprising: Strong All White Fireclay Pedestal Closet, S or P Trap, with Side Seat Pads; Two-gallon Strong Fitted, Tested and Stamped, Cast-iron "London" Cistern and Brackets; Brass Chain and Hardwood Pull; Galvanized Telescopic Flush Pipe and Clip.

Price, .. .. 60/- per set.

If with Cane and White Closet.

Price, .. .. 57/- per set.

If with Lead Fall Pipe with Wiped Joint to Cistern Union,

6/6 per set extra.

When ordering please state whether S or P Trap.

## “Lodown” Closet Suites in Fireclay



No. P 6809.

Comprises : White Glazed Fireclay Closet ; Three-gallon White Glazed Fireclay Cistern and Cover, fitted with Incorrodible Valveless Syphon Fittings ; Painted Iron Brackets ; 1½-inch Brass Flushing Pipe and Connection ; Closet fitted with Mahogany Seat Pad.

Price, .. £6 15 0 per set.

Height from floor to top of cistern, 3 ft. 8 ms.

No. P 6810.

Comprises : White Glazed Fireclay Closet, Dished Top ; Three-gallon White Glazed Fireclay Cistern and Cover, large Single Valve, and Hinged Seat with Brass Fittings.

Price, .. £8 5 0 per set.



Height from floor to top of cistern, 2 ft. 9 ins.

## "Lodown" Closet Suites



No. P 6813.

### THE "SALWAY" COMBINATION SUITE

Comprises: Enclosure in Walnut or Mahogany; Two-gallon Vitreous Enamelled Cast-iron Cistern, with Valve Syphon; Fireclay "Munio" Closet, **S** or **P** Trap.

Price, .. £8 10 0 per set.


If with Valveless Syphon, 8/- extra.

No. P 6814.

### THE "SAXONIA" COMBINATION SUITE

Comprises: Best Walnut or Mahogany Enclosure, with Seat and Cover; Three-gallon Copper Cistern, with Valveless Syphon and Regulating Stop Tap; "Saxonia" White-ware Wash-down Closet, **S** or **P** Trap.

Price, .. £12 15 0 per set.




# Patent Earth Closets

(MOULE'S SYSTEM)

## APPARATUS FOR USE IN CLOSETS


h form of Apparatus throws  $1\frac{1}{2}$  pints of Earth each time the Closet is used. When ordering Apparatus state whether it is proposed to fix the same over a vault, or whether over a tank or pail.

### No. P 2851. PULL - OUT APPARATUS




h Galvanized Iron Rim and Brass Handle, as shown.  
Price, .. .. 36/9 each.

### No. P 2852. PULL - UP APPARATUS



With Galvanized Iron Rim and Iron Handle.  
Price, .. .. 45/- each.


### No. P 2855. SELF-ACTING



Earth Closet, with Galvanized Iron Rim, Cast-iron Lever  
s, and Deal Seat on Bearers, fixed ready for placing in  
tion.

Price, .. .. 75/9 each.

### No. P 6134. PULL - OUT APPARATUS




With Galvanized Iron Rim and Brass Handle and Deal  
Seat on Bearer, fixed ready for placing in position.

Price, .. .. 48/9 each.

**All Apparatus are tested and guaranteed.**

### No. P 2854. PULL - UP APPARATUS



With Galvanized Iron Rim and Iron Handle, and Deal  
Seat on Bearers, fixed ready for placing in position.

Price, .. .. 63/- each.


**All Apparatus are tested and guaranteed.**

# Patent Earth Closets (Moule's System) -Continued.

**Apparatus for Use in Closets** (Each form of Apparatus throws 1½ pints of Earth each time the Closet is used. When ordering Apparatus state whether it is proposed to fix the same over a vault, or whether over a tank or pail.

No. P 2856 **APPARATUS**

"Pull-Up"




With White Earthenware Rim, Galvanized Iron Valve beneath the rim, best Handle and Teak or Mahogany Seat, 3 feet wide, on bearers fixed and ready for placing in position.

Price, .. .. 180/- per set.

No. P 2857.  
**COMMODOES OR PORTABLE  
EARTH CLOSETS**

The Drawing  
represents  
Nos. F and H.




Commodes about 3 ft.  
high, 1 ft. 10 ins.  
wide, and 2 ft. 3  
ins. from back to  
front.

- |  |            |
|--|------------|
| No. P 2857A.—Commode, "Pull-out" in Plain Deal (Unvarnished), with Iron Handle and Iron Rim.                           | 75/- each. |
| .. P 2857B.—Commode, "Pull-up" (new patent), in Plain Deal (Unvarnished), with Iron Handle and Iron Rim.               | 90 - ..    |
| .. P 2857C.—Commode, "Self-acting" (new patent), in Plain Deal (Unvarnished), with Iron Rim.                           | 100/6 ..   |
| .. P 2857D.—Commode, "Pull-up" (new patent), in Plain Deal (Varnished), with Brass Handle and Earthenware Rim.         | 120 - ..   |
| .. P 2857E.—Commode "Self-acting" (new patent), in Plain Deal (Varnished), with Earthenware Rim.                       | 126/- ..   |
| .. P 2857F.—Commode, "Pull-up" (new patent), in Panelled Deal (Varnished), with best Brass Handle and Earthenware Rim. | 150/ ..    |
| .. P 2857G.—Commode, "Self-acting" (new patent), in Panelled Deal (Varnished), with Earthenware Rim.                   | 162/- ..   |
| .. P 2857H.—Commode, "Pull-up" (new patent), in Panelled Teak or Mahogany (French polished), of the very best make.    | 247/6 ..   |
| .. P 2857J.—Commode, "Self-acting," in Teak or Mahogany (French polished), of the very best make.                      | 262/6 ..   |
- Each Commode is furnished with a Pail and Cover, excepting A, B, and C, included in the above prices.


## Receptacles for use in Earth Closets (Extra to all the foregoing Nos. P 2851 to P 2856.)

No. P 2858. **PAIL**




Holds 12 Charges.  
Light, .. 4/6 each. Heavy, .. 6/- each.  
Covers for same, .. 2/- extra.

No. P 2859. **W.O. PAIL**




Holds 20 Charges.  
Price, .. .. 8/3 each.  
Cover for same, .. .. 2/- extra.

No. P 3439.  
**"MIDDLESBRO" EARTH CLOSET PAN**




24 ins. long by 16 ins. wide by 16 ins.  
deep, strong, .. 14/3 each.  
20 ins. long by 14 ins. wide by 14 ins.  
deep, .. 13/- ..

No. P 2862. **TANK**



Made to be removed from back of Closet.  
With Wheels, holds 36 Charges, .. 39/ each.  
The riser must be 1 ft. 10½ ins. high with a 6½  
inch step. Also made to be removed from  
front or side of Closet.

No. P 2863. **SELF-ACTING CINDER SIFTER**



Amongst the many advantages of this novel and ingenious invention the most noticeable is the almost entire ABSENCE OF TROUBLE AND DIRT.


The arrangement of Sifters being self-acting, it is merely necessary to empty the cinders into the hopper, and as they descend they are entirely separated, the ashes passing into the top drawer and the cinders into the lower one.

Price, .. .. 45/- each.

Although designed for use in conjunction with the earth closet system, this Cinder Sifter will be found invaluable for any household.


# Pedestal Bidets and Native Closets

No. P6815. "BRITANO" BIDET



Length, .. 25 ins.  
Width, .. 15½ "  
Height, .. 15½ "

No. P6816. "BRITANO" BIDET



Whiteware Pedestal, fitted with Mahogany Seat Pads, with Brass Portable Waste; 1½-inch Out-go; ½-inch Hot and Cold Smooth Pattern Valves; Mixing and Dividing Arrangement for Rim Supply and Uprising Spray; Ivoryite Handle Nickel-Plated.


Price, .. .. £6 15 0 each.

Whiteware Pedestal, with Clear-way Safety Overflow; 1½-inch Waste; Rubber Plug, and Chain; ½-inch Smooth Pattern Hot and Cold Valves; Mixing and Dividing Arrangement for Rim Supply and Uprising Spray; Ivoryite Handle; Nickel-plated Mountings.

Price, .. .. £5 18 0 each.

x Bidets packed in a Crate measures approximately 46 cubic feet, and weigh—gross, 4½ cwt. or 215 kilos; Earthenware, 1½ cwt. 2 lbs. or 90 kilos; Nickel-plated Brass, ¼ cwt. 17 lbs. or 21 kilos.

No. P6817. BOMBAY NATIVE CLOSET  
WITH TRAP, VENT, AND CIRCULATING RIM.



Height, 18½ ins.  
Overall size on Rim,  
23 × 12 ins.

Also made with Inlet  
at opposite end to that  
shown in illustration at  
the same prices.

		White.	Printed one Color.	Enamelled in Color.
With P or S Trap, ..	.. .. .	Price, 18/9	23/3	28/6 each.
Closet only, no Trap, ..	.. .. .	15/9	18/9	23/3 "

## Pedestal Bidets

These Bidets are furnished with a Circulating Rim, which is warmed by the passage of water into Bidet. A wooden seat is therefore unnecessary, and a most hygienic combination is secured.



No. P 6812. Pedestal Bidet, with Circulating Rim, Fittings for Hot and Cold Water to supply through Rim; Plug and Washer, complete; height, 16 inches; overall measurements on rim, 22 x 15 inches.


With White Bidet, ..	Price, <b>57/-</b> each.
With Printed .. ..	<b>64/6</b> ..
Enamelled in Colors Bidet, ..	<b>72/-</b> ..

The Fittings are Nickel Plated.

No. P 6811. Pedestal Bidet, with Circulating Rim, Fittings complete for Hot and Cold Water to supply through Rim or Spray; combined Lift-up Waste and Overflow; height, 16 inches; overall measurement on rim, 22 x 15 inches.

With White Bidet, .. ..	Price, <b>105/-</b> each.
With Printed .. ..	<b>112/6</b> ..
Enamelled in Colors Bidet, ..	<b>120/-</b> ..


The Fittings are Nickel Plated.





## Reversible Trough Closet Range

No. P 6827. Reversible Trough Closet Range, in buff glazed fireclay, with fan at front and back of openings; galvanized wrought-iron automatic flushing cistern, painted brackets and flush pipe, and 6-inch (15 c/m.) salt glazed trap.



**NOTE.**— The introduction of open fans in these Trough Closets is a decided improvement. At each flush a considerable quantity of water thoroughly washes the sides of the trough, just under the openings, preventing the adhesion of any objectionable matter and keeping the troughs sweet and clean. The fan shape of the inlet also assists in scouring the sides of the troughs. The cistern supplied is nearest stock size to 6 gallons per seat.

<b>Range of 2, 2 ft. 3 ins. centres (68 c/m.),</b>	<b>.. .. Price, £7 10 0</b>	<b>Range of 5, 2 ft. 3 ins. centres (68 c/m.),</b>	<b>.. .. Price, £13 2 6</b>
" 3, 2 " 3 " " " "	" " " 9 7 6	" 6, 2 " 3 " " "	" " " 14 13 9
" 4, 2 " 3 " " " "	" " " 11 5 0	" 7, 2 " 3 " " "	" " " 16 5 0

11	with	2 ft. 6 in. centres	(76 c/m.),	..	..	..	..	..	add	3/9 per person.
..	2	.. 0 ..	(84 c/m.),	..	..	..	..	..	..	7/6 ..
..	3	.. 0 ..	(91 c/m.),	..	..	..	..	..	..	11/3 ..


[illegible]

**Orders of £10 net value and upwards are delivered Free to nearest Railway Station.**

## Closet Ranges in Vitrolite Non-porous Fireclay

No. P 6835. Range of Wash-down Closets, in "**Vitrolite**" Fireclay, white porcelain enamelled inside, buff glazed outside; each Closet trapped separately, and connected to heavy cast-iron soil pipe, coated with Dr. Smith's solution; galvanized wrought-iron automatic flushing cistern; painted cast-iron cantilever brackets; supply and distributing pipes.

Centre of Closets, 2 ft. 3 ins. (68 c/m.), but this may be increased at a slight extra cost.



WITH UNPOLISHED SEATS.				WITH POLISHED SEATS.			
		Fixed Pad.	Ring.			Fixed Pad.	Ring.
Range of 2,	.. ..	Price, £8 15 0	Price, £9 0 0	Price, £9 0 0	Price, £9 5 0		
" 3,	.. ..	" 11 12 0	" 12 0 0	" 12 0 0	" 12 7 6		
" 4,	.. ..	" 14 10 0	" 15 0 0	" 15 0 0	" 15 10 0		
" 5,	.. ..	" 17 10 0	" 18 2 6	" 18 2 6	" 18 15 0		

When there are more than Five Closets in a Range Two Cisterns will be supplied.

If Basins white inside and out, add 5/- per basin extra.

Slate Divisions, with Supports as shown, .. Price, 31/3 each.


Ventilating Shaft is not included in above prices.

**Orders of £10 net value and upwards are delivered Free to nearest Railway Station.**

## Closet Ranges in Vitrolite Non-porous Fireclay

No. P 6829. Range of Wash-down Closets, in "Vitrolite" Fireclay, white porcelain enamelled inside, buff glazed outside; each Closet trapped separately, and connected above floor line to heavy cast-iron soil pipe, coated with Smith's solution; galvanized wrought-iron automatic flushing cistern, painted cast-iron cantilever brackets; supply distributing pipes and connections to Closets.

Centres of Closets, 2 ft. 3 ins. (68 c/m.), but this may be increased at a slight extra cost.



WITH UNPOLISHED SEATS.				WITH POLISHED SEATS.			
		Fixed Ped.	Ring.			Fixed Ped.	Ring.
Range of	2.	Price, £8 18 9	Price, £9 3 9	Price, £9 3 9	Price, £9 9 0		
"	3.	" 11 18 0	" 12 5 0	" 12 5 0	" 12 12 0		
"	4.	" 14 17 6	" 15 10 0	" 15 10 0	" 15 17 6		
"	5.	" 18 0 0	" 18 12 6	" 18 12 6	" 19 7 6		

When more than Five Basins in a Range, Two Cisterns will be supplied.

If Basin white inside and out, add 5/- per basin extra.

Slate Divisions, with Supports as illustrated, 31/3 each.


Ventilating Shaft is not included in the above prices.

Orders of £10 net value and upwards are delivered Free to nearest Railway Station.

## Automatic Syphonic Latrine Range

No. P 6828. Range of **Syphonic Fireclay Closet Pans**, white porcelain enamelled inside, buff glazed outside, with "Fixonia" or "Ring" seats; connected to heavy cast-iron soil pipes, with traps, syphon, and access door; lead suction pipe; galvanized wrought-iron automatic flushing cistern; painted cast-iron cantilever brackets; supply and distributing pipes and connections to Closets.

**IMPORTANT FEATURE.**—This latrine is so arranged that syphonic action is started without the water rising in the pans, thus eliminating a fault found in many similar systems.




Range of 2, 2 ft. 3 ins. (68 c/m.) centres, ..	Price, £10 12 6	Range of 7, 2 ft. 3 ins. (68 c/m.) centres, ..	Price, £26 17 6
" 3, 2 " 3 " " " " " " " " " "	13 15 0	" 8, 2 " 3 " " " " " " " " "	30 0 0
" 4, 2 " 3 " " " " " " " " " "	16 17 6	" 9, 2 " 3 " " " " " " " " " "	33 2 6
" 5, 2 " 3 " " " " " " " " " "	20 0 0	" 10, 2 " 3 " " " " " " " " " "	36 5 0
" 6, 2 " 3 " " " " " " " " " "	23 15 0		

Can be supplied to any centres above 2 ft. 3 ins. (68 c/m.) at extra cost. Prices quoted to enquiry.  
When more than Five Closets are supplied in one Range, the Outlet Syphon will be placed in centre.

**Orders of £10 net value and upwards are delivered Free to nearest Railway Station.**

# Closet and Closet Divisions

SUITABLE FOR SCHOOLS, WORKSHOPS, &c.



No. P 6807. Closet Division, with Door and Mountings. Made of two buff glazed fireclay slabs, 2½ inches thick, with rebated joints, painted cast-iron post, with root, ramp, and sill, including 1½-in. pine door, 5 ft. 0 in. × 2 ft. 3 ins., with hinges and handle. This Division cannot be scratched or written upon. It may be cleansed with a hose pipe.

3 ft. 8 in. Projection,	..	Price, £12 18 0
3 ft. 6 in.	..	.. 12 12 0



No. P 6808. The "MANCUNIAM" Side Out-go Closet Suite, comprising: "Densitas" ware buff and white closet, with hardwood inserted pads; side out-go. with brass inspection cap; 3-gallon buff fireclay cistern, cast-iron cover and brackets; safety school galvanized pull; 1½ inch galvanized wrought-iron flush pipe, clip and connection.

Price, £4 16 0 per set.

Closets made 12 and 16 inches high.

Made also opposite hand.

# Earthenware Lavatory Basins


No. P 102. **ROUND PLUG BOWL**



Overall Measurements—


Sizes,	..	..	..	11	12	13	14	15	ins.
No. P 102. With Overflow,	2/9	3/-	3/6	4/-	5/6	each.			
„ P 101. Without „	2/3	2/6	3/-	3/6	4/6	„			
Sizes,	..	..	..	16	17	18	19	20	ins.
No. P 102. With Overflow,	7/-	9/-	12/-	17/3	21/6	each.			
„ P 101. Without „	5/6	7/6	11/-	15/6	20/-	„			

No. P 5257. **FLAT WALL LAVATORY**



No. P 5259. Size, 19½ × 10½ ins.,	..	Price, 8/3 each.
„ P 5258. „ 21½ × 10½ „	..	„ 9/6 „
„ P 5257. „ 25 × 12 „	..	„ 14/3 „


No. P 104. **FLAT WALL LAVATORY BASIN**



suitable for rooms where space is limited.

Size, 13 × 13 ins.; Basin, 9½ ins.  
White, .. .. . Price, 9/- each.

No. P 105. **ANGULAR LAVATORY**




Size, 10 × 15 ins., with 12-in. sides and 9½-in. Basin.  
White, .. .. . Price, 9/- each.

# New Series of Lavatory Basins

LATEST IMPROVED MODELS.

No. P 6609. **THE "PATRICIA"**


Oblong Lavatory Basin Plain, Roll Edge, with Skirting at back.



Sizes, .. .. .	22 x 10	25 x 17	27 x 19 inches.
Prices, .. .. .	15/-	18/-	21/- each.

No. P 6621. **THE "SYLVIA"**

Round Front Lavatory Basin, Plain Roll Edge, with Skirting at back.




Sizes, .. .. .	22 x 10	25 x 18	27 x 19 inches.
Prices, .. .. .	15/-	18/-	21/- each.

Attention is drawn to the bold appearance of these Basins and the ease with which they can be kept perfectly clean. They have been designed in accordance with the most up-to-date ideas in hygiene, all surfaces being plain and smooth.

# New Series of Lavatory Basins

LATEST IMPROVED MODELS.


No. P6607. **THE "ALICIA"**



Angular Square Front Lavatory, Plain Roll Edge, with Skirting.

Sizes,	..	..	..	..	..	..	22 x 18	24 x 18	27 x 20 inches.
Prices,	..	..	..	..	..	..	15/-	16/6	19/6 each.

No. P6608. **THE "DOROTHEA"**



Shaped Front Lavatory, with Deep Roll Edge, Secret Overflow, ½-inch Hot and Cold Brass Pillar Taps, Slotted Brass Waste and Chain.

Size,	..	..	..	..	..	..	..	..	..	25 x 13 inches.
Price,	..	..	..	..	..	..	..	..	..	31/6 per set.

If Fittings are Nickel Plated, 4/- per set extra.


Attention is drawn to the bold appearance of these Basins and the ease with which they can be kept perfectly clean. They have been designed in accordance with the most up-to-date ideas in hygiene, all surfaces being plain and smooth.



## Earthenware Lavatory Basins

No. P 6629. **THE "NURAS"**

The new features introduced into this Lavatory are the Large Bowl (20 x 10½ inches); the Soap Trays are arranged to drain into the Overflow, and the Taps are placed in the most convenient position.




Size,  
22 × 16 inches.

**Bowl,**  
**20 × 10½ inches.**

With $\frac{1}{2}$ -inch Hot and Cold Brass Pillar Taps, 1-inch Plug and Union, Chain and Stay,	..	£1	2	6	per set.
If with Heavy Pattern Gun-metal Taps,	.. .. .	1	7	0	„
Cast-iron Bracket Frame for supporting Basin,	.. .. .	0	4	6	„

No. P 5844. **THE "UTILITAS" WALL LAVATORY**  
WITH SECRET OVERFLOW.



22 x 12 inches, with ½-inch Brass Pillar Taps, Slotted Brass Waste Chain and Stay,	..	..	<b>£1 4 0</b>	per set.
25 x 12 " " " " " " " "	..	..	<b>1 7 0</b>	"
Can also be supplied with separate Overflow at	..	..	<b>0 2 6</b>	.. less.


**These Basins will be found very useful for rooms where space is limited.**

# New Designs in Earthenware Lavatory Suites

SUPERIOR FINISH

## No. P 6622. **THE "CECILIA"**


Round Front Lavatory, with Skirting, Bar Soap Recesses, Open Overflow, Metal Supports, and Fittings complete.



Dimensions, 25 x 18 ins. over all ; Basin, 18½ x 12 ins.,	.. .. .	78/- each.
„ 27 x 19 „ „ „ 19½ x 12½ „ .. .. .	.. .. .	81/- „

## No. P 6623. **THE "FRANCES"**

Angular Lavatory, with Plain Roll Edge, Bar Soap Recesses, Open Overflow, Metal Supports, and Fittings complete.



Dimensions, 24 x 18 ins. over all ; Basin, 13 x 10 ins.,	.. .. .	Price, 72/- each.
„ 27 x 20 „ „ „ 16 x 10½ „ .. .. .	.. .. .	„ 78/- „


All Fittings and Supports to both the above Lavatories are Nickel Plated.

# Earthenware Lavatory Basins

THE BASINS SHOWN ON THIS PAGE ARE SOLID PRESSED.

## OBLONG LAVATORY BASIN


With Skirting, Oval Bowl, Soap and Brush Trays, drained.



	DIMENSIONS.		PRICE.
No. P 106.	18 × 18 inches.	.. ..	17/3 each.
„ P 110.	22 × 16 „	.. ..	19/6 „
„ P 111.	25 × 17 „	.. ..	22/6 „
„ P 119.	27 × 19 „	.. ..	27/6 „

## OBLONG LAVATORY BASIN


Without Skirting, Oval Bowl, Soap and Brush Trays, drained.



	DIMENSIONS.		PRICE.
No. P 107.	18 × 18 inches,	.. ..	14/3 each.
„ P 108.	22 × 16 „	.. ..	16/6 „
„ P 109.	25 × 17 „	.. ..	19/6 „
„ P 120.	27 × 19 „	.. ..	22/6 „

## ROUND FRONT ANGULAR BASIN


With Oval Bowl, Soap and Brush Trays, drained.



	DIMENSIONS.		PRICE.
No. P 115.	19 × 17½ inches,	.. ..	12/- each.
„ P 116.	20½ × 20½ „	.. ..	17/3 „
„ P 117.	26 × 22 „	.. ..	28/6 „

## SQUARE FRONT ANGULAR BASIN


With Oval Bowl, Soap and Brush Trays, drained.



	DIMENSIONS.		PRICE.
No. P 465.	21 × 19 inches.	.. ..	16/6 each.
„ P 466.	26 × 20 „	.. ..	24/- „


## Lavatory Sets

No. P 5843. Special Cheap Suite, consisting of **White Earthenware New Pattern Lavatory Basin**,  $\frac{1}{2}$ -inch Brass Hot and Cold Pillar Cocks, Waste Plug, Union and Chain, and Fine Cast and Painted Iron Bracket Frame.




Sizes, ..	..	..	22×16	25×18	27×19 inches.
Prices,	..	..	27/9	33/-	37/6 per set.

No. P 5850. **White Earthenware Pressed Lavatory Basin**,  $\frac{1}{2}$ -inch Brass Hot and Cold Pillar Taps, Plug and Union, Chain and Stay, and Heavy Pattern Fine Cast and Painted Bracket Frames.



Sizes, ..	..	..	22×16	25×17	27×19 inches.
Prices,	..	..	42/-	45/9	51/- per set.


No. P 5842. **Round Front Angular Pressed White Lavatory Basin**,  $\frac{1}{2}$ -inch Brass Hot and Cold Pillar Taps, Plug and Union, Chain and Stay, and Fine Cast and Painted Iron Bracket Frame.



Sizes, ..	..	..	19×17½	20½×20½	26×22 inches.
Prices,	..	..	24/-	28/6	39/- per set.


Nickel-plated Fittings to either of the above Suites, 3/9 per set extra.

No. P 4404. **White Earthenware Pressed Lavatory Basin**, Scroll Skirting,  $\frac{1}{2}$ -inch Brass Hot and Cold Pillar Taps, Plug and Union, Chain and Stay, and Fine Cast and Painted Iron Bracket Frame.




Sizes, ..	..	..	22×16	25×17	27×19 inches.
Prices,	..	..	33/-	37/6	42/- per set.

No. P 4406. **Round Front White Earthenware Pressed Lavatory Basin**,  $\frac{1}{2}$ -inch Brass Hot and Cold Pillar Taps, Plug and Union, Chain and Stay, and Fine Cast and Painted Iron Bracket Frame.




Sizes, ..	..	..	18×18	21×18	25×18 inches.
Prices,	..	..	31/6	33/9	37/6 per set.

No. P 5841. **New Pattern Plain Lavatory Basin**, Angular Square Front,  $\frac{1}{2}$  inch Brass Hot and Cold Pillar Taps, Plug and Union, Chain and Stay, and Fine Cast and Painted Iron Bracket Frame.



Sizes, ..	..	..	24×18	27×20 inches.
Prices,	..	..	31/6	36/- per set.

## Lavatory Suites



### THE "NEW CHELMER"

No. P 4426. White Earthenware Basin, Hot and Cold Brass Pillar Taps, Waste Plug and Union, with Chain and Stay ; Ironwork Fine Cast and Painted One Coat.

Sizes, .. .. 22×16    25×17    27×19 inches.

Prices, .. .. 42/-    46/6    51/- per set.

If with Heavy Gun-metal Taps, .. 4/6 per set extra.

.. „ Nickel-plated Fittings, .. 3/9 .. ..


### THE "CALEDONIAN"

No. P 6125. Best White Earthenware Lavatory Basin, Cast-iron Bracket Frame, Porcelain Enamelled,  $\frac{1}{2}$ -inch Heavy-pattern Hot and Cold Gun-metal Pillar Taps, Waste and Chain.

Sizes, .. .. 22×16    25×17    27×19 inches.

Prices, .. .. 52/6    57/-    63/- per set.

Nickel-plated Fittings, 3/9 per set extra.




## New Series of Lavatories

### "BRITANO" LAVATORY BASIN, with Stand and Fittings.


No. P 6624. 27×19 ins. White Lavatory, with Cast-iron Stand painted one coat; Strong Waste, 1½-inch Rubber Plug, 1½-inch Out-go Union, Smooth Chain, ½-inch Hot and Cold Smooth pattern Pillar Taps.

Price, .. .. £3 10 0 per set.

All Fittings are Nickel Plated.



### "BRITANO" LAVATORY BASIN, with Brackets and Fittings.




No. P 6625. 23×17 ins., White Lavatory, with Cast-iron Brackets painted one coat; Strong Waste, 1½-inch Rubber Plug, 1½-inch Out-go Union, Smooth Chain, ½-inch Smooth Pattern Pillar Taps.

Price, .. .. £2 17 0 per set.

All Fittings are Nickel Plated.

# Fine Cast Lavatory Stands

WITH HAND PRESSED BASINS.




No. P 6100. **THE "BERKELEY"**


Comprising Ironwork, Fine Cast and Painted one coat ; Bevelled Mirror, Colored Tiles, Brass Towel Rail, 27×19 inch White Lavatory Basin, Hot and Cold Heavy Gun-metal Pillar Taps, Waste Plug. Chain and Stay, .. .. . Price per set,		<b>£5 0 0</b>
If Ironwork is Enamelled in Colors, Third Finish, ..		<b>6 12 0</b>
" " " " Best Finish, and relieved in Gold, .. .. .		<b>7 4 0</b>
If Fittings are Nickel Plated, .. .. . extra,		<b>0 3 6</b>

No. P 6101. **THE "MAYFAIR"**


Comprising Ironwork, Fine Cast and Painted one coat ; Bevelled Mirror, Colored Tiles, Brass Towel Rail, 27×19 inch White Lavatory Basin, Hot and Cold Heavy Gun-metal Pillar Taps, Waste Plug and Union, Chain and Stay, .. .. . Price per set,		<b>£4 10 0</b>
If Ironwork is Enamelled in Colors. Third Finish, ..		<b>5 10 0</b>
" " " " Best Finish, and relieved in Gold, .. .. .		<b>6 9 0</b>
If Fittings are Nickel Plated, .. .. . extra,		<b>0 3 6</b>



## Folding Lavatories



No. P 6627. Folding Lavatory, closed.




No. P 6627. Folding Lavatory, open

DIMENSIONS : Closed Height, 20½ ins. ; Width, 20 ins. ; Depth, 7½ ins.  
Open     "     20½     "     20     "     21½     "



No. P 6628. Folding Lavatory, open.



No. P 6628. Folding Lavatory, closed.

DIMENSIONS : Closed—Height, 42 ins. ; Width, 20½ ins. ; Depth, 8½ ins.  
Open     "     42     "     20½     "     22½     "


These Lavatory Enclosures are made in polished mahogany or walnut, best cabinet work, and include whiteware anti-splash bowl 15 x 15 inches, with soap dishes, cold, or hot and cold combined taps, and fittings nickel plated, zinc hopper, and in the case of No. P 6628 also portable waste water receiver, white japanned interior.

No. P 6628.	With Cold Water Spring Valve as shown,	..	..	..	..	..	..	..	..	Price, £8 17 0
..	Hot and Cold Screw-down Taps, as No. P 6627.	..	..	..	..	..	..	..	..	9 15 0
.. P 6627.	Hot and Cold Taps,	..	..	..	..	..	..	..	..	6 6 0
..	Cold Water Spring Valve, as No. P 6628,	..	..	..	..	..	..	..	..	5 11 0
If Basin and Soaps Gold Lined, 9/- extra.										

The Enclosures may be in any other suitable wood, and can be white enamelled outside. Prices on application.




## Improved Pedestal Lavatories



**THE "BUCKINGHAM"**

No. P 6326. Oval Pedestal Lavatory, 30×22 ins.; height, 31½ ins.; including ½-inch heavy pattern Hot and Cold Pillar Taps, and Lift-up Waste; all Fittings Nickel Plated.

Price, complete as drawn. . . 93/- each.



**THE "CLIFTONVILLE"**

No. P 6327. Oblong Pedestal Lavatory, 27×19 ins.; height, 30½ ins.; including ½-inch heavy pattern Hot and Cold Pillar Taps, and Lift-up Waste; all Fittings Nickel Plated.

Price, complete as drawn. . . 84/- each.

Considerable improvement has been effected in the designs of these two Lavatories, viz., the elimination of all unnecessary mouldings which would allow of the accumulation of dirt, and a bolder and more pleasing shape, introducing plain roll edges.

## Superior Quality Pedestal Lavatories



No. P 6605. **THE "MARLBOROUGH"**

**IMPROVED PEDESTAL LAVATORY.**—Firmly secured to floor by wood strip fixed in interior of base of Pedestal.


**OVAL LAVATORY BASIN.** New plain pattern, with combined Open-stream Overflow and Waste ; 31½ 24 inches over all ; height, from floor 33 inches ; including ½-inch heavy pattern Nickel-plated Hot and Cold Pillar Taps, Plug and Waste, and Grid to Overflow, Malleable-iron Stretcher for securing Lavatory to Pedestal, and Oak Fitting Strip for fixing to floor.

Price, .. .. . **£7 10 0** each.

No. P 6606. **THE "ST. JAMES,"**

**PEDESTAL LAVATORY AND BASIN,** with Round Front, Deep Roll Edge, and Plain Fluted Pedestal ; ordinary Overflow ; including ½-inch heavy pattern Nickel-plated Hot and Cold Pillar Taps, 1½-inch Nickel-plated Plug and Waste, with Tail Piece and Malleable-iron Stretcher for securing Lavatory to Pedestal, and Oak Fitting Strip for fixing to floor ; height, 32½ inches.


Size, 30×22 inches, .. Price, **£6 15 0** each.  
 „ 27×19 „ .. „ **5 0 0** ..



## New Design Lavatory

WITH SHOWER AND EYE SPRAY.

No. P 6626. THE "LAVENHAM"




No. P 6626. Lavatory, 30×22 inches, in Best Quality Whiteware; Ivoryite Lever Handle, Quarter-turn Smooth Pattern Hot and Cold Valves, Quick Lift-up Waste. Swivel Shower and Eye Spray—all Nickel Plated.

Price, £13 10 0 per set.

# Pure White Porcelain Enamelled Fireclay Lavatory

No. P 6592. THE "MALVERN" LEADLESS GLAZED.



Length over all, 34 ins. (86 c/m); width over all, 22 ins. (56 c/m); height over all, 30 ins. (76 c/m).

SPECIFICATION.—No. P 6592. Oval Faena Lavatory and Pedestal, in best pure White Porcelain Enamelled Fireclay; half-inch (13 m/m) Hot and Cold Quarter-turn Taps with Porcelain Lever Handles, and Standing Waste and Overflow in Polished Gun Metal.

Price, complete as specified, .. .. . £14 10 0

## EXTRAS.

If Fittings are Nickel-plated, add .. .. .	£0 7 0	S Trap with Vent Connection, Down Pipe and Floor Plate,	
Porcelain Vases and Soap Dish with Nickel-plated Holder, ..	2 2 0	Nickel-plated, .. .. .	£2 2
Bevelled Plate-glass Mirror in White French-polished Frame, ..	5 2 6	Supply Pipes with Floor Plates and Connections, Gun Metal, p. pair, ..	0 17
S Trap with Vent Connection, Down Pipe and Floor Plate,		" " " " " Nickel-plated, ..	1 5
Gun Metal, .. .. .	1 17 6		

This Lavatory is arranged to stand clear of wall.

# Porcelain Enamelled Fireclay Lavatory Ranges

No. P 6591. **THE "MATLOCK"**

LEADLESS GLAZED.



**SPECIFICATION.**—No. P 6591. Lavatory Range, comprising Three Basins in Pure White Porcelain Enamelled Fireclay with Overlap Joints, and Skirting to back and sides. Half-inch (13 m/m) Hot and Cold Gun-metal Screw-down Taps, 1¼-inch (32 m/m) Gun-metal Plug and Washer with Chain and Stay to each Basin. Painted Cast-iron Solid Web Wall Brackets to support Basins.

		20 × 18 ins. (51 × 46 c/m.)	24 × 18 ins. (61 × 46 c/m.)	26 × 20 ins. (66 × 51 c/m.)
Prices complete for Range of Three, .. .. .		<b>£9 5 0</b>	<b>£10 6 0</b>	<b>£11 7 6</b>
Add for each additional Basin, .. .. .		<b>2 17 0</b>	<b>3 5 0</b>	<b>3 10 0</b>

**NOTE.**—These Basins are white enamelled on the underside, and can be supplied with lugs to build into wall, instead of brackets, at same prices as above.

The above Lavatories can also be supplied in buff glazed.


		20 × 18 ins. (51 × 46 c/m.)	24 × 18 ins. (61 × 46 c/m.)	26 × 20 ins. (66 × 51 c/m.)
Prices complete for Range of Three, <b>Buff Glazed</b> , ..		<b>£8 5 0</b>	<b>£9 0 0</b>	<b>£9 15 0</b>
Add for each additional Basin, .. .. .		<b>2 12 0</b>	<b>2 17 0</b>	<b>3 1 6</b>

<b>EXTRAS.</b> —If Brackets are White Porcelain Enamelled, .. .. .	add per bracket,	<b>5/-</b>
.. Brackets are Galvanized, .. .. .	.. ..	<b>4/-</b>
.. White Porcelain Enamelled Fireclay Cantilevers, instead of Cast Iron, ..	.. ..	<b>6/9</b>
.. Buff Glazed .. .. .	.. ..	<b>4/6</b>
.. Fittings are Nickel Plated, .. .. .	add per basin,	<b>4/-</b>
.. Gun-metal Cover to Overflow, .. .. .	.. ..	<b>3/-</b>
.. Nickel-plated Cover to Overflow, .. .. .	.. ..	<b>3/6</b>

# Porcelain Enamelled Fireclay Lavatory Ranges

No. P 6590. **THE "HARROGATE"**

LEADLESS GLAZED.




SPECIFICATION.—No. P 6590. Lavatory Range, comprising Three Basins in Pure White Porcelain Enamelled Fireclay, with Ground Butt Joints and Brick to build in wall. Half-inch (13 c/m) Hot and Cold Screw-down Taps, Burnished Gun-metal Standing Waste and Wall Hook to each Basin.

All exposed surfaces are enamelled white, and all flat surfaces slope to the bowl.

										24 x 18 ins. (61 x 46 c/m.)
Price complete for Range of Three,	..	..	..	..	..	..	..	..	..	<b>£10 15 0</b>
Add for each additional Basin complete,	..	..	..	..	..	..	..	..	..	<b>3 10 0</b>
EXTRAS.—If Fittings are Nickel Plated,	..	..	..	..	..	..	..	..	add per basin,	<b>5/6</b>
If Fittings are in White Metal,	..	..	..	..	..	..	..	..	„ „	<b>15/6</b>
DEDUCTIONS.—If Basins are made with Open Weir Overflow and fitted with										
Plug and Washer,	..	..	..	..	..	..	..	..	deduct per basin,	<b>9/-</b>
If Basins are Buff Glazed,	..	..	..	..	..	..	..	..	„ „	<b>7/6</b>

# Improved Fireclay Slop Hoppers

No. P 6610



## CORNER SLOP SINK

With or without Hinged Brass Grating.

DIMENSIONS.—Top, 25×21 inches; height from floor to front edge, 12 inches; height from floor to top of skirting, 18 inches

	White in, Buff out.	White in and out.
No. P 6610. Corner Slop Sink, with Hinged Brass Grating. . . . .	£3 10 6	£4 0 0
No. P 6611. Do., without Hinged Grating. . . . .	2 11 0	3 0 0
If with S or P Trap, add . . . . .	0 12 0	0 15 0

No. P 6612.


## FLAT BACK SLOP SINK

With or without Brass Grating.

DIMENSIONS.—Top, 18×18 inches; height from floor to front edge, 12 inches; height from floor to top of skirting, 18 inches.

	White in, Buff out.	White in and out.
No. P 6612. Flat Back Slop Sink, with Hinged Brass Grating. . . . .	£3 10 6	£4 0 0
No. P 6613. Do., without Hinged Grating. . . . .	2 11 0	3 0 0
If with S or P Trap, add . . . . .	0 12 0	0 15 0

No. P 6614.



## SLOP SINKS

In Three Pieces.

DIMENSIONS.—No. P 6614—Top, 18×18 inches; height from floor to front edge, 18 inches; height from floor to top of skirting, 23 inches. No. P 6615—Top, 25×21 inches. Other sizes as No. P 6614.


	White in, Buff out.	White in and out.
No. P 6614. Flat Back Slop Sink in Three Pieces, Top, Hopper, and Trap, S or P. . . . .	£2 11 0	£3 3 0
No. P 6615. Corner Slop Sink in Three Pieces, Top, Hopper, and Trap, S or P, . . . . .	2 11 0	3 3 0
If with Hinged Brass Grating fitted, add . . . . .	1 1 0	1 1 0

For Flushing Cisterns for these Sinks, refer to pages 160 and 161.  
For Taps, refer to page 146.

# Drainer Sink and Lavatory and Draw-off Sinks

No. P 6601. **THE "MARYLAND"**

Also made  
left hand.




Fluted Fireclay Sink and Lavatory, in one piece, White Glazed, 54 20 49 ins. deep, with  $\frac{1}{2}$ -inch Gun-metal Hot and Cold Pillar Taps to each, large Clearway Overflow,  $1\frac{1}{2}$ -inch Waste with Out go Union; also Cast-iron White Painted supporting Brackets.

Price complete, . . . . . **£12 15 0**

No. P 6602.

**Draw-off and Slop Sink**



OUTSIDE SIZES.—18 ins. wide, 14 ins. high, 14 ins. back to front, 7 ins. deep.


White inside and outside, with Brass Hinged Grating, 2-inch Waste and Union, and Brackets.

Price, . . . . . **64/6 each.**

Half-inch Taps with Back  
Plate, as shown, **18/-** per pair extra.

No. P 6603.

**Draw-off and Slop Sink**  
With Rounded Corners.



OUTSIDE SIZES.—21 ins. wide, 14 ins. high, 16 ins. back to front, 7 ins. deep.


White inside and outside, with Brass Hinged Grating, Teak Rim, 2-inch Waste and Union, and Brackets.

Price, . . . . . **83/- each.**

Half-inch Taps with Back  
Plate, as shown, **18/-** per pair extra.

No. P 6604.

**Angular Draw-off and Slop Sink**



OUTSIDE SIZES.—22 $\frac{1}{2}$  ins. wide, 16 ins. back to front, 14 ins. high, 7 ins. deep.

White inside and outside, with Brass Hinged Grating, 2-inch Waste and Union, and Brackets.


Price, . . . . . **64/6 each.**

Half-inch Taps with Back  
Plate, as shown, **18/-** per pair extra



# Improved Slop Hoppers

No. P 6616. FOR CORNER.




DIMENSIONS.— Top, 24×24 inches; height at front, 14 inches; height to top of skirting, 18 inches.

This Suite comprises finest White-glazed Fireclay Slop Hopper and Trap in one piece (either S or P Trap), and loose Fireclay Grid, 2-gallon Cast-iron Valveless Syphon Cistern, Pull and Chain and Eye, Brackets and 1½-inch Galvanized Wrought-iron Flush Pipe, as shown, with Clip and Connections, .. .. . £7 1 0

EXTRAS.—½-inch Taps, .. .. 18/ per pair.  
Teak Curb, .. .. 10/6  
Brass Hinged Grating, .. 21/-

No. P 6617. FOR FLAT WALL.




DIMENSIONS.— Top, 18×18 inches; height at front, 14 inches; height to top of skirting, 18 inches.

This Suite comprises finest White-glazed Fireclay Slop Hopper and Trap in one piece (either S or P Trap), and loose Fireclay Grid, 2-gallon Cast-iron Valveless Syphon Cistern, Pull and Chain and Eye, Brackets and 1½-inch straight Galvanized Wrought-iron Flush Pipe, with Clip and Connections, .. .. . £6 7 6

EXTRAS.—½-inch Taps, .. .. 17/6 per pair.  
Teak Curb, .. .. 10/6  
Brass Hinged Grating, .. 21/-

# Improved Drainer and Slop Sink

No. P 6618. THE "BELMONT"



DIMENSIONS.—Drainer Sink, 36×18×8 ins. outside; Slop Hopper, 18×18×20 ins. high; Sink and Hopper, 4 ft. 6 ins. extreme length.

No. P 6618. Combination Drainer Sink and Slop Hopper. made in Strong Fireclay, includes 1½-inch Sink Plug and Chain, One Cast-iron Bracket, Two Pairs ½-inch Hot and Cold Taps with Back Plates (no Lead Piping), Slop Hopper, 2½-gallon Fireclay Valveless Syphon Cistern, Iron Cover and Brackets, Pull and Chain and Guide Eye, 1½-inch Galvanized-iron Flush Pipe with Connections, .. .. .										White Glazed in and out.	White Glazed inside, Buff outside.
										£15 0 0	£12 15 0
,, P 6619. Slop Hopper, with Cistern and Flush Pipe. as above described, .. .. .										6 15 0	6 6 0
,, P 6620. Drainer Sink, with Two Brackets, Plug and Chain only, .. .. .										6 0 0	5 2 0


EXTRAS —If Slop Hopper is supplied with Brass Hinged Grating, add 21/-

If Teak Roll to Hopper and Drainer Sink, add 10/6 to each.

If Nos. P 6619 and P 6620 are supplied with ½-inch Taps and Back Plates, add 18/- per pair.

# “Excelsior” Superior Quality Fireclay Lavatory Range

LATEST UP-TO-DATE MODEL



No. P 6850. **Lavatory Range**, comprising basins with skirting and overlap joint in best quality “Excelsior” fireclay ware, with weir overflow,  $\frac{1}{2}$ -inch hot and cold gun-metal pillar taps, gun-metal washer, with chain and rubber plug, fireclay pedestals, and floor channel with sockets; galvanized down pipes and gun-metal dome-shaped grating.

					Basins.		White Enamelled.		Buff Glazed.
Range for 2 Persons,	..	..	..	..	26 × 20 inches.		Price, £11 0 0		Price, £9 10 0
.. 2 ..	..	..	..	..	24 × 18 ..	..	10 6 0	..	8 18 0
.. 2 ..	..	..	..	..	20 × 18 ..	..	9 10 0	..	8 6 0
Extra per Person,	..	..	..	..	26 × 20 ..	..	4 16 0	..	4 0 0
.. ..	..	..	..	..	24 × 18 ..	..	4 7 6	..	3 15 0
.. ..	..	..	..	..	20 × 18 ..	..	4 0 0	..	3 10 0

If with Nickel-plated Fittings, add 4/6 per person.

Overall dimensions, 26 × 20 inches	(68 × 51 centimetres).	Bowls, 19½ × 13 inches	(49 × 33 centimetres).
.. .. 24 × 18 ..	(61 × 46 .. ).	.. 18½ × 12 ..	(47 × 30 .. ).
.. .. 20 × 18 ..	(51 × 46 .. ).	.. 15 × 12 ..	(38 × 30 .. ).


Channel—Width, 9 inches (23 centimetres); depth, 5 inches (13 centimetres).

Height to top of Lavatory Basins at front, 30 inches (76 centimetres).

# Enamelled Fireclay Sinks

## ORDINARY PATTERN SINK


Outlet in centre at end. Cane glazed outside on both sides.  
For either right or left hand.



Outside Size.	No. P 5274. Cane Glazed inside and out.	No. P 5275. White Glazed inside and out.
24 x 16 x 7 ins.	Price, 9/6 each.	Price 13/6 each.
24 x 18 x 7 "	" 10/6 "	" 14/3 "
27 x 18 x 7 "	" 12/6 "	" 17/3 "
30 x 18 x 7 "	" 13/6 "	" 19/6 "
36 x 20 x 7 "	" 19/6 "	" 27/- "

## ROUNDED CORNER SINK


With Beaded Rim. Outlet in centre at back.



Outside Size.	No. P 5273. White Glazed inside and on front and both end.
24 x 18 x 6 ins.	Price, 19/6 each.
27 x 18 x 6 "	" 22/6 "
30 x 18 x 6 "	" 24/- "
36 x 20 x 7 "	" 36/- "
42 x 24 x 8 "	" 57/- "

## "EDINBURGH" PATTERN SINK

With Overflow Outlet in centre at end. Unglazed outside for  
woodwork covering.




Outside Size.	No. P 5281. Cane Glazed inside and out.	No. P 5282. White Glazed inside and out.
18 x 15 x 8 ins.	Price, 9/- each.	Price, 12/- each.
21 x 15 x 8 1/2 "	" 11/3 "	" 15/- "
24 x 18 x 8 1/2 "	" 12/6 "	" 16/6 "
27 x 17 x 9 "	" 16/6 "	" 22/6 "
30 x 17 x 9 "	" 18/6 "	" 26/3 "
36 x 17 x 9 "	" 22/6 "	" 31/6 "

## "BELFAST" PATTERN SINK

With Overflow Outlet in centre at end. Cane Glazed outside on both sides.  
For either right or left hand.



Outside Size.	No. P 5249. Cane inside and out Price, 10/6 each.	No. P 5270. White inside and Cane out Price, 14/3 each.
21 x 16 x 7 ins.	" 12/6 "	" 17/3 "
27 x 18 x 7 "	" 14/3 "	" 19/6 "
30 x 18 x 7 1/2 "	" 16/6 "	" 22/6 "
24 x 18 x 10 "	" 18/6 "	" 24/9 "
27 x 18 x 10 "	" 21/- "	" 27/- "
30 x 18 x 10 "	" 24/- "	" 33/- "



## The "Krator" Fireclay Sink Support

For Sinks 16 ins. to  
18 ins. wide.

The Pair, in Cane,  
Price, .. 10/6 per set.

The Pair, in White,  
Price, .. 13/6 per set.

No. P 6226. Galvanized Cast-iron  
Cantilever Sink Brackets



Sizes, 12 14 16 18 22x6 ins. Batt.  
Prices, 3/6 4/- 4/6 5/- 6/- each.

## SINK, with Pedestals


White Glazed inside and on front  
and ends outside, with Overflow,  
Outlet in centre at back, and Supports.

SINKS - No. P 5284. Outside sizes.

24 x 18 x 10 ins., at	30/- each.
30 x 18 x 10 "	" 36/- "
36 x 18 x 10 "	" 42/- "
36 x 24 x 11 "	" 52/6 "
39 x 24 x 12 "	" 75/- "
42 x 24 x 12 "	" 84/- "


SUPPORTS No. P 5286. White.

20 ins. high x 4 1/2 ins., at	11/3 each.
20 " " x 18 " "	" 12/6 "
20 " " x 22 " "	" 13/6 "



# **“Excelsior” Superior Quality Fireclay Sink**

LATEST UP-TO DATE MODEL.



No. P 6852. **Combination Sink**, with 6-inch fast back, fluted drainer, and pedestals, in best quality “Excelsior” fireclay ware, white porcelain enamelled; with gun-metal  $\frac{3}{4}$ -inch hot and cold taps, 2-inch waste union with rubber plug, chain, and stay, and with teakwood inset rim.

Dimensions, 48 × 21 × 10 × 16 inches, .. .. . Price, **£8 15 0** each.

„ 42 × 21 × 10 × 16 „ .. .. . „ **7 15 0** „


„ 36 × 21 × 10 × 16 „ .. .. . „ **6 18 0** „

							48	42	36 inches.
If without 6-inch Fast Back,	..	..	..	..	..	deduct,	<b>22/6</b>	<b>19/6</b>	<b>16/3</b> per sink.
„ Teakwood Inset Rim,	..	..	..	..	..	„	<b>10/6</b>	<b>8/3</b>	<b>6/3</b> „
If with Teakwood Drainer,	..	..	..	..	..	add,	<b>10/6</b>	<b>8/3</b>	<b>6/3</b> „

These Sinks can be supplied with Fast Plain Drainer at same prices as above.

# **“Excelsior” Superior Quality Fireclay Sink**

LATEST UP-TO-DATE MODEL




No. P 6851. **Combination Sink**, with 6-inch fast back, slides under sink for drainer, and weir overflow, with pedestals in best quality “Excelsior” fireclay ware, white porcelain enamelled, with teakwood drainer and teakwood inset rim ;  $\frac{3}{4}$ -inch gun-metal hot and cold bib taps, and 2-inch gun-metal washer, with chain and rubber plug.

Dimensions, 48 × 21 × 10 × 16 inches,	..	..	..	..	..	Price, <b>£10 0 0</b> each.
„ 42 × 21 × 10 × 16 „	..	..	..	..	..	<b>8 15 0</b> ..
„ 36 × 21 × 10 × 16 „	..	..	..	..	..	<b>7 15 0</b> ..

# "Excelsior" Superior Quality Fireclay Sinks

LATEST UP-TO-DATE MODELS




No. P 6853. **Combination Sink**, in best quality "Excelsior" fireclay ware, white porcelain enamelled, with overflow and fast plain drainer.

Dimensions, 48	21	10 inches.	..	..	..	..	..	..	..	Price, £4 5 0 each.
" 42	21	10 "	..	..	..	..	..	..	..	" 3 10 0 "
" 36	21	10 "	..	..	..	..	..	..	..	" 2 18 0 "

If with 6-inch Fast Back, ..	..	..	..	..	..	..	..	..	..	add 48	42	36 inches.
" Teakwood Inset Rim, ..	..	..	..	..	..	..	..	..	..	add 22 6	19 6	15 9 per sink.
										" 10 6	8 3	6 3 "

If with Gun-metal Washer, with Rubber Plug and Chain and Stay, add 9 - per sink.



No. P 6854. **Combination Sink**, with slides under sink for drainer, and with weir overflow, in best quality "Excelsior" fireclay ware, white porcelain enamelled.



Dimensions, 48 x 21 x 10 inches.	..	..	..	..	..	..	..	..	..	Price, £4 18 0 each.
" 42 x 21 x 10 "	..	..	..	..	..	..	..	..	..	" 4 2 6 "
" 36 x 21 x 10 "	..	..	..	..	..	..	..	..	..	" 3 9 0 "

If with 6-inch Fast Back, ..	..	..	..	..	..	..	..	..	..	add 48	42	36 inches.
" Teakwood Inset Rim all along front, ..	..	..	..	..	..	..	..	..	..	add 22/6	19/6	15/9 per sink.
										" 21/-	16/6	12/6 "

Pedestals suitable for either of the above Sinks, 27/6 per pair.

# Automatic Flushing Cisterns

No. P-441. **THE "TOMATON"**



No increase in water supply is required to start the flush. The last drop does this. Before that drop, the Cistern is sound and watertight. IMMEDIATELY AFTER, the Cistern is flushing at full speed.

## EXPLANATION OF DIAGRAM.

As the water rises in the cistern, the float **A** tries to rise with it, but is held down by the catch **B**. When the cistern is nearly full, float **C** rises and releases catch **B**. Then float **A** instantly rises and opens valve **D**, starting the syphon at full speed. As the cistern empties, the arrangement automatically re-sets itself.


The floats are ABSOLUTELY SEAMLESS and made of sheet copper.

Capacity, .. .. .	1	2	3	4	6	9 gallons.
Size of Outlet,.. ..	1	1½	1½	1½	1½	2 inches.
Prices, Painted, .. ..	24/-	27/-	32/6	36/-	39/-	48/- each.
„ Galvanized, .. ..	30/-	33/-	39/-	45/-	51/-	63/- „

Other sizes specially quoted for. Larger sizes than 10 gallons have galvanized wrought-iron bodies and no covers.

No. P 6787. **THE "TIP UP"**


A most reliable Automatic Cistern with Drip Cock complete.  
No Ball Valve required.



Capacity, ..	1	2	3	4	6 gallons.
Painted, ..	25/6	27/6	35/6	39/6	45/- each.
Galvanized, ..	30/-	34/6	45/-	49/6	57/- „

No. P 6788 **AUTOMATIC FLUSHING TANK**

Suitable for Ranges of Closet Latrines.  
Galvanized Wrought Iron, with Cast-iron Trap and  
Wrought-iron Cylinder.




Capacity, ..	20	30	40	50	60	70 galls.
Prices, 16 Gauge,	81/6	87/6	96/-	105/-	112/6	115/- each.




# Improved Earthenware Urinals

**FLAT WALL "BEDFORD"**




Design.	No.	Height.	Diameter.	Price.
No. P 414.	..	14 ins.	12 x 7 1/2 ins.	15/- each.
" P 415.	..	16 "	13 x 8 "	18/- "
" P 416.	..	18 "	16 x 8 1/2 "	21/- "

**ANGULAR LIPPED "BEDFORD"**



Design.	No.	Height.	Diameter.	Price.
No. P 411.	..	10 ins.	14 x 14 ins.	19/6 each.
" P 412.	..	11 "	16 x 15 1/2 "	23/3 "
" P 413.	..	12 "	17 x 16 1/2 "	27/6 "

**FLAT WALL LIPPED "BEDFORD"**



Design.	No.	Height.	Diameter.	Price.
No. P 126.	..	14 ins.	12 x 11 ins.	19/6 each.
" P 127.	..	16 "	13 x 11 "	22/6 "
" P 128.	..	18 "	16 x 13 "	27/6 "

**ANGULAR "BEDFORD"**





Design.	No.	Height.	Diameter.	Price.
No. P 122.	..	10 1/2 ins.	14 x 12 ins.	15/- each.
" P 123.	..	11 "	16 x 13 "	18/- "
" P 124.	..	12 "	18 x 15 "	21/- "

# Improved Urinal Stalls

IN FIRECLAY, HIGHLY GLAZED.

No. P 6597. THE "MALL"

No. P 6599. THE "STRAND"



DIMENSIONS.—3 ft. 6 ins. high; sides, 1 ft. 6 ins.

No. P 6597. Corner Urinal, with Tile-filled Tread, 11 ins. broad.  
 " P 6598. " " with Glazed Fluted Tread, 6 ins. broad,  
 as No. P 6600.

DIMENSIONS.

MEDIUM SIZE.—3 ft. 6 ins. high; 1 ft. 10 ins. centres; 1 ft. deep.  
 LARGE SIZE.—4 ft. high; 2 ft. centres; 1 ft. 1 in. deep.

No. P 6600. Single Urinal, with Glazed Fluted Tread, 6 ins. broad.  
 " P 6599. " " but with Tile-filled Tread, 11 ins. broad  
 as No. P 6597.

These Urinals include tread, glazed fireclay automatic cistern, painted brackets, brass flush pipe and spreader, also brass arched out-go grid.


PRICES.

	No. P 6597.	No. P 6598.
Buff Glazed, .. ..	£10 1 0	£8 15 0
White Glazed, .. ..	£10 1 0	9 6 0

	No. P 6600.	No. P 6599.
Medium Size.	£7 10 0	Medium Size.
Large Size.	7, 17 6	Large Size.
		£8 5 0
		8 15 6
		£8 15 6
		£9 10 6

# Porcelain Enamelled Fireclay Urinal

No. P 6595. **THE "MOORGATE"** LEADLESS GLAZED.



MEASUREMENTS.--From floor to top of stall, 3 ft. 5 ins. (m 1.06) ; width of stall, 2 ft. 2 ins. (m 0.66) ; depth of foundation, 5 ins. (m 0.13) ; length of side, 18 ins. (m 0.46).

SPECIFICATION.--No. P 6595. Single Angular Urinal Stall, comprising Back with Sole and accessible Channel in one piece, loose Fluted Tread and Cistern Casing all in best quality Fireclay. Automatic "Drop by Drop" Syphon, Polished Solid-drawn Copper Supply Pipe with Gun-metal Union and Distributor. Enamelled Cast-iron Brackets to support Cistern. Outlet fitted with Gun-metal Dome-shaped Grid.

Prices complete as specified, Pure White Enamelled, £9 7 6; Buff Glazed, £8 0 0

# Porcelain Enamelled Fireclay Urinal

No. P 6594. **THE "LUDGATE"** LEADLESS GLAZED.

MEASUREMENTS.—From floor to top of stall  
3 ft. 5 ins. (m 1.06) ; width of stall, 1 ft.  
10½ ins. (m 0.59) ; from floor line to top  
of cistern, 7 ft. (m 2.13).

MEASUREMENTS.—From floor to foundation,  
5 ins. (m 0.13) ; projection from wall  
above floor, 12 ins. (m 0.30) ; projection  
from wall to edge of tread, 1 ft. 3 ins.  
(m 0.38).





SPECIFICATION.—No. P 6594. Single flat back Urinal Stall, comprising Back with Sole and accessible Channel in one piece, loose Fluted Tread and Cistern Casing, all in best quality Fireclay. Automatic "Drop by Drop" Syphon, Polished Solid-drawn Copper Supply Pipe with Gun-metal Union and Distributor, Enamelled Cast-iron Brackets to support Cistern, Outlet fitted with Gun-metal Dome-shaped Grid.

Price, complete as specified, Pure White Porcelain Enamelled. £9 7 6 ; Buff Glazed, £8 0 0

# Improved Urinal Range

No. P 6596.—THE "BELGRAVIA"



Section of Urinal.

These Urinal Stalls are **made in one piece of highly-glazed fireclay, and are free from sharp curves or corners.** They include glazed automatic cistern with brackets, copper flush pipes and spreaders, and arched out-go grid.

**DIMENSIONS.**—SMALL—3 feet 6 inches high; centres, 1 foot 5 inches; divisions, 1 foot.

MEDIUM—3 feet 6 inches high; centres, 1 foot 11 inches; divisions, 1 foot 1 inch.

LARGE—4 feet high; centres, 2 feet; divisions, 1 foot 1 inch.


					Small.	Medium.	Large.
Prices for 3 or more Stalls in a Range, White	..	..	..	..	97/6	115/-	142/6 per Stall.
" " 3 " " " Buff,	..	..	..	..	93/-	100/6	128/- " "

# Porcelain Enamelled Fireclay Urinal Range

No. P6593. THE "PICCADILLY." LEADLESS GLAZED.

MEASUREMENTS.—Medium size—From floor line to top of stall, 3 ft. 5½ ins. (m 1.06) ; from floor line to top of division, 4 ft. 5½ ins. (m 1.46) ; from floor line to foundation 5 ins. (m 0.13) ; from centre to centre of stalls, 23½ ins. (m 0.60) ; from wall to front of stall, 12 ins. (m 0.305) ; from wall to front of division, 17 ins. (m 0.43) ; from wall to front of tread, 16 ins. (m 0.41) ; from floor line to top of cistern, 8 ft. 6 ins. (m 2.44).

MEASUREMENTS.—Small size—From floor line to top of stall, 3 ft. (m 0.76) ; from floor line to top of division, 4 ft. (m 1.12) ; from floor line to foundation, 5 ins. (m 0.13) ; from centre to centre of stalls, 18 ins. (m 0.46) ; from wall to front of stall, 12 ins. (m 0.305) ; from wall to front of division, 17 ins. (m 0.43) ; from wall to front of tread, 16 ins. (m 0.41) ; from floor line to top of cistern, 7 ft 6 ins. (m 2.30).



SPECIFICATION.—No. P6593. Urinal Range, comprising backs with soles and accessible channel in one piece. Suspended Divided Columns with High Divisions, Loose Fluted Tread and Cistern Casing all in Best-quality Fireclay. Automatic "Drop by Drop" Syphon. Polished Solid-drawn Copper Supply Pipes with Gun-metal Fittings and Distributors. Outlet fitted with Gun-metal Dome-shaped Grid. Enamelled Cast-iron Brackets to support Cistern.

Prices, complete as specified—

						Medium Size.		Small Size.	
						Pure White Enamelled.	Buff Glazed.	Pure White Enamelled.	Buff Glazed.
Range of	2 Stalls,	..	..	..	..	£17 0 0	£15 0 0	£15 15 0	£13 12 0
"	3 "	..	..	..	..	25 15 0	22 0 0	23 0 0	19 15 0
"	4 "	..	..	..	..	34 0 0	28 15 0	30 0 0	26 0 0
"	5 "	..	..	..	..	42 0 0	36 0 0	36 10 0	32 2 6
"	6 "	..	..	..	..	50 5 0	42 15 0	44 12 0	38 7 6

NOTE.—The above Urinals can also be supplied 3 ft. 10 ins. (m 1.18) from floor to top of stalls. 4 ft. 10 ins. (m 1.48) to top dimensions at an extra cost of 15/- per stall.

The above Ranges will be supplied with ends to stand exposed and right-hand outlet unless ordered otherwise.

# **Japanned and Metallic Enamelled Cast-Iron Baths**


WITH FITTINGS.

No. P 6541.     **THE "MODEL"**



Bath Suite, comprising Bath 5 ft. 6 ins. long, with 3½-inch broad flat Roll Edge, Japanned Imitation Mahogany, the outside of Bath being Green Marbled; Hot and Cold Globe Cocks, Trapped Waste and Chain, and Overflow; Japanned Sea Green inside, .. .. . Price per set, £4 0 0  
 Nickel-plated Fittings, .. .. . 4/6 extra.

No. P 3165.     **THE "ROLLARGIO"**



Superior Bath Suite, comprising Bath 5 ft. 6 ins. long, with 3½-inch Round Roll; Green Marbled outside and on roll; Hot and Cold **Gun-metal** Globe Cocks, Trapped Waste and Chain, and Overflow; Japanned Sienna, .. .. . Price per set, £4 8 0  
 Second Finish Metallic Enamelled Sienna or Sea Green, .. .. . 5 15 0  
 Nickel-plated Fittings, .. .. . 4/6 extra.

No. P 6542.     **THE "SPA"**




Combination Bath, 5 ft. 6 ins. long; Parallel Pattern. Recessed End; 3-inch Roll, with Hot and Cold Pillar Taps, Lift-up Waste and Soap Tray.  
 Second Finish, Metallic Enamelled Sea Green, .. .. . Price per set, £7 10 0  
 White Porcelain Enamelled, .. .. . 9 0 0  
 Nickel-plated Fittings, .. .. . 7/6 extra.

# **Japanned and Metallic Enamelled Cast-Iron Baths**


No. P 982. **Flat Edge Bath** for Casing in.

		SIZE INSIDE.	
		5 ft. 0 ins.	5 ft. 6 ins.
Japanned Sienna or Sea Green, .. .. .	42 -	46	6
Second Finish, Metallic Enamelled Sienna or Sea Green, .. .. .	62/-	66	6




No. P 993. **Roman Bath**, with 1 3/4-in. Roll.

		SIZE INSIDE.	
		5 ft. 0 ins.	5 ft. 6 ins.
Japanned Sienna or Sea Green, .. .. .	50 -	52	-
Second Finish, Metallic Enamelled Sienna or Sea Green, .. .. .	75 -	78	-



No. P 5457. **Roman Bath**, with 3-in. Roll.

		SIZE INSIDE.	
		5 ft. 0 ins.	5 ft. 6 ins.
Japanned Sienna or Sea Green, .. .. .	60 -	63	/-
Second Finish, Metallic Enamelled Sienna or Sea Green, .. .. .	85/-	88	-



No. P 4565. **Superior Roll Edge Bath**  
3 1/4-in. bold Roll.

		SIZE INSIDE.	
		5 ft. 0 ins.	5 ft. 6 ins.
Japanned Sienna or Sea Green, .. .. .	66 -	69	-
Second Finish, Metallic Enamelled Sienna or Sea Green, .. .. .	90/-	95	/-





# Porcelain Enamelled Bath

MEDIUM QUALITY.

## THE "VILLA"



No. P 5696. Cast-iron Bath, 5 feet 6 inches long inside, White Porcelain Enamelled inside and over the Roll, Plain Painted outside, with  $\frac{3}{4}$ -inch Hot and Cold Brass Screw-down Globe Bath Cocks,  $1\frac{1}{4}$ -inch Bent Waste and Chain, and  $1\frac{1}{4}$ -inch Overflow.

Prices, complete,  $1\frac{3}{4}$ -inch Roll, **125/-**;  $2\frac{1}{2}$ -inch Roll, **132/-**; 3-inch Roll, **140/-** each.

Nickel-plated Fittings, **4/6** extra. Corner Soap Trays fitted, **8/6** extra.

If Trapped Waste in lieu of Bent, **1/6** extra.

5 feet (inside measure) Baths can be supplied at **2/6** each less.

# Porcelain Enamelled Bath

MEDIUM QUALITY.

## THE "LANCASTER"



No. P 5869. Cast-iron Parallel Bath, 5 feet 6 inches inside measure, with 3-inch Roll Edge, White Porcelain Enamelled inside and over the Roll, Plain Painted outside, with large Enamelled Soap Tray, Dolphin pattern Ornamental Feet,  $\frac{3}{4}$ -inch Gun-metal Hot and Cold Pillar Taps,  $1\frac{1}{4}$ -inch Trapped Waste and Chain, and  $1\frac{1}{4}$ -inch Overflow.


Price, complete, . . . . . **162/6** each.

Nickel-plated Fittings, . . . . . **6/-** extra.

# Porcelain Enamelled Bath

MEDIUM QUALITY.

## THE "BUCKINGHAM"



No. P 5699. Cast-iron Bath, 5 feet 6 inches long (inside measure), with 3 $\frac{1}{4}$ -inch Bold Flat Roll. White Porcelain Enamelled inside and over the Roll, Plain Painted outside, with  $\frac{3}{4}$ -inch Brass Hot and Cold Pillar Taps, 1 $\frac{1}{4}$ -inch Bent Waste and Chain, 1 $\frac{1}{4}$ -inch Overflow, and Porcelain Enamelled Soap Tray.


Price, complete, .. **£7 15 0** each.

Nickel-plated Fittings, **5**/- extra. It Trapped Waste in lieu of Bent, **1/6** extra.

# Porcelain Enamelled Bath

MEDIUM QUALITY.

THE "COUNTY"



No. P6132. Parallel Combination Bath, 5 feet 6 inches inside measure, 3-inch Roll, with  $\frac{3}{4}$ -inch Hot and Cold Pillar Taps. Porcelain Enamelled Waste Plunger, Glass Enamelled Trap, with  $1\frac{1}{2}$ -inch Outlet.


Price, complete, . . . **£8 10 0** each.

Nickel-plated Fittings, . . . **7 6** extra.

This Bath can be fitted with Brass Rod Waste and separate Overflow if desired.

# Best Quality Porcelain Enamelled Baths and Fittings

## THE "HARROGATE"



No. P 6335. 2 $\frac{3}{4}$ -inch Roll Edge Bath (5 ft. 6 ins. long inside), White Porcelain Enamelled, with Nickel-plated Quick-turn Lever Handle, Octagon pattern Bath Cocks, Trapped Waste and Chain, and Overflow, complete; Plain Painted outside.

Price, .. .. . £7 10 0 per set.

## THE "TUNBRIDGE WELLS"



No. P 6336. New pattern Parallel Combination Bath (5 ft. 6 ins. long inside, 6 ft. 3 $\frac{1}{2}$  ins. over all); 4-inch Roll,<sup>1</sup> Open-end Waste, Glass-lined Trap above Floor line, Nickel-plated Fittings, with Lift-up Waste Tube forming Overflow.

Price, .. .. . £13 10 0 per set.


This Bath can also be supplied with 3-inch Roll.

Price, .. .. . £12 5 0 per set.

# Porcelain Enamelled Cast-Iron Parallel Baths

ROOMY SHAPE. BROAD BOTTOM.

No. P 6332. **THE "MARQUIS"**



END VIEW, showing Plug and Chain.


No. P 6332. Best White Porcelain Enamelled inside Bath, 3-inch Roll, 5 ft. 6 ins. long inside, 1 ft. 10 ins. wide inside. Plain Painted outside, with  $\frac{3}{4}$ -inch Nickel-plated Hot and Cold Taps,  $1\frac{1}{2}$ -inch Trapped Waste, and  $1\frac{1}{4}$ -inch Overflow.

Price, .. .. . **£8 15 0** each.

Can also be supplied, 5 ft. long inside at a reduction of **6/6** per Bath.

No. P 6333. As above, but Recessed End, 5 ft. 6 ins. inside. .. .. . Price, **£9 0 0** each.

No. P 6334. **THE "VISCOUNT"**



END VIEW, showing Rod Waste.

No. P 6334. Best White Porcelain Enamelled Recessed-end Combination Bath, 3-inch Roll, 5 ft. 6 ins. long inside. Plain Painted outside, with  $\frac{3}{4}$ -inch Nickel-plated Hot and Cold Taps,  $1\frac{1}{2}$ -inch Nickel-plated Tubular Waste and Overflow, and 2-inch Iron Trap.

Price, .. .. . **£10 10 0** each.


Can also be supplied 5 ft. long inside at a reduction of **6/6** per Bath.

This Bath also supplied with Rod Waste and Top Overflow, if required, at **13/6** per Bath less.

**Special Rates quoted for these Baths in quantities for Export.**

# Superior Porcelain Enamelled Combination Bath and Fittings

## THE "KENSINGTON"




No. P6339. Parallel Bath, 5 feet 6 inches long inside, 3 $\frac{1}{4}$ -inch Roll Edge. White Porcelain Enamelled inside and outside. 1-inch heavy pattern Nickel-plated Quarter Turn Taps, with China Handle, removable exposed Cast-iron Enamelled Bracket Plunger, 2-inch Glass Enamelled Trap above floor.

Price, . . . **£15 0 0** per set.

This Bath can also be supplied with Safety Roll, as section shown, at **37/6** extra.

# Superior Porcelain Enamelled Baths and Fittings


## THE "CHELTENHAM" BATH AND FITTINGS



No. P6337. Parallel Cast-iron Broad Bottomed Bath, 5 feet 4 inches long, 2 feet 0 inches wide and 1 foot 7 inches deep inside, with 4-inch Curled Rim. Porcelain Enamelled inside, Plain Painted outside; 2-inch Tubular Waste and Overflow, 2-inch Trap and Union, Combination 1-inch Hot and Cold Taps, Steamless and Noiseless Supply, and 4-inch Hand Spray with Rubber Tube, Nickel-plated Fittings.

Price, £17 5 0 per set.

## THE "NEW COTTAGE" BRAMSTONE COMBINATION BATH AND LAVATORY



No. P6128.

Comprising 5 feet 6 inches Combination Bramstone Bath and Lavatory, 2-inch Roll to Bath; Whiteware Lavatory Basin, 22 x 18 ins.; Cast-iron Frieze; Y.M. 4-inch Hot and Cold Taps, with Mixing and Dividing Arrangement for Bath and Lavatory; 1 1/4-inch Rubber Plug and Chain; Straight Union to Lavatory; 1 1/4-inch Overflow and 1 1/4-inch Bath Plug and Bent Union.


Price, £11 5 0 per set.



# Porcelain Enamelled Bath

SUPERIOR FINISH.

## THE „ELYSIAN”




No. P 6127. THE “ELYSIAN” BATH, 5 feet 3½ inches long inside, with 3½-inch Bold Roll. Best White Porcelain Enamelled inside and over the Roll. Plain Painted outside, with Nickel-plated Taps to Bath, Supply Pipes to, and including Nickel-plated Shower, with Ring and Best Waterproof Curtain.

Price, complete, . . £19 10 0 per set.

# Superior Porcelain Enamelled Combination Bath and Fittings

## THE "RITZ"



No. P 6338. Parallel Cast-iron Broad Bottomed Bath, 5 feet 4 inches long, 2 feet 0 inches wide, and 1 foot 7 inches deep inside, with 4-inch Curled Rim. Porcelain Enamelled inside, Plain Painted outside; 2-inch Brass Tubular Waste (and Overflow, 2-inch Trap and Union, Combination 1-inch Hot and Cold Taps, Steamless and Noiseless Supply, and Brass Shower with a pair of Best Waterproof Curtains. Nickel-plated Fittings.

Price, .. £21 15 0 per set.

# Superior Quality Porcelain Enamelled Combination Shower and Slipper Bath

## THE "CHATSWORTH"



No. P 6099. Porcelain Enamelled Parallel Cast-iron Slipper Bath, 5 feet 6 inches inside, 4-inch Roll, recessed end. 1½-inch Tubular Waste and Out-go Trap above floor; Strong Zinc Enclosure; 2/2 Class Japan Enamelled in and out; ¾-inch Hot and Cold Taps and Mixing Arrangement; China Index Plate; Lettered Spray, Shower and Bath, with Brass Connecting Pipes therefrom, to and including 7-inch Vented Shower Rose; Brass Needle Spray and Bath Connection. All Nickel Plated.


Price, . . . £30 0 0 per set.

Can also be supplied with a 3-inch Roll, at a reduction of 45/-

# Latest Design Spray Bath

SUPERIOR FINISH.

No. P 6537. THE "CECIL"



DIMENSIONS.—Outside sizes, 5 ft. 6 ins. long, 2 ft. 9 ins. wide, 2 ft. 1 in. deep ; Inside sizes, 5 ft. 10 ins. long, 2 ft. 1 in. wide, 1 ft. 8½ ins. deep.

Spray, Shower and Slipper Bath, comprising Porcelain Enamelled Extra Roomy Shape Reclining Bath, 2-inch Recessed Waste and Trap ; Plate Zinc Spray Enclosure, Japan Enamelled ; Brass Tubes, Copper Shower ; 1-inch Hot and Cold Taps, with mixing and dividing arrangement ; Brass Supply and Connecting Pipes as shown, all Nickel Plated.

Price,	..	..	..	..	..	..	..	..	..	..	..	£45	0	0	each.
--------	----	----	----	----	----	----	----	----	----	----	----	-----	---	---	-------

If with Uprising Douche or Spray.	..	..	..	..	..	..	..	..	..	..	..	2	0	0	extra.
-----------------------------------	----	----	----	----	----	----	----	----	----	----	----	---	---	---	--------


No. P 6538. Sponge Basket, Nickel Plated.	..	..	..	..	..	..	..	..	..	..	..	0	14	9	„
---	----	----	----	----	----	----	----	----	----	----	----	---	----	---	---

No. P 6539. Soap Dish, in China, Nickel Plated.	..	..	..	..	..	..	..	..	..	..	..	0	14	9	„
---	----	----	----	----	----	----	----	----	----	----	----	---	----	---	---


This Bath is also made left hand.

# New Pattern Spray and Shower Bath

EXCEPTIONAL VALUE.



Brass Needle Bath.



SCALE OF PLAN  $\frac{3}{4}$ " = 1 foot.

Bath Plan.  
Size, 2 x 2 feet centres.

DIMENSIONS.—Height to bottom of spray tube, 1 ft. 6 ins. ; height to top of spray tube, 4 ft. 10 ins. ;  
height to shower rose, 6 ft. 8 ins. ; copper shower rose, 6 ins. diameter.


No. P 6540. Needle Bath in Polished Brass, comprising five  $\frac{1}{2}$ -inch Horizontal Spray Tubes, four 1-inch Vertical Tubes, two  $1\frac{1}{4}$ -inch Front Pillars,  $\frac{3}{4}$ -inch Hot and Cold Valves, with Mixing and Dividing Arrangement for Spray and Shower, with Connecting Pipes thereto.

Price. . . . . £18 18 0 each.

Nickel Plating, 51/- extra.

# Towel Airers for Bathrooms, Lavatories, &c.


No. P 6797.



Two Single Rails and Double Top Rail.  
Width, 36 inches ; Height, 36 inches.

		Diameter of Tubes, .. $1\frac{1}{2}$ .. $1\frac{1}{2}$ ins.	
Polished Brass, .. .. .	Price, <b>136/-</b>	<b>165/-</b>	each.
Nickel Plated, .. .. .	„ <b>174/-</b>	<b>204/-</b>	„

No. P 6798.




Three Single Rails and Wall Flanges.  
Width, 36 inches ; Height, 36 inches.

		Diameter of Tubes, .. $1\frac{1}{2}$ .. $1\frac{1}{2}$ ins.	
Polished Brass, .. .. .	Price, <b>135/-</b>	<b>153/-</b>	each.
Nickel Plated, .. .. .	„ <b>153/-</b>	<b>180/-</b>	„

Projection, Wall to Centre, 5 inches.


No. P 6799.



Three Single Rails.  
Width, 36 inches ; Height, 36 inches.

		Diameter of Tubes, .. $1\frac{1}{2}$ .. $1\frac{1}{2}$ ins.	
Polished Brass, .. .. .	Price, <b>117/-</b>	<b>141/-</b>	each.
Nickel Plated, .. .. .	„ <b>141/-</b>	<b>168/-</b>	„

No. P 6800.



Three Single Rails, with Wall Flanges.  
Width, 36 inches ; Height, 27 inches.

		Diameter of Tubes, .. $1\frac{1}{2}$ .. $1\frac{1}{2}$ ins.	
Polished Brass, .. .. .	Price, <b>135/-</b>	<b>160/-</b>	each.
Nickel Plated, .. .. .	„ <b>150/-</b>	<b>180/-</b>	„


Projection, Wall to Centre, 5 inches.

Prices include Regulating Valve and Air Tap as shown, but which can be fitted in other positions to suit clients' requirements.  
Towel Airers made to other dimensions and designs than shown above, at correspondingly low prices.

# GEYSERS

## THE "EVER-READY" (Patent)


A high-class Geyser constructed with open water chambers of improved design. A splendid bath heater. It is made of strong hardened copper; the water chambers are coated with pure tin. The outside body is splendidly polished and lacquered. The "Ever-Ready" Geyser is made with a fixed burner, which allows the prices to be based at a low figure without reducing the quality of copper used in manufacture.




No.	Description	* Heats per minute. 1½ to 2 galls.	£	s	d
No. P5806A.	With Gas Tap only, ... ..	1½ to 2 galls.	£3	2	6
" P5806B.	" " " " " " " " " " " "	2 " 3 "	3	12	6
" P6566A.	" Interlocking Gas and Water Taps, ...	1½ " 2 "	3	13	0
" P6566B.	" " " " " " " " " " " "	2 " 3 "	4	3	0
" P6567A.	" Automatic Gas Controlling Valve, ...	1½ " 2 "	4	5	0
" P6567B.	" " " " " " " " " " " "	2 " 3 "	4	17	6

## THE "CHAMPION" (Patent)

The "Champion" Geyser is made entirely of stout copper, the inside parts are carefully coated with pure tin, the outside polished and lacquered, presenting a handsome appearance. It is complete with swing-out copper burner, ensuring safety in lighting, and the prices include gas tap and union ready for fixing. The water flows into the Geyser from a tap fixed at a convenient height over the machine, which will work equally well with or without water pressure. At slight extra cost it is supplied complete with patent improved interlocking gas and screw-down water taps, so arranged that the gas tap cannot be turned on before the water tap is opened. The addition of the patent "Rotary" Valve, which automatically turns down the gas when the water for any reason ceases to flow into the machine, is strongly recommended. The patent "Rotary" Valve is constructed throughout of metal and is practically indestructible.



No.	Description	* Heats per minute. 2 galls.	£	s	d
No. P1019I.	Not including cold water tap, ... ..	2 galls.	£4	4	0
" P1019O.	" " " " " " " " " " " "	3 "	5	10	0
" P1019U.	" " " " " " " " " " " "	4 "	7	2	6
" P1019X.	" " " " " " " " " " " "	8 "	18	10	0
" P1019I.	With Patent Interlocking Gas and Water Taps, ...	2 "	5	0	0
" P1019O.	" " " " " " " " " " " "	3 "	6	5	0
" P1019U.	" " " " " " " " " " " "	4 "	7	17	6
" P1019X.	" " " " " " " " " " " "	8 "	21	0	0
" P1019I.	With Patent Automatic "Rotary" Valve, ...	2 "	5	15	0
" P1019O.	" " " " " " " " " " " "	3 "	7	2	6
" P1019U.	" " " " " " " " " " " "	4 "	8	15	0
" P1019X.	" " " " " " " " " " " "	8 "	22	10	0



## THE "TRIUMPH" (Patent)

The "Triumph" Geyser is manufactured to meet the demand for a cheap geyser where first cost has to be carefully considered. It is made of hardened copper throughout (with the exception of the burner). The "Triumph" is well finished, and although low in price it produces good heating results.


No.	Description	* Heats per minute. 2 galls.	£	s	d
No. P6568A.	With Gas Tap only, ... ..	2 galls.	£2	12	6
" P6568B.	" " " " " " " " " " " "	4 "	4	12	6
" P6569A.	With Interlocking Gas and Water Taps, ...	2 "	3	2	0
" P6569B.	" " " " " " " " " " " "	4 "	5	2	6

\* The temperature of the water flowing at the above rates per minute is raised 40 degrees Fahrenheit above that of the cold supply.

The temperature may be increased or diminished according to the size of the stream.

# GEYSERS

## THE "LIGHTNING" (Patent Registered)



The "Lightning" Geyser is made of stout copper of best quality which is specially hardened, the outside being highly polished and lacquered. In the manufacture of the "Lightning" Geyser a large quantity of copper is used, owing to the special construction of the water chambers. The very large heating surface thus procured, the life of this Geyser is far longer than that of the less expensive patterns. The water chambers are carefully coated with pure tin and sealed, so that the fumes from the burnt gas cannot come in contact with the water.

The "Lightning" Geyser, as well as producing hot water, will also boil water which may be used for drinking or other purposes, as well as for the bath. The automatic valve prevents the gas being turned full on, unless the water is passing into the Geyser. The copper burner swings out for lighting.


Always sent right hand (as illustrated) unless otherwise ordered.

	Heats per min.	Boils per min.		Heats per min.	Boils per min.	
No. P 1020B.	1½ galls.	3 pints.	£5 5 0	No. P 1020D.	3 galls.	3 quarts. £9 9 0
No. P 1020C.	2 ..	2 quarts.	7 7 0	No. P 1020E.	4 ..	4 .. 11 11 0

## THE "ELITE" (Patent)

The inner chambers of the "Elite" Geyser are strongly made and will withstand any pressure up to 100 lbs. to the square inch. The force of the hot or cold shower, of course, depends upon the pressure of the cold supply.

The "Elite" Geyser is fitted with automatic valve which shuts the gas down to a pilot as soon as the water is turned off, and the price includes patented safety gas tap with pilot for lighting, and high pressure water tap with unions all ready for fixing. The water chambers of the "Elite" Geyser are made of copper throughout; the outside of the Geyser of copper bright polished and lacquered; the valve, gas tap and fittings are of brass, heavily made and bright polished. The "Elite" Geyser will be found a rapid and economical bath heater, and will, in addition, provide hot or cold shower, the temperature of which can be regulated at will. The "Elite" Geyser is not, however, constructed to supply actually boiling water or water for drinking purposes.



	Heats per min.	
No. P 6562A.	2½ galls.	£6 6 0
No. P 6562B.	4 ..	11 11 0


## THE "VICTOR" (Patent Registered)

This Geyser is constructed (with the exception of the burner) of stout hardened copper throughout; the water chambers are sealed from contact with the gas fumes and carefully coated with pure tin, therefore the water is not contaminated in any way in passing through the Geyser, but issues from the spout as fresh and pure as it enters. It will supply actually boiling water, fit for drinking or cooking purposes, as well as simply hot water for bath use.

The "Victor" is strongly recommended to purchasers desiring a really good Geyser at a moderate price, especially on occasions where first cost has to be considered. It is supplied with interlocking taps (as illustration), gas taps only, or automatic gas controlling valve.

		Heats per min.	Boils per min.	
No. P 6563A.	With Gas Tap only,	2½ galls.	2 quarts.	£2 17 6
No. P 6563B.	" "	4 ..	4 ..	6 7 6
No. P 6564A.	With Interlocking Gas and Water Taps,	2½ ..	2 ..	3 7 0
No. P 6564B.	" "	4 ..	4 ..	6 17 6
No. P 6565A.	With Automatic Valve,	2½ ..	2 ..	4 7 6
No. P 6565B.	" "	4 ..	4 ..	7 19 6

\* The temperature of the water flowing at the above rates per minute is raised 40 degrees Fahrenheit above that of the cold supply. The temperature may be increased or diminished according to the size of the stream.






# GEYSERS

"SEALED SYSTEM," Patented and Registered.

Hot Water Under Pressure.



## No. P 6543. THE "SUPREME" GEYSER

The "Supreme" Geyser has been specially designed to meet the demand for a durable and well-made water-heater, at a low price. It is automatic in action, the burners lighting from a single pilot light when water is being drawn from any tap to which it is connected. The "Supreme" Geyser will supply hot water to bath, lavatory and kitchen sinks or other taps as may be required. Where a kitchen boiler has been previously used, the "Supreme" may be easily connected to the existing hot water supply pipes at small cost. The hot water is delivered under the same pressure as that of the cold water service. The "Supreme" may therefore be fixed in any position where the flow pipe is most easily connected to the draw-off taps.


Tested to stand a pressure of 150 lbs. The outer case of copper panelled, polished and lacquered, while all working parts are made of hardened copper, the "Supreme" may be fitted in any house with the knowledge that a thoroughly satisfactory water heating system has been installed. Hot water is produced at the rate of 2½ to 3 gallons per minute. Made in one size only.

Price, .. .. . £9 9 0

## No. P 6544. THE "BRILLIANT" LAVATORY GEYSER (Patent)

The "Brilliant" is specially designed for supplying hot water quickly to lavatory basins, &c. It produces about one gallon of hot water per minute. Made of stout hardened copper, complete with fittings and wall brackets as illustrated; the outside polished and lacquered.

Without Shampoo, £1 11 6; with Shampoo, Fixed or Flexible, £2 2 0



## No. P 6545. THE "RADION" CIRCULATOR (Patent Registered)

For Heating Water for Domestic Purposes, &c.



The "Radion" Circulator can be attached to the hot water pipes at present fixed in any house or flat. It heats the whole of the hot water system, so that by its use hot water may be obtained at any hot water tap in any part of the house or flat. Early in the morning or late at night a match put to the "Radion" Circulator ensures a prompt and plentiful supply of hot water. The installation (which means just connecting up to the present hot water pipes) therefore causes little trouble or disturbance and the expense incurred is usually small.

The "Radion" Circulator is placed in a convenient position (usually fixed on a bracket against the kitchen wall, as shown on the illustration) and connected to the present flow and return pipes.

By this small expenditure one obtains the great convenience - even luxury of an ample supply of hot water at any part of the house connected with the hot water system at any time. The cost of the gas consumed is more than saved in the reduction of the coal bill. The time and trouble in setting and lighting the kitchen fire and the inconvenience (and expense) of keeping the kitchen range alight throughout the long summer days are saved.

In fact, in the warm weather, with the "Radion" Circulator to heat the water and a gas cooker, the kitchen range never need be lit.

The "Ewart" Heat Regulating Valve **automatically** controls the gas supply. The heat of the water by means of the valve raising or lowering the gas flame, thus the hot water is always kept at the pre-arranged desired temperature, and only the minimum amount of gas necessary to produce this effect is consumed.


No. P 6545 A A.	* Heats 45 gallons per hour,	.. ..	£3 3 0
No. P 6545 B B.	" 100 " " "	.. ..	7 7 0
No. P 6545 A.	With Automatic Heat Valve,	.. ..	4 15 0
No. P 6545 B.	" " " "	.. ..	9 9 0

\* The temperature is raised 40 degrees Fahrenheit.



# Geysers and Accessories

## The "Victor" Oil Geyser




The "Victor" Oil Geyser is made throughout of stout hardened copper, the inside parts are coated with pure tin, the outside bright polished and lacquered. This Geyser is constructed on the "Sealed" system, so that the fumes from the burnt oil do not come in contact with the water. The water issues from the spout as fresh and pure as when it entered the Geyser, therefore it may safely be used for drinking or other purpose, as well as for the bath.

The illustration shows the "Victor" Oil Geyser complete, with wickless Lamp Stove (which burns ordinary paraffin), and also the cast-iron stand.

		Heats per minute.	Boils per minute.	
No. P 6547A.	.. ..	2 gallons.	2 quarts.	<b>£4 12 6</b>
No. P 6547B.	.. ..	4 "	1 gallon.	<b>8 15 0</b>

## Geyser Ventilating Appliances



No. P 6548. **Cap**

2½, 3, 3½, 4, 4½, 5 inches.  
Price, **3/6** each.

No. P 6549. **Baffler**

To stop down draught.

Galvanized Iron, Stove Enamelled.  
2½, 3, 3½, 4, 4½, 5 inches.  
Price, **9/6** each.



No. P 6560. **Corrugated Round Elbow**

Diameter, .. .. .	2½	3	3½	4	4½	5 ins.
Made of Black Iron, Galvanized and Stove Enamelled,	<b>1/4</b>	<b>1/8</b>	<b>1/8</b>	<b>1/8</b>	<b>1/9</b>	<b>2/-</b> each.
„ Black Iron, Galvanized, .. .. .	<b>1/-</b>	<b>1/3</b>	<b>1/3</b>	<b>1/3</b>	<b>1/6</b>	<b>1/6</b> „
„ Copper, Polished and Lacquered, .. .. .	<b>3/-</b>	<b>4/-</b>	<b>4/-</b>	<b>4/6</b>	<b>5/6</b>	<b>6/6</b> „


No. P 6561. **Ventilating Pipe**

In 2 feet lengths.

Diameter, .. .. .	2½	3	3½	4	4½	5 ins.
Made of Galvanized Iron, Enamelled and Stoved,	<b>1/-</b>	<b>1/2</b>	<b>1/2</b>	<b>1/3</b>	<b>1/4</b>	<b>1/5</b> per length.
„ Galvanized Iron, not enamelled, .. .. .	<b>8d.</b>	<b>9d.</b>	<b>9d.</b>	<b>10d.</b>	<b>11d.</b>	<b>1/-</b> „
„ Copper, Polished and Lacquered, .. .. .	<b>3/9</b>	<b>4/3</b>	<b>4/3</b>	<b>4/6</b>	<b>4/9</b>	<b>5/-</b> „


# Bathroom Accessories

No. P 6870.  
**SPONGE, SOAP, AND BRUSH HOLDER**




Price, .. .. . 5 3 each.

No. P 6871.  
**BATH SPONGE AND SOAP HOLDER**




Japanned White, Blue, or  
Green, .. .. . Price, 3/9 each.  
Brass, Nickel Plated, .. .. . 8/3 ..

No. P 6872.  
**BATH SOAP HOLDER**




Japanned, .. .. . Price, 2/- each.  
Nickel Plated, .. .. . 4/6 ..

No. P 6873. **BATH TRAY**




Japanned, .. .. . Price, 5 3 each.  
Nickel Plated, .. .. . 12/9 ..

No. P 6874. **BATH SEAT**




Plain Oak Seat, .. .. . Price, 5/3 each.  
Polished Oak Seat, .. .. . 6/9 ..  
Patent Cork Seat, .. .. . 8/3 ..

No. P 6877. **TOILET PAPER HOLDER**




Good Quality, Nickel Plated on Brass, .. .. . Price, 7/3 each.

No. P 6878. **TOILET PAPER HOLDER**  
SUPERIOR QUALITY.




Nickel Plated on Brass, .. .. . Price, 19/6 each.

No. P 6875. **THE "DESIRABLE" BATH SEAT**  
Oak, with Nickel-plated Brass Supports.



Price, .. .. . 14/3 each.




No. P 6876.  
**BRASS  
NICKEL-PLATED  
SPONGE HOLDERS**  
10½ ins. long.  
5½ ins. wide. 3½ ins. deep.  
Price, 11/3 each.

# Bathroom Fittings

Covered with X-L-ONITE, the new Hygienic Covering for Woodwork, and the nearest approach to Porcelain.

## No. P 6819. X-L-ONITE SPONGE RACK

With Brass Nickel-plated Net and Two Lugs for Hanging on Wall.



Price, .. .. . 11/3 each.

## No. P 6820. X-L-ONITE SPONGE RACK



Price, .. .. . 18/- each.

## No. P 6822. X-L-ONITE TOWEL RAIL AND BRACKETS




24 inches long,	..	..	..	..	Price, 13/6 each.
30   "   "	..	..	..	..	"   16/6   "
36   "   "	..	..	..	..	"   21/-   "

## No. P 6818. X-L-ONITE BATH SEAT



Price, .. .. . 33/- each.


## No. P 6821. X-L-ONITE SANITARY PAPER RACK



Price, .. .. . 10/6 each.

## No. P 6823. X-L-ONITE SOAP RACK

With Two Brass Nickel-plated Lugs to Hang on Wall.




Price, .. .. . 14/3 each.

HIGH  
CLASS  
MANUFACTURE.


## High-Class Bathroom Accessories

No. P 6855. **TOWEL RAIL**



**Nickel plated Brass Rail and Brackets.**


					18	24	30	36 ins. long
1	inch diameter,	..	..	..	Prices, 6/9	7/-	8/-	8/9 each.
2	"	"	..	..	" 5/9	6/9	7/-	7/6 "
3	"	"	..	..	" 5/-	5/3	5/9	6/- "
4	"	"	..	..	" 4/6	4/9	5/3	5/9 "

No. P 6856. [ **DOUBLE TOWEL RAIL** ]

### Nickel-plated Brass Brackets and Rails

				24	30	36 ins. long.
1 inch diameter,	..	..	..	Prices, <b>13/6</b>	<b>15/-</b>	<b>16/6</b> each.
2 "	"	"	"	" <b>12/-</b>	<b>12/9</b>	<b>14/3</b> "
3 "	"	"	"	" <b>10/-</b>	<b>11/3</b>	<b>12/-</b> "

No. P 6857. **ADJUSTABLE TOWEL RACK**



Bars, 18  $\frac{1}{2}$  in. diameter.

Nickel-plated Brass,	..	..	..	..	..	..	Price, 24/- each.
Nickel Silver,	..	..	..	..	..	..	36/- ..

No. P 6859. **COMB AND BRUSH TRAY**





Plate-glass Tray, 12 x 5 x 1 in., with Nickel-plated Brass Brackets, .. .. . Price, **17/3** each.


No. P 6858. **OPAL GLASS TOWEL RAIL**



**1-inch Opal Glass Rail and Plated Brackets.**

					24	30	36 ins.
Prices, ..	..	..	..	..	<b>14/3</b>	<b>16/6</b>	<b>18/- each.</b>

### GLASS SHELF AND TOWEL RAIL




No. P 6800. Glass Shelf, 36 x 5 ins.; Rail, 30 x 1 in. diameter.  
Nickel-plated Brass Brackets and Rail, Prices, **24/9** without Rail, **20/9**  
Nickel Silver Brackets and Rail, " **33/-** " **27/-**

No. P 6861. Glass Shelf, 30 x 5 ins.; Rail, 24 x  $\frac{3}{4}$  in. diameter.  
 Nickel-plated Brass Brackets and Rail, Prices, 22/6 without Rail, 19/6  
 Nickel Silver Brackets and Rail, " 28/6 " 25/6  
 Extra for Wood Wall Plates, . . 1/3 each.

# Toilet Mirrors and Frames

No. P 6766.




Composition Frame, Enamelled White or Mahogany.  
 $\frac{3}{4}$ -inch Bevelled Plate.

28 x 20 inches,	.. .. .	Price, 27/- each.
26 x 20 "	.. .. .	" 22/6 "

Also made with a Slighter Frame.

19 x 12 inches,	.. .. .	Price, 16 6 each.
24 x 18 "	.. .. .	" 21/- "


No. P 6768.



Iron Frame, Enamelled Best Finish White or Mahogany.  
 $\frac{3}{4}$ -inch Bevelled Plate.

31 x 22 inches,	.. .. .	Price, 45/- each.
28 x 22 "	.. .. .	" 40/- "

No. P 6767.



Composition Frame, Enamelled White or Mahogany.  
 $\frac{3}{4}$ -inch Bevelled Plate.

28 x 20 inches,	.. .. .	Price, 27/- each.
26 x 20 "	.. .. .	" 22/6 "

Can also be made as a Full-length Mirror.

54 x 16 inches,	.. .. .	Price, 60/- each.
-----------------	---------	-------------------

No. P 6769.




Iron Frame, Enamelled Best Finish, White or Mahogany.  
 $\frac{3}{4}$ -inch Bevelled Plate.

31 x 22 inches,	.. .. .	Price, 46/6 each.
28 x 22 "	.. .. .	" 42/- "

# New and Improved Bath and Lavatory Showers


No. P 6801.



Brass Shower, with  $\frac{1}{2}$ -in. Hot and Cold Taps, .. .. . Price, **63/-** each.  
 Nickel Plated, .. .. . **11/3** extra.  
 If with Ring and Waterproof Curtain, .. **127/6** each.  
 Nickel Plated, .. .. . **18/6** extra.


Centre of Taps to underside of Shower, 3 ft. 6 ins.; Arm, 1 ft. 6 ins. from Wall to centre of Shower; Shower Rose, 8 ins. diameter.

No. P 6806.



Hot and Cold Shampoo Hand Spray, with Rubber Tube.  
 Brass, .. .. . Price, **46/6** each.  
 Nickel Plated, .. .. . **8/3** extra


No. P 6802.



Combination Hot and Cold Brass Taps, with 5 feet of Rubber Tube and Hand Rose.  
 The Taps to this Shower may be turned to a horizontal position without extra cost.

	$\frac{1}{2}$	$\frac{3}{4}$ in.
Taps apart, Centres, ..	6 $\frac{1}{2}$	8 ins.
Diameter of Rose, ..	3	4 "
Price, .. ..	<b>52/6</b>	<b>62/6</b> each.
Nickel Plated, .. ..	<b>10/-</b>	<b>12/6</b> extra.

No. P 6805.



Combined Lavatory Taps, with Swivel Shower in Brass,  $\frac{1}{2}$ -in. Taps, 6 $\frac{1}{2}$ -in. Centres.

Price, .. .. **42/-** each.  
 Nickel Plated, .. **10/6** extra.


No. P 6803.



Combined Lavatory Taps, with Swivel Shower and Eye Spray in Brass,  $\frac{1}{2}$ -in. Taps, 6 $\frac{1}{2}$ -in. Centres.

Price, .. .. **72/-** each.  
 Nickel Plated, .. **12/6** extra.

No. P 6804.



These Shower Roses are made in copper on a new plan. They are strong and of good appearance.

The Inlets to these Showers can also be made horizontal to come through wall at same prices.



Brass Bracket Shower,  $\frac{1}{2}$ -in. Union.

Rose, ..	6	8 ins. diam.
Prices, ..	<b>27/-</b>	<b>30/-</b> each.
Nickel Plated, ..	<b>6/-</b>	<b>7/6</b> extra.

18-in. projection from wall to centre of shower.

# Portable Tip-Up Bath

FOR COTTAGE PROPERTY.



This Bath has been specially designed for modern small house property, flats, workmen's and model dwellings, and all situations where space is limited. The material and workmanship are of the highest standard, and the design is neat. A special feature of the Bath is the round shape, base, sides and rolled edge all being made of one piece. The advantages of this are that less water is required, as there are no useless corners to be filled, whilst the absence of longitudinal seams renders the Bath comfortable to the user and easy to clean. A further advantage due to the rounded form is the prevention of splashing over; there is consequently no need to make the Bath of the same height as the usual old-fashioned Baths with straight sides, and the weight and floor space required for it when tipped up are therefore reduced to the minimum. A Waste Valve of ample size is provided to rapidly drain off the water. Three feet of Flexible Armoured Tubing is supplied with each Tip-up Bath to connect to the nearest Waste Pipe.


The illustration clearly shows the simple and substantial construction of this Bath. For fixing, all that is required is four coach screws to fasten down the floor plate.

MADE OF IRON, GALVANIZED AFTER MAKE.

No. P 6532.	Length, 5 ft. 3 ins.;	width, 2 ft. 2 ins.;	depth, 1 ft. 3 ins.;	..	..	..	..	..	Price, £3 4 6
„ P 6533.	„ 5 „ 7 „	„ 2 „ 2 „	„ 1 „ 3 „	..	..	..	..	..	„ 3 9 0

## Portable Bath

This Bath is of the same construction and finish as the Tip-up Bath but without the tip-up arrangement. When not in use it can be stood on end in any convenient corner, without taking up much room; is therefore especially valuable in houses or flats without bath-rooms. If desired, these Baths can also be supplied with iron or rubber-tyred castors.



No. P 6534.	Extreme length, 5 ft. 3 ins.;	width, 2 ft. 2 ins.;	depth, 1 ft. 3 ins.;	weight about 31 lbs.,	..	Price, 30/- each.
„ P 6535.	„ 5 „ 7 „	„ 2 „ 2 „	„ 1 „ 3 „	„ 32 „	..	„ 36/- „
„ P 6536.	„ 5 „ 10 „	„ 2 „ 4 „	„ 1 „ 5 „	„ 37 1/2 „	..	„ 39/- „



# Porceliron Sanitary Ware

The Porceliron Lavatories, Sinks, &c., illustrated on this and the following pages are constructed of refined iron, well finished and finely enamelled.


NOT AFFECTED BY CLIMATIC CHANGES.

ABSOLUTE PURITY OF THE ENAMEL IS GUARANTEED.

Its superiority, strength, and durability warrants the slight initial extra outlay in cost, as compared with the ordinary form of enamelled goods.



A list of **Porceliron Lavatory Ranges** suitable for Factories, Sports Clubs, etc., sent upon application.




No. P 2656.

## DEEP PATTERN PLUG BASIN

To Fit Holes in Slate, ..	8½	10	10½	11	11½	12½	12½	13	13½	14	14½	15	16	16½	17½	20 ins.
Outside Diameter, ..	10	11	11½	12½	13	13½	14	14½	15	15½	16	16½	17½	18½	19½	22 "
With Plug Hole only, ..	4/3	4/6	5/-	5/6	6/-	6/9	7/6	8/3	9/-	9/9	10/6	11/3	12/9	15/-	18/-	22/6 each.
With Plug and Overflow																
Holes, ..	5/-	5/3	5/9	6/3	6/9	7/6	8/3	9/-	9/9	10/6	11/3	12/-	14/3	16/6	19/6	24/- "

No. P 6845.

## ANGLE BACK LAVATORY




Curved front, with roll rim and skirting.

Width, 22½ ins.; projection, 21 ins.; bowl, 15 × 12½ ins.

With Ordinary Overflow, ..	..	..	..	..	Price, 36/9 each.
With Self-contained Overflow, ..	..	..	..	..	39/9 "
Without Overflow, ..	..	..	..	..	35/3 "
If without Skirting, ..	..	..	..	..	3/- less.
If with Painted Cast-iron Brackets as illustrated, ..	..	..	..	..	5/3 extra.
If with Hot and Cold Pillar Taps and Plug, ..	..	..	..	..	12/- "

No. P 4650.

## OBLONG LAVATORY




Square back with ogee rim.

Size, 27 19 ins.; bowl, 19 × 13 ins.

With Ordinary Overflow, ..	..	..	..	..	Price, 40/6 each.
With Self-contained Overflow, ..	..	..	..	..	43/6 "
Without Overflow, ..	..	..	..	..	39/- "
If without Skirting, ..	..	..	..	..	4/6 less.
If with Painted Cast-iron Plain Brackets, ..	..	..	..	..	5/3 extra.

# Porceliron Sanitary Ware


No. P 2660. **LAVATORY BASIN**



Flat back and curved front, with roll rim.  
Width, 22 $\frac{1}{2}$  ins.; projection, 17 ins.; bowl, 17 x 14 ins.

With Ordinary Overflow, .. .. .	Price, <b>25/6</b> each.
With Self-contained Overflow, .. .. .	<b>28 6</b> ..
Without Overflow, .. .. .	<b>24/-</b> ..

No. P 2652. **JAW BOX**



Improved pattern with round corners and secret (self-contained) overflow  
draining into outlet, fitted with brass barred seating and brass plug,  
with chain and stay.

15 ins. x 11 ins. 7 ins. deep, .. .. .	Price, <b>22/6</b> each.
18 " x 12 " x 7 " " .. .. .	<b>26 3</b> ..
21 " x 13 " x 7 " " .. .. .	<b>30/-</b> ..
24 " x 14 " x 7 " " .. .. .	<b>33/9</b> ..
27 " x 15 " x 7 " " .. .. .	<b>37/6</b> ..
30 " x 16 " x 7 " " .. .. .	<b>45</b> ..
36 " x 16 " x 7 " " .. .. .	<b>60/-</b> ..
36 " x 18 " x 7 " " .. .. .	<b>67 6</b> ..

Ebonite Plugs, .. **1/3** extra.

No. P 6843. **ANGLE LAVATORY**



Oval bowl, ogee rim, and skirting.	
Width, 9 $\frac{1}{2}$ ins.; projection, 21 $\frac{1}{2}$ ins.; bowl, 16 x 12 ins.	
With Ordinary Overflow, .. .. .	Price, <b>36/9</b> each.
With Self-contained Overflow, .. .. .	<b>39/9</b> ..
Without Overflow, .. .. .	<b>35/3</b> ..
It with "Falcon" Pattern Brackets as illustrated, .. .. .	<b>5/3</b> extra.

No. P 6844. **THE "COLWYN"**




Oblong Lavatory, with ogee rim and skirting, oval bowl, with self-contained  
overflow, Porceliron frieze, with legs.  
27 x 19 ins.; bowl, 19 x 13 ins.; height, 50 ins.  
Complete, with Fittings, .. .. . Price, **105/-** each.  
Nickel-plated Fittings, .. **3/6** extra.

## Porceliron Sanitary Ware

No. P 6841.

### THE "RYDE"



**Oblong Lavatory**, with ogee rim and skirting, oval bowl with self-contained overflow, porceliron frieze with brackets.


27 x 19 ins.; bowl, 19 x 13 ins.

Price, complete with Fittings, .. .. . 95/- each.

Nickel-plated Fittings, .. 3/6 extra.

No. P 6842.

### THE "VENTNOR"




**Angle Lavatory**, with ogee rim and skirting, oval bowl with self-contained overflow, porceliron frieze, with webbed brackets.

Width, 26½ ins.; projection, 21½ ins.; bowl, 16 x 12 ins.

Price, complete with Fittings, .. .. . 87/- each

Nickel-plated Fittings, .. 3/6 extra.



No. P 6849.

### THE "IMPERIAL" WASHING TUBS


Rectangular, with bold roll rim (2½ ins.) at front and ends.

These Tubs are provided with cast-iron standards (painted one coat), with building-in stays, and with either lugs on feet to let into concrete floor, or holes in feet for screwing down; also with 1½-in. brass plug and washer, with chain, and galvanized wrought-iron waste pipe.

Length.	Width.	Depth.	Height.	Price.
24½ ins.	19½ ins.	15 ins.	34 ins.	120/- each.
29½ "	19½ "	15 "	34 "	135/- "

# Porceliron Sanitary Ware

No. P 6837.  
**THE "RITZ"**




**Porceliron Combination Lavatory**, with roll rim, D-shape bowl, and deep frieze (cast in one piece), porceliron roll rim back, fitted with bevelled plate-glass mirror.

Length, 27 ins. ; projection, 20 ins. ; bowl,  $18\frac{1}{2} \times 12$  ins. ;  
height of lavatory, 30 ins.  
Total height, .. .. 66 ins.

With  $\frac{1}{2}$ -in. Nickel-plated Hot and Cold Pillar Taps, Plug Waste and Chain.  
Two Bracket Holders with China Vases, and One Bracket Holder  
with China Dish.

Price, complete, .. .. **£10 15 0** per set.

No. P 6838.  
**THE "CARLTON"**



**Porceliron Combination Lavatory**, with roll rim, D-shape bowl, and deep frieze (cast in one piece), porceliron roll rim back, fitted with bevelled plate-glass mirror.


Length, 27 ins. ; projection, 20 ins. ; bowl,  $18\frac{1}{2} \times 12$  ins. ;  
height of lavatory, 30 ins.  
Total height, .. .. 66 ins.

With  $\frac{1}{2}$ -in. Nickel-plated Hot and Cold Pillar Taps, Combination Pull-up  
Waste and Overflow, with Grating Connection and Union, Two Bracket  
Holders, with best China Vases, and Brush and Comb Tray.

Price, .. .. **£12 15 0** per set.

# Porceliron Sanitary Ware

No. P 6839. **THE "BRIGHTON"**



**Porceliron Oval Lavatory**, D-shape bowl, with roll rim and continuous deep frieze (cast in one piece), and Porceliron oval fluted pedestal. A handsome Lavatory, presenting a complete white porcelain surface.

Although designed and prepared for modern Bath and Toilet Rooms, it is also suitable for Bedrooms; it takes the place of the ordinary Washstand, which is both cumbersome and inconvenient, whereas this Lavatory gives the decided advantage of a hot and cold water supply, ready to hand, in a most desirable and convenient form for ablutionary purposes.


SIZE OVERALL:—Top, 33 × 22 ins.; bowl, 18 × 13 ins.; height, 31 ins.

PRICE, complete with Heavy Nickel-plated Pillar Taps, Hot and Cold, Combination Pull-up Waste, with Grating,

Connection and Union. . . . . **£10 15 0**

# Porceliron Sanitary Ware

No. P 6836. **THE "WHITEHALL"**




**Porceliron High-back Roll Rim Lavatory**, D-shape bowl, with deep frieze (cast in one piece); length, 27 inches; projection, 20 inches; bowl,  $18\frac{1}{2} \times 12$  inches; back, 12 inches high; height of lavatory, 30 inches. Porceliron roll rim mirror frame, oblong or oval, fitted with bevelled plate-glass mirror,  $27 \times 17$  inches overall; mirror,  $22 \times 12$  inches.

PRICE, with  $\frac{1}{2}$ -inch Nickel-plated Hot and Cold Pillar Taps,  $1\frac{1}{4}$ -inch Waste, with Rubber Plug, Union,

Chain and Stay, and Hinged Overflow Grating, .. .. . **£8 10 0** per set.

# Soil Pipe Ventilators


No. P348. Air Inlet Valve



For fixing over the mouth of a fresh-air induct-pipe to a waste-pipe, soil-pipe, or drain, to prevent the escape of foul air; for fixing to pipes of the following internal diameters:—


Sizes,	...	3	4	6 ins.
Prices, Vertical, encased in Galvanized Cast-iron, with Brass Grating and Mica Valve,	...	3/6	3/6	10/6 each.
Ditto,	ditto,	...	39/-	39/- 120/- per doz.

No. P5809. Patent Self-acting Exhaust Ventilator



Diameter.	Head.	Pipe.	Price.
Ins.	Ins.	Ins.	
10	5	...	18/- each.
12	6	...	21/- "
15	8	...	27/- "
18	9	...	36/- "
21	10	...	45/- "
24	12	...	57/6 "

No. P5810. Patent Soil Pipe Cowl




Diameter.	Head.	Pipe.	Price.
Ins.	Ins.	Ins.	
4	2	...	8/3 each.
5	2½	...	9/- "
6	3	...	10/- "
7	3½	...	11/3 "
8	4	...	12/6 "
9	4½	...	15/- "
10	5	...	17/3 "
12	6	...	19/6 "
15	8	...	24/- "
18	9	...	31/6 "

No. P5808. Patent Self-acting Exhaust Ventilator



Diameter.	Head.	Pipe.	Each.
Ins.	Ins.	Ins.	
12	6	...	27
15	8	...	39/-
18	9	...	45/9
21	10	...	60/-
24	12	...	82/6

No. P3540. Improved Air Inlet Brackets



	Plain Front.	Mid. Front, as drawn.
	Each.	Each.
7 x 3½ x 14 ins.,	11/3	15/9
8 x 4 x 16 "	13/6	18/9
9 x 4½ x 18 "	16/6	22/6
10 x 5 x 20 "	19/6	24/-
11 x 5½ x 22 "	22/6	29/-
12 x 6 x 24 "	27/-	36/-

Fitted with regulating valve, having brass fist handle, indicating when open or shut; brass wire gauge, air filter, deflecting shield.

No. P5495. Soil Pipe, Drain, and Sewer Ventilator




	Each.
4 ins. diam. of Pipe,	19/6
6 "	33/-
9 "	51/-
10 "	66/-
12 "	82/6
14 "	105/-

No. P3725. Soil Pipe Cowl



4 in. head, 2 in. pipe,	...	5/3 each.
5 "	2½ "	6/- "
6 "	3 "	6/9 "
7 "	3½ "	7/6 "
8 "	4 "	9/- "
9 "	4½ "	11/3 "
10 "	5 "	13/6 "
12 "	6 "	15/9 "

No. P1542. "Archimedeian" Ventilator



Made to fit on round iron pipes, for ventilating drains, closets, &c.

4 ins. diameter,...	21 - each.
6 "	24/- "
8 "	27/6 "
9 "	30/6 "
10 "	36/- "
11 "	40/- "
12 "	42/- "
13 "	50/6 "
14 "	57/- "
16 "	67/6 "
18 "	85/- "

No. P1541.

"Archimedeian" Ventilator




Body japanned stone color. Hood vermilion.

	Each.
6 ins. diameter, ...	26/6
8 "	30 -
9 "	32/6
10 "	38 -
11 "	44 -
12 "	48
13 "	54 -
14 "	59 -
16 "	76 -
18 "	92/-


# Latest Designs in Ventilators

## PATENT SELF-ACTING EXHAUST ROOF VENTILATORS


MADE OF STRONG, BEST ROLLED STEEL PLATES, RIVETED AND GALVANIZED, AND PAINTED TWO COATS OF OIL PAINT.



No. P 5811.		
Diameter.	Pipe.	Price.
Head. Ins.	Ins.	Each.
12	7	33/-
15	9	52/6
18	10	75/-
21	12	82/6
24	14	115/-
27	16	140/-
30	18	167/6
36	21	240/-



No. P 5812.		
Diameter.	Pipe.	Price.
Head. Ins.	Ins.	Each.
12	7	36/-
15	9	56/-
18	10	80/-
21	12	96/-
24	14	120/-
27	16	148/-
30	18	175/-
36	21	255/-




No. P 5813.		
Diameter.	Pipe.	Price.
Head. Ins.	Ins.	Each.
12	7	40/-
15	9	64/6
18	10	88/-
21	12	105/-
24	14	130/-
27	16	160/-
30	18	200/-
36	21	275/-

The above designs can also be made in Copper Prices quoted upon application.

## PATENT RIDGE AND INVISIBLE ROOF VENTILATORS


WITH BASE AND FLASHING TO PITCH OF ROOF.

No. P 5814. Ridge Ventilator



Length.	Price.
Inches.	each.
12 .. ..	55/-
18 .. ..	66/-
24 .. ..	84/-
30 .. ..	101/3
36 .. ..	120/-
42 .. ..	147/6
48 .. ..	180/-
54 .. ..	215/-
60 .. ..	248/-
66 .. ..	290/-
72 .. ..	330/-


No. P 5815. Ridge Ventilator



Length.	Price.
Inches.	each.
12 .. ..	75/-
18 .. ..	95/-
24 .. ..	120/-
30 .. ..	147/6
36 .. ..	178/-
42 .. ..	220/-
48 .. ..	266/-
54 .. ..	280/-
60 .. ..	360/-
66 .. ..	420/-
72 .. ..	480/-

No. P 5816.

Invisible Roof Ventilator




Length.	Price.
Inches.	each.
12 .. ..	67/6
18 .. ..	80/-
24 .. ..	105/-
30 .. ..	120/-
36 .. ..	140/-
42 .. ..	167/6
48 .. ..	200/-
54 .. ..	230/-
60 .. ..	270/-
66 .. ..	310/-
72 .. ..	365/-

Above Prices are for Roofs not less than 45 degrees. Special quotation for lower pitch on application. Automatic Valves can be supplied to Nos. P 5814, P 5815, and P 5816 at extra cost according to size of Ventilator.

WHEN ORDERING, PLEASE SEND PITCH OF ROOF.



# VENTILATORS



No. P 6546. **"EMPRESS" VENTILATOR.** "ARCHIMEDEAN" PATTERN.

This Ventilator differs from the ordinary so-called "Archimedeian" Ventilator in some important points. In the ordinary "Archimedeian" Ventilator the whole of the top revolves, in the "Empress" the cap is stationary and only the fans and screw revolve, thus throwing less weight upon the central point, thereby reducing the friction.

Again, the ordinary "Archimedeian" Ventilator is open to the base of the fans, rendering easy ingress to gusts of wind or driving rain to the discomfort of those within the building. To obviate this serious defect the "Empress" is constructed with an interior cone placed at such an angle, with a flat top plate, so that the wind striking the cone is deflected and escapes at the other side of the fans instead of blowing down the tube.

## PRICES.


Diameter of Pipe.	Outside Diameter.	Made of Stout Zinc.	Made of Tinned Iron not Japanned.	Made of Tinned Iron, Japanned.	Made of Hardened Copper.
4 inches,	6 inches,	16/6	18/-	21/9	31/6 each.
6 "	9 "	20/3	22/6	25/6	39/9 "
8 "	11 "	31/6	33/9	41/3	66/- "
10 "	14 "	36/9	38/3	47/3	82/6 "
12 "	17 "	45/-	46/6	57/-	108/- "
15 "	20 "	67/6	72/-	82/6	150/- "
18 "	23 "	90/-	93/-	109/-	212/- "

Prices for larger sizes submitted on application.

## Improved Air Inlet Wall Panels


MANUFACTURED OF BEST SHEET STEEL, GALVANIZED AND PAINTED.

No. P 5781.




Size of Box.		Price.
9 ins. x 7 ins.	..	15/- each.
12 " x 6 "	..	17/3 "
10 " x 8 "	..	18/6 "
9 " x 9 "	..	19/6 "
14 " x 7 "	..	21/9 "
11 " x 9 "	..	22/6 "
10 " x 10 "	..	23/3 "
12 " x 10 "	..	28/6 "
16 " x 8 "	..	30/- "
12 " x 12 "	..	34/6 "

No. P 5782.



Size of Box.		Price.
9 ins. x 7 ins.	..	21/6 each.
12 " x 6 "	..	24/- "
10 " x 8 "	..	26/3 "
9 " x 9 "	..	27/6 "
14 " x 7 "	..	33/- "
11 " x 9 "	..	34/6 "
10 " x 10 "	..	36/- "
12 " x 10 "	..	39/- "
16 " x 8 "	..	42/6 "
12 " x 12 "	..	48/- "


No. P 5783.



Size of Box.		Price.
9 ins. x 7 ins.	..	18/- each.
12 " x 6 "	..	20/- "
10 " x 8 "	..	22/6 "
9 " x 9 "	..	23/3 "
14 " x 7 "	..	27/- "
11 " x 9 "	..	28/6 "
10 " x 10 "	..	29/6 "
12 " x 10 "	..	33/- "
16 " x 8 "	..	36/- "
12 " x 12 "	..	40/- "


## Improved Air Inlet Wall Brackets

No. P 5787. OBLONG PATTERN.




Width.	Depth.	Height.	Price.
7	3½	14 ins., ..	<b>12 9</b> each.
8	4	16 .. ..	<b>15 9</b> ..
9	4½	18 .. ..	<b>18 6</b> ..
10	5	20 .. ..	<b>22 6</b> ..
11	5½	22 .. ..	<b>27 9</b> ..
12	6	24 .. ..	<b>33 9</b> ..

No. P 5788. ANGULAR PATTERN.



Width.	Depth.	Height.	Price.
7	3½	14 ins., ..	<b>18 -</b> each.
8	4	16 .. ..	<b>21 9</b> ..
9	4½	18 .. ..	<b>25 6</b> ..
10	5	20 .. ..	<b>30 -</b> ..
11	5½	22 .. ..	<b>36 -</b> ..
12	6	24 .. ..	<b>42 -</b> ..


No. P 5789. MOULDED FRONT.



Width.	Depth.	Height.	Price.
7	3½	14 ins., ..	<b>18 -</b> each.
8	4	16 .. ..	<b>21 9</b> ..
9	4½	18 .. ..	<b>25 6</b> ..
10	5	20 .. ..	<b>30 -</b> ..
11	5½	22 .. ..	<b>36 -</b> ..
12	6	24 .. ..	<b>42 -</b> ..


## Ventilating Wall Tubes and Brackets

Improved Air Inlet Wall Tubes, for the introduction of fresh air into a building without creating draughts, whilst entirely excluding dust. Constructed in a most substantial manner from best galvanized steel, painted one coat. Fitted with regulating valve, with brass handle indicating when open or closed. Brass wire gauze air filter and deflecting shield.




No. P 5784.  
OBLONG PATTERN.

Width.	Depth.	Height.	Price.
Ins.	Ins.	Ins.	each.
8	4	69	<b>24 -</b>
9	4½	69	<b>27 9</b>
10	5	69	<b>33 -</b>
11	5½	69	<b>36 -</b>
12	6	69	<b>39 -</b>



No. P 5785.  
ORNAMENTAL DESIGN.

Width.	Depth.	Height.	Price.
Ins.	Ins.	Ins.	each.
7	3½	32	<b>57 6</b>
8	4	34	<b>63 -</b>
9	4½	36	<b>72 -</b>
10	5	38	<b>82 6</b>
11	5½	40	<b>95 -</b>
12	6	42	<b>110 -</b>




No. P 5786.  
MOULDED FRONT.

Width.	Depth.	Height.	Price.
Ins.	Ins.	Ins.	each.
8	4	69	<b>34/6</b>
9	4½	69	<b>39/-</b>
10	5	69	<b>45/-</b>
11	5½	69	<b>51/-</b>
12	6	69	<b>57/6</b>

# Cottage, Yard, Contractors, Manure, Chain, Lift and Force Pumps


No. P 1008.  
Pitcher Spout



No. P 1001.  
Cottage.




No. P 1002.  
Cottage



No. P 1003.  
Cottage



No. P 1012.  
Yard



No. P 2207.  
Yard




No. P 1171.  
Contractors'



No. P 1172.  
Suction




No. P 1173.  
Manure




		BORE OF WORKING BARREL, .. ..		2	2½	3	3½	4	4½	5	6 ins.
No. P 1008.	Pitcher Spout Pump, open top, with Brass Union, .. ..	-	13 6	15/-	16/6	20 -	-	-	-	-	each.
.. P 1001.	Cottage Pump, for bolting down, complete with Brass Union, .. ..	12 -	15/-	18/6	26/3	33/9	-	-	-	-	"
.. P 1002.	Cottage Pump, with Brackets, for Bolting to plank or wall, complete with Brass Union, .. ..	12	15 -	18/6	26/3	33 9	-	-	-	-	"
.. P 1003.	Cottage Pump, for bolting to wall, complete with Brass Union .. ..	12	15/-	18/-	26/3	33 9	-	-	-	-	"
.. P 1012.	Strong Yard Pump, 36 ins. under Spout, with Wrought-iron Handle and Access Valve, .. ..		55/-	57/6	66/-	78/-	-	-	-	-	"
.. P 2207.	Strong Yard Pump, 36 ins. under Spout, C.I. Handle, .. ..		49/6	54/-	60/9	69/9	-	-	-	-	"
	It with Wrought iron Handle, extra, .. ..		6/-	6/9	6/9	7/6	-	-	-	-	"
.. P 1171.	Galvanized Sheet Steel Contractors' Pump, 7 ft. 6 ins. under Spout, .. ..		-	75/-	-	81/-	-	88/-	100/-	-	"
.. P 1172.	Galvanized Sheet Steel Sliding Suction Pipe, 8 ft. long, .. ..	-	-	20/3	-	22/6	-	26/3	30/-	-	"
.. P 1173.	Galvanized Sheet Steel Manure Pump, on Wrought iron Tripod Legs, complete with Brass Union for 2 in. Hose, and Galvanized Iron Strainer, .. ..		-	-	-	-	72/-	-	-	-	"
.. P 1031.	Chain Lift Pump, open top, complete 12 ft. under Spout, .. ..	84/-	95 -	102/6	120 -	160 -	-	-	-	-	"
.. P 1029.	Chain Lift Pump, covered top, complete 12 ft. under Spout, .. ..	102/-	115 -	130/-	150 -	200 -	-	-	-	-	"
	Exceeding 12 ft. under Spout, Nos. P 1031 or P 1029, .. ..	-	4 6	5 -	5 6	7/6	per foot extra.				
.. P 1015.	Wrought ironwork for Lead Jack Pump, .. ..	-	4 6	6 -	8 3	10 6	set.				
.. P 1013.	Lead Jack Pump, complete with Handle, Bucket and Sucker, and Clacks, .. ..	-	26 3	34 6	52 6	72 -	each.				
.. P 1031.	Strong Standard Pattern Brass Lift and Force Pump, on oak plank, .. ..	80/6	98 6	115 -	138 -	160 -	"				
.. P 1033A.	Brass Lift and Force Pump, Brass Air Vessel, Brass D.O. Cock, Wrought-iron Handle, on plank, .. ..	112 -	135 -	158/-	184/-	212/-	"				

No. P 5400.  
The "York" Pump  
Fitted with Brass Linings.



2½ 3 3½ 4 ins.  
27/9 33/- 39/- 46/6 each.

No. P 1034.  
Chain




No. P 1029.  
Chain




No. P 1015.  
Handle




No. P 1013.  
Lead Jack  
Pump



No. P 1031.  
Brass Lift and  
Force



No. P 1033A.  
Brass Lift and  
Force




# Deep Well Pumps

No. P 1036.  
Deep Well  
Lift




No. P 1009.  
Deep Well  
Pump



No. P 1017.  
Deep Well  
Pump




No. P 1018.  
Deep Well  
Pump




No. P 1116.  
Lever on  
Plank



No. P 1117.  
Lever on  
Plank



No. P 5255  
Geared Rotary Pump  
Motion  
on Cast-iron Standard.



Diameter of Bore of Pump Top, Tree, and Main Pipe  
of Working Barrel.

No. P 1036. Deep Well Lift Pump, fitted with wrought-iron handle weighted to balance rods. The rods are of wrought-iron, with joggled joints and brass sleeves; all necessary flanged suction and delivery pipes, with joints, bolts, and nuts for well 30 ft. to surface, .. .. .

Exceeding 30 ft. to surface, .. .. .

Diameter of Bore of Working Barrel, .. .. .  
Suction and Delivery Pipes, .. .. .

No. P 1009. Strong All-Brass Single Barrel Deep Well Pump, with full size flanges. This is a high-class Pump and is greatly in demand. 62 6

.. P 1017. Extra Strong Single Iron Barrel Deep Well Pump, with Brass Lining and Bucket Rod, fitted with Doors for access to Suction and Retaining Valves. 92/-

.. P 1018. Extra Strong Double Iron Barrel Deep Well Pump, with Brass Linings and Bucket Rod, fitted with Doors for access to Suction and Retaining Valves, .. .. .

Cast-iron Air Vessel, .. .. .

No. P 1116. Strong Wrought-iron Lever Motion Working Arrangement mounted on face of Strong Oak Plank, .. .. .

.. P 1117 is similar to No. P 1116, but Lever is arranged to work through Strong Oak Plank, .. .. .

.. P 5255. Cast-iron Pump Motion Frame, of heavy design, with Flywheel and Countershaft and Wheel Gearing, 2, 3, or 3 1/2 to 1 ratio, as required. £12 15 0 per set.

3 2 1/2	3 1/2 3	4 3 1/2	4 1/2 4	inches. "
150/- 3 9	165/- 4 3	195/- 4 9	225/- 5/-	each. per ft. extra.
2 1 1/2	3 1 1/2	3 1/2 2	4 2	inches. "
62 6	75	88/-	107/-	126/- each.
	92/-	120/-	142/6	190/- ..
	250/- 28/6	285/- 28/6	350/- 39/-	390/- 39/-
				extra.
	2, 2 1/2, and 3 ins.,	50/- each.	3 1/2 and 4 ins.,	60/- each.
	2, 2 1/2, and 3 ins.,	50/- each.	3 1/2 and 4 ins.,	60/- each.
				£12 15 0 per set.

## PUMP FITTINGS

No. P 1841. Wood Buckets



No. P 1841. Plain.

2 2 1/2 3 3 1/2 4 ins.  
4/6 5/3 6/9 9/- 10/6 doz.

No. P 1841 1/2. Leathered.

2 2 1/2 3 3 1/2 4 ins.  
13/6 16/6 21/- 30/- 36/- doz.

No. P 1842. Woodsucker



No. P 1842. Plain.

2 2 1/2 3 3 1/2 4 ins.  
3/- 3/- 3 9 4 6 6 - doz.

No. P 1842 1/2. Leathered.

2 2 1/2 3 3 1/2 4 ins.  
6 - 7 6 9 - 12 - 13/6 doz.

No. P 1861. Cup Leather



2 2 1/2 3 3 1/2 4 5 ins.  
9d. 1 - 1 3 1/6 2 3 4/- each.

No. P 1845. Paragon Bucket



No. P 1845. Iron.

2 2 1/2 3 3 1/2 4 ins.  
3 9 4 3 5 6 7 3 each.

No. P 1845 1/2. Brass.

2 2 1/2 3 3 1/2 4 ins.  
5/- 5/9 6/9 11/3 13/6 each.

No. P 1848.

Single Roller Guides



Sizes, .. 5 7 7 1/2 in.  
Prices, .. 5/3 5/9 8/3 each.

No. P 1849.

Coupling Joint for  
Well Rod



5 7 7 1/2 in.  
5/3 6/- 8/3 each.

No. P 1850. Cast-iron Foot Valve and Strainer  
Screwed for Tube.

Sizes, .. 1 1 1/2 1 1/2 2 ins.  
Prices, .. 4/- 4/6 4/9 5/6 6/6 8/3 each.



No. P 1864. Iron Retaining Valve

Sizes, .. 1 1 1/2 2 2 1/2 ins.  
Prices, .. 5/- 6/- 7/6 9/- 12/- each.



# The "Paragon" Diaphragm Pump

SUITABLE FOR CONTRACTORS AND GENERAL PURPOSES.

In this Pump a rubber diaphragm takes the place of a plunger or bucket in an ordinary pump, which renders it particularly suitable for raising muddy water, sewage, or water containing sand, small stones, chips, or other foreign matter.

## SIZES AND PRICES

Diameter of Suction.	Gallons per hour (about).	PRICE.
2½ ins. .. ..	1,800 .. ..	<b>160/-</b> each.
3 .. ..	4,000 .. ..	<b>175/-</b> ..
4 .. ..	6,000 .. ..	<b>345/-</b> ..

## FITTINGS AND ACCESSORIES

	2½	3	4 ins.
Brass Half Hose Union, .. ..	<b>18/-</b>	<b>24/-</b>	<b>37/6</b> each.
Cast-iron Foot Valve and Strainer, with connection ribbed for Hose Pipe, ..	<b>22/6</b>	<b>30/-</b>	<b>48/-</b> ..
Cast-iron Foot Valve and Strainer, Screwed for Tube, .. ..	<b>15/-</b>	<b>19/6</b>	<b>33/-</b> ..
4-Ply Vulcanized Rubber and Canvas Suction Hose, wired inside, .. ..	<b>5/6</b>	<b>6/9</b>	<b>9/-</b> foot.
Spare Diaphragms, .. ..	<b>21/9</b>	<b>27/-</b>	<b>31/6</b> each.

This Pump can also be supplied with bottom inlet, prices for which will be quoted upon application.

# Double-Acting and Quadruple-Acting Semi-Rotary Pumps

No. P 4538.

## DOUBLE-ACTING PUMP

Sizes, ..	0	1	2	3	4	5	6	7	8
Suction and Delivery, .. ..	½	¾	1	1¼	1½	1½	1½	2	2 ins.
Capacity per Hour, .. ..	240	420	450	570	870	960	1,320	1,560	2,310 gallons.
Iron Pump, Brass Valves, and Seatings, ..	<b>19 6</b>	<b>22 6</b>	<b>27 -</b>	<b>31 6</b>	<b>39 -</b>	<b>43 6</b>	<b>50 -</b>	<b>63/-</b>	<b>75/-</b> each.
All Brass Pump, Valves, and Seatings, ..	<b>36/-</b>	<b>40</b>	<b>51 -</b>	<b>70/-</b>	<b>84/-</b>	<b>105/-</b>	<b>120/-</b>	<b>150/-</b>	<b>192/-</b> ..

No. P 5779.

## QUADRUPLE-ACTING SEMI-ROTARY PUMP

Sizes, ..	1	2	3	4	5	6	7	8
Suction and Delivery, .. ..	¾	1	1¼	1½	1½	1½	2	2 ins.
Capacity per Hour, .. ..	495	615	930	1,200	1,440	1,860	2,100	2,760 gallons.
Iron Pump, Brass Valves, and Seatings, ..	<b>27/-</b>	<b>31/6</b>	<b>39/-</b>	<b>48/-</b>	<b>57/-</b>	<b>69/-</b>	<b>75/-</b>	<b>96/-</b> each.
All-Brass Pump, Valves, and Seatings, ..	<b>48/-</b>	<b>60/-</b>	<b>78/-</b>	<b>102/6</b>	<b>129/-</b>	<b>145/-</b>	<b>189/-</b>	<b>240/-</b> ..


Where a Pump is only in occasional use for water, an All-Brass Pump is recommended.

The Suction Pipe of Semi-Rotary Pumps should in all cases be fitted with a Foot Valve and Strainer.


# "Paragon" Colonial Suction and Force Pumps

WITH LUGS FOR BOLTING TO WALL OR PLANK, AND ALSO MOUNTED UPON PLANK.


No. P 5441.




No. P 5443.




No. P 5445.




No. P 5442.



No. P 5441.



No. P 5446.



The above Pumps are suited for raising water from shallow wells or cisterns not exceeding 27 feet in depth, and forcing it up to elevated cisterns. Although of moderate cost they are simple and effective, and are thoroughly well fitted and finished. The Handle is reversible, and the Suction and Delivery Chambers are fitted with Brass Union Tails screwed for Iron Pipe. The Piston Rod and Stuffing Box are of Brass. Each Tail Piece is fitted with "Paragon" Brass Valve Seating.

The Brass Cylinder Pumps, Figs. P 5441A, P 5443A, P 5445A, P 5442A, P 5441B, P 5446A have a Solid Polished Brass Barrel, also a Brass Bucket and Valve.

The Brass Pumps, Figs. P 5441B, P 5443B, P 5445B, P 5442B, P 5441A, P 5446B, have all parts Brass except Handle Fulcrum, Top Chamber, Base, and Air Vessels.

By raising the Handle to its full height the Pump Barrel is emptied of water, and breakage by frost prevented.

All parts are made to gauge by special machinery, and are interchangeable, and can be renewed.

## SPECIFICATION.

- No. P 5441. "Paragon" IRON Colonial Suction and Force Pump, with Lugs for bolting upon wall or plank, having Brass Union Tail screwed for Iron Pipe upon Suction and Delivery Chambers.
- " P 5443. "Paragon" IRON Colonial Suction and Force Pump, with Lugs for bolting upon wall or plank, having an Air Chamber upon the Delivery fitted with Top and Side Outlets. One Outlet is fitted with a Brass Union Tail, and one with a Blank cap. These are interchangeable. The Suction is also fitted with a Brass Union Tail.
- " P 5445. "Paragon" IRON Colonial Suction and Force Pump, with Lugs for bolting upon wall or plank, having an Air Chamber upon the Delivery fitted with Top Outlet, and an Iron Draw-off Cock with Brass Plug at side, the nozzle of Cock is screwed for Hose Coupling, both Suction Inlet and Delivery Outlet are fitted with Brass Union Tail screwed for Iron Pipe.
- " P 5442. Is exactly as No. P 5441, but is mounted upon strong wood plank.
- " P 5444. Is exactly as No. P 5443, but is mounted upon strong wood plank.
- " P 5446. Is exactly as No. P 5445, but is mounted upon strong wood plank.

## PRICE LIST.

		0	2	4	6	8	
Number of Pump, .. .. .		2	2 1/2	3	3 1/2	4	ins.
Bore of Working Barrel, .. .. .		1 1/4	1 1/2	1 3/4	1 3/4 or 2	2	"
Bore of Suction and Delivery Pipes, .. .. .		6	6	7	7 1/2	7 1/2	"
Length of Stroke, .. .. .		35/-	37/-	43/-	69/-	73/-	each.
No. P 5441. "Paragon" IRON Suction and Force Pump as per Engraving and Specification, .. .. .		60/-	63/-	72/-	105/-	132/-	"
" P 5441A. "Paragon" BRASS CYLINDER Suction and Force Pump as per Engraving and Specification, .. .. .		86/-	102/6	126/-	180/-	215/-	"
" P 5441B. "Paragon" BRASS Suction and Force Pump as per Engraving and Specification, .. .. .		42/-	44/-	51/-	81/-	85/-	"
" P 5443. "Paragon" IRON Suction and Force Pump as per Engraving and Specification, .. .. .		64/6	66/-	76/-	112/6	145/-	"
" P 5443A. "Paragon" BRASS CYLINDER Suction and Force Pump as per Engraving and Specification, .. .. .		92/-	102/6	132/-	190/-	226/-	"
" P 5443B. "Paragon" BRASS Suction and Force Pump as per Engraving and Specification, .. .. .		48/-	50/-	58/-	87/-	91/-	"
" P 5445. "Paragon" IRON Suction and Force Pump as per Engraving and Specification, .. .. .		72/-	75/-	87/-	128/-	157/-	"
" P 5445A. "Paragon" BRASS CYLINDER Suction and Force Pump as per Engraving and Specification, .. .. .		98/-	107/-	142/-	190/-	230/-	"
" P 5445B. "Paragon" BRASS Suction and Force Pump as per Engraving and Specification, .. .. .		37/-	39/-	45/-	71/-	75/-	"
" P 5442. "Paragon" IRON Suction and Force Pump as per Engraving and Specification, .. .. .		63/-	66/-	75/-	110/-	140/-	"
" P 5442A. "Paragon" BRASS CYLINDER Suction and Force Pump as per Engraving and Specification, .. .. .		87/-	95/-	120/-	172/-	212/-	"
" P 5442B. "Paragon" BRASS Suction and Force Pump as per Engraving and Specification, .. .. .		44/-	46/-	53/-	83/-	87/-	"
" P 5444. "Paragon" IRON Suction and Force Pump as per Engraving and Specification, .. .. .		66/-	69/-	77/6	120/-	145/-	"
" P 5444A. "Paragon" BRASS CYLINDER Suction and Force Pump as per Engraving and Specification, .. .. .		95/-	102/6	130/-	186/-	226/-	"
" P 5444B. "Paragon" BRASS Suction and Force Pump as per Engraving and Specification, .. .. .		50/-	52/-	60/-	89/-	93/-	"
" P 5446. "Paragon" IRON Suction and Force Pump as per Engraving and Specification, .. .. .		72/-	75/-	84/-	125/-	150/-	"
" P 5446A. "Paragon" BRASS CYLINDER Suction and Force Pump as per Engraving and Specification, .. .. .		100/-	110/-	135/-	190/-	232/-	"
" P 5446B. "Paragon" BRASS Suction and Force Pump as per Engraving and Specification, .. .. .		6/6	7/6	9/-	10/-	12/-	"
Iron Pumps with Brass Linings, .. .. .	extra,	5/6	6/-	8/-	10/-	12/-	"
Iron Pumps with Brass Bucket and Valves, .. .. .	"	6/6	9/-	12/-	15/-	17/-	"
Pumps arranged for Hot Liquor, .. .. .	"						"

# The "Hercules" Lift and Force Pump

THE PUMP IS A HYDRAULIC PUMP, NOT AN AIR PUMP.


AN IMPROVEMENT ON THE "LITTLE GIANT."

Makes its own connections, does all its work by itself.

EASY TO OPERATE.

With Unique Attachments to fit any ordinary plumbing fixture.

The Pump is made of heavy polished brass with attachments of pure rubber. For its purpose, no pump made to sell at five times its cost can equal it.




NO SKILL REQUIRED.

Just place Pump over opening of pipe and work piston up and down, and pipe is quickly freed of obstruction. No bucket, hose, or any other tool required.

WILL LAST A LIFETIME.

The "HERCULES" is able to do the work of pumps that cost five times as much, because of its Patent Lift and Force Cup, and an exclusive feature that makes it the only pump having lift and force without a valve. A special feature of this Pump is that it will rapidly withdraw an obstruction if desired.




It is both a Lift and a Force Pump, and the only known invention of a pump that both lifts and forces without a valve. The Patent Lift and Force Cup does the work, giving pump a reciprocating force, and with little effort does the work better than any other device known.




ADJUSTABLE WASHER.

There is no ordinary plumbing fixture to which this Pump is not adapted. Suitable for Lavatory Basins of all sizes.


HORSE SHOE



ROUND



OVAL



The Pumps are supplied complete with either of the above pattern cups at 20/- each complete, with Adjustable Washer.

Please state clearly which shape of cone is desired when ordering.

**A UNIQUE FEATURE.**—The New Patented and Registered Oval and D or Horse Shoe Cups have been designed to provide a PERFECT connection for any shape of Closet, and no plumber's outfit is complete without same.

# Decorators' Paint, Color, Varnish and Enamel Section

BRUSHES, TOOLS, AND SUNDRIES  
PAPER, STUCCO & PLASTER ROOM DECORATIONS



"ARTDEC" PURE PAINT MIXING

**O**UR Machinery for Paint Grinding and Mixing is of the most compact and up-to-date description, replete with every modern mechanical device for the handling of colors of all kinds, driven by electric power, thus ensuring cleanliness in all sections




PUGGING AND MIXING



PULP AND STIFF PAINT GRINDING

Separate machines are reserved for dealing with our continually increasing business in "Alpine White" enamels and "Artdec" pure paints, every batch of which is thoroughly tested before storing.

We can deal expeditiously with any quantity of special shades to meet customers' requirements, ground in either Oil, Turps, Gold Size, Varnish, or Water.





**NET PRICES.****VARNISHES****NET PRICES.**

FOR  
 DECORATORS, . . . .  
 PAINTERS, . . . .  
 PAPERHANGERS, &c. .



FOR  
 ENGINEERS, . . . .  
 YACHT AND COACH . .  
 BUILDERS, &c. . . .

The Varnishes enumerated in this list can be thoroughly relied upon to fulfil the purposes for which they are specially manufactured as described to each line. They are well matured, packed in new cans, hermetically sealed, and stored in an equable temperature to prevent the possibility of chilling.

In using Varnishes, whether of the cheaper or finer qualities, it is well to note that in order to obtain the best results, great care must be exercised to remove, before applying the varnish, every particle of solution used in cleaning the work to be treated. Varnish should be poured into a clean utensil some while before using. After the required quantity is taken out the can must again be tightly corked.

PRICES PER GALLON (subject to the variations of the market).

B 1985. "Albion" White Copal, palest Varnish made, . . . . . **18/-**  
 B 161. Superfine Copal Carriage Varnish, is recommended for both interior and exterior work, specially suitable for shop fronts, . . **16 -**  
 B 191. Pale Elastic Copal Carriage Varnish, a shade darker than above, a good useful Varnish, . . . . . **14 -**  
 B 154. Supertine Copal Varnish. This is particularly recommended where only one class of varnish can be used. It dries and wears equally well inside and outside, . . . . **10 6**  
 B 153. Pale Elastic Oak, a thoroughly reliable Varnish for outside work. We have supplied this Varnish to our clients for over 25 years with continuous satisfaction to all users, **8 6**  
 B 125. Pale Inside Oak, a pure Gum Varnish for inside work. The same remarks apply to this as an inside Varnish as to B 153 as one for outside use, . . . . . **7 6**

B 705. Front Door Copal, a high-grade Varnish for outside work, dries with a splendid face, guaranteed to wear well, weather resisting, **14/-**  
 B 170. Special Pale Copal Oak, for jobbing work inside or out, dries well with a good gloss and takes the place of a more expensive Varnish when price is in question, . . **8 6**  
 B 329. Finest Hard Drying White Copal, for inside decorations and wall papers; pale, hard drying, and non-blooming, made from the finest materials, . . . . . **12/-**  
 B 162. Extra Pale French Oil Varnish, for the most delicate tints, . . . . . **18/-**  
 B 157. Best Crystal Paper Varnish, for best white or marbled papers, . . . . . **10 6**  
 B 156. Fine Crystal Paper, suitable for colored papers, . . . . . **8 6**  
 B 190. Best Pale Copal, will stand any amount of wear and is particularly adapted for shop and bar fittings, . . . . . **12 6**

NOTE. -Special Varnishes not on our Lists will be quoted for on application.

All above prices are for 1-gallon free cans,  $\frac{1}{2}$  galls., 6d.;  $\frac{1}{4}$  galls., 9d.; and pint cans, 1/- per gallon extra.

**NET PRICES.**

B 347. Extra Pale Gold Size, highly recommended for binding qualities, and for preparing the lightest shades of paint, ..	8/6
E 159. Best Japan Gold Size, a better drier than the above, and where color is of no great moment should have the preference in use,	7/6
B 1747. Writers' or Gilders' Gold Size, for sign writing, &c., .. .. .	9/-
B 2463. Durable Oak Varnish, a pure gum varnish for either inside or outside use, its lasting qualities are exceptional. Best value in the trade, .. .. .	7/6

B 318.	Hard Church Oak, second grade,	..	<b>7 6</b>
B 1836.	Cottage Oak (square cans, free),	.	<b>5 9</b>
B 810.	Extra Pale Floor Varnish,	.	<b>10 -</b>
B 2073.	Engine Copal Varnish,	..	<b>16/-</b>

**B 192. Black Varnish.** This Varnish is found invaluable for many estate purposes, being more economical and at least as durable as ordinary paint. Its superiority to tar is shown by its facility in application, no preparation or heating being required, whilst it has the advantage of drying with a nice gloss and hard surface, not being softened by the heat of the sun. The Varnish possesses a good body and covering power. One coat is generally found sufficient to produce a good result.

<b>B 352.</b>	<b>Best Elastic Carriage Varnish.</b>	A shade darker than No. B 349,	.. .. .	<b>12/6</b>
<b>B 344.</b>	<b>Best Hard Carriage Varnish.</b>	A hard drying Varnish for first coating the wheels, &c., of carriages,	.. .. .	<b>12/6</b>
<b>B 353.</b>	<b>Hard Drying Van Varnish.</b>	A full-bodied, quick drying and good wearing Varnish of great brilliancy; it is specially made for vans and other vehicles where more expensive Varnishes are not required,		<b>9/6</b>
<b>B 365.</b>	<b>Superior Black Japan.</b>	The best coach-builders' Japan which can be produced for getting up the black groundwork of carriages; it is also exceptionally suited for panels,..		<b>14/-</b>
<b>B 366.</b>	<b>Fine Black Japan,</b>	.. .. .		<b>10/6</b>

265

**NET PRICES.****Ship, Yacht and Boat Varnishes, &c.****NET PRICES.**

		Price, per gallon.
No. B 324.	Superfine Yacht Copal, ..	18/-
„ B 323.	Pale Yacht Varnish, ..	12/6
„ B 198.	Boat Varnish, .. ..	8/6
„ B 324 A.	Mast and Spar Varnish,	6/6
„ B 323 B.	Pine Varnish, .. ..	4/6

**NOTE:**

FOR SUPERFINE YACHT ENAMELS,  
SHIP PAINTS, AND  
SPECIAL IRON AND STEEL PAINTS,  
SEE OPPOSITE PAGE.

**POLISHES, LACQUERS, &c.**

No. B 750.	Best French Polish, ..	8/6	per gallon.	No. B 168.	Best White Hard Varnish,	6/-	per gallon.
„ B 754.	No. 2 „ „ ..	7/-	„	„ B 675.	„ Spirit Black Lacquer,	6/6	„
„ B 758.	Best White „ ..	8/6	„	„ B 199.	„ Shellac Varnish, ..	8/6	„
„ B 194.	„ Brush „ ..	8/6	„	„ B 186.	Pale Gold Lacquer, ..	9/-	„
„ B 775.	„ Red „ ..	8/6	„	„ B 187.	Deep „ „ ..	9/-	„
„ B 174.	„ Ebony „ ..	8/6	„	„ B 805.	Colorless „ ..	8/6	„
„ B 778.	Patent Glaze, .. ..	7/6	„	„ B 2307.	Electric Bulb Lacquer		
„ B 179.	Methylated Finish, ..		„		(air drying), ..	16/-	„
„ B 167.	Best Brown Hard Varnish,	6/-	„				

**WOOD STAINS**

No. B 809.	Dry Stains, soluble in boiling water; colors, Oak, Walnut, Mahogany, Rosewood, Satinwood or Ebony, in 1-lb. tins,	4/-	per lb., or .. .. .	6d.	per oz.
No. B 183.	Water Stains in above shades and Green, put up in 6d. and 1/- bottles, or ¼, ½ and 1 gallon bottles, ..	5/-	per gallon.		
No. B 184.	Spirit Varnish Stains, in above shades and Green, put up in 6d. and 1/- bottles, or ¼, ½ and 1 gallon bottles, ..	7/-	„		
No. B 185.	Oil Varnish Stains, in above shades, put up in 6d. and 1/- bottles, or ¼, ½ and 1 gallon bottles, ..	8/6	„		



We strongly recommend **Oil Varnish Stains** for general purposes in preference to **Spirit Varnish Stains** generally offered for sale. They are not so liable to crack, and are much easier to apply to large surfaces, such as floors. The chief objection to Spirit Stains is that they set so quickly, that in covering large surfaces dark ridges are observable where the edges of the work are joined. Spirit Stains are, however, very useful for patching worn parts of floors, &c., as they may safely be walked over in two or three hours. Unless otherwise specified in the order, OIL VARNISH STAIN is supplied.

**We Stock HARLAND'S VARNISHES as follows:—**

No. B 2056.	Extra Pale French Oil Varnish, .. ..	24/-	per gallon.	No. B 2064.	Church Seat Oak Varnish,	12/-	per gallon.
„ B 2057.	Pale Copal Varnish, ..	16/-	„	„ B 2075.	Pale Oil Paper Varnish, ..	12/-	„
„ B 2061.	Pale Oak Varnish, for outside,	12/-	„	„ B 2076.	Hard Crystal Paper Varnish,	10/-	„
„ B 2062.	„ „ „ inside,	10/-	„	„ B 2065.	Pale Signboard Varnish, ..	16/-	„
				„ B 2058.	Decorators' Carriage Varnish,	16/-	„

The above prices are in 1-gallon free cans; extra charged if in smaller packages.

**When ordering please quote Number.**

**NET PRICES.****ENAMELS****NET PRICES.**

FOR DECORATORS, YACHT AND COACH BUILDERS, &amp;C.



To meet the growing popularity of "White Enamel" as a decorative medium, we have, after careful experiments, put on the market our

"ALPINE WHITE ENAMEL,"

"ALPINE WHITE-SNOW FLAKE,"

"COTTAGE WHITE,"

and we have priced them to meet all requirements.

The quality of each make at the price mentioned is superior to anything yet produced.



	1 Gallon.	1 Gallon.	1 Gallon.	Pints.
Alpine White Enamel, .. .. .	15 -	15 3	15 6	16/- per gallon.
Alpine White-Snow Flake, .. .. .	12 6	12 9	13/-	13 6 "
Cottage White, .. .. .	10 6	10 9		— "

**"ARTDEC" ELASTIC FINISH ENAMEL**

FOR USE IN HOSPITALS, MOTORS, CARRIAGES, STEAMSHIPS, YACHTS, &amp;C.

A special finishing enamel paint. Can be used over any surface that has been properly prepared, although we recommend its use over work prepared with our Undercoating. Easy flowing, drying with an enamel face, is permanent and sanitary. Can be used for outside work in exposed positions, and is of great covering power. Unequalled for all classes of decorative work. One gallon will cover approximately 100 square yards.

In 24 shades.	Prices, .. .. .	1 Gallon.	1 Gallon.	1 Gallon.	Pints.
		18 -	18 6	19/-	20/- per gallon, in free tins.
		Or in 1/6 tins.			

**"ARTDEC" BATH ENAMEL or ACID PROOF GLOSS FINISH**

Manufactured in 11 shades, suitable for either baths, refrigerators, and wherever soda solutions or chemicals are in use.

Prices, .. .. .	1 Gallon.	1 Gallon.	1 Gallon.
	18 6	19 -	20 - per gallon, in free tins.
	Or in 1/- and 1 6 tins, sufficient for small and large baths.		

**HOUSEHOLD ENAMELS**

In artistic shades. Packed in 6d. and 1/- tins.

**"ARTDEC" ENAMEL UNDERCOATING**

A scientific preparation to be used as a filler or undercoating for all enamels, dries quickly and sets very hard, cuts down with a beautiful flat surface, so that the finishing coats of enamel hold up perfectly.

Prepared in paste form and packed in 7 lb. and 14 lb. free tins. Price, .. .. 48/- per cwt.

*Shade Cards of our Enamels supplied on application.*

NET PRICES.

## Proprietary Enamels

NET PRICES.



### "ROBBIALAC"

Prices, .. 1 gall., 18 -;  $\frac{1}{2}$  gall., 18/6;  $\frac{1}{4}$  gall., 19 - per gallon.

Also in 1/6 Tins, sufficient for a motor cycle.

"Robbialac" is used throughout the Navy.

### "RYSTOLITE"

The 12 6 Enamel. Stocked in all sizes.

### "JAPANOL"

The durable, brilliant and hygienic enamel paint.

Prices, Shade Cards, &c., on application.

### "VELURE"

Flexible as a kid glove.

Trade and ordinary prices on application.


### "PARIPAN"

The more you wash it the better it looks.

Prices and Shade Cards on application.

### "RIPOLIN"

Stocked and sold at manufacturers' prices. Shades on application.



## ALUMINIUM OR GALVANIZING PAINT

A rust preventive. Useful for the underparts of motor cars; withstands the action of grease drippings. For iron staircases, fire exits, wrought ironwork and various other purposes.

Packed in 6d., 1 - and 2 6 tins; or in  $\frac{1}{4}$  gallon, 4 6;  $\frac{1}{2}$  gallon, 8/3; or 1 gallon, 16,- each.

### "ARDENBRITE" THE KING OF GOLD PAINTS

Packed in 6d., 1 -, 1 6 and 2 6 bottles;  $\frac{1}{4}$  gallon, 16 6;  $\frac{1}{2}$  gallon, 31,-; 1 gallon, 60,-. Packages free.

## JET BLACK ENAMEL

This preparation produces a brilliant finish, is thoroughly hard drying and rustproof. One coat only needed. For use on motors, bicycles, bedsteads, stoves, &c. Dries quickly and very hard. Stoves and ranges do not smell when in use after application. Economical in use. Packed in 6d. and 3 $\frac{1}{2}$ d. tins. Special prices quoted for bulk quantities.

## DULL BLACK ENAMEL

A specially manufactured Gun Metal Dull Black Enamel for all kinds of work requiring a dull black finish.

Packed the same as Jet Black Enamel.

## "ARTDEC" BLACKBOARD SLATING

A dead black finish for renewing old blackboards, &c. Prepared ready for use.

Prices, .. .. .  $\frac{1}{4}$  gallon, 8 -; 1 gallon, 15 -; or in tins, 1  $\frac{1}{2}$ , 1 6, and 2 6 each.

## "ARTDEC" SHEEP MARKING COMPOSITION

Is not injurious to the fleece, is permanent and not affected by weather. It is easily removed after scouring, and is prepared in four colors - Red, Blue, Yellow and Black. Price, 4 6 per gallon.

## FARM WAGON AND IMPLEMENT GLOSS PAINT

For use on wagons, threshing machines, mowers and general farm implements. Prepared in Black, Blue, Light and Dark Green, Yellow and Red. Prices -  $\frac{1}{2}$  gallon, 4 6; 1 gallon, 8 6 Free tins.

**NET PRICES.****Prepared Paint****NET PRICES.****"ARTDEC" PURE READY MIXED PAINT**

This Paint, manufactured by us to a specific formula, contains nothing but the purest ingredients: Pure lead, pure American turpentine and genuine refined linseed oil, and a special liquid drier in sufficient quantity to ensure good drying without detriment to the life of the paint.

Each package bears our guarantee of its purity, and the tins, both 7 and 14 lbs., have handles so that they can be used as paint kettles.

"ARTDEC" is put up in 30 shades, and these may be mixed in any proportion to produce other tints, or may be reduced with white.

A handsome hanging Shade Card will be supplied upon application.

Prices, .. .. 7-lb. tins, **38/-**; 14-lb. tins, **36/-**; or 1 cwt. drums, **34/6** per cwt.

The drums are charged and are returnable; the tins are free.

*N.B. "ARTDEC" is subject to market fluctuations.*

**Water Paints****"ARTDEC" WASHABLE DISTEMPER**

In paste form, packed in kegs and tins. This is a thoroughly reliable distemper, sanitary and washable, lime resisting and sets hard in a few hours, and can be freely washed three or four weeks after application.


"Artdec" Washable Distemper may be painted or papered over at any time without preparation.

"Artdec" Washable Distemper for outside work should be used with special thinners, the use of which does not increase the cost, as it covers better if treated in this way instead of water.

Prices in charged packages, .. .. 1 cwt., **26/-**;  $\frac{1}{2}$  cwt., **26/-**; or 28-lb. kegs, **26/-** per cwt.

Prices in free tins, .. .. 14 lb., **28/-**; 7 lb., **29/-** per cwt.

Tints on application.

**HALL'S SANITARY  
WASHABLE DISTEMPER**

Packed in kegs and tins.

Prices and shades on application.


**"MURALINE"**

A powder which when mixed with an equal quantity of water produces a sanitary washable distemper.

**PRICES.**

White No. 60,	..	<b>28/-</b>	per cwt., or	<b>2/-</b>	per 7-lb. packet.
Nos. 61 to 76,	..	<b>32/-</b>	"	<b>2 3</b>	" "
" 77 to 80,	..	<b>40/-</b>	"	<b>2 9</b>	" "
" 86 to 91,	..	<b>44/-</b>	"	<b>3/-</b>	" "

Shade Card on application.



We are Agents for "Duresco" (for the East London District), also "Wal-Pu-Mur" Washable Distemper.

Color lists and prices on application.

# White Lead, Oils, Colors, &c.

## NET PRICES.

## "ARTDEC" BRAND.

Subject to the Variations of the Market.

Quality A. Genuine.

The finest manufactured.

Suitable for decorators and coachbuilders  
for best class work.



Quality B. Medium.

Good and serviceable.

Specially suitable for general purposes.

The above Colors are packed in 28, 56, and 112 lb. kegs, charged and returnable (see our Package List), but can be packed if specially ordered in non-returnable tins (which are very useful as paint kettles) at the following rates:

1 lb., 8/-; 2 lb., 6/-; 4 lb., 4/-; 7 lb., 3/-; 14 lb., 2/- per cwt. extra.

## COLORS GROUND IN OIL

BLACKS.	Quality A	Quality B
Black Paint,	24/-	18/- per cwt.
Drop Black,	10d.	6d. per lb.
Pure Veg. Black (No. 2)	62/-	50/- per cwt.

BLUES.	Quality A	Quality B
Blue Paint,	32/-	20/- per cwt.
Celestial Blue,	44/-	36/- "
Chinese Blue,	26	19 per lb.
Prussian Blue,	26	19 "
Ultramarine,	9d.	6d. "

BROWNS.	Quality A	Quality B
Chocolate,	24/-	20/- per cwt.
Purple Brown, P. M. & D.,	30/-	21/- "
Vandyke,	50/-	42/- "
Burnt Sienna (strong stainer),	80/-	60/- "
Raw Sienna,	70/-	52/- "
Burnt Turkey Umber,	40/-	30/- "
Raw Turkey Umber,	36/-	28/- "

REDS.	Quality A	Quality B
Indian,	36/-	28/- per cwt.
Oxide of Iron,	24/-	18/- "
Venetian,	24/-	18/- "
Signal and Wagon,	1/-	6d. per lb.
Vermilionette,	1/-	6d. "
Fast Red,	2/6	"

WHITES.	Quality A	Quality B
Gen. Zinc White.		
Gen. Stack made English White Lead.		

## AT MARKET PRICES.

DRIERS.	Quality A	Quality B
Finest White Driers,	28/-	per cwt.
Best Patent Driers,	21/-	"
Special White Driers in 28-lb. kegs only,	20/-	"
Patent Driers,	14/-	"

GREENS.	Quality A	Quality B
Brunswick, P. M. & D.,	36/-	24/- per cwt.
Chrome Green,	42/-	28/- "
Bronze Green,	42/-	32/- "
Navy or Marine,	1/2	per lb.
Mineral or Varnish,	2/-	"
Emerald Tint,	44/-	per cwt.
Gen. Emerald Green,	1/6	per lb.

YELLOWWS.	Quality A	Quality B
Chromes in 3 shades,	1/-	9d. per lb.
Oxford Ochre (golden),	40/-	30/- per cwt.
Yellow Ochre,	28/-	24/- "

PUTTY.	Quality A	Quality B
Black and Red,	12/-	per cwt.
Gen. Linseed Oil Putty,	10/-	"
Reduced Linseed	8/-	"
Red Lead Putty,	24/-	"
Greenhouse Putty (Plasticine),	16/-	"

Ivory Black,	1/-	per lb.
Prussian Blue,	26	"
Ultra Blue,	1/6	"
Burnt Sienna (and Raw),	11d.	"
Burnt Umber ( " ),	8d.	"
Dutch Pink,	8d.	"

COLORS IN TURPENTINE	Quality A	Quality B
Bronze Green,	9d.	per lb.
Brunswick,	7d.	"
Quaker Green,	9d.	"
Indian Red,	8d.	"
Mahogany Lake,	3/-	"
Fast Red,	2/6	"

Signal Red,	1/6	per lb.
Sunlight Red,	2/3	"
Vermilion,	4/6	"
Flake White,	8d.	"
Zinc White,	9d.	"
Chromes (pale, middle, and deep),	1/3	"

## COLORS IN WATER

Chinese Blue,	3/-	per lb.
Damp Blue,	6d.	"
Burnt Sienna,	6d.	"
Burnt Turkey Umber,	4d.	"
Dutch Pink,	6d.	"

Raw Sienna,	5d.	per lb.
Carnation Rose,	3/6	"
Raw Turkey Umber,	4d.	"
Vandyke Brown,	5d.	"
Brown Lake,	1/6	"

Mahogany Lake,	1/6	per lb.
Rose Pink,	6d.	"
Crimson Lake,	1/6	"
Chromes (pale, middle, and deep),	1/-	"

N.B.—All above are packed in free lever tins, except those water colors which are liable to deteriorate; these latter are packed in stone jars, charged returnable. Special colors ground in turps or water at short notice.

# DRY COLORS

## NET PRICES.

Subject to the Variation of Markets without notice.

NOTE. "Genuine" always supplied unless otherwise stated at time of ordering.

### BLACKS.

	Quality		
	A	B	
Blue Black, ...	12/-		per cwt.
Drop Ivory Black, ...	9d.	6d.	per lb.
Lamp Black, loose in bulk, ...	24/-	20/-	per cwt.
" " in 1 lb., ½ lb., ¼ lb. packets, ...	32/-	24/-	"
Vegetable Black, " " " " " "	10d.	6d.	per lb.
" " in 7-lb. casks (free), ...	7/6	5/6	each.

### BLUES.

Antwerp Blue, ...	3/6		per lb.
Brunswick " " " " " "	36/-		per cwt.
Celestial " " " " " "	36/-	28/-	"
Chinese " " " " " "	3/-	2/6	per lb.
Indigo " " " " " "	8/6	6/-	"
Lime " for distemper, ...	36/-	28/-	per cwt.
Prussian " " " " " "	2/6	2/-	per lb.
Ultramarine, deep, in 7-lb. wood boxes, ...	1/-	9d.	"

### BROWNS.

Dutch Pink, ...	5d.		per lb.
English Umber, ...	8/6		per cwt.
Finest Brown Madder Lake, ...	8/-		per lb.
Italian Pink, ...	5/-		"
Lime Chocolate, ...	5d.		"
Oxide Iron, ...	20/-	16/-	per cwt.
Purple Brown (pale, mid, and deep), ...	36/-	28/-	"
Spanish " " " " " "	10/-		"
Terre de Sienna, Raw, ...	56/-	46/-	"
" " Burnt, ...	74/-	56/-	"
Turkey Umber, Raw, ...	32/-	26/-	"
" " Burnt, ...	36/-	30/-	"
Vandyke, ...	56/-	37/-	"

### GREENS.

Albert (pale, mid or deep shade), ...	56/-		per cwt.
Ash Green, ...	4d.		per lb.
Bronze (pale, mid, or deep shade), ...	42/-	32/-	per cwt.
Brunswick " " " " " "	37/-	20/-	"
Chrome Green " " " " " "	48/-		"
Coach " " " " " "	6d.		per lb.
Emerald " " " " " "	1/6		"
Emerald Tint, ...	66/-	48/-	per cwt.
Lime Green, ...	36/-	28/-	"
Olive, ...	6d.		per lb.
Peacock Green, ...	1/3		"
Quaker (pale, mid, or deep shade), ...	66/-		per cwt.
Royal " " " " " "	1/6	1/-	per lb.
Sage Green, ...	42/-		per cwt.
Spring " " " " " "	6d.		per lb.
Suffield " " " " " "	6d.		"
Turquoise Green, ...	1/2		"
Verdine Green, non-poisonous, for blinds, sun shutters, &c., ...	1/9		"
Verdigris Green, ...	1/-		"
Veridian " " " " " "	7/6		"
Victoria (pale, mid, or deep shade), ...	8d.	6d.	"
Zinc Green, ...	1/6		"

### REDS.

	Quality		
	A	B	
Bordeaux Red, ...	1/2		per lb.
Carmine, Imitation, ...	2/-		"
Carmine Lake, ...	3/6		"
Chinese Red, ...	10d.	8d.	"
Crimson Lake, Finest, ...	18/-		"
" " Ordinary, ...	3/-		"
" Madder Lake, ...	7/6		"
Wagon Red, ...	5d.		"
Fast Red, ...	1/3		"
Fire Red, ...	1/6		"
Indian Red (pale, mid, or deep shades), ...	4d.	3d.	"
Mahogany Lake, ...	2/6		"
Orange Lead, ...			"
Oxide Iron, ...	20/-	16/-	per cwt.
Persian Red, ...	8d.	6d.	per lb.
Pompeian Red, ...	6d.		"
Red Lead, ...			"
" Ochre, ...	8/6		per cwt.
Royal Red, in 3 shades, ...	1/-		per lb.
Scarlet Lake, Finest, ...	14/-		"
Signal, ...	10d.		"
Sunlight Red, ...	1/-		"
Turkey " " " " " "	6d.		"
Tuscan " " " " " "	9d.		"
Venetian " " " " " "	10/6	7/6	per cwt.
Vermilion, Genuine, ...			"
Vermillionette, ...	1/6	1/-	per lb.
Victoria Red, ...	6d.		"

### LAKES.

Blue, ...	10/-		per lb.
Carnation, ...	5/-		"
Geranium, ...	16/-		"
Green—3 shades, ...	5/-		"
Magenta, ...	8/-		"
Maroon, ...	6/-		"
Purple, ...	24/-		"
Rose, ...	6/-		"
Victoria, ...	3/-		"
Violet, ...	8/-		"
Yellow, ...	11/-		"
" Indian, ...	8/-		"

### PINKS.

Rose, ...	6d.		per lb.
-----------	-----	--	---------

### YEELLOWS.

Cadmium Yellow (pale, mid, or deep), ...	18/-		per lb.
Chrome, in 3 shades, ...	1/-	9d.	"
French Ochre, ...	8/6	6/-	per cwt.
Italian " " " " " "	24/-		"
Naples Yellow (pale or deep), ...	2/6		per lb.
Red Ochre, ...	8/6		per cwt.
Zinc Yellow, ...	1/6		per lb.

### WHITES.

Gilders' Whiting, in cakes, ... 2/3 per cwt.  
Dry White Lead and Zinc White.

In quantities of not less than 1 cwt.  
Prices upon application.



# NET PRICES.

# Special List of Cheap Grindings, &c.

# NET PRICES.

**WHITES, in Oil.**  
**"Caledonian" Brand Genuine White Lead and Zinc**  
 White, in 7 and 14 lb. tins. Prices upon application.

**BLACKS, ground in Oil.** 7 14 lb. tins. Per cwt.  
 Black Paint, .. .. 1/6 2/6 each. 18/-

**BLUES, ground in Oil.** 7 14 lb. tins. Per cwt.  
 Chinese Blue, .. .. 12/6 each.  
 Prussian Blue, .. .. 12/6 "  
 Celestial Blue, .. .. 2/6 4/9 " 36/-

**GREENS, ground in Oils.**  
 Brunswick Green, pale, middle 7 14 lb. tins. Per cwt.  
 or deep shade, .. .. 1/9 3/3 each. 24/-  
 Bronze Green, do., do., 2/3 4/3 " 32/-

**YELLOWWS, in Oil.**  
 Chrome, pale, middle, or deep 7 14 lb. tins. Per cwt.  
 shade, .. .. 5/6 10/9 each.  
 Oxford Ochre, .. .. 2/3 4/3 " 32/-  
 Stone Ochre, .. .. 1/9 3/3 " 24/-

**BROWNS, in Oil.** 7 14 lb. tins. Per cwt.  
 Raw Turkey Umber, .. 2/- 3/9 each. 28/-  
 Burnt Turkey Umber, .. 2/3 4/3 " 32/-  
 Purple Brown, pale, middle  
 or deep shade, .. .. 1/9 3/3 " 21/-  
 Chocolate, .. .. 1/9 3/3 " 20/-  
 Raw Terre de Sienna, .. 3/9 7/3 " 56/-  
 Burnt Terre de Sienna, .. 4/6 8/9 " 64/-

**REDS, ground in Oil.** 7 14 lb. tins. Per cwt.  
 Indian Red, .. .. 2/- 3/9 each. 28/-  
 Signal Red, .. .. 3/9 7/3 " 56/-  
 Oxide Iron, red or purple  
 brown shade, .. .. 1/6 2/9 " 18/-  
 Venetian Red, .. .. 1/6 2/9 " 18/-

**COLORS, in Oil. (Requiring Thinnings and Driers only.)**  
 7 14 lb. tins. Per cwt.  
 Stone Color, .. .. 1/9 3/3 each. 24/-  
 Buff Color, .. .. 1/9 3/3 " 24/-  
 Lead Color, .. .. 1/9 3/3 " 24/-

**COLORS, in Turps.** 7 14 lb. tins.  
 Drop Ivory Black, .. .. 3/9 7/- each.  
 Emerald Green, .. .. 10/6 20/- "  
 Flake White, .. .. 5/6 10/9 "

**COLORS, in Water.** 7 14 lb. tins.  
 Dutch Pink, .. .. 2/6 4/9 each.  
 Rose Pink, .. .. 2/6 4/9 "  
 Vandyke Brown, .. .. 3/9 7/3 "  
 Raw Sienna, .. .. 4/3 8/- "  
 Burnt Sienna, .. .. 5/- 9/9 "

**DRIERS.** 7 14 lb. tins. Per cwt.  
 Patent Driers, .. .. 1/- 1/10 each. 14/-

**PUTTY.** Per cwt.  
 Putty, No. 1, .. .. —

Bulk packages charged and returnable.

## "Caledonian" Brand Varnishes

Reliable quality, English manufacture and well matured. Guaranteed equal to Varnishes in the market at much higher prices.

Per Gall.  
 B 1921. Pale Oak Varnish, for indoor jobbing work, 4/9  
 B 1922. Fine Oak Varnish, good body, for jobbing  
 work, .. .. 5/6  
 B 1923. Copal Oak Varnish, for inside work, .. 7/6  
 B 1924. Pale Elastic Oak Varnish, for outside work, 8/3  
 B 1925. Hard Church Oak Varnish, specially made  
 for hand-rails, and work liable to be handled, 7/6

Per Gall.  
 B 1926. Crystal Paper Varnish, good body and pale, 8/6  
 B 1927. Terebene, .. .. 5/9  
 B 1928. Patent Knotting, .. .. 6/6  
 B 1929. Brunswick Black, .. .. 5/-  
 B 1930. Black Varnish, .. .. 1/3

When ordering, "Caledonian" brand must be specified, otherwise Quality "A" is always sent, carriage forward.  
 Packed in 1 gallon tins free. Extra for smaller packages - 1/2 galls., 6d.; quarts, 9d.; pints, 1/- per gallon, and not returnable.

## "SUN" BRAND READY MIXED PAINTS



A good serviceable Paint for either household or small property use.

Packed in 1 and 2 lb. tins, 32/- per cwt.; 7-lb. tins, 31/- per cwt.; 1-cwt. drums, 30/- per cwt., drums charged and returnable.

Manufactured in the same shades as "Artdec" series.

## STEEL AND IRON PROTECTIVE PAINT

**RED AND BROWN.** Best. 2nd.  
 In 5 gallon drums, .. .. 7/6 4/6 per gallon.  
 " 1 " free cans, .. 7/9 4/9 "  
 " 1/2 " " .. 8/- 5/- "

## READY MIXED BROWN

For rough work such as fencing, outbuildings, sheds, &c.  
 1 gallon free tin, .. .. 4/3 per gallon.  
 5 " drums and barrels, .. 4 - "

**NET PRICES.****Decorators' Tube Colors****NET PRICES.**

Ground in refined linseed oil and packed in collapsible tubes, they have the advantage of being always perfectly clean and ready for use, whilst the required quantity being taken out the remainder is preserved from skinning and hardening.



For purity and permanence of color, fineness of grinding, and strength of staining power, these colors are unrivalled, and far and away excel ordinary painters' colors. The tubes hold a uniform quantity, but vary in weight according to the color.

COLOR.	5 x 1½ ins.	COLOR.	5 x 1½ ins.	COLOR.	5 x 1½ ins.
Antwerp Blue, ..	1/4	Crimson Lake, ..	5/-	Raw Sienna, ..	8d.
Blue Black, ..	8d.	Emerald Green, ..	1/4	Raw Umber, ..	8d.
Bronze Green, Pale,		Flake White, ..	1 -	Rose Madder, ..	5/-
"    "    Medium,	8d.	Gamboge, ..		Sap Green, ..	
"    "    Deep,		Indian Red, ..	8d.	Scarlet Lake, ..	5/-
Burnt Sienna, ..	8d.	Indigo Blue, ..	1/4	Terra Vert, ..	6d.
Burnt Umber, ..	8d.	Ivory Black, ..	8d.	Ultramarine, Light,	
Chrome Green, Light,		Lamp Black, ..	8d.	"    Deep, }	1/-
"    "    Middle,		Light Red, ..	8d.	Vandyke Brown, ..	8d.
"    "    Deep,		Madder Lake, ..	5 -	Vermilion, Light or Deep,	4 -
"    Yellow, Pale,	1/-	Olive Green, ..	1 -	Yellow Ochre, ..	8d.
"    "    Deep,		Prussian Blue, ..	1 4	Zinc White, ..	8d.
"    Orange, ..		Purple Lake, ..	4,		

**Gold Leaf, &c.**

FOR CARVERS AND GILDERS, SIGN WRITERS, COACH AND VAN BUILDERS, BOOKBINDERS, DECORATORS, &c.

For quantities of 5000 leaves and upwards we shall be pleased to quote specially.

No.	Description	Per 1000 Leaves.	Per Book.
B 442.	Best Deep English Gold Leaf, for Carvers and Gilders, ..	46/-	1/2
" B 443.	" " " transferred on to tissue paper, for Sign Writers' and Decorators' use, ..	48/-	1/3
" B 444.	Best Dark Lemon Shade English Gold Leaf, for Van Writers (to be varnished over), ..	46/-	1/2
" B 445.	" " " transferred on to tissue paper, for outdoor work (to be varnished over), ..	48/-	1/3
" B 446.	Best Pale Lemon Shade English Gold Leaf, for Van Writers (to be varnished over), ..	42/-	1/1
" B 448.	" " " transferred on to tissue paper (to be varnished over), ..	44/-	1/2
" B 449.	Foreign Deep Gold Leaf, Extra Fine Quality, ..	42/-	1/1
" B 450.	" " " transferred on to tissue paper, ..	44/-	1/2
" B 453.	" Pale " ordinary quality (to be varnished over), ..	33/-	10d.
" B 454.	" " " transferred (to be varnished over), ..	35/-	11d.
" B 455.	Aluminium Leaf, now largely used in place of Silver Leaf which so readily tarnishes, ..	18/-	6d.
" B 456.	Silver Leaf, ..	16/-	3d.

N.B. —Not less than 500 leaves charged at the 1000 rate, smaller quantities at the rate per book.

**Gold, Aluminium, and Colored Bronzes for Wall Paper Manufacturers, Printers, Lithographers.**

Samples matched and lowest Continental Prices quoted. We hold stocks when required.

	Per lb.		Per lb.
Gilders' Oil Gold Size in tins 6d. or 1/- each, or in jars, ..	2/6	Gilders' Compo, ..	1/-
" Burnishing Gold Size, ..	1/6	" Clay, ..	1/-
" Matt Gold Size, ..	1/6	" Parchment Cuttings, ..	1/-

Gilders' Cushions, Knives, Tips, Burnishers, &c., kept in stock.

**NET PRICES.****Decorators' Sundries****NET PRICES.****Silicate Cotton and Slag Wool Products**

- No. B1897. Silicate Cotton Wire Net Felting, 1 in. thick, with brown paper backing, .. 4d. per foot super.
- .. B1898. Silicate Cotton Wire Net Felting, 1 inch thick, with felt or canvas backing, 6d. " "
- .. B1910. Silicate Cotton Yarn Woven Strips,  $\frac{1}{2}$  in. thick  $\times$  4 ins. wide, .. 6 $\frac{1}{2}$ d. " "
- .. B1911. Patent Indestructible Strips, asbestos backing,  $\frac{1}{2}$  in. thick  $\times$  4 ins. wide, .. 1/0 $\frac{1}{2}$  " "
- .. B1912. Silicate Cotton, in sheets on canvas, 1 in. thick, .. 7d. " "
- .. B1899. Loose Silicate Cotton or Slag Wool (in  $\frac{1}{2}$  cwt. charged bags), .. 8/6 per cwt.

**Asbestos Products**

- No. B1433. Asbestos Plaited Packing, round or square, from  $\frac{1}{4}$  in. upwards, .. 2/- per lb.
- .. B1458. Asbestos Millboard, from  $\frac{1}{8}$  to 1 in., cut to size, 1/9 per lb.: small quantities, 9d. per lb., or 56/- per cwt.
- .. B1459. Asbestos Boiler Covering (special directions for use), .. 24/- "
- .. B2452. Asbestos Oil Paint (B). Recommended for places exposed to steam and acid gases, and general painting, white, light, or dark stone, drab, buff, fawn, leather color, light blue, silver grey, terra cotta, .. 36/- "
- Other shades quoted for upon application. Any required shade or tint can be matched.
- (One cwt. will cover about 500 sq. yds. one coat).
- .. B2453. Asbestos Special Paint (S), for machinery, tunnels, boilers, kiers, steam chests, ageing machines, &c., to stand great heat and acids. 1 cwt. will cover from 500 to 700 sq. yds. Any color (except vermilion), 7/- per gallon of 14 lbs., 50/- "
- Signal Red (1 cwt. will cover from 500 to 700 sq. yds.), 60/- "

**No. B2455. Graphite Paint****FOR STEEL AND IRON CONSTRUCTIVE WORK.**

Comparison of cost and surface spreading power on smooth iron-work free from rust:—One gallon of pure (natural color) graphite paint will cover 160 square yards, at a cost of  $\frac{1}{2}$ d. per square yard: weight per gallon, 12 to 13 lbs. One gallon of red or white lead paint will cover 80 square yards at a cost of  $\frac{1}{2}$ d. per square yard: weight per gallon, 24 to 30 lbs. One gallon of best quality oxide of iron paint will cover 100 square yards at a cost of  $\frac{1}{4}$ d. per square yard: weight per gallon, 18 to 20 lbs.

If the surface of the iron is pitted or corroded, about 25 per cent. must be deducted from the above figures.

Pure Graphite (natural color) and black, grey, bronze green, dark brown, dark red, .. 7/6 per gallon.

(Pure graphite and black are acid, alkali, and heat resisting.)

Large quantities are subject to special discounts.

Sold in drums containing one gallon and upwards; casks containing 40 gallons (casks free).

**Solignum**

No. B2506. A Stain and Preservative for Wood, also a Preservative for Stone or Brickwork.

	1 gallon.	5 gallon.	10 gallon drums.
Prices, Brown, in three shades,	3/6	10/6	19/6 each.
.. Green, .. .. .	4/6	15/-	30/- "

Drums free and not returnable.

In Barrels (free) of 42 gallons, 1/9 per gallon.

No. B2485. Solignum Varnish—

In 1 gallon Drums, .. Outdoor, 16/-: Indoor, 20/- per gallon.

In 5 and 16 gallon Drums, .. 10/-: .. 15/- "

Shades on application.

**No. B2486. Sideroleum**

A perfect Wood Preservative. Nut Brown in color.

Penetrates the wood deeply without pressure, is applied cold with a brush, drives out the sap, and renders the wood absolutely rot-proof.

Used by estate agents, builders, dock boards and collieries for fencing, sheds, beams, joists, piles, wharves, &c., &c., and by the leading makers of cooling towers in England.

Price, in 40 gallon casks (free and not returnable), 1/6 per gallon.

.. .. 10 .. drums ..	1/10 $\frac{1}{2}$ "
.. .. 1 .. cans ..	2/8 "

**No. B1105. Superior Preserved Paste**

For the use of bookbinders, newspaper publishers, paperhangers, manufacturers of paper bags, trunks, &c., and for general labelling purposes. It will keep good in any climate.

We claim that it is a decided improvement upon the common manufactured article, being fine, smooth and uniform in quality, and, as it is well preserved, all waste from souring or fermenting is avoided.

The Paste is of heavy body and will bear largely reducing with hot or cold water, and being then quite ready for use a considerable saving in time and labour is effected.

Put up in .. 2 cwt. 1 cwt. 56 lb. 28 lb. casks free.	
Prices, .. 9/6 5/6 3/9 2/9 each.	

Those who study convenience and economy will find it well worth their while to give it a trial.

**No. B3681.****The Sanitary Disinfectant Paint Remover Paste**

Is invaluable for removing old hard paint (any thickness), enamel, varnish, and wall paper from wood, stone, or iron. It is a disinfectant, and where used effectually destroys all insects or disease germs, and will not injure the surface of the paint or varnish afterwards applied, and is pronounced by first-class firms to be the cheapest and most effectual in the market. It is much liked for taking paint from baths for repainting, and is invaluable as applied to old wood carvings and all fine-art work. Will thoroughly clean and renew marble, &c.

Packed in .. 2 4 7 14 lb. tins (tins free).	
Prices, .. 10 $\frac{1}{2}$ d. 1/8 2/6 4/- each.	

Sample tins, post free, 6d. each.

LIQUID PAINT REMOVER,  $\frac{1}{2}$  gall., 4/9; 1 gall., 8/6 (tins free).

# Preparations for Damp Walls

## No. B 2391. Damp Wall Sanitary Enamel

*For Decorative Purposes.*

This material is specially recommended to resist effectually the damp in new plaster work, thus admitting of prompt papering of walls without risk of injury to the papers, the Transparent Enamel being specially recommended for this purpose.

It has three times the covering power of ordinary paint, no sizing required, absolutely non-porous, dries quickly, leaving a surface resembling porcelain.

The Transparent is also specially useful where a colored preparation is not desirable.

Adaptable for all work, whether brick, stone, cement, or plaster, and particularly valuable for new work.

One gallon will cover about 100 square yards.

**STOCK SHADES.** White, Transparent, Light Stone, Dark Stone, Red, Blue, Green. Other shades made to order.

Price, .. 8/- per gallon, in free cans.

Small quantities extra.

A free sample slab illustrating its use sent upon application.

## No. B 404. Damp Proof Spirit Varnish

This should be used as a substitute for damp solution on inside walls before papering or painting, when immediate completion of the work is required. The Varnish is applied in the usual manner, and dries hard within one hour. It must in all cases be applied to the bare walls, and all paint or paper must be removed before it is used. One coat is sufficient.

Price, 8/6 per gallon, in charged packages.

Apply with a flat varnish brush.

Brushes for above—2 ins., 1/6; 3 ins., 2/6

## No. B 169. Solution for Damp Walls

*For Preserving Stone and Brickwork, Priming Walls, and excluding Damp from Interior Walls of Houses.*

This Solution soaks into the wall, and effectually fills up all pores through which damp can penetrate, leaving a good surface on which either paint or paper can be safely applied. It can easily be used, both internally and externally, with but little discoloration of the wall, and this soon disappears. It is also an excellent preservative for stone or brickwork. In cases of ground damp, caused by bad foundation to the walls, application of the Solution is sure to prove beneficial, even if it does not effect a permanent cure. Walls of unpainted brick, stone, or compo, affected by damp, should receive a coat of Solution in preference to ordinary priming. It has the same effect in preventing absorption in the succeeding coat of paint.

### DIRECTIONS FOR USE.

The Solution to be applied in dry weather, with an ordinary paint brush, and to be well rubbed into the work. Two coats are necessary, the second coat to be applied when the first is hard. An interval of twenty-four hours is usually sufficient.

One gallon covers about 20 square yards.

Price, .. .. 7/6 per gallon.

Packages charged and returnable.

Wire Brushes for cleaning outside walls, 4/- each.

Surface Brushes for applying Solution, 4/6 and 3/- each.

**SZERELMEY STONE LIQUID and PRODUCTS** Stocked. *Prices and full particulars on application.*

**LAMINATED LEAD** for damp walls, sheets 36 x 22 ins., 6d. per sheet, or 4/6 per box containing 10 sheets.

**LEAD FOIL** for damp walls, in boxes containing 36 sheets, 22 x 18 ins., 3/6 per box.

## Waterproof Paper.

**PITCH PAPER,** in 12-yard rolls, 22 ins. wide, 4d.; in quantities of not less than 60 pieces, 2½d. per piece.

**OIL WATERPROOF,** „ 12 „ „ 22 „ 9d.; „ „ „ 60 „ 8d. „

**BROWN PAPER,** „ 12 „ „ 22 „ 4d.; „ „ „ 60 „ 3½d. „

**WATERPROOF PAPER,** Canvas Backed, 54 ins. wide, 3d. per yard; 10/6 per 50-yard roll.

**FILLING VARNISH**

FOR POROUS PLASTER WALLS AND CEILINGS. DRIES IN TEN MINUTES.

Prevents the unequal absorption of the paint on plaster, or on walls which have been stopped. It assists to prevent damp or stains showing through the work on ceilings. Old work which has been clear-coled or sized, should invariably receive a coat of Filling Varnish, or the surface may dry out unevenly. One gallon covers from 60 to 100 square yards.

Price, 4/- per gallon. 1/6 per quart (can included).

**"VITROLITE"**

Supersedes White Lead Paint for the protection of conservatories, greenhouses and all horticultural buildings, and also for all kinds of decorative work.

Made in 2 shades, White and Light Stone. Price, 8/6 per gallon.

Prices of Packages: 1/2 gall., 1/6; 1 gall., 2/-; 2 galls., 2/6; 3 galls. and upwards, 1/- per gall. (returnable).

Also sold in non-returnable cans containing 1 quart, 2/6; 1/2 gall., 4/9; 1 gall., 9/- each. Also in 6d. and 1/- tins (tins free).

**"PLASTINE" The Imperishable Putty**

Specially manufactured to withstand exposure to heat, cold and moisture on horticultural buildings, glass roofs of every description, wooden or iron sashbars. It will not harden, flake, shrink, decay or absorb moisture.

Price, .. .. 16/- per cwt.

Prices of Packages: 1/2 cwt., 1/6; 1/4 cwt., 2/6; 1 cwt., 4/6 (returnable).

Also sold in non-returnable tins containing 7 lbs. net, 1/3; 14 lbs. net, 2/6 each.

**"COVERINE"**

One coat undercoating, for use with enamels as a means for securing a perfect surface on which to apply them.

Price, .. .. 48/- per cwt. in 7 and 14 lb. free tins.

**PAINTERS' SOAPS****"THREE POPLARS" BRAND**

An extra strong sugar soap for painters and decorators.

Price, 3 1/2d. per packet or 24 6 per cwt.

**"OTIUM"**

For removing all dirt and grease from paint, enamel, and varnish work, plainwood wainscoting, stairways, &c. Price, 2d. per packet.

1 9 per doz. packets.

**No. B3681 A. "JELLO"**

A Jelly Soap for Washing down and Cleansing Enamel, Varnish, Paintwork, &c.



"Jello" will not injure the surface of the most delicate enamel or varnish. For all wall tiling, leaded glass and enamel work it imparts a brilliance which cannot be obtained by the use of ordinary soap and water.

Price, in 6d., 1/- and 2/6 tins.

Or in 28-lb., 56-lb. and 1-cwt. kegs.

Price, per cwt., on application.



# **“Lightning” Lime and Color Washer**

**Each Machine is an efficient Fire Engine. Always on hand.**



No. 6. A handy and compact Machine, supplied with 6-gallon removable pail, fitted with 5-ft. pole and single spraying nozzle, and 10 feet of special armored hose. The platform folds up against Machine. Gauge, **7/6** extra, if required.

Price, .. .. . **£6 15 0**

No. 6A. Specially designed to meet the demand for a cheap and efficient Machine. Fitted with strong wooden base and a detachable tank of 5 gallons capacity. It can easily be lifted about complete by the tank handle. 8-ft. armored delivery hose, single spraying nozzle, and 5-ft. pole, as illustrated.

Price, .. .. . **£5 5 0**

No. 7. Small pattern, to be used with an ordinary pail. Farmers and others will find this a useful and strong Machine at a very low price.

Price, .. .. . **£3 15 0**

## **IMPROVED LIMEWASH**

Much superior to ordinary Limewash slaked with water. Quickly mixed. Leaves a good surface.

There has been a growing demand of late years for distemper, or cold-water paints as they are termed, for use in works, factories, and other places. Owing to the expense of these, many are deterred from using the various makes on the market.

We have brought out a cheap form of limewash which can be used in our Lime and Color Washers, and which, while having the main advantages of the more expensive distempers, can be applied at less than half the cost.

The material is in the form of a powder ready for mixing with water, and is supplied in barrels containing 1 or 3 cwts.

Price, **13/8** per cwt., Carriage Paid (in England and Wales).

If in lots of 3 cwts. at a time, **12/8** per cwt. Supplied in Colors if desired, **3/-** per cwt. extra.

**DIRECTIONS FOR USE.** Mix in cold water to a stiff paste, using about one measure of cold water to three of the dry powder; then thin with cold water to suit the surface intended for, and it is ready for immediate use.

## **“YEMART” CEILING WHITE**

A ready prepared Whitewash. No trouble, no waste; thin down and it is ready for use.

Packed in Free Packages, Casks, 1½ cwts., .. .. **8/-** per cwt.

“ “ “ Lever Tins, 28 lbs., .. .. **9/6** “

“ “ “ “ 7 and 14 lbs., .. **10/6** “

**CELIN-KOTO and FILICOL** -Stocked and sold at Manufacturers' Prices.

# Glues, Chemicals, Soaps, &c.

## GLUES

Best Scotch, a pure Hide Glue, extra strong, in 1-cwt. bags, ... ..	54/-	per cwt.
Scotch No. 2, a very pale Hide Glue, in 1 cwt. bags, ... ..	40/-	"
" " 3, good and serviceable Glue, 1 " ... ..	32/-	"
Town Glue, Finest, ... .. 1 " ... ..	40/-	"
French Medal, ... .. 1 " ... ..	36/-	"
" Unstamped, ... .. 1 " ... ..	32/-	"
Marine A, ... ..	24/-	"
" B, ... ..	18/-	"
Concentrated Size or Glue Powder, 56-lb. 1-lb. ½-lb. bags, ... ..	52/- 56/- 57/-	per cwt.
"Sun Brand," A, ... ..	43/-	47/- 48/-
" B, ... ..		

Not less than 1 cwt. supplied at these prices.

Jelly Size, in firkins, XD, 2/- : XXX, 2/6; Patent, 4/6 each.

## SOAPS, &c.

Carbolic Soap, in bars, ... .. in 1 cwt. boxes, ... ..	22/-	per cwt.
Household Yellow Soap, in bars, ... .. in 1 " ... ..	24/-	"
Soft Soap, ... .. in 1 cwt. free tubs, ... ..	23/6	"
" ... .. in ½ " ... ..	25/-	"
" ... .. in 7-lb. free tins, ... ..	1/9	each.
Jelliso, for decorators (see page 276), ... ..		
Wylie's Sugar Soap (see page 276), ... ..		
Otium, Dry " (see page 276), ... ..		
Beeswax, Genuine, ... ..	2/6	per lb.
" Imitation, ... ..	9d.	"
Paraffin Wax, ... ..	6d.	"
Black Lead, in powder, ... .. 4d. per lb. or ... ..	26/-	per cwt.
Carr's Plumbers' Bindfast Black, ... .. 1 lb., ... ..	1/-	each.
French Chalk, ... ..	3d.	per lb.
Patent Filling, for coachbuilders' and painters' use, ... ..	20/-	per cwt.
Pumice Stone, ... ..	2½d.	per lb.
" specially picked for coachbuilders' use, ... ..	6d.	"
Resin, ... ..		
Shellac, Button, ... ..		
" Orange, ... ..		
" White, ... ..		
Soldering Fluid, in bottles, ... .. 6d. and ... ..	1/-	each.
" Paste, in tins, ... .. 6d. ... ..	1/-	"
Wood Block Floor Mastic, ½ cwt., 7/6; 1 cwt., 6/6; ... ..		
2 cwt., ... ..	6/-	"
Charcoal, for painters' use, ... .. in 56 lb. bags, ... ..	7/6	per cwt.
Filter Charcoal, Fine, Medium, and ... ..		
Coarse, ... .. in 56 lb. bags, ... ..	28/-	"

## GLASS PAPER, EMERY CLOTH, &c.

Emery Cloth, ... ..	24/-	per ream.
" Powder, Genuine, ... .. in 7-lb. parcels, ... ..	26/-	per cwt.
Glass Cloth, ... ..	18/-	per ream.
Oakey's Genuine Emery Cloth, ... ..	26/-	"
" Powder, ... ..	28/-	per cwt.
Oakey's Glass Cloth, 11½ x 8½ ins., ... ..	19/-	per ream.
" White Cabinet Glass Paper, 12 x 10 ins., ... ..	14/-	"
Y. & M.'s Glass Paper, ... ..	12/6	"
Engineers' Blue Twill Emery Cloth, ... ..	42/-	"

## DISINFECTANTS

Young & Marten's Sanitary Fluid, 1, 2, 5 and 10 gall. drums or in 40-gall. barrels, ... ..	2/6	per gall.
Disinfecting Powder, ... .. in 1-cwt. bags, ... ..	9/-	per cwt.
Disinfecting Liquid Soap, ... ..	3/-	per gall.
Chloride of Lime, 1-cwt. casks, 15/-; 5 to 6 cwt. casks, ... ..	13/6	per cwt.
Sulphur Dioxide, ... .. in metal tubes, 1/6 each, or 15/- per doz. ... ..		
" Candles, ... .. 6d. ... ..	4/6	"

## CHEMICALS, &c.

Acid, Fluoric, ... ..	1/-	per lb.
" Hydrochloric, 3d. per lb., or in carboys of about 120 lbs., ... ..	18/6	per cwt.
" Muriatic, or Spirits of Salts, 2d. per lb., or in carboys of about 180 lbs., ... ..	8/6	"
" Nitric, 5d. per lb., or in carboys of about 140 lbs., ... ..	4d.	per lb.
" Pyrogalllic, ... ..	10½d.	per oz.
" Sulphuric, 2d. per lb., or in carboys of about 180 lbs., ... ..	8/6	per cwt.
Alum, Powdered or Lump, 2d. per lb., or in 1-cwt. casks, ... ..	12/-	"
American Potash, ... ..	5d.	per lb.
Borax, ... .. 3d. per lb., or in 1-cwt. casks, ... ..	24/-	per cwt.
Caustic Soda, in 7-lb. kegs, 3d. per lb., or in 1-cwt. kegs, ... ..	22/-	"
Chloride of Lime, ... ..	15/-	"
Copperas, Green, ... .. 1d. per lb., or in 1 cwt. kegs, ... ..	6/-	"
" White, ... .. 2d. " " 1 " ... ..	16/-	"
Dextrine, ... ..	4d.	per lb.
Gum, Arabic, ... .. 1/- per lb., or 7 lbs., ... ..	9d.	"
" Benzoin, ... .. 4½d. per oz., or 7 " ... ..	4/-	"
Liquid Ammonia, 880, ... .. per Winchester quart, ... ..	7d.	"
Potash, Bichromate, ... .. 8d. per lb., or in 1-cwt. casks, ... ..	5d.	"
Silicate of Soda, ... ..	15/-	per cwt.
Soda Crystals, ... .. in 1-cwt. bags, ... ..	6/6	"
Sulphur Roll, ... .. 2d. per lb., or in 1-cwt. casks, ... ..	14/6	"
" Flour, ... .. 3d. " " 1-cwt. bags, ... ..	20/-	"
Other Chemicals quoted for upon application.		
Quantities specially quoted for.		

## GREASES, &c.

Petroleum Jelly, ... ..		
Stauffer's Lubricant, ... .. 7 lbs., 5/6 per tin; 14 lbs., ... ..	10/-	per tin.
Wheen's Axle Grease, ... .. 6d. and 1/-, and 5/- tins or ... ..	10/-	kegs.
Motor Grease, ... ..	34/-	per cwt.
Cart Grease, 7 lbs., 1/-; 14 lbs., 1/9; 28 lbs., 3/3; 56 lbs., 6/-; and 1 cwt., 12/- Free packages.		
Russian Tallow, ... ..		per cwt.
Australian Tallow, ... ..		"

## OILS

Axle Oil.	Castor Oil.	Gen. Lard Oil.
Bench Oil.	Colza Oil.	Heavy Machinery Oil.
Benzoline.	Creosote Oil.	Light Machinery Oil.
Cycle Lamp Oil.	Cylinder Oil.	Methylated Spirit.
Cycle Lubricating Oil.	Read Oil.	Neatsfoot Oil.
Black Oil.	Gas Engine Oil.	

Prices quoted upon application.



# Patent Portable Oil Blast Furnace

WITH ADDITIONAL IMPROVEMENTS.

Patented in the United States, Canada, Belgium, France, Germany, the Colonies, and the British Isles.

These Furnaces, of which we show four drawings, are fitted with movable tops, so that by taking off cover on Pipe Bending Furnace (Fig. A), it is suitable for heating pipes for bending purposes, or for heating copper bits, plumbing irons, branding irons, &c.; and placing on loose top, it is immediately converted into machine for melting lead, tin, solder, zinc, and other metals (Fig. B).




Fig. A No. B1469.

The SPECIAL ADVANTAGES are: It is portable, it can be carried to any place where heat is required, and at once got to work. Each machine is fitted with valve to regulate flame, so that a lower heat may be obtained, and metals or pipes can be kept at any desired temperature for any length of time.

Specially suitable for heating pipes for bending purposes and melting metals.

Always ready for use.

Perfectly safe and very powerful.

Requires little or no attention.




Fig. B.—No. B1480.

Burns common paraffin oil, and will melt 1 cwt. of lead with only one burner.




Fig. A No. B998.




Fig. B. No. B998.

Size Nos., ... ..						1	2	3	4	5	6
Melts Solder, { ... .. weight						10	16	28	56	112	224 lbs.
Heats Iron Pipes ready for bending, ... .. in						5	6	8	11	15	25 minutes.
Nos. B1469 or B998. Complete, with Metal Pot, Pipe-bending Cover and Loose Top, ... ..						1	1½	2	2½	3	4 ins. diam.
No. B1469 A. Metal Pots only, ... ..						73/6	90/-	100/-	140/-	190/-	246/- each.
No. B1469 B. Pipe-bending Cover only, ... ..						2/-	2/6	3/-	4/-	4/9	5/3 "
No. B1469 B. Pipe-bending Cover only, ... ..						7/3	9/3	9/9	10/6	11/-	12/- "


We accept no responsibility after delivery. All above Furnaces are in proper working order when they leave the works. No guarantee is given or implied. All Furnaces or Fittings for repairs must be sent in carriage paid. A number of the Furnace will be found stamped on the dial plate No. 2, and in any correspondence referring to the Machine this number must be quoted.

When ordering please quote Number of Furnace.


# LAMPS

## No. B2648. THE "SWEDISH" BLOW LAMPS

Burns Benzoline.



No. 5 Design.



No. 3 Design.

The "Swedish" Blow Lamps are well known throughout the trade, having been in use now for more than fifteen years. They hold  $\frac{3}{4}$ -pint of benzoline, and burn for  $1\frac{1}{2}$  hours.

The Lamps are without any complicated burners and without pumps. Every part can be taken out and cleaned.

No. 5 has Improved Handle, making it very convenient and easy to hold. The flame tube is horizontal.

No. 3 is the original pattern, with Inclined Burner.

No. 4 is the same as No. 3, but with Vertical Burner.

Price, ... 13/- each.

(Including box of Reserve Parts.)

## No. B2095. THE "VESUVIUS"

Burns Paraffin Oil.


Price, ... 17/- each.

Reserve Parts,  $\frac{2}{3}$  per set.



## No. B999A. BURNING-OFF LAMPS

HURRIDDGES' PATENT.



Burns Benzoline.

Price, ... 18/9 each.


## GASFITTERS' BLOW PIPES

No. B0. For Gasfitters' use, 2/6 each.


No. B1. " " " 4/3 "

No. B2. " " " 6/- "

No. B3. For Plumbers' use, 8/3 "



## The "Reliance" Paint Mills




No. B2314.

Stippling Brushes.



Height of Mill,	Best make.
Inside diameter of	
Capacity of Hoppe	
Diameter of Grinding	
Weight of Mill, with Handle,	
" " with Fly-wheel,	
" " with Pulley,	
Work, per hour,	
" Reliance," No. B2312. With Handle,	
" " No. B2313. " Hand Fly-wheel,	
" " No. B2314. " Pulley for Power,	

are the cheapest in the  
re of superior quality, have  
inding cone, white enamelled  
nned green outside, finished  
Each packed in a case,




No. B2312.

1	2	3	4	5	
12 $\frac{1}{2}$	15	17	19	24	inches.
6	7 $\frac{1}{2}$	8 $\frac{1}{2}$	9	11 $\frac{1}{2}$	"
2	4 $\frac{1}{2}$	6 $\frac{1}{2}$	9	13 $\frac{1}{2}$	pints.
4 $\frac{1}{2}$	5 $\frac{1}{2}$	6 $\frac{1}{2}$	7 $\frac{1}{2}$	10	inches.
16	29 $\frac{1}{2}$	41	52	—	lbs.
—	50 $\frac{1}{2}$	68	80 $\frac{1}{2}$	159	"
—	—	49	60	141	"
7	12	18	24	45	"
23/-	32/3	39/9	51/9	—	each.
—	43/6	47/6	63/3	141/-	"
—	—	57/6	78/3	146/6	"

# Burning-off Lamps, Furnaces, &c.

We accept no responsibility after delivery. All Lamps are in proper working order when they leave the Works.  
No guarantee is given or implied. Lamps repaired at short notice.

## No. B3675. The "Caledonian" Paint Remover and Soldering Lamp




The simplest Lamp on the market.  
Price, .. .. 13/- each.  
Pure benzoline only to be used.

## The "London" Furnace

Burns Paraffin.

Specially constructed for Plumbers, Builders, Engineers, Hot Water Fitters, Lead Burners, Electricians, Water, Gas, Railway, Telephone and Electric Lighting Companies, Shipbuilders, Dockyards, Dentists, &c.




In the "London" Furnace we have combined many of the advantages introduced in our other furnaces, and have been able to make several further improvements. The Furnace is supported by three legs. The lamp itself is of brass. The burner of this lamp is of a new type, and equally as powerful as two ordinary burners. The lamp stove itself can be taken out for cleaning, repairs, &c.

Iron pipes up to 1½ ins. (inner diameter) can be heated for bending in the flame while the lead is being melted in the pot. In the same manner plumbers' soldering irons and copper bits can be introduced by the side doors as shown in the illustration.

CAPACITY.—Tank holds 3½ pints of paraffin. One filling will last 2½ hours. Pot holds 26 lbs. of plumbers' metal.

Every stove is perfect. Flame—atmospheric blue, without smoke or smell. No wick; burns paraffin or petroleum. Every stove is tested under very high pressure.

Price complete, with Melting Pot (without Soldering Irons), 49/6 each.  
.. of Fireclay Cover for Heating Pipes, .. .. 1/3 ..



## No. B2591. Bellamy's Graining Rollers


Used for graining many woods, such as Spanish mahogany, satinwood, maple, oak veins, heart, &c.

Sizes, 3 4 5 6 7 8 ins. wide.  
Prices, 18/- 20/3 24/9 29/3 38/3 47/6 each.

In ordering, state wood required to imitate.

## No. B1108. The "Vulcan" Brazing Lamp

Burns Benzoline.



No. 20 Design.

Nos. 24 and 25 Design.

These Lamps are very powerful and constructed for brazing generally.

No. 20 will do all small ordinary brazing jobs.


.. 24 is intended for large brazing jobs, and is suitable for use in cycle works, shipyards (for taking off propellers, burning off old paint from vessels), &c.

.. 25 is like 24, but larger and still more powerful. It is for brazing jobs on a very large scale.

Nos.,	..	..	..	..	20	24	25
Capacity,	..	..	..	..	2	4	6 pints.
Consumption per hour,	..	..	..	..	1½	4	12 "
Weight, about	..	..	..	..	3½	7½	11½ lbs.
Prices,	..	..	..	..	27/9	68/6	82/3 each.

Prices include box of Reserve Parts.

Made to order with Vertical Burners at the same price.



## No. B1106.

## The "Ætna"

Burns Paraffin Oil, and is not affected by wind or rain.

Price, .. 17/-

Fig. B. No. B998

1	2	3	4
10	16	28	56
5	6	8	11
1	1½	2	2½

Boxes of Reserved Parts, 1/9 per set.

Nos. 1 and 2 Designs.

73/6 90/- 100/- 140/-

## No. B2479. Rubber Covered Seam Rollers

1½ ins. wide,	..	..	..	..	..	..	10½d. each.
2 "	"	"	"	"	"	"	1/- "

# Best Quality Painters' and Decorators' Brushes

WHEN BUYING BRUSHES PURCHASE THE BEST.

Young & Marten's Painting Brushes Every Brush Warranted.

No. B2515.

**Flat Set Dusters.**  
Black Bristles.


Prices, per dozen—

Size Nos., 1 2 3  
Best Make, 18/- 22/6 31/6

Size Nos., ... 4 5  
Best Make, ... 36/- 40/6



**Copper-bound Oval Ground Brushes.**  
Grey middles.



No. B173. Best Make (all Bristle), 63/- 75/- 82/3 per doz.  
No. B830. Hair, cheaper quality, 49/- 54/- 61/- "

**English Sash Tools.**



Size Nos.,	1	2	3	4	5	6	
No. B176.	3/9	4/9	6/-	7/3	10/9	14/-	per doz.
No. B968.	—	4/-	5/-	5/9	8/-	10/3	"

Size Nos.,	7	8	9	10	12	
No. B176.	18/9	23/9	27/-	37/3	49/9	per doz.
No. B968.	13/6	15/9	19/9	26/-	33/9	"

No. B3603. **Sash Cutting Tools in Tin.**




1/2 inch, 13/6; 3/4 inch, 15/9; 1 inch, 20/3 per doz.

No. B2893.


**Badger Softeners.**  
Best quality.

Prices, each.

Width, 2 1/2 ins., 9/-  
" 3 " 11/3  
" 3 1/2 " 13/6  
" 4 " 15/9  
" 4 1/2 " 18/-



No. B86. **Stippling Brushes.**



Best make.

Sizes, ... 4 x 3 6 x 4 7 x 5 8 x 6 ins.  
Prices, ... 6/- 10/- 12/6 15/- each.

No. B2589. **Iron-bound Glue Brushes.**



Size Nos., ... 2 ... 4 6 8 10  
Prices, ... 3/6 6/3 9/6 13/6 19/9 per doz.

No. B172. **Patent Oval Bevelled Varnish Brushes.**  
PURE LILY BRISTLES.



Viewed edgewise.


Warranted to remain sound when used in water, turps, oil, or varnish, and to wear with a true edge.

Size Nos., ... 1 2 3 4 5 6 7 8 9 10  
Young & Marten's Special make, 54/- 61/- 85/9 94/9 per doz.


No. B1955. **The "Sun" Varnish Brushes.**

Black Bristles.

1 in., 9d. 2 1/2 in., 2/3  
1 1/4 " 1/3 3 " 2/8  
2 " 1/9



**Copper-bound Ground Distemper Brushes.**



	8	9	10	11	12 oz.
No. B171					
Best Make (all Bristle)	142/-	155/6	169/-	182/6	196/- p. doz.
Grey Middles.					
No. B969.					
Best Make (all Bristle)	137/6	151/-	164/6	178/-	191/6 "
Black.					
No. B2099.					
Grey Middles (all Hair)	108/3	119/6	130/9	142/-	153/3 "
No. B2510. Mixed quality,			96/6		"

**Copper-bound Washing-down Brushes.**

Prices, per dozen—


No. B180. 6 8 oz.  
All Bristle, 67/9 108/-  
No. B962.  
All Hair, 52/- 85/9



No. B185. **Copper-bound Fibre Distemper, for Lime.**

Best quality.

6 oz. 10/3 doz.  
8 " 12/3 "  
10 " 14/9 "  
12 " 17/- "



No. B2538. **Flat Hog Hair Lining Tools.**



Sizes, 1/2 3/4 1 1 1/2 2 ins. wide.  
Prices, 4/6 5/9 6/9 7/9 10/3 12/6 13/6 18/- per doz.

**Paperhangers' Brushes (Groove Back).**




Prices, per dozen—

No. B2530. Best make.  
7 8 9 10 ins.  
52/- 59/6 64/3 74/-

No. B997. Second quality.  
7 8 9 10 ins.  
40/- 46/- 50/- 58/-

# BRUSHES—Continued.

## Tar Brushes



Size Nos., ...	1	2	3	
No. B2598. Short Handles, ...	10/3	12/6	14/9	per doz.
" B2599. Long ..	13/6	15/9	18/-	"

No. B2541. **Decorators' Hog Hair Tools**  
In Tin and on Polished Handles.




Size Nos., ...	1	2	3	4	5	6	
Round or Flat,	2/3	2/6	2/9	3/-	3/3	3/6	per doz.
Size Nos., ...	7	8	9	10	11	12	
Round or Flat,	4/6	5/-	6/3	7/3	8/-	8/6	per doz.



No. B2920.

## Decorators' Stencil Brushes

Size Nos.,	2	4	6	8	10	12	
Prices,	4/6	7/9	15/9	20/3	31/6	51/9	per doz.



## Decorators' Hog Hair Mottlers

Young & Marten's  
best make.

No. B2575. Thin, ...	Price, per Inch.	5½d.
" B2576. Medium, ...	6½d.	
" B2577. Intermediate, ...	7½d.	
" B2578. Thick, ...	10½d.	
" B2579. Extra Thick, ...	11½d.	



No. B1955A.

## Varnish Brushes

Tin Bound.

Sizes, ...	1	1½	2	2½	3	4 ins.	
White Handles, ...	10d.	1/6	1/11	2/6	2/10	3/6	each.
Polished Black or Cedar,	11d.	1/7	2/-	2/8	3/-	3/8	"



## Steel Wire Brushes

No. S59, 45/- per doz.  
" S53, 39/- ..




For brushing down  
concrete or  
brickwork.

No. B3632.

## Cleaning-down Brushes


With Handles, 27/- doz.

## Hair Broom Heads



Size Nos., ...	0	4	8	
No. B3621. Pure Bristle, ...	32/-	65/-	112/-	per doz.
Size Nos., ...	25	27		
No. B1942. All Hair, ...	60/-	74/-		per doz.

## No. B3625. Drawn Bass Brooms



Knots, ...	10 x 4	13 x 5	16 x 5 ins	
Best Quality, ...	17/-	24/-	30/-	per doz.

## Set Bass Brooms



Size Nos., ...	2	4	6	8	
No. B3624. Genuine Bass, ...	22/-	33/-	44/-	74/-	per doz.
Size Nos., ...	34	36	38		
No. B1944. Stiff Bass, ...	26/-	33/-	39/-		per doz.

## Dandy Brushes



No. B3645, ...	807,	16/6	per doz.
No. B3646, ...	816,	30/-	per doz.



## No. B3667. Wool Mops

Best Yarn, ...	14	18	ozs.	
Best Worsted, ...	16	20	ozs.	
	28/-	34/-		per doz.



No. B3641.

## Painters' Scouring Flannel

24 ins. wide, 32/- the piece.  
Flannel Squares, 6/9 doz.  
Scouring Cloths, 3/9 ..

Leading lines in Hamilton's and Kent's Brushes always stocked.

## Brushes and Oil Cabinets


No. B 2560.

### Gilders' Domed Camel Hair Dabbers (in Quills)




Size Nos., ...	0	1	2	3	4
Finest Quality, ...	3/6	4/3	6/9	12 -	16 6 per doz.
Size Nos., ...	5	6	7	8	
Finest Quality, ...	20.3	24.9	30.6	40.6	per doz.

### Decorators' Pencils (in Quills)



No. B 2864. Brown Sable Pencils								
Sizes—	Crow	Duck	Goose	L. Goose	No. 1 Swan	No. 2 Swan	No. 3 Swan	
Lark	2/3	3 -	4 6	9/-	13 6	22 6	27 -	33 9 per doz.
No. B 2871. Red Sable Pencils								
3 -	3 6	6 9	13.6	18 -	30 6	40 6	54 -	..
No. B 2885. Ox-Hair Pencils								
1/3	1/6	2 -	3/6	4/6				..


### Decorators' Lining Pencils (in Quills)



No. B 2868. Brown Sable Liners								
Sizes—	Crow	Duck	Goose	L. Goose	No. 1 Swan	No. 2 Swan	No. 3 Swan	
Lark	2/3	3/-	5/9	12/6	18 -	24/9	31/6	40/6 per doz.
No. B 2887. Ox-Hair Liners								
1/3	1/6	2/-	3/6	6/9	9/-	9.9	10/3	..

Cheaper Qualities MADE TO ORDER ONLY.

### Decorators' Writing Pencils (in Short Black Polished Handles and Albata Ferrules)




No. B 2880. Brown Sable Writers						
Size Nos., ...	1	2	3	4	5	6
Finest Quality, ...	5	6 -	8 -	10 -	12 -	16 - per doz.
No. B 2881. Red Sable Writers						
Finest Quality, ...	5 -	7 -	9 -	11 6	14 -	18 - ..

### Ox-Hair Writers (in Tin)



No. B 2890. Finest Ox-Hair Writers.							
Size Nos., ...	6	7	8	9	10	11	12
Prices, ...	4 -	5 -	6 -	7 -	8 -	9 -	10 - per doz.

### Decorators' Writing Pencils (in Quills)



No. B 2866. Brown Sable Writers									
Sizes—	Crow	Duck	S. Goose	Goose	L. Goose	No. 1 Swan	No. 2 Swan	No. 3 Swan	
Lark	2 3	3 -	5 -	10 -	12.6	18 -	24.9	31.6	40.6 per doz.
No. B 2873. Red Sable Writers									
3/6	4/-	6/9		16.6	20.3	32.9	40/6	56/6	..
No. B 2886. Ox-Hair Writers									
9d.	1/3	1/9		2/9	3/6	3/-	6/3	8/-	..

## The New Improved Patent Oil Cabinets

Capacity, ...	50	30	20	12	6 gals.
Sizes, ...	45 x 26 1/2	41 x 22	37 x 18	30 x 16 1/2	21 x 15 ins.
Prices, including packing, ..	66/-	58/6	52/6	44.3	36.-

EXTRAS (if required).

Union for screwing on Nose of Pump, 1/6 each. Patent Flexible Steel Hose, 1/10 1/2 per foot.  
Brass Padlock, 2/3 each. Tapered Union, 2/3 each.

NOTE.—For pumping oil direct from the barrels into the Cabinet, a union and two feet of hose for screwing on to nose of pump is supplied, if required, at 5/3 extra.



OIL CABINET (open).

**NET PRICES.**

# Decorators' Sundries

**NET PRICES.**

## No. B 037. ADJUSTABLE GILDING WHEELS



### Ribbon Gold Leaf and Adjustable Gilding Wheels.

For Railway and Tram Car Builders, Coach Builders, Ship Builders, Sign Writers, Bookbinders, Painters, Decorators, Picture Frame Makers, &c.

The finest 22-carat Gold Leaf is produced in the form of ribbon in lengths of 69 feet, in any width, and wound on bobbins, with a separating layer of transfer paper. By the use of this Gold Leaf 50 per cent. is saved in material and 90 per cent. in time and wages.


Suitable for flat or curved surfaces.

Complete Sets, with Brushes for Mouldings, .. 5/6 each.

### No. B 038. Ribbon Gold Leaf, on Reels.

$\frac{1}{8}$	$\frac{3}{16}$	$\frac{1}{4}$	$\frac{5}{16}$	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	$1\frac{1}{8}$	inches wide.
25	16	12	10	8	7	6	5	4	3	3	reels per box.
22/6	22/6	20/8	20/8	18/9	19/-	18/9	18/9	18/9	17/-	19/-	per box.
1/6	1/6	1/9	2/-	2/5	3/-	3/4	4/-	4/6	5/-	6/6	per single reel.

## No. B 2512. PURE LILY BRISTLE, COPPER-BOUND, CHISEL-EDGED SASH TOOLS



May be put in Varnish, Turpentine, Water, &c., without hurt.

	Nos.,	4	6	8	10	12
Prices, ..	..	7/9	13/6	23/6	46/6	75/9

## No. B 0964. SPECIAL "O.K."

"O. K." Brush after some use. Note the unique working shape.

Front View of same. First Bristle removed, Plate coming out with string.

Handle and Plates, showing ease of removal.

Brush with "O.K." Bridle, unused.

Gives an extra  $\frac{3}{4}$  in. of Bristle.

"O. K." Handle and Centre plates. Both Plates are slid out as wear renders necessary.

Not an "O. K." Handle. Note the wasteful blade. Some blades are longer.

	Sizes, ..	2/0	3/0	4/0	6/0	8/0
Prices, Pure Bristle, ..	..	58/-	69/-	80/-	88/-	96/- per dozen.

### The Removal of the Bridles is simplicity itself.

You wish to remove the top one first, naturally, as the brush wears. The illustration shows how the plate slides out when you have unwrapped the string bridle. **You just cut the string** and the plate slips out: no appliances for removal, no complications. You can draw out the plate on the end of the unwound string, if you care to cut the lowest lap. Could anything be quicker or simpler?

**The bottom plate comes out**, when you need it out, in just the same way. Think what this means—**three-quarters of an inch more available bristle**. However far brushes **without** the "O.K." can be worn, brushes **with** the "O.K." wear for at least another half inch.

The removable "O.K." bottom plate and the blade of the "O.K." handle are no deeper than the immovable blade of the ordinary brush.

## No. B 0965. 4/0 PURE BRISTLE BRUSH

As above, but with Fish-tail Handle.

Prices—No. B 0965, Unbridled, 57/- per dozen; No. B 0965A, Bridled, 62/- per dozen.

# Decorators' Tools

BEST SHEFFIELD MANUFACTURE

## No. B 2620. GLAZIERS' HACKING KNIVES




No. B 2620 Small, 5/9 per doz. No. B 2621. Large, 9/- per doz.

## No. B 2623. GLAZIERS' PUTTY KNIVES



No. B 2623. Plain, 6/3 per doz. No. B 2623A. Notched, 6/9 per doz.

## No. B 2632. PAINTERS' SCRAPERS



Blade 3 ins. wide, 13/6 per doz.  
" 4 " 20/3 "

## No. B 2633. PAPERHANGERS' SCRAPERS



12/- per doz.

## No. B 2622. PLUMBERS' CHIPPING KNIVES

## PLUMBERS' CHIPPING KNIVES



5 1/2 ins., 15/9 per doz.

## No. B 2629. GILDERS' KNIVES



Balance Ebony Handle. .. 6 ins., 12/- per doz.

## No. B 2627. PAINTERS' PALETTE KNIVES




Sizes, .. 4 6 8 10 12 ins.  
Riveted Handle, 5/9 9/- 13/6 22/6 38/3 per doz.

## No. B 2630. ARTISTS' PALETTE KNIVES



Ebony Handle, 3 ins., 7/6; 4 ins., 8/-; 5 ins., 9/-; 6 ins., 10/9 per doz.



## No. B 3693.


## PAPERHANGERS' ROLLERS

India Rubber covered, 7 ins., 40/6 per doz.  
Flannel covered, " 3 1/2 " 30/-  
" 7 " 28/3 "  
" 3 1/2 " 21/6 "

## No. B 2625. PAINTERS' STOPPING KNIVES




4 ins., .. 9/- per doz. | 5 ins., .. 10/- per doz.



## No. B 2634. PLUMBERS' SHAVE HOOKS

No. B 2634. Heart shape, .. 12/- per doz.  
" B 2635. Bent shank, .. 12/- "  
" B 2636. Triangular, .. 12/- "  
" B 2637. Gauge or Sill Pipe, .. 12/- "  
" B 2638. Spoon, .. 12/- "


## No. B 2640. PLUMBERS' DRAW KNIVES




No. B 2640. 10/3 per doz.

No. B 2639. Clasp Handle, small, 15/9; large, 30/- per doz.

## No. B 2531. PAPERHANGERS' SCISSORS




9 ins., 30/-; 10 ins., 38/-; 11 ins., 50/-; 12 ins., 64/- per doz.



## No. B 2612. PATENT STRAINERS

No. 1, 5 ins. diam. gauze, 1/9 each.  
" 2, 6 " " 2/3 "  
" 3, 6 1/2 " " 2/9 "  
Gauges for above  
4 1/2 d., 6 d. and 9 d. each.



## No. B 2586. STEEL GRAINING COMBS

Sets of 12 Assorted Combs, 1 to 1 ins., in paper, .. 2/6 per set.  
" " " " in case, .. 3/- "  
Single Combs, 2 1/2 d. per inch.

## No. B 228. STRONG GALVANIZED IRON PAINT KETTLES

5 ins. diam., 4/6; 6 ins., 6/-; 7 ins., 7/6; 8 ins., 10/6 per doz.

## No. B 2614. GLAZIERS' T SQUARES

Best Selected Wood and accurate.



Sizes, .. 24 30 36 42 48 ins.  
Prices, .. 2/6 3/- 4/- 5/6 6/9 each.

Brass Bound Stocks, 1/3 each extra.  
If Government stamped, 9d. each extra (to order only).

## No. B 2613. GLAZIERS' CUTTING LATHS

Finest Selected Wood and guaranteed accurate.



Sizes, .. 24 30 36 42 48 54 60 72 ins.  
Prices, .. 1/3 1/6 2/- 2/6 3/- 3/6 4/- 7/- each.  
If Government stamped, 9d. each extra (to order only).



## Decorators' Sundries

### No. B 1708. SPONGES

Strong, for Painters' Use.

Best, 9/- per lb.; 2nds, 6/- per lb.; Coarse, 4/- per lb.; 1st. Coarse, 2/6 per lb.  
Turkish, Honeycomb, and Velvets stocked.

### No. B 2590. PATENT OAK GRAIN FINISHERS



Price, . . . . . 3/9 each.

For finishing the lines made by the Oak Combing Roller, so as to carry them close to the edge of a panel. The tool consists of a small brass pinion with ribs of irregular lengths and a rubber roller in contact with it, both turning on pins attached to the handle. Color is spread on the rubber roller and the brass pinion rolled across the end of the panel on which it prints the grain.

### STENCIL PLATES

For marking Ladders, Steps, Packing Cases, &c.

**Alphabets in Zinc (A to Z inclusive).**

Sizes,  $\frac{1}{8}$  1 1 $\frac{1}{2}$  2 2 $\frac{1}{2}$  3 3 $\frac{1}{2}$  4 5 6 ins. high.  
Prices, 2 3 2 3 2 3 2 10 3 4 4 - 4 6 5 6 6 9 7/- 9/- 12/- 13/- per set.

**Figures in Zinc (0 to 9 inclusive).**

Sizes,  $\frac{1}{8}$  1 1 $\frac{1}{2}$  2 2 $\frac{1}{2}$  3 3 $\frac{1}{2}$  4 5 6 ins. high.  
Prices, . . 9d. 9d. 9d. 1 3 1 6 2 - 2 6 2 9 3 - 4/- 5/- per set.

Interlocking Stencils, in sets, made to form any word, at above prices, N.E.T.

**Stencil Ink**, Black, 9d. and 1 3 per tablet.

Stencil Ink in colors, red or green, obtained to order only.

**Architects' Sketches** for Stencil Decorations planned, drawn, and cut to order.

**Packing Case Stencils** cut at one day's notice.

### No. B 3600. BOXWOOD ROLLERS FOR ANGLES

No. B 3600. Boxwood Rollers  
for angles, 1 $\frac{1}{2}$  ins., 1/3 each.

No. B 3680. Boxwood Rollers  
for seams, 1 $\frac{1}{2}$  ins., 1/3 each.



### No. B 2470. RUBBER COVERED SEAM ROLLERS

Nickel-plated Frames in two pieces.

Polished Handles.

1 $\frac{1}{2}$  ins. wide, . . . 10d. each.

2 " " " " 1 " "



### No. B 2473. LIGNUM VITÆ SEAM ROLLERS



Nickel-plated Frames in one piece. Polished Handles.

No. B 2472. Oval Faced Rollers, 2 ins. wide, . . . 1/6 each.

" B 2473. Flat " " " 2 " " " " 1/6 "


### WIRE BRUSHES



No. B 055. Steel Wire, . . . 2 3 each.



No. B 054. Steel Wire, . . . 2/3 each.



No. B 053.

Bristle and Wire mixed, 2/8 each.



No. B 052. Whalebone and Wire, 1/3 each.



No. B 051. Steel Wire, . . . 1/4 each.


### No. B 2617. COTTON WASTE

In quantities of not less than 50 lbs.

White, 40/- and 44/- per cwt.; Colored, 28/-, 34/- and 40/- per cwt.  
Sponge Cloths, Cotton and Worsted Mops stocked.

### No. B 2952.

### OAK COMBING ROLLERS AND PATENT FEED BRUSHES



The illustration represents a Combing Roller, with the Patent Feed Brush attached by the metal blade fixed to its under side. This blade is so shaped that when pushed between the bars of the roller handle, the brush is firmly held in the required position, one hand only being necessary for the work.

### Combing Rollers Separately

$\frac{1}{8}$  2 3 3 $\frac{1}{2}$  4 $\frac{1}{2}$  ins. 3/9 each.

### Patent Feed Brushes

To fit 2 3 $\frac{1}{2}$  4 $\frac{1}{2}$  in. Rollers. 1/3 2/- 2/6 each.

Measurements are outside the frames.

### No. B 2474. LIGNUM VITÆ ROLLERS FOR ANGLES



Nickel-plated Frames. Polished Handles.

No. B 2474. Cone Faced Rollers, 1 in. wide, . . . 1/6 each.

" B 2475. Flat " " " 1 " " " " 1/6 "


### No. B 2476. PAPERHANGERS' KNIVES

American Manufacture. "Ideal" Casing Knives. Double Arm Brackets. Polished Handles.



With these Knives the paper can be trimmed on the wall while wet.  
1 $\frac{1}{2}$ -in. Serrated Blades, . . . 2 3 each.

### No. B 2477. PAPERHANGERS' KNIVES



Polished Handles, . . . 1/- each.

## Decorators' Stencils



No. B1579.  
Zinc, 1/6 each.  
No. B1580.  
Paper, 9d. each.  
Size, 11 x 2 1/2 ins.



No. B1581.  
Zinc, 1/6 each.  
No. B1582.  
Paper, 9d. each.  
Size, 8 x 4 1/2 ins.



No. B1583.  
Zinc, 1/6 each.  
No. B1585.  
Paper, 9d. each.  
Size, 10 1/2 x 5 1/2 ins.



No. B1652.  
Zinc, 1/6 each.  
No. B1653.  
Paper, 6d. each.  
Size, 16 x 3 1/2 ins.



No. B1710.  
Zinc, 1/6 each.  
No. B1711.  
Paper, 6d. each.  
Size, 13 x 2 1/2 ins.



No. B345. Zinc, 3 ins., 1/6 each.  
No. B353. Paper, 3 " 9d. "



No. B848. Zinc, 4 1/2 ins., 1/6 each.  
No. B849. Paper, 4 1/2 " 9d. "



No. B972. Zinc, 4 1/2 ins., 1/6 each.  
No. B978. Paper, 4 1/2 " 9d. "



No. B984. Zinc, 4 1/2 ins., 1/6 each.  
No. B985. Paper, 4 1/2 " 9d. "



No. B860. Zinc, 4 ins., 1/6 each.  
No. B831. Paper, 4 " 9d. "



No. B987. Zinc, 5 1/2 ins., 1/6 each.  
No. B988. Paper, 5 1/2 " 9d. "



No. B1714.  
Zinc, 10 ins. square, 4/- each.  
No. B1715.  
Paper, 10 ins. square, 2/- each.



No. B946. Zinc, 4 1/2 ins., 1/6 each.  
No. B947. Paper, 4 1/2 " 9d. "



No. B980. Zinc, 4 1/2 ins., 1/6 each.  
No. B961. Paper, 4 1/2 " 9d. "



No. B951. Zinc, 5 ins., 1/6 each.  
No. B953. Paper, 5 " 9d. "



No. B982. Zinc, 5 1/2 ins., 1/6 each.  
No. B983. Paper, 5 1/2 " 9d. "



No. B1575.  
Zinc, 10 1/2 ins. square, 4/- each.  
No. B1576.  
Paper, 10 1/2 ins. square, 2/- each.




No. B1577.  
Zinc, 10 1/2 ins. square, 3/- each.  
No. B1578.  
Paper, 10 1/2 ins. square, 1/6 each.



No. B1586.  
Zinc, 8 1/2 ins. sq., 2/6 each.  
No. B1587.  
Paper, 8 1/2 ins. sq., 1/3 each.

**SPECIAL STENCILS** cut in Zinc, Copper, Steel or Paper at one day's notice.


## Paper-Stucco Ceiling Centre Pieces




No. B2491.  
12 3/4 ins. diameter.  
4 " projection.  
Price, 2 6 each.



No. B2492.  
16 1/2 ins. diameter.  
3 " projection.  
Price, 3 3 each.




No. 2493.  
16 1/2 ins. diameter.  
2 1/2 " projection.  
Price, 3 3 each.




No. B2494.  
18 3/4 ins. diameter.  
2 " projection.  
Price, 4 4 each.

# Paper-Stucco Ceiling Centre Pieces and Overdoors



No. B 2500. 27½ ins. diam. 3½-in. projection.  
Price, 11/3 each.




No. B 2502. 24½ ins. diam. 4-in. projection.  
Price, 6/9 each.



No. B 1612. 37 ins. diam. 5½-in. projection.  
Price, 17/- each.



No. B 1606.  
28½ ins. diam. 3-in. projection.  
Price, 9 9 each.



No. B 1552.  
24½ ins. diam. 3-in. projection.  
Price, 6/6 each.



No. B 2497.  
22 ins. diam. 4½-in. projection.  
Price, 6/6 each.



No. B 2496.  
20½ ins. diam. 2½-in. projection.  
Price, 4 9 each.



No. B 2488.  
11 ins. diam. 2½-in. projection.  
Price, 3 3 each.



No. B 2489.  
12 ins. diam. 3-in. projection.  
Price, 2 4 each.



No. B 2490.  
12 ins. diam. 2½-in. projection.  
Price, 2 4 each.




No. B 1558.  
19 ins. diam. 3-in. projection.  
Price, 4/3 each.




No. B 1704. Overdoor, ... 38 42 45 50 ins.  
11 3 12 - 12/3 13/- each.



No. B 1698. Overdoor, 42 44 48 50 62 75 ins.  
12/3 12/6 13/- 13/3 13/6 14/3 each.



No. B 1694. Overdoor, 42 45 50 55 62 ins.  
15 6 16 - 16/6 17 - 17/9 each.



No. B 1691. Overdoor only, ... 45 53 54 56 ins.  
10/9 12 - 13/- each.  
No. B 1692. Overdoor and Panel complete, — 17/- 17/6 18 - per set.  
Over 56 ins. and up to 39 ins. wide to order only.

# Paper-Stucco Mouldings and Friezes


All the designs on this page have wooden beads top and bottom for fixing.



No. B1615. 1½ ins. wide. Price, 5½d. per foot.



No. B1622. 2 ins. wide. Price, 5½d. per foot.



No. B1631. 2¾ ins. wide. Price 7d. per foot.



No. B2320. 3 ins. wide. Price, 7d. per foot.



No. B1635. 3 ins. wide. Price, 8d. per foot.



No. B1650. 2¾-in. Ceiling by 4½-in. Wall.  
Price, 10½d. per foot.



No. B1652. 5-in. Ceiling by 4-in. Wall.  
Price, 11½d. per foot.



No. B1656. 5½-in. Ceiling by 4½-in. Wall.  
Price, 11½d. per foot.



No. B1658. 4-in. Ceiling by 6-in. Wall.  
Price, 1/1½ per foot.



No. B1660. 6¾-in. Ceiling by 4-in. Wall.  
Price, 1 2½ per foot.



No. B2315. 1½ ins. wide. Price, 5½d. per foot.



No. B1620. 2 ins. wide. Price, 5½d. per foot.



No. B1638. 3¼ ins. wide. Price, 9½d. per foot.



No. B1640. 4½ ins. wide. Price, 11d. per foot.



No. B1639. 4 ins. wide. Price, 9½d. per foot.



No. B1642. 4½ ins. wide. Price, 10½d. per foot.



No. B1645. 5 ins. wide. Price, 11½d. per foot.



No. B1644. 5 ins. wide. Price, 11½d. per foot.

**IR BRICKS; PITCH, TAR;**

No. B2371. 10 ins. wide. Price, 1/5 per foot.

Complete Catalogue and Samples of above sent upon application.


Special Nails for Fixing these Decorations, 6d. per lb.

When ordering quote the number only, do not cut the designs out.

# Fibrous Plaster Trusses

STOCK SIZES.

Packed for Rail in Crates, charged for and returnable.



No. B3753.  
Height, .. 14 ins.  
Width, .. 6½ ..  
Projection, .. 4 ..  
Price, .. 2/- each.



No. B3751.  
Height, .. 6 ins.  
Width, .. 3½ ..  
Projection, .. 2½ ..  
Price, .. 9d. each.



No. B3752.  
Height, .. 13 ins.  
Width, .. 5½ ..  
Projection, .. 3½ ..  
Price, .. 1/10½ each.




No. 3755.  
Height, .. 12½ ins.  
Width, .. 8½ ..  
Projection, .. 3 ..  
Price, .. 2/- each.



No. B3758.  
Height, .. 18 ins.  
Width, .. 9 ..  
Projection, .. 3½ ..  
Price, .. 3/- each.




No. B1730.  
Height, .. 13½ ins.  
Width, .. 6 ..  
Projection, .. 3½ ..  
Price, .. 3/- each.




No. B3982.  
Height, .. 13 ins.  
Width, .. 5 ..  
Projection, .. 5½ ..  
Price, .. 1-10½ each.




No. B1727.  
Height, .. 12 ins.  
Width, .. 4 ..  
Projection, .. 3 ..  
Price, .. 1/10½ each.



Two Sizes.  
Nos., .. B1734. B1735.  
Height, .. 11½ .. 11½ ins.  
Width, .. 9 .. 7½ ..  
Projection, .. 4 .. 4 ..  
Prices, .. 3/- .. 2 9 each.



Three Sizes.  
Nos., .. B1739. B1740. B1741.  
Height, .. 16 .. 16 .. 16 ins.  
Width, .. 7½ .. 12 .. 15½ ..  
Projection, .. 4½ .. 3½ .. 4½ ..  
Prices, .. 3 6 .. 5 .. 6/- each.



Three Sizes.  
Nos., .. B1736. B1737. B1738.  
Height, .. 12½ .. 12½ .. 12½ ins.  
Width, .. 14 .. 11 .. 9 ..  
Projection, .. 6 .. 6 .. 6 ..  
Prices, .. 5/- .. 4/6 .. 4/- each.



No. B1704. Overdoor, .. 38 42 45  
11 3 12 12 3

Stocked and patterns and prices will be forwarded on application.  
made and despatched on short notice.

of Truss and not the cap which projects over face and sides.  
quote number, do not cut out the designs.

## Window Decoration

an inexpensive preparation, especially where it is desirable to obscure unsightly exteriors, such as back premises of an inornate character. It is a thin transparent substance, insoluble in water, and is easily affixed (not transferred) to the glass. It is supplied in sheets of varying size, and is so arranged that a continuous pattern can be affixed on glass of any dimensions. It can be used on any size, shape or style of window, fanlight or panel.

We will forward a Book of Designs with prices upon receipt of enquiry. A charge of 2/- is made when sending the Catalogue, but the amount is credited upon its return here in good condition, post paid.

"Yeardec" Window Transparencies, similar to above but of slightly cheaper cost, full particulars on application.

# **WHARF DEPARTMENT**

## **SECTION**

### **DAMP COURSE**

SLATES, FELT, BITUMEN, AND STONEWARE

### **STONEWARE DRAIN PIPES**

CONNECTIONS, GULLIES, AND INTERCEPTORS

### **LIME**

GREY AND CHALK, LUMP, GROUND AND BLUE LIAS

### **CEMENT**

PORTLAND, KEENE'S, PARIAN, AND ROMAN

### **PLASTER**

COARSE AND FINE, SIRAPITE, RENT LATHS

### **BRICKS**

BUILDING, BLUE STAFFS, RED FACINGS, FIRE, AND GLAZED

### **PAVING**

BLUE STAFFS, STABLE, RED AND BUFF TILES

### **ROOFING**








SLATES, TILES, AND FELT









**SINKS, RIDGE TILES, CHIMNEY POTS, AIR BRICKS; PITCH, TAR;  
FIRECLAY, BRICKS, AND TILES; FURNACE LUMPS AND SHAPES**

# Glazed Stoneware Drain Pipes and Connections

STANDARD LIST PRICES.

No. W 1400.	No. W 1401.	No. W 1402.	No. W 1402A.	No. W 1404.	No. W 1405.	No. W 1404 A.
						

			Sizes,	2 and 3	4	6	9	12 ins. diam.
No. W 1400.	Straight Pipes and Channel Pipes,		.. .. .	1/3	1 6	2 3	4 6	7 6 per yard.
.. W 1401.			.. .. .					
.. W 1402.	Taper Pipes,		.. .. .	—	2 -	3 -	6 -	10 - per 2 feet pipe.
.. W 1402A.			.. .. .					
.. W 1404.	Junctions,		.. .. .	1 8	2 -	3 -	6 -	10 - „ „
.. W 1404A.			.. .. .					
.. W 1405.			.. .. .					

No. W 1408.	No. W 1408A.	No. W 1409.	No. W 1411.	No. W 1411A.	No. W 4023.
					

										Sizes,	2 and 3	4	6	9	12 ins. diam.	
No. W 1408.	Easy Bends,	..	..	..	..	..	..	..	..	}						
.. W 1408A.	Medium ..	..	..	..	..	..	..	..	..							
.. W 1409.	Sharp ..	..	..	..	..	..	..	..	..		1 3	1 6	2 3	4 6	7 6 each.	
.. W 1411.	Knuckle ..	..	..	..	..	..	..	..	..							
.. W 1411A.	Long Knuckle Bends,	..	..	..	..	..	..	..	..							
											Sizes,	3 to 4	4 to 6			
.. W 4023.	Paper Bend Sharp, Medium, Easy, and Knuckle,	..	..	..	..	..	..	..	..		2 6	3 9	to 9 ins. diam.			
														7 6 each.		

No. W 1416.	No. W 1416B.	No. W 1416C.	No. W 1416E.	No. W 1416F.
				

										Size of Grating,	4	6	9	12	ins.
No. W 1416.	Gulleys, P. )														
.. W 1416B.	.. S. )									3 9	4 7	7 6	13 4	each.	
.. W 1416C.	.. with Back Inlet, )									4 9	5 7	8 6	14/4	..	
.. W 1416E.	.. .. Side .. )														
.. W 1416F.	.. .. R.W. .. )									5 3	6 1	9 -	14 10	..	
Iron Grates, Black, ..										7 1/2 d.	1 -	2 1	4 2	..	
.. .. Galvanized, ..										1/3	2 -	4 2	8 4	..	

Extra Inlet to Gulleys, Horizontal, 1 - each: Vertical (bent), 1 6 each extra.

Drain Pipes and ordinary connections can be supplied in FULL TRUCK LOADS DIRECT FROM WORKS to any railway station at special discounts, quoted upon receipt of specification. To assist the making up of truck orders, we give the approximate number of pieces of each size required for truck loads:

3-inch, 400; 4-inch, 300; 6-inch, 175; 9-inch, 100; 12-inch, 60.


# Glazed Stoneware Drain Connections, Syphons, Interceptors, &c.

STANDARD LIST PRICES.

No. W 1412.



No. W 1633.



No. W 1634.



No. W 1745.



No. W 5214.



	Sizes,	2 and 3	4	6	9 ins. diam.
No. W 1412.	Plain Syphon,	4/2	5/-	7/6	15/- each
„ W 1412A.	Syphon, with Inlet,	5/2	6	8/6	16/- „
„ W 1633.	Interceptor,	—	11/8	15/-	25/- „
„ W 1634.	„	—	11/8	15/-	25/- „
„ W 1745.	„	—	11/8	15/-	25/- „
„ W 5214.	„	—	11/8	15/-	25/- „

No. W 1414.



No. W 1415.



No. W 4025.



No. W 5204.




No. W 5205.




	Sizes,	2 and 3	4	6	9 ins. diam.
No. W 1414.	S Trap,	4/2	5/-	7/6	15/- each.
„ W 1415.	P „	4/2	5/-	7/6	15/- „
„ W 4025.	Oblique Saddle Junction,	—	2/-	3/-	6/- „
„ W 5204.	Double Socket,	1/8	2/-	3/-	6/- „
„ W 5205.	Reducing Collar,	—	2/-	3/-	6/- „

No. W 3970.  
Mud Gulley



Complete with galvanized bucket and grate.  
Top, 12×12 ins. over all.  
4-in. outlet. 18 ins. deep.  
Price, 18/4 each.

No. W 3149.  
Combination Gulley Trap and Channel




4-in. outlet, S or P.  
With galvanized wire cover.  
Price 20/- each.  
Galvanized Grating,  
2/- extra, net.

No. W 3164.  
Deans' Grease Trap




Complete with radiating brick, bucket and grid.  
Prices—6 ins., 14/2; 9 ins., 24/2 each.  
Extra for Galvanized Cast-iron Bucket and Grid, 6 ins., 5/-; 9 ins., 10/-

No. W 5211.  
Couzen's Patent Ball Valve Gulley




9-in. top. 4-in. outlet.  
Price, 60/- each.



No. W 4027.

## SINK BENDS

Sizes,	2 or 3 ins. diam.
No. W 4027	2/1 each.
„ W 4027A,	2/1 „
„ W 1413,	2/1 „




No. W 1413.



# Glazed Stoneware Pipe Connections

## STANDARD LIST.



W 5209.

STREET GULLY.

### STREET GULLEYS

Diam. inside,	9	9	12	12	12	15	15	18	18 ins.
Depth,	24	30	24	30	36	30	36	36	42 "
Prices,	10/-	12/6	15/-	17/6	20/-	23/4	27/6	36/8	42/6 each.

Cast-iron Hinged Gratings for above are priced in the Castings Section of this List.

### INSPECTION PIPES AND TRAPS



W 5206.



W 5203.



W 5202.



W 5207.

No. W 5206.	Socketted Access Pipe,	..	..	..	..	4	6	9 ins.
.. W 5203.	Access Pipe and Cover,	..	..	..	..	4/-	6/-	12/- each.
.. W 5202.	Inspection Bend, Sharp, Medium or Easy, Handed,	..	..	..	..	2/6	3/9	7/6 "
.. W 5207.	Pipe Flap Trap,	..	..	..	..	3/6	5/3	10/6 "
		..	..	..	..	12/6	18/4	27/6 "

### BROWN GLAZED STONEWARE CHANNELS

W 1409½.


W 1408½.



HALF SECTION  
CHANNEL BENDS.

Nos. W 1409½ and W 1408½ Channel Bends,	..	..	..	..	..	2 & 3	4	6	9	12 ins.
(Also supplied in same shapes as Bends shown on previous pages),	..	..	..	..	..	1/3	1/6	2/3	4/6	7/6 each.
No. W 4019. ¾ Section,	..	..	..	..	..	..	3/-	4/6	—	— "

Nos. W 4019 and W 4020.



THREE QUARTER SECTION CHANNEL BENDS.

### WHITE GLAZED STONEWARE CHANNELS

No. W 1400.	Straight Channels,	..	4	6	9 ins.
.. W 1402A.	Taper Channels,	..	—	2/3	— per ft. run.
.. W 1404A.	Oblique Junction,	..	2/1	3/9	— each.
.. W 1408.	Bends for Main Channels ½ Section.				
.. W 1408½.					
.. W 1409½.					
.. W 1411.					
.. W 1411A.	Ditto, ¾	..	5/10	8/4	— "
.. W 4020.	Junction Bend, ¾ Sect.	4/2	5/10	—	..

# ROOFING SLATES, SLATING, AND TILING

We carry large stocks of Roofing Slates, both at our wharves and at North Wales Quarries. As the railway rates vary for different districts, it is impossible to quote general carriage paid prices, but we shall be pleased to quote on receipt of specification.

## PERMANENT BLUE SLATES- ANGERS VEIN

In stock at our Wharf, Millwall.

Sizes, .. .. 24 x 12    22 x 11    20 x 10    18 x 10    18 x 9    16 x 10    16 x 8 inches.

## PORTMADOC AND BANGOR SLATES

In stock at Quarries; also at our Siding, Maryland Point. In all usual sizes.

## DAMP COURSE SLATES

Sizes, .. .. 18 x 9    14    9 x 4½ inches.

## BEST QUALITY PORTMADOC SLATE ROLL AND WINGS

Can be included with Truck Loads of Slates from Quarries, or supplied from stock at our Siding, Maryland Point.

1½ inch Roll,	.. ..	per foot run.	5 inch Wings,	.. ..	per foot run.
1¼ " "	.. ..	" "	6 " "	.. ..	" "
2 " "	.. ..	" "			

We also undertake . . .

## SLATING AND TILING

In any part of the United Kingdom, and will be pleased to quote COMPETITIVE PRICES upon receipt of specification. We have a large staff of skilled and competent workmen at our command, and can ensure promptitude and efficiency in this class of work.

We can also supply from our Stock or in Truck Loads direct from Works:—

BEST ENGLISH PORTLAND CEMENT.

GREY STONE LUMP LIME.

CHALK LIME.

GROUND BLUE LIAS.

KEENE'S CEMENT.

PARIAN CEMENT.

ROMAN CEMENT.

FIRE CLAY.

COARSE WHITE PLASTER.

COARSE PINK PLASTER.

FINE WHITE PLASTER.

COARSE SIRAPITE.

FINISH SIRAPITE.

GRANITE CHIPPINGS.

FLETON BRICKS.

PIT SAND.

Prices quoted upon application, giving particulars of approximate quantities required and destination.

# Ridge Tiles and Finials



**Plain Ridge Tile**  
No. W 1512. 18 ins. long, 6-in. wings, Red or Blue.  
No. W 1512A. For party walls, 18 ins. long, 7-in. wings.



**Roll Ridge Tile**  
No. W 1513. 18 ins. long, 6-in. wings, Red or Blue.  
No. W 1513A. For party walls, 18 ins. long, 7-in. wings.



**Plain Capped Ridge Tile**  
No. W 1571. 18 ins. long, 6-in. wings, Red or Blue.  
No. W 1571A. 18 ins. long, 7-in. wings.



**Half-round Ridge Tile**  
No. W 5250. 12 ins. long, Red.  
No. W 5250A. Half-round "Yorkshire" Ridge Tile, 12 ins. long.

PRICES QUOTED UPON APPLICATION.



No. W 1574. **Ornamental**  
12 ins. long, 6-in. wings, Red.  
Price, 10½d. each.



No. W 4261. **Half Crest**  
12 ins. long, 6-in. wings, Red.  
Price, 9d. each.



No. W 4262. **Ornamental**  
12 ins. long, 6-in. wings, Red.  
Price, 10½d. each.



No. W 4263. **Ornamental**  
12 ins. long, 6-in. wings, Red.  
Price, 10½d. each.



No. W 4267.  
**Red Hip Finial**  
Price, 5/3 each.



No. W 4268.  
**Red Hip Finial**  
Price, 6/- each.



No. W 5230.  
**Red Gable Finial**  
Price, 5/6 each.



No. W 5232.  
**Red Gable Finial**  
Price, 6/- each.



No. W 5231.  
**Red Hip Finial**  
Price, 5/6 each.



No. W 5234  
**Red Griffin Finial (Hip)**  
Price, 4/5 - each.



No. W 4269.  
**Red Octagon Finial**  
Price, 9/- each.



No. W 5233.  
**Red Octagon Finial**  
Price, 8/3 each.



No. W 5235.  
**Red Griffin Finial (Gable)**  
Price, 4/5 - each.

## RED "YORKSHIRE" TILES



No. W 5248. **French Pantile**  
Price, 12/- per 100.



No. W 1510. **Pantile**  
Price, 12/- per 100.



No. W 5249. **Corrugated Tile**  
Price, 12/- per 100.




No. W 5236. **Plain Tiles**  
Price, Holed only, 6/- per 100.

We can supply "Staffordshire," "Reading," "Bridgwater," and other Tiles, of same pattern. Prices on application.

Quotations given for Tiling in town or country.

Prices on this page include delivery within five miles of our wharf; beyond that distance a reasonable charge will be made.

NOTE: We are able to quote specially LOW PRICES for the goods shown above or Full Truck Loads Delivered Free to any Railway Station.



No. W 1419.

## Chimney Pots, Air Bricks, and Tiles

Height.	1 ft.	1 ft. 6 ins.	1 ft. 10 ins.	2 ft.	2 ft. 3 ins.	2 ft. 6 ins.	3 ft.	3 ft. 6 ins.	4 ft.	4 ft. 6 ins.	5 ft.	6 ft.
No. W1419,	1/1½	1/4½	1/7½	1/10½	2/3	3/-	4/6	5/7½	7/1½	8/3	9/4½	12/- each.
„ W1420,	1/4½	1/6	1/9	2/-	2/6	3/3	4/10½	6/-	7/6	8/7½	9/9	12/4½ ..


These are supplied in both Red and Buff Color.



No. W 1420.

### LOUVRE CHIMNEY POTS

Red or Buff.



No. 1426.

Sizes.	Prices.	Prices.
	Red.	Buff.
2 ft. ..	5/3 each.	4/10½ each.
2 ft. 3 ins. ..	5/6 ..	5/1½ ..
2 ft. 6 ins. ..	5/9 ..	5/3 ..
3 ft. ..	6/9 ..	6/3 ..
3 ft. 6 ins. ..	8/3 ..	7/6 ..
4 ft. ..	10/6 ..	9/9 ..
5 ft. ..	12/- ..	11/3 ..


### PEYTON'S PATENT "CHAMPION" CHIMNEY POT

This is designed to prevent the admission of down-draughts, and has been most successful in curing smoky chimneys.

Salt Glazed Stoneware, 4 ft. high.

Red or Buff, Terra Cotta, 4 ft. high.

Prices quoted on application.




No. W 5251.



No. W 1430.

Height, 2 feet.


Red, .. 2/6 each.  
Buff, .. 2/3 ..



No. W 1421.

Height, 1 ft. 8 ins.

Red or Buff, 1/10½ ea.



No. W 1420.

Height, 1 ft. 8 ins.

Red or Buff, 4/6 each.



No. W 1431.

Louvre Top, with Spigot.  
Red, .. 3/4½ each.  
Buff, .. 3/- ..

Louvre Top, without Spigot.  
Red, .. 2/10½ each.  
Buff, .. 2/6 ..




No. W 1432.


Height, 1 ft. 3 ins.

Red, .. 2/9 each.  
Buff, .. 2/6 ..


### EARTHENWARE AIR BRICKS



No. W 5265.



No. W 5264.



No. W 5266.

Sizes,	9×3	9×6	9×9	12×6	12×9 inches.
Prices—Red, Buff. or Salt Glazed,	4/6	9/-	15/9	18/-	48/- per dozen.

### QUARRY AND PAVING TILES

Supplied in Red, Blue or Buff.



No. W 1520.

Sizes, 4×4×½ 6×6×¾ 9×9×1½ ins.  
Prices, .. per 1000.

Prices quoted on application.

Red Yorkshire Pavers, 12×12×1½ ins., .. 30/- per 100.

### GARDEN TILES

No. W 1514.

Fluted Tile



Size, 7×7 inches.

Price, .. per 100.

Prices quoted on application.

No. W 1515.

Cable Tile

9×7 inches.

Blue, .. Price,
























per 100.










Salt Glazed, ..

# Blue Staffordshire Bricks, Fire Bricks, and Tiles

SPECIAL PRICES QUOTED TOP TRUCK LOADS.

No. W 1516.  18/- per 100.	No. W 4694.  18/9 per 100.	No. W 4695.  18/9 per 100.	No. W 4696.  18/9 per 100.	No. W 4697.  18/9 per 100.	No. W 4698.  4d. each.	No. W 4699.  4d. each.
No. W 1517.  18/- per 100.	No. W 1518.  18/- per 100.	No. W 1519.  18/- per 100.	No. W 1585.  18/- per 100.	No. W 4701.  72/- per 1000.	No. W 1586.  9 x 4 1/2 x 2, 15/9 per 100. 10 x 5 x 2, 18/- "	
No. W 4702.  12/- per dozen.	No. W 1535.  3/9 per dozen.	No. W 4703.  7/6 per dozen.	No. W 4704.  Size, 9 x 3 1/2 inches. Centres, .. 2/3 per doz. Ends, .. 9d. each.	No. W 4705.  Size, 12 x 9 x 4 ins. Price, .. 1/- per ft. run.		
No. W 1579.  Half Round Coping. 9 x 3 ins., 18/9 per 100. 9 x 6 " 41/3 "	No. W 4706.  Angle. 9 x 9 ins., 3/9 each.	No. W 4707.  T Junction. 9 x 9 ins., 4/6 each.	No. W 1582.  Ridge Coping. 11 x 7 x 3 ins. 26/3 per 100.	No. W 4700.  Saddle Back Coping. 12 x 12 x 5 ins., .. 1/- each.		

## BEST STOURBRIDGE FIRE BRICKS AND TILES

No. W 5199A. <b>Square Fire Brick</b>  9 x 4 1/2 x 2 1/2 ins., 15/- per 100.	No. W 5199. <b>Large Crown Fire Brick</b>  Size, 9 x 4 1/2 to 3 1/2 x 2 1/2 ins. Price, .. 16/6 per 100.	No. W 5195. <b>Arch Fire Brick</b>  Size, 9 x 4 1/2 x 2 1/2 to 2 ins. Price, .. 15/- per 100.	No. W 1523. <b>Fire Tile</b>  <table border="0"> <tr> <td>7 x 7 x 1 1/2,</td> <td>per doz.</td> <td>12 x 12 x 2,</td> <td>per doz.</td> </tr> <tr> <td>7 x 7 x 2,</td> <td>"</td> <td>14 x 14 x 2,</td> <td>"</td> </tr> <tr> <td>8 x 8 x 1 1/2,</td> <td>"</td> <td>14 x 14 x 2 1/2,</td> <td>"</td> </tr> <tr> <td>8 x 8 x 2,</td> <td>"</td> <td>15 x 15 x 3,</td> <td>"</td> </tr> <tr> <td>9 x 9 x 1 1/2,</td> <td>"</td> <td>18 x 18 x 3,</td> <td>"</td> </tr> <tr> <td>9 x 9 x 2,</td> <td>"</td> <td>20 x 20 x 3,</td> <td>each.</td> </tr> <tr> <td>10 x 10 x 1 1/2,</td> <td>"</td> <td>24 x 24 x 3,</td> <td>"</td> </tr> <tr> <td>10 x 10 x 2,</td> <td>"</td> <td>18 x 9 x 3,</td> <td>"</td> </tr> <tr> <td>12 x 8 x 2,</td> <td>"</td> <td>18 x 9 x 4 1/2,</td> <td>"</td> </tr> <tr> <td>12 x 9 x 2,</td> <td>"</td> <td>24 x 9 x 4 1/2,</td> <td>"</td> </tr> <tr> <td>12 x 10 x 2,</td> <td>"</td> <td>24 x 10 x 5,</td> <td>"</td> </tr> <tr> <td>12 x 12 x 1 1/2,</td> <td>"</td> <td>30 x 10 x 5,</td> <td>"</td> </tr> </table> <p>Prices quoted on application. Other sizes also in stock.</p>	7 x 7 x 1 1/2,	per doz.	12 x 12 x 2,	per doz.	7 x 7 x 2,	"	14 x 14 x 2,	"	8 x 8 x 1 1/2,	"	14 x 14 x 2 1/2,	"	8 x 8 x 2,	"	15 x 15 x 3,	"	9 x 9 x 1 1/2,	"	18 x 18 x 3,	"	9 x 9 x 2,	"	20 x 20 x 3,	each.	10 x 10 x 1 1/2,	"	24 x 24 x 3,	"	10 x 10 x 2,	"	18 x 9 x 3,	"	12 x 8 x 2,	"	18 x 9 x 4 1/2,	"	12 x 9 x 2,	"	24 x 9 x 4 1/2,	"	12 x 10 x 2,	"	24 x 10 x 5,	"	12 x 12 x 1 1/2,	"	30 x 10 x 5,	"
7 x 7 x 1 1/2,	per doz.	12 x 12 x 2,	per doz.																																																
7 x 7 x 2,	"	14 x 14 x 2,	"																																																
8 x 8 x 1 1/2,	"	14 x 14 x 2 1/2,	"																																																
8 x 8 x 2,	"	15 x 15 x 3,	"																																																
9 x 9 x 1 1/2,	"	18 x 18 x 3,	"																																																
9 x 9 x 2,	"	20 x 20 x 3,	each.																																																
10 x 10 x 1 1/2,	"	24 x 24 x 3,	"																																																
10 x 10 x 2,	"	18 x 9 x 3,	"																																																
12 x 8 x 2,	"	18 x 9 x 4 1/2,	"																																																
12 x 9 x 2,	"	24 x 9 x 4 1/2,	"																																																
12 x 10 x 2,	"	24 x 10 x 5,	"																																																
12 x 12 x 1 1/2,	"	30 x 10 x 5,	"																																																
No. W 5196. <b>Bevel Side Fire Brick</b>  Size, 9 x 4 1/2 x 2 1/2 ins. Price, .. 16/6 per 100.	No. W 5197. <b>Cupola Fire Brick</b>  Size, 9 ins. outside curve x 4 1/2 x 3 ins.; 18 ins. radius. Price, .. 18/- per 100.	No. W 5198. <b>Arched Fire Tile</b>  9 x 9 x 1 1/2, .. 1/- each. 10 x 10 x 1 1/2, .. 1/3 " 12 x 12 x 1 1/2, .. 1/6 "	Red Oven Tiles, 12 x 12 x 2 ins., .. 11/3 per doz.																																																

# Damp Course Material, Roofing Felts

## THICK SLATES FOR DAMP COURSE

18×9 inches, .. .. .	Prices
14×9 " .. .. .	quoted on application.
12×9 " .. .. .	
16×4½ " .. .. .	
9×4½ " .. .. .	

## PURE BITUMEN DAMP COURSE

In Rolls 24 feet long.				
Width, .. .. .	4½	9	13½	18 inches.
Prices, .. .. .	2/6	5/-	7/6	10/- per roll.
Lots of 25 rolls and upwards carriage paid to any railway station within 50 miles of London.				

## ROOFING FELTS

Best Asphalted Roofing Felt, ..	per 25 yard roll, 32 ins. wide.
Best Asphalted Sarking Felt, ..	" 25 " 32 "
Best Asphalted Sheathing Felt, ..	" 25 " 32 "
Best Bituminous Inodorous Felt, ..	" 25 " 32 "
Thin Bituminous Inodorous Felt, ..	" 25 " 32 "
Prices quoted on application.	

## STONIFLEX ROOFING FELT

No. 1 Quality, .. .. .	Price, per 15 yard roll, 36 inches wide, 10 6
" 2 " .. .. .	" 15 " 36 " 9/-
" 3 " .. .. .	" 15 " 36 " 7 6
Carriage paid to stations in England or Wales on 12 rolls and upwards.	


## NON-CONDUCTING DRY HAIR BOILER FELT

For clothing Boilers and Steam Pipes to preserve the heat covering Water Pipes and Cisterns to exclude the frost and lining under Roofs, &c., to equalise the temperature. It is also very effective in deadening sound in partitions and ceilings.

In Sheets, size 34 × 20 inches. Weight per sheet.

No. 1. For Roofs, &c., .. .. .	about 1 lb. 6d. per sheet.
" 2. " .. .. .	" 1½ " 8d. "
" 3. For Water Cisterns, Pipes, &c., ..	" 2 " 9d. "
" 4. For Steam Boilers and Pipes, ..	" 2½ " 1/- "
" 5. For Large Boilers, &c., .. .. .	" 3 " 1/3 "

## PATENT HAIR FABRIC, for Covering Steam and other Pipes.



In 8-yard lengths, 4 ins. wide, about 1 in. thick, 3/9 per length

## PLASTERERS' HAIR.

In 1-ton lots, .. .. .	Price, 200/- per ton.
Small lots, .. .. .	12/- per cwt.
(In ½, ¼ and 1 cwt. Bags free.)	

## PLASTERERS' LATHS (English)

Single, .. .. .	45/- per load of 30 bundles. 1/6 per 300 ft. bundle.
Lath and a half, .. 72/6	" 30 " 2/6 " 300 "
Double, .. .. 112/6	" 30 " 4/6 " 300 "

## VITRIFIED STONEWARE DAMP COURSE



In 6-inch lengths.	
For 4½ inch Wall, .. .. .	Price, 3d. each.
" " " " .. .. .	" 6d. "
" 1½ " " " " .. .. .	" 9d. "
1½ inches thick, with tongue and groove joints.	

## MASTIC DAMP COURSE

In Rolls, 33 feet long.	
Width, .. .. .	4½ 9 13½ inches.
Prices, .. .. .	per roll.
Prices quoted on application.	

## SANDED MASTIC ROOFING FELT

(Requires no annual coating.)

No. 1. For Permanent Roofs, in 15 yard lengths, 36 ins. wide,	per roll.
" 2. For Under Slates, &c., 15 " 36 " "	"
" For Insulating, 15 " 36 " "	"
Prices quoted on application.	


6 Rolls and upwards sent carriage paid to any railway station in England.

## TAR AND PITCH

Refined Coal Tar, in barrels, .. .. .	
Stockholm Tar, in barrels, .. .. .	
British Pitch, in casks, .. .. .	
Swedish Pitch, in casks, .. .. .	
" " in 28 and 14 lb. boxes,	
" " in 1 and 2 lb. packets,	
" " in ½ lb. packets, .. .. .	

Prices quoted on application.

## Section of a FIBROUS SLAB showing actual thickness



STOCK SIZES
5'0" x 2'6"
5'3" x 2'6"
5'6" x 2'6"
5'9" x 2'6"
4'0" x 2'6"

## Improved Hand-made FIBROUS PLASTER SLABS

No. W 1005.

Rapid System of Plastering.

FIRE-RESISTING.  
STRONG.  
NEVER CRACK.  
EASILY APPLIED.

Rooms habitable in 24 hours after finishing coat is applied.

- A = 1" x ½" Laths (2 in each slab)
- B = Rough Face of Slab to act as key for finishing coat.
- C = Inner Layer of Canvas

Price, 1 4½ per yard super.

# Glazed Stoneware Sinks and Glazed Bricks

See also BUTLERS' SINKS, &c., in SANITARY ENGINEERS' SECTION of this Catalogue, pages 211 and 214.  
No. W 418. **LONDON PATTERN SINK**



No. W 419. **ANGULAR SINK**

Outside sizes,	17 x 13 x 5 ins.,	Cane Color.	Cane and White.
"	"	4/-	6/-
"	"	5/4	8/4
"	"	6/4	9/8
"	"	7/-	10/8
"	"	7/8	12/-
"	"	7/8	12/-
"	"	8/8	13/8
"	"	9/8	15/-
"	"	13/-	20/-
"	"	12/8	19/8
"	"	11/8	18/-
"	"	15/8	24/-
"	"	18/8	28/8
"	"	23/8	36/4
"	"	27/-	41/8

Across.	Side.	Cane Color.	Cane and White.
Outside sizes,	16 x 12 ins.,	3/4	5/4
"	"	4/-	6/8
"	"	5/4	8/4
"	"	8/8	11/8
"	"	12/-	18/-

We also stock London Pattern extra deep in following sizes :-

Outside sizes,	24 x 18 x 7 ins.,	Cane Color.	Cane and White.
"	"	11/-	16/8
"	"	12/4	19/-
"	"	13/8	21/-
"	"	19/-	29/4

When ordering please state whether Right or Left Hand is required. Illustration shows Left Hand.

## WHITE, SALT, AND COLORED GLAZED BRICKS

Size, 9 x 4 1/2 x 2 1/2 inches. Hard Leadless Glazes. Per 100, except where stated per Brick.

	White, Ivory, and Salt Glazed.	Best.	Other Colors.	Seconds.
Glazed on One Side,	Best.	Seconds.	Buff and Cream.	Other Colors.
" One End,	54/6	48/-	61/3	78/9
" One Side and One End, Bullnose, and 4 1/2 ins. or Flat Side,	52/3	45/9	59/-	76/6
" Two Sides,	69/6	63/3	78/9	94/3
" Two Ends,	78/9	72/3	92/-	107/3
" One Side and Two Ends,	65/6	59/-	78/9	94/6
" Cants, Squints and Octagons,	83/3	76/6	96/6	116/6
" Two Sides and One End,	76/6	69/6	96/6	98/6
Soap Stretchers,	87/6	81/-	100/9	118/3
Plinth and Hollow Bricks (Stretchers and Headers),	50/3	53/9	57/-	74/6
Double Bullnose, Round Ends and Bullnose Stops,	10d.	8d.	1/-	1/-
Rounded Internal Angles,	10d.	8d.	1/-	10d.
Moulded Bricks, Stretchers and Headers,	8d.	6d.	10d.	10d.
" Internal and External Angles,	1/4	1/4	1/4	1/4
Cill Bullnose, Stretchers and Headers,	2/4	2/4	2/4	2/4
	10d.	8d.	1/-	10d.

Above prices are for small quantities from our London stock. For full Truck Loads direct from Works we shall be pleased to quote special prices upon receipt of details and destination.

# Timber & Joinery Section

COMPRISING

INTERIOR AND FRONT DOORS . . . . .	} Manufactured at our Joinery and Moulding Works, Stratford
SASHES, FRAMES AND CASEMENTS . . . . .	
DRESSERS AND WARDROBES . . . . .	
ENTRANCE AND GARDEN GATES . . . . .	
WINDOWS AND JALOUSIES . . . . .	
PORCH BRACKETS, MOULDINGS AND SKIRTINGS . . . . .	
SASH AND GREENHOUSE MATERIAL . . . . .	

PINE AND SWEDISH DOORS  
TURNED NEWELS, BALUSTERS, TABLE LEGS, &c.  
FRETWORK, HANDRAILS, AND OVERDOORS  
. . . WOODCARVING . . .  
FENCING, LADDERS AND TRELLIS



We hold at our Wharves and Depots large stocks of all useful sizes of Builders' Timber, including Deals, Battens, Roofing Boards, Quartering, Flooring, Matching, Planed Boards, Feather Edge Board, Arris Rails, Palings, Slating Battens, Sawn Laths, Poles, Scaffold Boards, and Birch Putlogs. Full details of stock on hand and prices will be sent on receipt of requirements.



## FENCING MATERIALS

### OAK POSTS WITH BUTTS

6 × 4 ins.,	...	...	...	6 ft. 6/6	8 ft. 5/9	7 ft. 4/9	6 ft. 3/9 each
5 × 4 ins.,	...	...	...	5/9	5/3	4/3	3/6 ..
4 × 4 ins.,	...	...	...	6 ft. 2/8		4 × 3 ins.,	6 ft. 2/- each
Oak Spurs,	...	...	...	...	...	...	1/6 ..
9 ft. Oak Cant Rails,	...	...	...	...	...	...	4/3 per pair
9 ft. Oak Gravel Boards, 1½ × 9 ins.,	...	...	...	...	...	...	4/3 each
9 ft. Oak Gravel Boards, 1½ × 6 ins.,	...	...	...	...	...	...	2/9 ..

### OAK CLEFT PALINGS

Prices, ...	6 ft. 52/6	5 ft. 6 in. 46/6	5 ft. 37/6	4 ft. 6 in. 35/3	4 ft. 29/3	3 ft. 6 in. 24/6	3 ft. 20/3	2 ft. 6 in. 18/-	per 100
Oak Sawn Palings,	...	...	...	...	1/-	per 100 less			




# Ornamental Front Doors

Ex 2 inch Yellow Deal.


OUR OWN MANUFACTURE.

No. FD 4.



	Dimensions.		Price.	
6 ft.	6 ins. x 2 ft.	6 ins.,	19/3	each.
6 "	8 " x 2 "	8 "	19 9	"
6 "	10 " x 2 "	10 "	20 9	"
7 "	0 " x 3 "	0 "	21 6	"

No. FD 5.




	Dimensions.		Price.	
6 ft.	6 ins. x 2 ft.	6 ins.,	19/9	each.
6 "	8 " x 2 "	8 "	20/6	"
6 "	10 " x 2 "	10 "	21/6	"
7 "	0 " x 3 "	0 "	22/3	"

No. T 6048.




	Dimensions.		Price.	
6 ft.	6 ins. x 2 ft.	6 ins.,	22/3	each.
6 "	8 " x 2 "	8 "	23 -	"
6 "	10 " x 2 "	10 "	24 -	"
7 "	0 " x 3 "	0 "	24 9	"

No. T 5770.




	Dimensions.		Price.	
6 ft.	8 ins. x 2 ft.	8 ins.,	23 -	each.
6 "	10 " x 2 "	10 "	24 -	"
7 "	0 " x 3 "	0 "	24 9	"

No. T 5773.



	Dimensions.		Price.	
6 ft.	8 ins. x 2 ft.	8 ins.,	29 6	each.
6 "	10 " x 2 "	10 "	30/6	"
7 "	0 " x 3 "	0 "	31/6	"

No. T 6484.




	Dimensions.		Price.	
6 ft.	8 ins. x 2 ft.	8 ins.,	29 6	each.
6 "	10 " x 2 "	10 "	30 6	"
7 "	0 " x 3 "	0 "	31 6	"

# Ornamental Front Doors

Ex 2 inch Yellow Deal.


OUR OWN MANUFACTURE.

No. T 6480.




Dimensions.		Price.
6 ft.	8 ins. x 2 ft. 8 ins.,	<b>29/6</b> each.
6 "	10 " x 2 " 10 "	<b>30/3</b> "
7 "	0 " x 3 " 0 "	<b>31/-</b> "

No. T 6481.




Dimensions.		Price.
6 ft.	8 ins. x 2 ft. 8 ins.,	<b>28/6</b> each.
6 "	10 " x 2 " 10 "	<b>29/3</b> "
7 "	0 " x 3 " 0 "	<b>30/-</b> "

No. T 6482.




Dimensions.		Price.
6 ft.	8 ins. x 2 ft. 8 ins.,	<b>31/6</b> each.
6 "	10 " x 2 " 10 "	<b>32/3</b> "
7 "	0 " x 3 " 0 "	<b>33/-</b> "

No. T 6483.




Dimensions.		Price.
6 ft.	8 ins. x 2 ft. 8 ins.,	<b>33/-</b> each.
6 "	10 " x 2 " 10 "	<b>33/9</b> "
7 "	0 " x 3 " 0 "	<b>34/6</b> "

No. T 5772.



Dimensions.		Price.
6 ft.	8 ins. x 2 ft. 8 ins.,	<b>31/6</b> each.
6 "	10 " x 2 " 10 "	<b>32/3</b> "
7 "	0 " x 3 " 0 "	<b>33/-</b> "

No. T 5775.




Dimensions.		Price.
6 ft.	8 ins. x 2 ft. 8 ins.,	<b>35/6</b> each.
6 "	10 " x 2 " 10 "	<b>36/3</b> "
7 "	0 " x 3 " 0 "	<b>37/-</b> "

# Interior Doors

SELECTED YELLOW DEAL. OUR OWN MANUFACTURE.

No. T 6696.



9 Panels. Moulded on Solid.

7 ft. 0 ins. x 3 ft. 0 ins. ex. 2 ins., **26/6** each.  
 6 " 10 " x 2 " 10 " " 2 " **26/-** "  
 6 " 8 " x 2 " 8 " " 2 " **25/6** "  
 6 " 6 " x 2 " 6 " " 2 " **25/-** "  
 6 " 6 " x 2 " 6 " " 1½ " **20/6** "


No. T 6697.



4 Panels, top Panel raised. Moulded on Solid.

7 ft. 0 ins. x 3 ft. 0 ins. x ex. 2 ins., **27/-** each.  
 6 " 10 " x 2 " 10 " " 2 " **26/6** "  
 6 " 8 " x 2 " 8 " " 2 " **26/-** "  
 6 " 6 " x 2 " 6 " " 2 " **25/6** "


No. T 6698.



6 Panels, Raised. Moulded on Solid.

7 ft. 0 ins. x 3 ft. 0 ins. x ex. 2 ins., **39/6** each.  
 6 " 10 " x 2 " 10 " " 2 " **39/-** "  
 6 " 8 " x 2 " 8 " " 2 " **38/6** "  
 6 " 6 " x 2 " 6 " " 2 " **37/6** "


No. T 6699.



6 Flat Panels. Moulded on Solid.

7 ft. 0 ins. x 3 ft. 0 ins. x ex. 2 ins., **28/-** each.  
 6 " 10 " x 2 " 10 " " 2 " **27/6** "  
 6 " 8 " x 2 " 8 " " 2 " **27/-** "  
 6 " 6 " x 2 " 6 " " 2 " **26/6** "  
 6 " 6 " x 2 " 6 " " 1½ " **21/-** "

No. T 6700.




6 Flat Panels. Moulded on Solid, with Astragal Moulding.

7 ft. 0 ins. x 3 ft. 0 ins. x ex. 2 ins., **36/6** each.  
 6 " 10 " x 2 " 10 " " 2 " **36/-** "  
 6 " 8 " x 2 " 8 " " 2 " **35/6** "  
 6 " 6 " x 2 " 6 " " 2 " **35/-** "

Stiles and Rails Moulded on Solid where shown.

No. T 6701.




Framed, ledged, and braced; properly mortised, tenoned, and wedged, and filled in with 1-inch V-jointed Matching.

7 ft. 0 ins. x 3 ft. 0 ins. x ex. 2 ins., **30/9** each.  
 6 " 10 " x 2 " 10 " " 2 " **30/-** "  
 6 " 8 " x 2 " 8 " " 2 " **29/6** "  
 6 " 6 " x 2 " 6 " " 2 " **29/-** "

# Yellow Pine Doors

Properly mortised, tenoned, and wedged. Panels and Rails in one piece.

No. T 6053.



FIVE PANEL.

No. T 6053. Five Panel.


Ovolo moulded on solid.

Dimensions.	Ex.	Price,
6 ft. 10 ins. x 2 ft. 10 ins. x 2 ins.		<b>16/6</b> each.
6 " 8 " x 2 " 8 " x 2 "		" <b>15 -</b> "
6 " 6 " x 2 " 6 " x 2 "		" <b>13/6</b> "
6 " 6 " x 2 " 6 " x 1 1/2 "		" <b>10/6</b> "
6 " 4 " x 2 " 4 " x 1 1/2 "		" <b>9/9</b> "
6 " 4 " x 2 " 4 " x 1 1/4 "		" <b>9 -</b> "

No. T 6054. Six Panel.


Ovolo moulded on solid.

Dimensions.	Ex.	Price,
6 ft. 10 ins. x 2 ft. 10 ins. x 2 ins.		<b>17 -</b> each.
6 " 8 " x 2 " 8 " x 2 "		" <b>15/9</b> "
6 " 6 " x 2 " 6 " x 2 "		" <b>14 -</b> "
6 " 6 " x 2 " 6 " x 1 1/2 "		" <b>11/3</b> "
6 " 4 " x 2 " 4 " x 1 1/2 "		" <b>10/3</b> "
6 " 4 " x 2 " 4 " x 1 1/4 "		" <b>9/6</b> "



SIX PANEL.

No. T 6485.



FOUR PANEL.

No. T 6485. Four Panel.

Inlaid, moulded both sides.

Dimensions.	Ex.	Price,
6 ft. 8 ins. x 2 ft. 8 ins. x 2 ins.		<b>16/6</b> each.
6 " 6 " x 2 " 6 " x 2 "		" <b>15/-</b> "
6 " 6 " x 2 " 6 " x 1 1/2 "		" <b>11/9</b> "

Inlaid, moulded one side.

Dimensions.	Ex.	Price,
6 ft. 6 ins. x 2 ft. 6 ins. x 1 1/2 ins.		<b>10/3</b> each.

Square.

Dimensions.	Ex.	Price,
6 ft. 6 ins. x 2 ft. 6 ins. x 1 1/2 ins.		<b>9/-</b> each.

Ovolo moulded on solid.


Dimensions.	Ex.	Price,
6 ft. 6 ins. x 2 ft. 6 ins. x 1 1/2 ins.		<b>9/-</b> each.
6 " 4 " x 2 " 4 " x 1 1/2 "		" <b>8/6</b> "
6 " 6 " x 2 " 6 " x 1 1/4 "		" <b>8/3</b> "
6 " 4 " x 2 " 4 " x 1 1/4 "		" <b>7/6</b> "
6 " 0 " x 2 " 0 " x 1 1/2 "		" <b>6/9</b> "

No. T 6486. French Casement Doors.

Yellow Deal. Our manufacture.

Dimensions.	Ex.	Price,
7 ft. 0 ins. x 4 ft. 0 ins. x 2 ins.		<b>19/6</b> per pair.
7 " 0 " x 3 " 6 " x 2 "		" <b>19/-</b> "
6 " 10 " x 3 " 10 " x 2 "		" <b>19/3</b> "
6 " 8 " x 3 " 8 " x 2 "		" <b>18/9</b> "

No. T 6486.




FRENCH CASEMENT DOOR.  
In Yellow Deal.


# Swedish Yellow Doors

## STANDARD LIST PRICES.

No.	Ex.	6 ft.	8 ins.	× 2 ft.	8 ins.	× 2 ins.			
G24.		6 ft.	8 ins.	× 2 ft.	8 ins.	× 2 ins.	Bead and butt and square,	..	17/- each.
G25.		6 "	6 "	× 2 "	6 "	× 2 "	" " "	..	16/6 "
G53.		6 "	6 "	× 2 "	6 "	× 1½ "	Bead and flush and square,	..	11/3 "
G58.		6 "	6 "	× 2 "	6 "	× 1½ "	Bead and butt and square,	..	10/9 "
G60.		6 "	4 "	× 2 "	4 "	× 1½ "	" " "	..	10/3 "
162.		6 "	10 "	× 2 "	10 "	× 2 "	Moulded both sides,	..	14/10 "
G64.		6 "	8 "	× 2 "	8 "	× 2 "	Square both sides,	..	11/6 "
164.		6 "	8 "	× 2 "	8 "	× 2 "	Moulded both sides,	..	14/4 "
G66.		6 "	6 "	× 2 "	6 "	× 2 "	Square both sides,	..	11/- "
166.		6 "	6 "	× 2 "	6 "	× 2 "	Moulded both sides,	..	13/10 "
G70.		6 "	8 "	× 2 "	8 "	× 1½ "	Square both sides,	..	8/10 "
H70.		6 "	8 "	× 2 "	8 "	× 1½ "	Moulded one side,	..	10/2 "
170.		6 "	8 "	× 2 "	8 "	× 1½ "	Moulded both sides,	..	11/6 "
K70.		6 "	8 "	× 2 "	8 "	× 1½ "	Moulded on solid,	..	8/10 "
G72.		6 "	6 "	× 2 "	6 "	× 1½ "	Square both sides,	..	8/3 "
H72.		6 "	6 "	× 2 "	6 "	× 1½ "	Moulded one side,	..	9/7 "
172.		6 "	6 "	× 2 "	6 "	× 1½ "	Moulded both sides,	..	11/- "
K72.		6 "	6 "	× 2 "	6 "	× 1½ "	Moulded on solid,	..	8/3 "
G74.		6 "	4 "	× 2 "	4 "	× 1½ "	Square both sides,	..	7/9 "
H74.		6 "	4 "	× 2 "	4 "	× 1½ "	Moulded one side,	..	9/1 "
174.		6 "	4 "	× 2 "	4 "	× 1½ "	Moulded both sides,	..	10/6 "
K74.		6 "	4 "	× 2 "	4 "	× 1½ "	Moulded on solid,	..	7/9 "
G83.		6 "	6 "	× 2 "	6 "	× 1¼ "	Square both sides,	..	7/8 "
K83.		6 "	6 "	× 2 "	6 "	× 1¼ "	Moulded on solid,	..	7/8 "
G87.		6 "	0 "	× 2 "	0 "	× 1¼ "	Square both sides,	..	5/9 "
K87.		6 "	0 "	× 2 "	0 "	× 1¼ "	Moulded on solid,	..	5/9 "
G90.		6 "	4 "	× 2 "	4 "	× 1¼ "	Square both sides,	..	6/7 "
K90.		6 "	4 "	× 2 "	4 "	× 1¼ "	Moulded on solid,	..	6/7 "



FOUR-PANEL DOOR.



MARGINAL LIGHT DOOR.


No. C28.	6 ft. 8 ins. × 2 ft. 8 ins. × 2 ins.	Two top panels beaded for glass; bottom panels moulded both sides,	13/- each.
A29.	6 ft. 8 ins. × 2 ft. 8 ins. × 1½ ins.	Two top panels beaded for glass; bottom panels bead and flush and moulded,	12/7 "
C29.	6 ft. 8 ins. × 2 ft. 8 ins. × 1½ ins.	Two top panels beaded for glass; bottom panels moulded both sides,	11/10 "
A30.	6 ft. 6 ins. × 2 ft. 6 ins. × 1½ ins.	Two top panels beaded for glass; bottom panels bead and flush and moulded,	11/6 "
C30.	6 ft. 6 ins. × 2 ft. 6 ins. × 1½ ins.	Two top panels beaded for glass; bottom panels moulded both sides,	10/9 "
G100.	6 ft. 6 ins. × 2 ft. 6 ins. × 1½ ins.	Two top panels beaded for glass; bottom panels square,	9/- "
L100.	6 ft. 6 ins. × 2 ft. 6 ins. × 1½ ins.	Two top panels beaded for glass; bottom panels bead and butt,	11/- "
AG100.	6 ft. 4 ins. × 2 ft. 4 ins. × 1½ ins.	Two top panels beaded for glass; bottom panels square,	8/- "
AL100.	6 ft. 4 ins. × 2 ft. 4 ins. × 1½ ins.	Two top panels beaded for glass; bottom panels bead and butt,	10/- "
C123.	6 ft. 6 ins. × 2 ft. 6 ins. × 1½ ins.	Marginal light; bottom panels moulded both sides,	10/9 "
C124.	6 ft. 4 ins. × 2 ft. 4 ins. × 1½ ins.	Marginal light; bottom panels moulded both sides,	9/8 "
A123.	6 ft. 6 ins. × 2 ft. 6 ins. × 1½ ins.	Marginal light; bottom panels bead and flush and moulded,	11/6 "
A124.	6 ft. 4 ins. × 2 ft. 4 ins. × 1½ ins.	Marginal light; bottom panels bead and flush and moulded,	10/5 "

No. H92.	2 ft. 8 ins. × 1 ft. 3 ins. × 1½ ins.	Dwarf Cupboard Doors.	Moulded one side,	5/3 per pair.
H98.	2 " 8 " × 1 " 4 " × 1½ "	" "	" "	5/6 "
H99.	2 " 8 " × 1 " 6 " × 1½ "	" "	" "	6/- "
H94.	2 " 10 " × 1 " 4 " × 1½ "	" "	" "	6/- "
H96.	2 " 10 " × 1 " 6 " × 1½ "	" "	" "	6/9 "

# Sashes and Frames, Casements, and Cupboard Fronts

SELECTED YELLOW DEAL. OUR OWN MANUFACTURE.

No. T 6690.




Double Hung Sashes and Frame.  
Ex. ¾-inch Linings, 1-inch Pulley Stiles,  
Iron Pulleys.

Ex. 1½ ins., .. from 9½d. per foot super.  
" 1½ " .. " 10½d. " "  
" 2 " .. " 11½d. " "

One Upright Bar to both Sashes included  
in above prices.

Extra for Bars, to sketch, 2/6 each.  
Minimum charge, 15 feet per opening.

No. T 6691.




Double Hung Sashes and Frame.  
Ex. ¾-inch Linings, 1-inch Pulley Stiles, Iron  
Pulleys, Top Sash with Camber Head.

Ex. 1½ ins., .. from 11½d. per foot super.  
" 1½ " .. " 1 - " "  
" 2 " .. " 1.0½ " "

Pitch Pine Sills, ¾d. per foot super extra.

Oak Sills and Brass Face Pulleys,  
1½d. per foot super extra.

No. T 6692.




Casements, in pairs, and ex. 4 x 3 ins.  
Solid Rebated Frames.

Ex. 1½ ins., .. 1 0½ per foot super.  
" 1½ " .. 1 1½ " "  
" 2 " .. 1 2½ " "

Minimum charge, 18 feet per opening.  
Fitting and Hanging Casements,  
1/3 each extra.

No. T 6693.



Casements with ex. 4 x 3 ins. Solid Rebated  
Frames, with Mullion and Transom.

Ex. 1½ ins., .. 1 7 per foot super.  
" 1½ " .. 1 8 " "  
" 2 " .. 1 9 " "

Minimum charge, 24 feet per opening.

Fitting and Hanging Casements,  
1/3 each extra.

No. T 6694.




Cupboard Front, with Doors in pairs.

Ex. 1½ ins., .. 1/- per foot super.  
" 1½ " .. 1/1½ " "

Minimum charge, 27 feet.

Fitting and Hanging Doors, 1/3 each extra.  
Moulding Doors (1 side), 4½d. per panel extra.

No. T 6695.



Cupboard Front, with Single Doors.

Ex. 1½ ins., .. 10½d. per foot super.  
" 1½ " .. 1 - " "

Minimum charge, 27 feet.


Fitting and Hanging Doors, 1/3 each extra.  
Moulding Doors (1 side), 4½d. per panel extra.

We make a Speciality of Pitch Pine and other Hardwood Joinery for Export.

## Front Door, with Solid Frame and Sidelights

OUR OWN MANUFACTURE.

SELECTED YELLOW DEAL.



No. T 6706.

No. T 6706.

Ex.  $4\frac{1}{2} \times 3$  ins. Solid Rebated Frame, with  $3 \times 6$  ins. Oak Sill.

Ex. 2 ins.  $7 \times 3$  ft. Front Door, lower panels raised, top prepared for glass. 2-in. Sidelights and Fanlights.

Over all,  $9 \times 6$  ft.

Price, .. .. 72/-

See preceding pages for further designs in Front Doors.

Frames and Sidelights supplied to match.

Prices on application.

## French Casement Doors and Frame with Wings


No. T 6707.

Ex.  $4\frac{1}{2} \times 3$  ins. Solid Rebated Frame with  $3 \times 6$  ins. Oak Sill to Door. Ex. 2 ins. French Casement Doors, Wings and Fanlights. Over all,  $8 \times 6$  ft.

Price, .. .. 63 -

Lobby Doors and Frames and French Casement and Frames made to Architects' designs and specifications.

Prices on application.




No. T 6707.

# Door and Wing Frames


SELECTED YELLOW DEAL. OUR OWN MANUFACTURE.

No. T 6702.




Door Frame, ex  $4\frac{1}{2} \times 3$  inches.  
Solid, Rebated, with Transom and  
Fanlight and  $3 \times 6$  inch Oak Sill.  
Price, .. 20/3 each.

No. T 6703.



Door Frame, ex  $4\frac{1}{2} \times 3$  inches.  
Solid, Rebated, with Transom and  
Fanlight and  $3 \times 6$  inch Oak Sill, with  
Circular Head. Price, 37/6 each.


No. T 6704.



Door Frame, ex  $4\frac{1}{2} \times 3$  inches.  
With Wing and Sliding Sashes;  
Oak Sill to Door.  
Price, ... 31/6 each.  
Also made with Casements in Wing.

## Solid Bay Frame and Casements

No. T 6705.



Framing, ex  $4\frac{1}{2} \times 3$  inch  
Yellow Deal.  
Ex  $8 \times 3$  inch Moulded Oak Sill.  
Ex 2-inch Casements and  
Fanlights.  
5 feet 9 inches high over all.  
Price, £6 6 0  
Also made  
Solid Oak throughout,  
Price, £11 14 0

BAYS MADE TO  
ARCHITECTS' OR CUSTOMERS'  
OWN DESIGNS.


Fitting and Hanging Casements and Fans on Iron Butts, 1/3 each extra.



# Windows, Jalousies, and Porch Brackets

SELECTED YELLOW DEAL.

No. T 6760.




Ex  $4\frac{1}{2} \times 3$  inch Solid Rebated and Moulded Frame, and ex 2 inch Casements,  $1\frac{1}{6}$  per ft. super.

Jalousie Shutters for same, with fixed slats, painted ordinary colors,  $3\frac{1}{2}$  per ft. super.

When made with Jalousie Shutters, Casements open inwards. Minimum, 18 ft. per opening.


No. T 6761.



Jalousie Shutters, with movable slats.

Prices on application, stating sizes required.

No. T 6762.




Jalousie Shutter, with Hinged Lower Portion.

Ex 2 inch, painted ordinary colors,  $2\frac{3}{4}$  per ft. super.

Minimum, 16 ft. per opening.

No. T 6763.




Double Hung Sashes and Frame.

Ex  $\frac{3}{4}$  inch Linings, ex 1 inch Pulley Stiles, with Cover Moulding to outside, and fitted with Jalousie Shutters, fixed slats.

$1\frac{1}{2}$  inch Sashes,  $3$  - per ft. super.

Minimum, 18 ft. per opening.

No. T 6764.



Fitting and Hanging Casements,  $1\frac{1}{3}$  each extra.


Jalousie Shutters,  $1\frac{1}{9}$  each extra.

Porch Bracket, 3 feet Projection, 3 inch Framework,  $27\frac{1}{2}$  per pair.

Framed Front, with Turned Pillars to match bracket,  $2\frac{1}{6}$  per ft. run.

Minimum, 6 ft.

No. T 6686.



## Wardrobe Cupboard Front

BEST YELLOW DEAL.

OUR OWN MANUFACTURE.

Wardrobe Cupboard Front with cornice and drawer with raised front. Door prepared for mirror.

Size up to 5 x 8 feet ex 1½ inches.

Price, £2 9 6

If with Rounded Corner and Return End,

Extra, 8 6

Any size made at proportionate prices.

Mirror supplied extra to order.

No. T 6687.

## High-Class Cabinet Dresser

WITH GLASS CUPBOARD OVER.

Four 1½-inch doors prepared for glass. Seven drawers with raised fronts. One pair 1½-inch doors with raised panels under. 1½-inch top with moulded edge. 1-inch pot board. Two return ends with raised panels.

Size, .. .. 6 x 9 to 10 feet.

Price, £8 15 0

No. T 6688. **CABINET DRESSER**, well made, but in plainer form. Three ex 1½-inch doors at top, with one up and one cross bar, rebated for glass. Three plain fronted drawers and three doors under. Two shelves and pot board, 1½-inch top.

Size, .. .. 6 x 8 feet 6 inches.

Price, £4 2 6

Other sizes at proportionate prices.


Dressers made to special design to order in any wood.

Special prices quoted for half-dozen lots.

SECTION.



No. T 6687.




# Ornamental Garden Gates

Ex 2 inch Yellow Deal.

OUR OWN MANUFACTURE.


No. T6456.



Dimensions.

3 ft. 0 ins. wide	× 3 ft. 8 ins. high,	..	Price, <b>16/6</b> each.
3 „ 3 „	× 3 „ 8 „	.. „	<b>17/6</b> „
3 „ 6 „	× 3 „ 8 „	.. „	<b>18/6</b> „


No. T6457.



Dimensions.

3 ft. 0 ins. wide	× 3 ft. 8 ins. high,	..	Price, <b>19/6</b> each.
3 „ 3 „	× 3 „ 8 „	.. „	<b>20/6</b> „
3 „ 6 „	× 3 „ 8 „	.. „	<b>21/6</b> „


No. T6458.



Dimensions.

3 ft. 0 ins. wide	× 4 ft. 0 ins. high,	..	Price, <b>24/9</b> each.
3 „ 3 „	× 4 „ 0 „	.. „	<b>25/9</b> „
3 „ 6 „	× 4 „ 0 „	.. „	<b>26/9</b> „

No. T6459.




Dimensions.

3 ft. 0 ins. wide	× 4 ft. 0 ins. high,	..	Price, <b>24/9</b> each.
3 „ 3 „	× 4 „ 0 „	.. „	<b>25/9</b> „
3 „ 6 „	× 4 „ 0 „	.. „	<b>26/9</b> „

# Entrance Gates

SELECTED YELLOW DEAL. OUR OWN MANUFACTURE.



No. T 6710


No. T 6710. MAIN ENTRANCE GATE.

For 10 ft. Opening, ex. 3 ins. thick, Price, **£9 5 0** per pair.  
 „ 9 „ „ 3 „ „ **9 0 0** „

No. T 6064.

WICKET OR GARDEN GATE to match.

3 ft. 6 ins. wide, ex. 2 ins., **33** - each.  
 3 „ 3 „ „ 2 „ **31 6** „  
 3 „ 0 „ „ 2 „ **30** - „



No. T 6712.

No. T 6711.

No. T 6712. WICKET GATE.

3 ft. 6 ins. wide, ex. 2 ins., **48** - each.  
 3 „ 3 „ „ 2 „ **46 6** „  
 3 „ 0 „ „ 2 „ **45** - „

No. T 6711. MAIN ENTRANCE GATE.


10 ft. wide, ex. 3 ins. thick, Price, **£6 18 0** each.  
 9 „ „ 3 „ „ **6 13 6** „

OAK POSTS.

9 feet long, 8 x 8 inches, with Butts and Square Caps, Price, **52** - each.

Hinges and Fastenings extra. For prices, see Ironmongery Section.  
 Above can be supplied in Pitch Pine or Oak to order. Prices on application.


# Wood Newels Round Turned and Carved



WN 22 WN 23 WN 24 WN 25 WN 27 WN 28 WN 29 WN 30 WN 31 WN 32 WN 33 WN 34 WN 35

4 feet 6 inches long.


PRICES, EACH.




WN 36 WN 37 WN 38 WN 39 WN 40 WN 41

No.	Size.	Deal.	P. Pine	Mahogany.	Oak	Walnut.
	Ex. 3 ins.	1 6	3/9	4/6	5/3	6/-
WN 22	" 3 1/2 "	2/3	4/9	5/7 1/2	6/9	8/3
WN 21	" 4 "	2 6	5/3	6 1/4	8/3	10/6
	" 4 1/2 "		6/9	9/-	10/6	14/3
	" 5 "		7/3	10/6	12/-	17/3
	" 6 "		9/9	14/3	15/9	24/-
WN 26	" 4 "	3 6	6/-	7/1 1/2	9/-	11/3
WN 27	" 4 1/2 "		7/6	9/9	11/3	15/-
WN 28	" 5 "		8/6	11/3	12/9	18/-
	" 6 "		11/-	15/-	16/6	25/6
WN 29 with 1 Loose Panel	" 4 "	4 3	6/9	8/3	10 1/2	12/9
	" 5 "		10/3	12/9	14/3	19/6
	" 6 "		12/9	16/6	18/9	27/9
	" 4 "	4 6	6/9	9/-	10/6	12/9
WN 30	" 1 1/2 "		9/9	12/-	13/6	17/3
	" 5 "		10/6	13/6	15/-	20/3
	" 6 "		14/3	18/-	19/6	29/3
WN 31 Fluted	" 4 "	6 6	8/3	10/6	12/-	13/6
WN 32 Octagon with 3 Loose Panels	" 4 1/2 "		9/9	12/9	14/3	18/9
	" 5 "		12/9	15/9	17/3	22/6
	" 6 "		17/3	21/9	23/3	30/-
	" 4 "	6 -	9/9	12/-	12/9	15/-
WN 33 Spiral	" 1 1/2 "		12/-	15/9	17/3	21/-
WN 34 Reeded	" 5 "		12/9	17/3	18/9	23/3
WN 35 Fluted	" 6 "		16/6	24/9	26/3	31/6
	" 4 "	7/10 1/2	10/6	12/9	13/6	15/9
WN 36	" 5 "		14/3	18/-	19/6	22/6
	" 6 "		21/-	24/-	26/3	31/6
WN 37 with 3 Loose Panels	" 4 "	10/6	13/6	16/6	17/3	20/3
	" 5 "		18/-	21/9	23/3	26/3
	" 6 "		23/3	27/-	28/6	34/6
WN 38 with 3 Carved Panels	" 4 "	10/6	13/6	16/6	17/3	20/3
	" 5 "		18/-	21/9	23/3	26/3
	" 6 "		23/3	27/-	27/6	34/6
WN 39 with 3 Loose Panels	" 4 "	10 6	13/6	16/6	17/3	20/3
	" 5 "		18/-	21/9	23/3	26/3
	" 6 "		23/3	27/-	28/6	34/6
WN 40, WN 41 with 3 Loose Panels	" 4 "	13 6	16/6	19/6	20/3	22/6
	" 5 "		21/9	26/3	27/9	31/6
	" 6 "	-	27/9	33/-	34/6	39/-

# Round Turned Wood Balusters



WB30 WB31 WB32 WB33 WB34 WB35 WB36 WB37 WB38 WB39 WB40 WB41 WB42 WB43 WB44 WB45 WB46 WB47



WB48 WB49 WB50 WB51 WB52 WB53 WB54 WB55 WB56 WB57 WB58 WB59 WB60 WB61 WB62 WB63 WB64 WB65 WB66 WB67 WB68 WB69 WB70 WB71 WB72 WB73 WB74 WB75

## PRICES, PER DOZEN.

3 feet long.

## PRICES, PER DOZEN.


No.	Size.	Deal.	P.Pine.	Mahogany.	Oak.	Walnut.	No.	Size.	Deal.	P.Pine.	Mahogany.	Oak.	Walnut.
WB30 to WB34	Ex. 1 1/2 ins.	2/3	5/-	7/6	7/6	9/9	WB53 Spiral Fluted	Ex. 1 1/2 ins.	4/6	7/6	11/3	12/-	13/6
	" 1 1/4 "	2/7 1/2	5/7 1/2	9/-	9/-	10/6		" 1 1/4 "	6/-	10/6	13/6	14/3	16/6
	" 1 1/2 "	3/9	7/3	11/3	11/3	14/3		" 2 "	7/6	12/-	17/3	18/-	21/-
	" 2 "	4/6	8/6	12/9	12/9	17/3		" 2 "	7/6	10/6	15/9	16/6	18/9
WB35, WB36, WB37	" 1 1/2 "	3/-	6/1 1/2	9/4 1/2	9/4 1/2	11/3	WB54 Fluted WB55 Octagon	" 1 1/2 "	7/6	10/6	13/6	14/3	16/6
	" 1 1/4 "	4/1 1/2	7/6	11/7 1/2	11/7 1/2	15/-		" 1 1/4 "	9/9	13/6	18/-	18/9	21/-
	" 1 1/2 "	4/10 1/2	9/4 1/2	13/6	13/10 1/2	18/-		" 2 "	10/6	15/-	19/6	20/3	24/-
	" 2 "	3/4 1/2	6/7 1/2	9/4 1/2	9/4 1/2	11/3		" 2 "	13/6	16/6	22/6	23/3	24/9
WB38, WB39	" 1 1/2 "	4/6	8/-	11/7 1/2	12/-	15/-	WB56, WB57 WB58 WB59 Octagon	" 1 1/2 "	13/6	16/6	22/6	23/3	24/9
	" 1 1/4 "	5/3	10/3	13/6	14/3	18/-		" 1 1/4 "	14/3	18/-	24/-	24/9	27/-
	" 1 1/2 "	4/1 1/2	7/6	9/9	9/9	11/3		" 2 "	15/9	21/-	24/9	26/3	27/-
	" 2 "	5/3	10/3	13/6	14/3	18/-		" 2 "	16/6	22/6	26/3	27/-	29/3
WB40 to WB43	" 1 1/2 "	4/1 1/2	7/6	9/9	9/9	11/3	WB60 to WB64	" 1 1/2 "	15/9	21/-	24/9	26/3	27/-
	" 1 1/4 "	5/3	9/-	12/-	12/9	15/-		" 2 "	16/6	22/6	26/3	27/-	29/3
	" 1 1/2 "	6/-	11/-	15/-	15/-	18/-		" 2 1/2 "	21/-	31/6	40/6	42/-	45/-
	" 2 "	6/-	10/3	12/-	12/-	13/6		" 2 1/2 "	18/-	24/-	27/9	29/3	31/6
WB44 to WB49	" 1 1/2 "	7/6	12/-	14/3	15/-	17/3	WB65, WB70	" 2 1/2 "	27/-	31/6	42/-	43/6	48/-
	" 1 1/4 "	8/3	13/6	16/6	17/3	21/-		" 2 1/2 "	24/9	31/6	36/-	37/6	40/6
	" 1 1/2 "	7/6	13/1 1/2	13/6	13/6	15/-		" 2 1/2 "	34/6	37/6	48/-	51/-	54/-
	" 2 "	9/9	15/3	18/-	18/9	22/6		" 3 "	40/6	48/-	63/-	66/-	69/-
WB50, WB51	" 1 1/2 "	9/9	13/6	16/6	17/3	18/9	WB75	" 2 1/2 "	54/-	60/-	67/6	69/-	72/-
	" 1 1/4 "	9/9	13/6	16/6	17/3	18/9		" 3 "	57/-	63/-	75/-	78/-	81/-
	" 2 "	11/3	18/9	21/-	21/9	26/3							
	" 2 1/2 "	11/3	18/9	21/-	21/9	26/3							

# Turned Newels and Balusters


## NEWELS

4 feet 6 inches long.

PRICES, EACH.




Pattern No.	Size.	Deal.	P. Pine.	Mahogany.	Oak.	Walnut.
T 6434	Ex. 4 x 4 ins.	6 -	7 6	9 -	10 6	12 9
	" 4½ x 4½ "		11 -	12 -	14 3	18 -
	" 5 x 5 "		12 -	14 3	16 6	21 -
T 6435	" 6 x 6 "		16 -	18 9	24 -	29 3
	" 4 x 4 "	6 6	8 6	10 6	12 -	14 3
	" 4½ x 4½ "		12 9	13 6	16 6	19 6
T 6436	" 5 x 5 "		14 -	15 9	18 -	23 3
	" 6 x 6 "		19 6	21 -	27 -	31 6
T 6437	" 4 x 4 "	7 6	9 4½	11 3	13 6	15 9
	" 4½ x 4½ "		14 -	15 -	18 -	21 -
	" 5 x 5 "		15 3	17 3	19 6	24 9
	" 6 x 6 "		21 -	22 6	29 3	33 9



## BALUSTERS

PRICES, PER DOZEN.

Pattern No.	Size.	Deal.	P. Pine.	Mahogany or Oak.	Walnut.
T 6440 Spiral Fluted	Ex. 1½ ins.	4 3	8 3	11 3	12 9
	" 1½ "	6 -	11 -	14 3	16 6
	" 2 "	6 10½	12 -	16 6	19 6
T 6439 Octagon	" 1½ "	6 10½	11 3	13 6	15 -
	" 1½ "	9 -	13 6	17 3	20 3
	" 2 "	10 3	15 6	19 6	22 6
T 6441 Spiral	" 1½ "	13 6	19 6	22 6	24 9
	" 2 "	15 3	21 -	24 -	27 -
	" 2½ "	22 10½	31 3	36 -	40 6



## FRET-CUT BALUSTERS


Deal, Pitch Pine and Whitewood planed up.  
Mahogany, Oak, and Walnut are finished for polishing.

3 feet long.

PRICES, PER DOZEN

Pattern No.	Size.	Deal.	P. Pine or Whitewood.	Oak or Mahogany.	Walnut.
T 6442	Ex. 1 x 3 ins.	9 4½	14 6	20 3	21 9
T 6443, T 6444	" 1 x 3½ "	11 -	16 3	24 -	26 3
	" 1 x 4 "	12 -	16 10½	27 -	30 -
T 6445, T 6446	" 1 x 4 "	12 9	18 9	28 6	31 6
	" 1 x 4½ "	14 6	22 -	33 -	36 -
T 6447	" 1 x 4 "	14 6	21 -	30 9	33 9
	" 1 x 4½ "	16 10½	23 9	35 3	38 3

## Round Turned Table Legs




PRICES, PER SET OF FOUR.

No.	Size	Deal.	P. Pine.	Birch.	Mahog.	Oak or Ash	Walnut	No.	Size	Deal.	P. Pine.	Birch.	Mahog.	Oak or Ash	Walnut.
	EX. 2 x 30 ins.	1/1 1/2	3/2	3 -	4/6	4/6	5		EX. 3 1/2 x 28 ins.	5 7/2	9/-	8/3	10/6	10/6	14/3
T 50	2 1/2 x 30	1/9	4/3	3/9	5/3	5/3	6/9	T 54	3 1/2 x 30	5 7/2	9/4 1/2	9/-	11/3	12/-	15/-
	3 x 30	2/1 1/2	6/-	5 7/2	6/9	6/9	9		4 x 26	6/7	11/3	10/6	13/6	15/9	18/9
	3 1/2 x 30	3/9	7/6	6/9	9/9	9/9	13/6		4 x 30	6/7	12/3	11/3	15/-	16/6	21/-
	4 x 30	4/4 1/2	9/9	9/9	12/9	13/6	19/6		4 1/2 x 26		14/3	12/9	17/3	21/-	26/3
T 51	2 x 30	1 7/2	3/9	3/9	4 10/2	4 10/2	5/3	T 59 Octagon	5 x 26		17/9	17/3	21/-	22/6	27/9
	2 1/2 x 30	2/1	4/9	4/6	5/3	5 7/2	6/9		6 x 26		28/2	24/-	28/6	33/-	42/-
	3 x 30	2/6	6/7	6/-	7 1/2	7 1/2	9		3 x 30			8/3	9/4 1/2	9/9	11/3
	3 1/2 x 30	4/9	8/6	8/3	10/6	10/6	14/3		3 1/2 x 30			10/6	12/9	13/6	17/3
T 52	3 1/2 x 26	4/9	8/6	7/6	9/9	9/9	12/9	T 60 Reeded	4 x 26			12/9	15/9	17/3	20/3
T 53	4 x 30	5/7 1/2	10/4	10/6	13/6	15/-	19/6	T 61 Fluted	4 1/2 x 26			15/9	20/3	21/9	25/6
	4 x 26	5 7/2	10/4	9/9	12/9	14/3	17/3		5 x 26			20/3	24/9	26/3	31/6
	4 1/2 x 30		14/3	12/-	17/3	19/6	24/-		6 x 26			27/9	33/-	37/6	45/-
	4 1/2 x 26		13/1 1/2	11/7 1/2	15/9	18	21/9		3 x 30			10/4 1/2	10/6	11/3	12/9
T 54	5 x 26		16/10 1/2	15/9	19/6	21/-	26/3	T 62 Best Reeded, Round Top; T 63 Nailed T 64 Straight Ornamental Flutes T 65 Spiral Flutes	3 1/2 x 30			12/-	14/3	15/-	18/9
	6 x 26		26/3	22/6	27/-	30/-	39/-		4 x 26			14/3	17/3	18/9	21/9
T 55	2 x 30	2/6	4/4 1/2	4/3	5/6	5/6	6/-		4 1/2 x 26			18/-	22/6	24/-	27/9
T 56	2 1/2 x 30	2/10	5/3	5/-	6	6/-	7/6		5 x 26			22/6	27/-	28/6	33/9
	3 x 30	3/4	7/1 1/2	6/9	7 10/2	7 10/2	9/9		6 x 26			30/-	36/-	40/6	48/-

Special Prices given for large quantities on application.

## Fret-Cut Balusters

PLANED AND CLEANED UP READY FOR FIXING.




PRICES, PER DOZIN.

No.	Size	Deal.	P. Pine.	Mahog.	Oak.	Walnut.
T 76	EX. 3 1/2 x 2 ins.	11/3	15/-	23/3	24/-	24/9
T 77, 78	3 1/2 x 2	16/6	27/-	33/-	34/6	36/-
T 77, 78	4 1/2 x 2	17/3	27/9	36/-	37/6	39/-
T 79	4 1/2 x 2	30/-	37/6	45/-	48/-	49/6
T 5504						
T 5505						
T 5506	3 1/2 x 2	21/-	31/6	37/6	39/-	40/6
T 5507						
T 5507	4 1/2 x 2	22/6	34/6	40/6	42/-	43/6
T 5508						
T 5509	9 x 1 x 30 ins.	57/6	82/6	108/-	111/-	115/6



# Square Turned and Carved Newels

TURNED PARTS CLEANED UP READY FOR POLISHING.



4 feet 6 inches long

PRICES, EACH.

No.	Size.	Deal.	P. Pine.	Mahogany.	Oak.	Walnut.
	Ex. 4 x 4 ins.	12 9	14 3	16 6	18 -	20/3
SN 80	.. 4 1/2 x 4 1/2 ..		17 3	21 -	22 6	25/6
	.. 5 x 5 ..		20 3	24 -	25 6	28/6
	.. 6 x 6 ..		27 -	33 -	37 6	40 6
SN 82 and SN 83	.. 4 x 4 ..	15 9	18/9	21 9	23 3	24 9
	.. 4 1/2 x 4 1/2 ..		21/9	25 6	28 6	30 -
	.. 5 x 5 ..		24/9	31 6	34 6	36 -
	.. 6 x 6 ..		36 -	42 -	45 -	48 -
SN 86	.. 4 x 4 ..	20 3	23/3	26 3	27 9	29 3
	.. 5 x 5 ..		28/6	34 6	36 9	39 -
	.. 6 x 6 ..		39 -	45 -	48 -	51 -
SN 88	.. 4 x 4 ..	27	31 6	34 6	36 -	37 6
	.. 5 x 5 ..		41 3	44 3	46 3	48 9
	.. 6 x 6 ..		51	57 -	60 -	63 -


PRICES, EACH.

No.	Size.	Deal.	P. Pine.	Mahogany.	Oak.	Walnut.
	Ex. 4 x 4 ins.	21 9	25 6	28 6	30 -	31 6
SN 80	.. 5 x 5 ..		34 6	40 6	42/9	45 -
	.. 6 x 6 ..		46 6	52 6	55/6	58/6
SN 81	.. 4 x 4 ..	37 6	42 -	45 -	47/3	48/9
	.. 5 x 5 ..		48/9	54 -	57 -	60 -
	.. 6 x 6 ..		60 -	64 6	68/3	62 -
SN 83	.. 4 x 4 ..	33 -	37/6	40/6	42 -	43/6
	.. 5 x 5 ..		46 6	51 -	52/6	54 -
	.. 6 x 6 ..		60 -	64 6	67 6	70 6
SN 85	.. 4 x 4 ..	45 -	49/6	52/6	55 6	58/6
	.. 5 x 5 ..		55/6	60 -	63 -	66 -
	.. 6 x 6 ..		67/6	72 -	75 -	78 -

Estimates given for Square or Special Turning, Carving, &c., of all descriptions.

# Turned, Carved and Built-up Square Newels

WITH SOLID CENTRE, CLEANED UP READY FOR FIXING.



No. SN 64.

No. SN 66.

No. SN 67.

No. SN 69.

No. SN 70.

No. SN 71.

No. SN 72.

No. SN 73.

No. SN 74.

No. SN 78.

4 feet 6 inches long.


## PRICES, EACH.

No.	Size.	P. Pine.	Mahogany.	Oak.	Walnut.	Polishing.
SN 64	Ex. 7 x 7 ins.	87/-	91/6	94/6	96/-	9/-
SN 66	8 x 8 "	33/-	45/-	45/-	48/-	9/-
	10 x 10 "	60/-	76/6	76/6	82/6	13/6
SN 67	8 x 8 "	37/6	49/6	49/6	52/6	9/-
	10 x 10 "	63/-	81/-	81/-	87/-	13/6
SN 69	7 x 7 "	48/-	57/-	57/-	60/-	9/-
	8 x 8 "	51/-	63/-	63/-	66/-	10/6
	10 x 10 "	96/-	108/-	108/-	111/-	15/-
SN 70 and SN 71	7 x 7 "	63/-	72/-	72/-	75/-	9/-
	8 x 8 "	72/-	81/-	81/-	84/-	12/-
	10 x 10 "	111/-	120/-	120/-	123/-	15/-

## PRICES, EACH.

No.	Size.	P. Pine.	Mahogany.	Oak.	Walnut.	Polishing.
SN 72	Ex. 7 x 7 ins.	78/-	90/-	90/-	96/-	10/6
	8 x 8 "	90/-	102/-	102/-	108/-	13/6
	10 x 10 "	132/-	144/-	144/-	150/-	18/-
SN 73	7 x 7 "	69/-	76/6	76/6	81/-	9/-
	8 x 8 "	78/-	87/-	87/-	90/-	12/-
	10 x 10 "	117/-	126/-	126/-	129/-	18/-
SN 74	8 x 8 "	78/-	87/-	87/-	90/-	13/6
	10 x 10 "	117/-	126/-	126/-	129/-	18/-
SN 76	7 x 7 "	91/6	97/6	100/6	103/6	
	8 x 8 "	111/-	120/-	123/-	126/-	

Estimates given for Square or Special Turning, Carving, &c., of all descriptions.



## Square Turned Newels, Caps, and Balusters

### SQUARE NEWELS (Squares Planed)


Length 4 feet 6 inches Work 20 inches.

PRICES, EACH.

Pattern No.	Size in In.	Deal.	P. Pine.	White wood.	Mahog.	Oak.	Walnut.
T 6422	EX. 4 x 4.	12 -	13 6	13 6	15 -	17 3	18 9
	" 4 1/2 x 4 1/2.		16 3	15 9	16 -	21 -	22 6
	" 5 x 5.		18 9	18 -	21 -	23 3	26 3
	" 6 x 6.		24 6	23 3	26 3	33 -	37 6
T 6423	" 4 x 4.	13 6	15 3	15 -	16 6	18 9	20 3
	" 4 1/2 x 4 1/2.		17 9	17 3	20 3	22 6	24 -
	" 5 x 5.		20 3	19 6	22 6	25 6	27 9
	" 6 x 6.		26 3	24 9	28 6	34 6	39 -
T 6421	Not Fluted, same price as No. T 6423.						
T 6421 Fluted	EX. 4 x 4.	16 9	18 9	18 -	19 6	21 9	23 3
	" 4 1/2 x 4 1/2.		22 3	21 -	24 -	26 3	27 9
	" 5 x 5.		25 6	24 -	27 -	30 -	32 3
	" 6 x 6.		31 3	29 3	33 -	39 -	43 6
	" 7 x 7.		67 6	63 -	66 -	75 -	84 -
T 6425 Fluted, with Sq. Caps fixed	" 8 x 8.		76 -	72 -	75 -	84 -	90 -
	4 x 4 cap 7 7.	13 6	17 -	16 6	18 -	20 3	23 3
	5 x 5 " 8 x 8.		22 -	21 -	23 3	25 6	31 6
T 6426, with Sq. Caps fixed finished	6 x 6 " 9 x 9.		28 6	27 9	30 -	36 -	42 -
	4 x 4 " 6 x 6.	13 6	16 -	15 9	17 3	18 9	21 9
	5 x 5 " 7 x 7.		21 3	20 3	22 6	24 9	29 3
	6 x 6 " 8 x 8.		29 9	27 -	30 -	36 -	39 9

### SQUARE CAPS

Pattern No.	Size in Ins.	P. Pine.	White wood.	Mahog.	Oak.	Walnut.
T 6427	EX. 7 x 7 x 3.	4 9	4 3	4 6	4 10 1/2	5 3
T 6428	" 8 x 8.	5	4 10 1/2	5 3	5 7 1/2	6
T 6429	" 9 x 9.	6 9	6 4 1/2	6 9	7 6	7 6
	" 10 x 10.	7 6	7 6	8 3	9 -	9 -



T 6427

PRICES, EACH.

Pattern No.	Size in Ins.	P. Pine.	White wood.	Mahog.	Oak.	Walnut.
T 6427	EX. 6 x 6 x 2.	3 4	3 -	3 4 1/2	3 6	3 9
T 6428	" 7 x 7 x 2.	3 9	3 6	3 9	4 -	4 6
T 6429	" 8 x 8 x 2.	4 6	4 1 1/2	4 6	4 10 1/2	5 3

For CAPS Nos. T 6428 and T 6429, see NEWELS Nos. T 6425 and T 6426

### SQUARE TURNED BALUSTERS

PRICES, PER DOZEN.

Pattern No.	Size.	Deal.	P. Pine.	Mahogany.	Oak.	Walnut.
T 6430	EX. 1 1/2 inches.	7 6	11 3	14 3	15 -	15 9
	" 1 1/2 "	10 -	12 6	17 3	18 -	20 3
	" 2 "	11 -	14 3	20 3	21 -	22 6
	" 2 1/2 "	18 3	23 6	30 -	31 6	36 -
T 6431	" 2 1/2 "	21 9	28 3	34 6	36 -	42 -
	" 1 1/2 "	8 6	12 6	15 -	15 9	16 6
	" 1 1/2 "	11 -	14 3	18 -	18 9	21 -
	" 2 "	11 9	16 -	21 -	22 6	23 3
T 6432 Fluted	" 2 1/2 "	20 -	25 -	31 6	33 -	37 6
	" 2 1/2 "	23 6	31 -	36 -	37 6	43 6
	" 1 1/2 "	11 -	15 -	18 9	19 6	20 3
	" 1 1/2 "	13 6	16 -	21 9	22 6	24 9
T 6433 Fluted	" 2 "	14 3	17 6	24 9	25 6	27 -
	" 2 1/2 "	22 6	28 6	37 6	39 -	43 6
	" 2 1/2 "	28 3	35 -	43 9	45 -	51 -
	Plain, price as No. T 6431.					
T 6433 Fluted	EX. 1 1/2 inches	13 6	18 -	21 -	21 9	22 6
	" 1 1/2 "	16 -	19 3	24 -	24 9	27 -
	" 2 "	16 9	21 -	27 -	28 6	30 -
	" 2 1/2 "	30 -	35 -	40 6	42 -	46 6
	" 2 1/2 "	33 6	41 -	46 6	48 -	52 6



T 6430



T 6431




T 6432



T 6433

# Square Cut Newels with Balusters to Match

Made by patent machinery on a new principle, the faces being finished perfectly square, and the moulds cut bold and clean, with perfect intersection of mitres.



SQUARE CUT NEWELS. PRICES, EACH.

Pattern Nos.	Size.	Length, Ft. Ins.	Pitch Pine.	Canary Whitewood.	Mahogany.	Oak.	Walnut Teak.
T 5751	4 ins.	4 6	12/	13 3	16 6	18	18 6
	4 1/2	5 6	13 3	14 6	18 3	20 6	21
	4 3/4	4 6	14 6	15 6	19 9	22 3	22 9
	4 1/2	5 6	15 6	17 6	22 3	25 3	25 9
	5	4 6	16 6	18	22 9	25 6	27
	5 1/2	5 6	18	19 6	25 6	29 6	30 6
T 5752	6	4 6	21 6	23 9	30 6	34 9	37 3
	6 1/2	5 6	23 9	25 6	34 6	39 6	42
	4	4 6	15	16 3	19 6	21	21 6
	4 1/2	5 6	16 3	17 6	21 3	23 6	24
	4 3/4	4 6	17 9	18 6	22 9	25 3	26 6
	4 1/2	5 6	19 3	21 6	25 3	28 3	29 6
T 5753	5	4 6	19 9	21 3	26 6	29	30 3
	5 1/2	5 6	21 6	22 6	29	32 9	34 3
	6	4 6	25 6	27 3	34 6	38 6	40 9
	6 1/2	5 6	27 6	29 6	38 6	43 6	45 6
	4	4 6	18 6	19 9	23 6	25	25 6
	4 1/2	5 6	19 9	21 3	25 3	27	27 6
T 5755	4 3/4	4 6	21 3	22 6	27	28 9	42
	4 1/2	5 6	22 9	24	29 6	31 9	33
	5	4 6	24	25 6	30 6	33	34 6
	5 1/2	5 6	25 6	27 6	33	37 3	38 6
	6	4 6	30	31 9	39	43 3	45 6
	6 1/2	5 6	31 10	33 6	42 6	48	50 6
T 5756	4	4 6	22 6	23 9	27	28 6	29 6
	4 1/2	5 6	23 9	24 6	28 9	30 6	31 6
	4 3/4	4 6	25 6	26 6	30 6	33	34 3
	4 1/2	5 6	27	28 3	33	36	37 3
	5	4 6	28 3	30	34 6	37 3	38 6
	5 1/2	5 6	30	31 3	37 3	40 9	42 6
	6	4 6	34 6	36 3	43 6	47 9	49 9
	6 1/2	5 6	36 6	38 6	47 6	52 6	54 6
	7	4 6	43 6	46 3	55 6	61 3	64 9
	8	4 6	46 3	49 3	61 3	67 6	71 6
	8 1/2	5 6	55 3	57 6	71 6	78	84
	8	5 6	58 6	62 6	78 6	87	91

Extra charge for Newels with two squares


Sizes.	4	4 1/2	5	6	7	8 ins.
Prices.	1	1 3	1 4	1 10	2 3	2 9

SQUARE CUT BALUSTERS. UP TO 3 FEET LONG.

PRICES, PER DOZEN.


Pattern Nos.	Size.	Yellow Deal and Pine.	Pitch Pine.	Canary Whitewood.	Mahogany.	Oak.	Walnut Teak.
T 5760	12 ins.	6 9	7 6	8 9	12 6	13 6	14 3
	1 1/2	8 3	9	10 3	16 9	18	18 6
	2	10 6	11 6	12 6	21 6	23 6	24
	2 1/2	15	16 3	18 6	29 6	31 3	32 6
	3	8	19 3	21 6	35 9	37 9	39
	3 1/2	24 6	26 6	30 6	37 6	53 6	54 6
T 5761	1 1/2	7 6	8 6	9 3	13	14 6	15
	1 1/2	9	9 6	10 9	17 9	18 6	19 6
	2	11 6	12	13 6	22 6	24	25
	2 1/2	16 3	17 6	19 6	30 3	32 6	33 3
	3	19 3	20 6	22 9	36 6	39	40 3
	3 1/2	26 6	27 6	32 6	51 3	55	56 6
T 5763	1 1/2	10 3	10 9	12	15 6	16 9	17 9
	1 1/2	10 9	12 3	13 6	20 6	21 6	22 6
	2	13 9	14 6	16 3	25 3	26 9	27 6
	2 1/2	17 6	18 6	20 9	31 6	33 3	34 6
	3	21 6	22 9	25 6	39 3	41 9	42 6
	3 1/2	28 9	30 3	35	54	57 3	59
T 5764	1 1/2	13 3	13 9	15	18 6	19 9	20 6
	1 1/2	14 6	15 3	16 6	23 6	24 3	25 3
	2	16 9	17 9	19 3	28 3	29 9	30 6
	2 1/2	20 6	21 3	23 9	34 6	36 3	37 6
	3	24 6	25 9	28 6	42 6	44 6	45 6
	3 1/2	32	33 3	37 6	57	60 6	63
T 5765	1 1/2	21 6	22 6	23 9	27 3	28 6	29 6
	1 1/2	23 6	24	25 3	31 9	33	34
	2	25 6	26 6	27 6	37 3	38 9	39
	2 1/2	28 9	30	32 6	43 3	45	46 3
	3	33 3	34 6	37 3	51	53 6	54 6
	3 1/2	40 6	42	46 6	65 9	69	70 6

# Square Turned Wood Balusters



3 feet long.

## PRICES, PER DOZEN.




No. 109, BALUSTERS worked on rake to any pitch.

Quotations given upon receipt of details of quantities required.

	Size.	Deal.	P. Pine.	Mahogany.	Oak.	Walnut.
SB 80, 81	Ex. 1 1/2 ins.,	8 6	12 3	15 -	15 9	16 6
	" 1 1/2 "	11 -	14 6	18 -	18 9	21 -
	" 2 "	12 -	16 -	21 -	22 6	23 3
SB 82	" 1 1/2 "	9 4 1/2	13 1 1/2	15 -	16 6	18 -
	" 1 1/2 "	12 9	15 3	19 6	20 3	22 6
	" 2 "	13 6	16 10 1/2	21 9	22 6	24 9
SB 83, 84, 85, 86	" 1 1/2 "	11 3	13 6	17 3	18 -	19 6
	" 1 1/2 "	12 9	15 -	20 3	21 -	23 3
	" 2 "	13 6	17 3	21 9	22 6	24 9
SB 90, 91	" 1 1/2 "	12 9	14 3	18 9	19 6	21 9
	" 1 1/2 "	14 3	16 6	22 6	23 3	26 3
	" 2 "	15 9	18 -	24 -	24 9	27 9
SB 92	" 1 1/2 "	16 6	18 9	22 6	23 3	24 9
	" 1 1/2 "	18 9	22 6	27 -	27 9	30 -
	" 2 "	20 3	24 -	28 6	30 -	32 3
SB 93	" 1 1/2 "	16 6	18 -	23 3	24 -	25 6
	" 1 1/2 "	18 9	22 6	27 -	27 9	30 -
	" 2 "	20 3	24 -	30 -	31 6	33 -
SB 94	" 2 1/2 "	26 3	31 6	40 6	43 6	48 -
SB 95, 96	" 1 1/2 "	16 6	19 6	24 -	25 6	27 -
	" 1 1/2 "	19 6	22 6	30 -	31 6	36 -
	" 2 "	21 -	24 9	33 -	34 6	37 6
SB 99	" 2 1/2 "	18 9	24 -	33 -	34 6	39 -
	" 2 1/2 "	21 -	27 9	39 -	42 -	46 6
	" 2 1/2 "	24 9	28 6	33 -	34 6	37 6
SB 100	" 2 1/2 "	30 -	36 -	45 -	46 6	51 -
	" 2 1/2 "	39 -	45 -	54 -	57 -	61 6
SB 103	" 3 1/2 x 2 ins.,	31 6	36 -	48 -	51 -	54 -
	" 3 1/2 x 3 1/2 "	63 -	72 -	90 -	93 -	97 6
	" 4 1/2 x 2 1/2 "	69 -	78 -	96 -	99 -	105 -
SB 106 Panels 4 Sides	" 4 x 4 "	90 -	102 -	120 -	124 6	129 -
	" 4 x 2 "	49 6	60 -	81 -	84 -	87 -
	" 4 x 2 "	60 -	69 -	90 -	93 -	96 -

# Wood Hand Rails and Brackets



No. WH 1.



No. WH 2.



No. WH 3.



No. WH 42.



No. WH 5.



No. WH 6.




No. WH 32.




No. WH 33.




No. WH 34.



No. WH 27.



No. WH 28.



No. WH 29.

PRICES, PER 100 FEET RUN.

Pattern WH.	Size.	Deal.	P. Pine.	Mahogany.	Oak.	Walnut.
Nos. 1 or 2.	EX. 2½ x 2 ins.	26/3	40/-	82/6	82/6	120/-
.. 1 or 2.	.. 3 x 2 ..	26/3	42/6	90/-	90/-	127/6
No. 3.	.. 2 x 3 ..	42/-	50/6	109/6	109/6	132/-
.. 3.	.. 3½ x 2 ..	45/-	54/9	120/-	120/-	142/6
.. 42.	.. 4 x 2 ..	39/-	59/3	90/-	90/-	120/-
.. 5.	.. 3½ x 2½ ..	55/6	94/6	165/-	172/6	180/-
.. 5.	.. 4 x 3 ..	72/-	113/6	195/-	210/-	225/-

Pattern WH.	Size.	Deal.	P. Pine.	Mahogany.	Oak.	Walnut.
No. 6.	EX. 3½ x 2½ ins.	63/-	105/-	174/-	183/-	192/-
.. 32.	.. 3 x 2½ ..	29/6	54/9	112/6	120/-	135/-
.. 33.	.. 3½ x 2½ ..	48/-	59/3	127/6	142/6	150/-
.. 34.	.. 3½ x 2½ ..	54/-	63/3	157/6	165/-	180/-
.. 27.	.. 4 x 3½ ..	90/-	168/9	240/-	255/-	300/-
.. 28.	.. 4 x 3 ..	97/6	185/9	265/-	270/-	314/6
.. 29.	.. 4 x 3½ ..	135/-	185/9	265/-	270/-	314/6

## Carved Brackets



No. CW 1.



No. CW 2.



No. CW 3.



No. CW 4.


PRICES, EACH.

No.	Size.	Deal.	P. Pine.	Mahogany.
CW 1 or 2.	9½ x 3 x 3 ins.	1/-	1/4	1/8
CW 1 or 2.	12 x 4 x 4 ..	2/-	3/-	4/-
CW 3.	9½ x 3 x 3 ..	1/6	2/-	2/6
CW 3.	12 x 4 x 4 ..	2/6	3/4	4/3
CW 4.	12 x 3 x 4 ..	3/-	4/-	5/-
CW 4.	15 x 4 x 5 ..	4/6	5/9	6/8

These patterns can be made to any size or length.  
Price upon application.

## Fret-cut Stair Brackets

FOR 9-INCH TREADS.



No. T 5.



No. T 6.



No. T 7.



No. T 8.

PRICES, PER DOZEN

No.	Size.	Deal.	P. Pine.	Oak, Mahogany or Walnut.
No. T 5.	.. ..	4/3	5/9	7/6
.. T 6 or 8.	.. ..	6/9	9/-	10/9
.. T 7. Carved	.. ..	31/6	33/-	45/-

# Carved Wood Overdoors

AMERICAN WHITEWOOD.

No. T 6580.




Up to 38 inches wide. Price, 6 - each.

No. T 6581.



Up to 38 inches wide. Price, 9 - each.

No. T 6582.




Up to 40 inches wide. Price, 9½ - each.

No. T 6583.



Up to 40 inches wide. Price, 9 - each.

No. T 534.




Up to 42 inches wide. Price, 9½ - each.

No. T 540.



Up to 42 inches wide. Price, 9 - each.

No. T 5500.




Up to 40 inches wide. Price, 10 6 each.

No. T 562.




Up to 42 inches wide. Price, 19 6 each.

No. T 6584.



Up to 42 inches wide. Price, 21 - each.

No. T 6585.




Up to 42 inches wide. Price, 21 - each.


Above made to order in any other wood. Prices upon application.

# Carved Caps, Bases, Brackets and Corners


FOR SHOP FITTINGS.





No. T 5520.



No. T 5521.




No. T 5519.



No. T 5510.



No. T 5511.




No. T 5512.

No.	Size.	Description.	Mahogany, Oak, or Walnut.	White wood.
No. T 5510.	12 x 12 ins.	Carved Face and Moulded Edge.	8	7 3
„ T 5511.	15 x 15 „	„ „ „	11 3	10 6
„ T 5512.	10 x 10 „	Fret Panels.	2 8	2 1
	15 x 15 „	„ „ „	4 -	3 3

No.	Description	Size.	Price, Mahogany, Oak, or Walnut.
T 5513.	Plain Turned Cap.	Ex. 6 x 6 ins., „ 5 x 5 „ „ 4 x 4 „ „ 3 x 3 „	3 9 each. 3 - „ 2 - „ 1 6 „
T 5514.	Turned and Carved Cap.	„ 6 x 6 „ „ 5 x 5 „ „ 4 x 4 „ „ 3 x 3 „	10 9 „ 9 - „ 6 - „ 3 9 „
T 5518.	„	„ 6 x 6 „ „ 5 x 5 „	27 6 „ 22 6 „
T 5515.	„	„ 5 x 5 „	17 6 „
T 5516.	„	„ 4 x 4 „	13 6 „
T 5517.	„	„ 3 x 3 „	10 - „
T 5519.	Base Carved.	„ 6 x 6 „ „ 5 x 5 „ „ 4 x 4 „ „ 3 x 3 „	13 - „ 11 - „ 8 3 „ 4 9 „
T 5520.	Base Turned only.	„ 6 x 6 „	4 - „
T 5521.		„ 5 x 5 „	3 - „
		„ 4 x 4 „ „ 3 x 3 „	2 3 „ 1 6 „

All Bases are priced as 8 inches long, but we can supply longer to order.

## Fretwork Brackets to form Arches



No. T 6586.  
Size, 24 x 24 ins.  
Price, .. 12/- per pair.



No. T 6587.  
Size, 24 x 24 ins.  
Price, .. 12 - per pair.



No. T 6588.  
Size, 24 x 24 ins.  
Price, .. 9 - per pair.




No. T 6589.  
Size, 24 x 18 ins.  
Price, .. 9/- per pair.

Ex. 1-in. American Whitewood, finished, ready for Painting.




# Fretwork Arches



No. FW 51.

Size.	Price.
48 x 30 inches.	19 6 each.
60 x 30 "	23 9 "
72 x 30 "	27 6 "


Fretwork, ex. 1 inch Whitewood, other parts Yellow Deal, cleaned, ready for painting.



No. FW 6576.

Size.	Price.
48 x 28 inches.	27 - each.
60 x 28 "	33 - "
72 x 30 "	39 9 "


Fretwork, ex. 1 inch Whitewood, other parts Yellow Deal, cleaned, ready for painting.



No. FW 50.

Size.	Price.
48 x 30 inches.	21 - each
60 x 30 "	25 6 "
72 x 30 "	30 - "


Fretwork, ex. 1 inch Whitewood, other parts Yellow Deal, cleaned, ready for painting.



No. FW 6577.

Size.	Price.	Without Top Panel, as A to B.
48 x 24 inches.	21	16 6 each.
60 x 24 "	25 6	21 - "
72 x 24 "	30	24 - "


Fretwork, ex. 1 inch Whitewood, other parts Yellow Deal, cleaned, ready for painting.



No. FW 6578.

Size.	Price.	Without Top Panel, as A to B.
48 x 27 inches.	22 6	18 - each.
60 x 27 "	27 6	22 6 "
72 x 27 "	33 -	26 9 "
60 x 36 "	33 -	26 9 "
72 x 36 "	39 6	31 6 "

Fretwork, ex. 1 inch Whitewood, other parts Yellow Deal, cleaned, ready for painting.




No. FW 6579.

Size.	Price.
48 x 30 inches.	18 - each.
60 x 30 "	22 6 "
72 x 30 "	27 - "
60 x 42 "	33 - "
72 x 42 "	37 6 "

Fretwork, ex. 1 inch Whitewood, other parts Yellow Deal, cleaned, ready for painting.

## Hall Fitments



No. 6708.

No. 6708.

### FRET WORK

EX 1 INCH AMERICAN WHITEWOOD.

Box Base. 9-inch Linings. 12-inch Top.  
Cleaned up ready for painting or enamelling.

Size, 9 x 5 feet.

Price, .. .. £4 17 6

Any size made to order at proportionate prices.

See also pages 327 and 328.

No. 6709.

### FRET WORK

EX 1 INCH AMERICAN WHITEWOOD.


Box Base. 9-inch Lining. 12-inch Top.  
Carved Panels.  
Cleaned up, ready for painting or enamelling.

Size, 9 x 7 feet.

Price, with Pediment, .. £7 10 0

„ without „ .. .. 6 19 6

Fret cutting and carving of all descriptions carried out  
to customers' or architects' designs.



No. 6709.

# Architrave, Dado and Picture Mouldings

BEST YELLOW DEAL. OUR OWN MANUFACTURE.

PRICES, PER 100 FEET RUN.



No. T 5575.  
Size.  
Ex.  $1 \times 2\frac{1}{2}$  ins., 5/3  
" 1 3 " 6/-



No. T 5576.  
Size.  
Ex.  $1 \times 2\frac{1}{2}$  ins., 6/-  
" 1 3 " 6/3  
" 1 4 " 9/-  
"  $1\frac{1}{2} \times 4$  " 10/9



No. T 5577.  
Size.  
Ex.  $1 \times 2\frac{1}{2}$  ins., 6/-  
" 1 3 " 6/3  
" 1 4 " 9/-  
"  $1\frac{1}{2} \times 4$  " 10/9



No. T 6050.  
Size.  
Ex.  $1 \times 2\frac{1}{2}$  ins., 6/-  
" 1 3 " 6/3  
" 1 4 " 9/-  
"  $1\frac{1}{2} \times 4$  " 10 9



No. T 6051.  
Size.  
Ex.  $1 \times 3$  ins., 7/3  
" 1 4 " 10/3  
"  $1\frac{1}{2} \times 4$  " 12/-



No. T 6052.  
Size.  
Ex.  $1 \times 3$  ins., 7/3  
" 1 4 " 10/3  
"  $1\frac{1}{2} \times 4$  " 12/-



No. T 6450.  
Size.  
Ex.  $1 \times 3$  ins., 7/3  
"  $1\frac{1}{2} \times 3$  " 9/-  
"  $1\frac{1}{2} \times 4$  " 12/-



No. T 6451.  
Size.  
Ex.  $1 \times 3$  ins., 6 3  
"  $1\frac{1}{2} \times 3$  " 8 -  
"  $1\frac{1}{2} \times 4$  " 10 9



No. T 6452.  
Size.  
Ex.  $1 \times 3$  ins., 6/3  
"  $1\frac{1}{2} \times 3$  " 8/-  
"  $1\frac{1}{2} \times 4$  " 10/9



No. T 6055.  
Size.  
Ex.  $3\frac{1}{2} \times 1\frac{1}{2}$  ins., 13/-




No. T 6056.  
Size.  
Ex.  $3 \times 2$  ins., 7/3



No. T 6057.  
Size.  
Ex.  $3 \times 1$  ins., 8/-



No. T 6058.  
Size.  
Ex.  $2\frac{1}{2} \times 1$  in., 7/3



No. T 6454.  
Size.  
Shelf, ex.  $1\frac{1}{2} \times 3\frac{1}{2}$  ins., 14 6  
Moulding, "  $1\frac{1}{2} \times 2\frac{1}{2}$  " 9 9



No. T 6453.  
Size.  
Ex.  $3 \times 1\frac{1}{2}$  ins., 9/-



No. T 1403.  
Size.  
Ex.  $2\frac{1}{2} \times 1$  in., 6 3



No. T 1401.  
Size.  
Ex.  $2\frac{1}{2} \times 1$  in., 5 9  
" 2 1 " 5 6




No. T 6059.  
Size.  
Ex.  $2\frac{1}{2} \times 1$  in., 6/3  
" 2 x 1 " 5 9




No. T 6455.  
Size.  
Ex.  $2\frac{1}{2} \times 1\frac{1}{2}$  ins., 8 -  
"  $2\frac{1}{2} \times 1$  " 6 3

# Bolection and Panel Mouldings

BEST YELLOW DEAL.




No. M 204. Price, 9 6




No. M 203. Price, 8 -



No. M 93. Price, 8 -




No. M 206. Price, 12 6




No. M 96. Price, 9 6




No. M 95. Price, 6 7



No. T 6448. Price, 12 6



No. T 6449. Price, 11 6



No. T 6487. Price, 10 -



No. T 6418. Price, 4 -



No. T 6419. Price, 3 -



No. T 6420. Price, 4 3



No. T 6421. Price, 3 3



No. M 104. Price, 4 3



No. M 103. Price, 3 9



No. M 1234. Price, 5 -



No. M 1236. Price, 4 9



No. M 1235. Price, 4 -



No. M 13. Price, 3 7



No. M 14. Price, 2 11



No. M 15. Price, 2 5

# Prepared Sash and Frame Material

FOR 1½, 1¾, AND 2 INCH SASHES AND FRAMES. SELECTED YELLOW DEAL.

**Prepared Lining.**



No. M 260 B. Ex. ½ × 4½ ins., 7/8 per 100 feet run.

**Prepared Lining.**




No. M 260 A. Ex. ½ × 4½ ins., .. 7/8 per 100 feet run.  
 „ T 6460. „ ½ × 4 „ .. 6/6 „ „

**Back Lining.**



No. M 251. Ex. ½ × 4½ ins., .. 3/9 per 100 feet run.  
 „ M 267. „ ½ × 5½ „ .. 4/- „ „  
 „ T 6461. „ ½ × 6 „ .. 4/9 „ „

**Pulley Stile**




No. M 259 B. Ex. 1 × 4 ins., .. 8/3 per 100 feet run  
 „ M 272 B. „ 1 × 4½ „ .. 9/- „ „  
 „ T 6713. „ 1 × 5 „ .. 11/- „ „

**Way Tail.**




No. M 258. Price, 1/8

**Sill**



No. M 257. Ex. 3 × 5 ins., .. 31/6 per 100 feet run.  
 „ M 270. „ 3 × 5½ „ .. 34/6 „ „  
 „ T 6466. „ 3 × 6 „ .. 39/6 „ „

**Stile.**



No. M 253. Ex. 1½ × 2 ins., .. 9/- per 100 feet run.  
 „ M 266. „ 1½ × 2½ „ .. 11/3 „ „  
 „ T 6462. „ 2 × 2½ „ .. 13/6 „ „


**Meeting Rails.**



No. M 261. Ex. 1½ × 1½ ins., .. 8/3 per 100 feet run.  
 „ M 275. „ 1½ × 2 „ .. 10/3 „ „  
 „ T 6463. „ 1½ × 2½ „ .. 12/6 „ „  
 „ M 262. „ 1½ × 1½ „ .. 8/3 „ „  
 „ M 274. „ 1½ × 2 „ .. 10/3 „ „  
 „ T 6464. „ 1½ × 2½ „ .. 12/6 „ „


NOTE.—Nos. M 275 and M 274 match Stile No. M 266.  
 No. T 6463 and T 6464 match Stile No. T 6462.

**Bottom Rail.**



No. M 252. Ex. 1½ × 3½ ins., .. 14/6 per 100 feet run.  
 „ M 265. „ 1½ × 4 „ .. 16/6 „ „  
 „ M 6465. „ 2 × 4 „ .. 19/6 „ „

**Bars.**




No. M 211. No. SB 210. No. SB 215.  
 4/9 6/- 6/10  
 per 100 feet run. per 100 feet run. per 100 feet run.

# Solid Casement Frame Material, Jamb Lining and Door Stops


BEST YELLOW DEAL.

PRICES, PER 100 FEET RUN.




No. T 6467. Jambs and Head.

Size.  
Ex.  $3 \times 4\frac{1}{2}$  ins., .. 43/9  
..  $3 \times 4$  .. .. 37/6




No.  
T 6468.

Jamb  
Lining.



No. T 6469. Mullion.


Size.  
Ex.  $3 \times 4\frac{1}{2}$  ins., .. 45/-  
..  $3 \times 4$  .. .. 38/6



No. T 6470. Sill.


Size.  
Ex.  $3 \times 4\frac{1}{2}$  ins., .. 43/9  
..  $3 \times 4$  .. .. 37/6

Size.  
Ex.  $1\frac{1}{2} \times 6$  ins., 22/6  
..  $1\frac{1}{2} \times 5\frac{1}{2}$  .. 21/-  
..  $1\frac{1}{2} \times 4\frac{1}{2}$  .. 18/-  
Size.  
Ex.  $1\frac{1}{4} \times 6$  ins., 19/6  
..  $1\frac{1}{4} \times 5$  .. 17/-  
..  $1\frac{1}{4} \times 4\frac{1}{2}$  .. 15/6



No. T 6471. Door Stop.

Size.  
Ex.  $\frac{3}{4} \times 2\frac{1}{2}$  ins., .. 6/-  
..  $\frac{3}{4} \times 2$  .. .. 4/6  
..  $\frac{3}{4} \times 1\frac{1}{2}$  .. .. 3/6




No. T 6472. Door Stop.

Size.  
Ex.  $\frac{3}{4} \times 2\frac{1}{2}$  ins., .. 6/3  
..  $\frac{3}{4} \times 2$  .. .. 4/9  
..  $\frac{3}{4} \times 1\frac{1}{2}$  .. .. 3/9



No. T 6473. Door Stop

Size.  
Ex.  $\frac{3}{4} \times 2\frac{1}{2}$  ins., .. 6/3  
..  $\frac{3}{4} \times 2$  .. .. 4/9  
..  $\frac{3}{4} \times 1\frac{1}{2}$  .. .. 3/9




No. T 6474. Transom.

Size.  
Ex.  $3 \times 4\frac{1}{2}$  ins., .. 44/6  
..  $3 \times 4$  .. .. 39/-

Special Quotations for Large Quantities.


# Skirtings, Cornices, Nosing, Rounds and Beads

BEST YELLOW DEAL. PRICES, PER 100 FEET RUN.



No. T6475.

Size.  
Ex. 1x9 ins., 27/6  
,, 1x7 .. 18/9




No. T6476.

Size.  
Ex. 1x9 ins., 27/6  
,, 1x7 .. 18/9




No. T6477.

Size.  
Ex. 1x9 ins., 27/6  
,, 1x7 .. 18/9




No. T6478.

Size.  
Ex. 1x9 ins., 27/6  
,, 1x7 .. 18/9  
,, 1x7 .. 13/6



No. M193. 7/2



No. M194. 17/3



No. M195. 6/8




No. M307. 8/-



No. M308. 5/-



No. M232. 3/6




No. M283.


No. M289. 1/2 in., 2/1  
,, M282. 3/4 .. 2/9  
,, M281. 1 .. 2/11  
,, M276. 1 1/4 .. 3/7  
,, M278. 1 1/2 .. 5/8  
,, M287. 1 3/4 .. 6/3  
,, M283. 1 3/4 .. 9/-  
,, M286. 1 1/2 .. 9/11  
,, M288. 2 .. 12/-



No. M226. 6/3



No. M227. 6/7



No. M309. 4/6



No. M221. 2/4



No. M222. 2/9



No. M1306. 2/9




No. M1253. 3/6




No. M240. 2/-



No. M241. 1/10



No. M231. 2/-




No. M362.


No. M364. 1/2 in., 4/-  
,, M363. 3/4 .. 4/3  
,, M362. 1 .. 4/3  
,, M361. 1 1/4 .. 7/-  
,, M360. 1 1/2 .. 9/6

# Best Yellow Horticultural Bars and Prepared Timber


STANDARD LIST.—PRICED PER 100 FEET RUN.




No. SB 220.  
Price, 53



No. SB 1.  
Price, 69




No. SB 217.  
Price, 76




No. SB 8.  
Price, 83



No. SB 9.  
Price, 99




No. SB 10.  
Price, 106




No. SB 12. Price 12

No. M 23, Ridge.

Sizes,  $1\frac{1}{2} \times 6$   $1\frac{1}{2} \times 7$  ins.  
Prices, 27 6 34 6




No. M 3, Ventilator Stile and Top Rail.




Sizes, ..  $1\frac{1}{2} \times 2$   $1\frac{1}{2} \times 2\frac{1}{2}$   $1\frac{1}{2} \times 3$  ins.  
Prices, .. 9 9 12 15 6

No. M 15, Ventilator Seat.




Size, ..  $1\frac{1}{2} \times 2\frac{1}{2}$  ins.  
Price, .. 12

No. M 7, Pit Light Stile and Top Rail.



Size, ..  $2 \times 3$  ins.  
Price, .. 17 3

No. 6 M, Pit Light Bottom Rail.




Sizes, ..  $1\frac{1}{2} \times 4\frac{1}{2}$   $1 \times 4$  ins.  
Prices, .. 16 6 11 9

No. M 24, Capping.




Sizes, ..  $1 \times 4$   $1\frac{1}{2} \times 4$  ins.  
Prices, .. 13 6 16 6

No. 13 M, End Rafter.




Sizes, ..  $2\frac{1}{2} \times 3$   $3 \times 3$  ins.  
Prices, .. 23 6 28 6

No. M 11, Strengthening or Division Rafter.



Sizes, ..  $2\frac{1}{2} \times 3$   $3 \times 3$  ins.  
Prices, .. 23 6 28 6

No. M 17, Side Plate.



Sizes, ..  $3 \times 3$   $8 \times 4$  ins.  
Prices, .. 28 6 37 6

Any Section made to Order

Special Quotations for large Quantities.




# The Patent Safety Extension Ladder

Invaluable to Builders, Painters, Sign Writers, Decorators, Window Cleaners, Gardeners, Hotel Proprietors and others, being simple, strong, safe and light.

THE SIMPLEST AND MOST RELIABLE EXTENSION LADDER MANUFACTURED.

This Ladder, owing to its special construction, is the simplest and most reliable extension ladder on the market. There are no complicated catches, springs, screws or hinges to work loose, and no mechanism to get out of order. The working of it is simplicity itself. There is no fixing or arranging in position; immediately the Ladder is raised to the required height (which can easily be done by ONE man with any ladder up to 56 rungs), a simple automatic retaining hook is set free and must necessarily fall into its proper position, firmly securing the Ladder. The best Archangel joinery deals and seasoned English oak rungs are used in the manufacture. The retaining hooks are made of the best malleable iron. Each Ladder is made in two detachable lengths. If a short ladder only is required the bottom length is used, when a longer one is needed the bottom ladder is first raised, the extension piece is then placed on the top and pulled up with the cord. The extension piece will slide easily up a wall or tree, or the Ladder may be held perpendicularly and raised without support, and adjusted to the desired height. All Ladders are sized and varnished before delivery so that the quality of the materials can be seen.



No. T 5528. TWO SECTION.										No. T 5529. THREE SECTION.		
Ref. Letter.	O	D	E	F	G	H	I	J	K	L	M	N
Size, ..	16	18	20	24	28	32	36	40	48	50	59	68
Height closed, 6	7½	8	9½	11	12½	14	15½	18½	13½	15½	18	feet.
Extends to .. 11	13	14½	17½	20½	22½	26	29	34½	33½	40½	46½	..
Varnished, .. 30	36 9	41 3	53 3	66 9	77 3	89 3	107	130 6	150	183 9	219	- per set.

Ladders E to N have rope and pulley attachment as illustration. When extreme lightness is required, we supply a specially light make at the same price. Carriage paid to any station in the United Kingdom.  
NOTE: The top section of Ladder K and all three sections of Ladders M and N have a steel cable inserted in the back. This adds greatly to the rigidity of the Ladder; for this no extra charge is made.

# The Patent Safety Extension Step Ladder


A LONG-FELT WANT SUPPLIED. COMBINED STEP AND EXTENSION LADDER.  
ESSENTIAL FOR ALL ESTABLISHMENTS.

Used as steps, automatically opens and locks. When done with, closes itself. To use as a ladder, slide up the back part and let the hooks catch. Lowered just as easily. No complicated parts. Best materials used in manufacture. All stained and varnished before delivery. Light, strong and safe.

Delivery: Light, strong and safe.


No. T 5759.						
Reference Letter,	A	B	C	X	Y	Z
No. of Steps as Step Ladder,	5	6	7	8	9	10
.. .. in Ladder,	9	11	13	15	17	19
Height closed,	4½	5	6	6½	7½	8½ feet.
.. extended,	6½	8½	10	11½	13	15 ..
Prices,	18 -	20 3	22 6	30 -	39 -	43 6 per set.

Carriage paid on all orders to any station in the United Kingdom.  
Kindly state reference letter when ordering.



# Extending Trellis


FLAT PLANED



Nos., ..	1	2	3	4	5	6	7	8	9	10	11
Size (open), ..	12x1	12x1½	12x2	12x2½	12x3	12x3½	12x4	12x4½	12x5	12x5½	12x6 ft.
Prices, per piece											
3½ in. Mesh, 9½	1 1½	1 6	1 10½	2 3	2 7½	3 -	3 4½	3 9	4 1½	4 6	
2½ .. ..	1 -	1 6	2 -	2 6	3 -	3 6	4 -	4 6	5 -	5 6	6 -

The Flat Trellis folds up into a very small compass, the laths being 1 inch wide by ¾ inch thick, planed, and every joint riveted.

ORNAMENTAL, HALF-ROUND.



Nos., ..	1	2	3	4	5	7	9	11
Size (open), ..	12x1	12x1½	12x2½	12x2½	12x3	12x4	12x5	12x6 ft.
Prices, per piece,	1 9	2 3	3 6	4 3	4 9	6 6	7 6	9 -

This Trellis is made of best Swedish yellow wood, the laths being about 1 inch wide by ¾ inch thick in the centre. It closes and extends similar to ordinary trellis—but is stronger made, much easier to paint, and requires less paint.

**TRELLIS RAILS.** Of 2x1½ inch Yellow Deal. Prepared and grooved for flat trellis.  
Prices, per 100 feet run - Top Rail, 10 -; Bottom Rail, 10 -; Outside Posts, 10 -; Inside Posts, 11 3

# Cleft Chestnut Paling Fencing

This Paling is of British material and manufacture throughout. The timber is home grown, the pales being cleft with the grain from hard slow grown chestnut poles. The wires are of best annealed drawn steel galvanized, which will not break in twisting. The fence is woven by machinery and made up in bundles containing 10 yards of any fence up to 4 ft. 6 ins. high, or 6 yards of any fence 5 ft. high or over.

**PALES.**—These are placed as near as possible at the distances apart stated on the list, which are calculated on the following basis:—

About 5 ins. apart—84 Pales in 10 yards. | About 2 ins. apart—86 Pales in 10 yards  
" 3 " " 75 " 10 " | " 1 1/2 " " 117 " 10 "

If almost absolute regularity is wanted, specially selected pales can generally be put in at an extra cost of 10 per cent.


**WIRES.**—Four wires tightly twisted together form each complete strand. Every pale is stapled to one of the fence wires.

**INTERMEDIATE POSTS AND STRAINING POSTS.** If more posts are required than are included in price of fence, the price each of the additional ones will be as under:—

Height of Fence, .. 2 2 1/2 3 3 1/2 4 4 1/2 5 5 1/2 6 ft.  
Intermediate Post, .. 7 1/2 8 1 9 1 11 1 13 1 14 1 17 1/2  
Straining Post and Strut, 3 1/2 3 9 4 1 4 6 5 3 6 9 7 6 8 3 9

STAPLES for attaching wires to posts are included in price of fence including posts.

No. T 6056. FENCING, with Two Lines of Wire. All pales full height of fence.



PRICES PER YARD, INCLUDING POSTS.\*

Height of Fence.	Distance apart of Pales.			
	5 Ins.	3 Ins.	2 Ins.	1 1/2 Ins.
2 ft. 0 ins.	1 1/4	1 1/4	1 1/4	1 9/16
2 " 6 "	1 1/2	1 1/2	1 1/2	1 11/16
3 " 0 "	1 3/4	1 3/4	1 3/4	1 13/16
3 " 6 "	1 5/8	1 5/8	1 5/8	1 15/16
4 " 0 "	1 7/8	1 7/8	1 7/8	2 1/16
4 " 6 "	1 10/16	1 10/16	1 10/16	2 1/8
5 " 0 "	2 1/8	2 1/8	2 1/8	2 1/4
5 " 6 "	2 1/4	2 1/4	2 1/4	2 5/8
6 " 0 "	2 5/8	2 5/8	2 5/8	3 1/8

PRICES PER YARD, WITHOUT POSTS.

Height of Fence.	Distance apart of Pales.			
	5 Ins.	3 Ins.	2 Ins.	1 1/2 Ins.
2 ft. 0 ins.	1 1/4	1 1/4	1 1/4	1 6/16
2 " 6 "	1 1/2	1 1/2	1 1/2	1 8/16
3 " 0 "	1 3/4	1 3/4	1 3/4	1 10/16
3 " 6 "	1 5/8	1 5/8	1 5/8	1 12/16
4 " 0 "	1 7/8	1 7/8	1 7/8	1 14/16
4 " 6 "	1 10/16	1 10/16	1 10/16	2 1/16
5 " 0 "	2 1/8	2 1/8	2 1/8	2 1/8
5 " 6 "	2 1/4	2 1/4	2 1/4	2 3/8
6 " 0 "	2 5/8	2 5/8	2 5/8	2 5/8


No. T 6057. FENCING, with Three Lines of Wire. All pales full height of fence.

PRICES PER YARD, INCLUDING POSTS.

Height of Fence.	Distance apart of Pales.			
	5 Ins.	3 Ins.	2 Ins.	1 1/2 Ins.
2 ft. 6 ins.	1 1/4	1 1/4	2 1/10	2 1/16
3 " 0 "	1 1/6	1 1/6	2 1/10	2 1/8
3 " 6 "	1 5/8	1 5/8	2 1/4	2 1/8
4 " 0 "	1 11/16	1 11/16	2 3/4	2 11/16
4 " 6 "	2 0/16	2 0/16	2 11/16	3 1/16
5 " 0 "	2 1/5	2 1/5	3 3/8	3 1/8
5 " 6 "	2 1/8	2 1/8	3 3/8	4 1/8
6 " 0 "	3 0/8	3 0/8	4 3/8	5 1/8

PRICES PER YARD, WITHOUT POSTS

Height of Fence.	Distance apart of Pales.			
	5 Ins.	3 Ins.	2 Ins.	1 1/2 Ins.
2 ft. 6 ins.	1 1/16	1 1/16	1 7/16	1 10/16
3 " 0 "	1 3/16	1 3/16	1 9/16	2 0/16
3 " 6 "	1 4/16	1 4/16	2 1/16	2 3/16
4 " 0 "	1 5/16	1 5/16	2 2/16	2 6/16
4 " 6 "	1 7/16	1 7/16	2 6/16	2 11/16
5 " 0 "	1 11/16	1 11/16	2 9/16	3 3/16
5 " 6 "	2 1/16	2 1/16	3 3/16	3 11/16
6 " 0 "	2 3/16	2 3/16	3 8/16	4 6/16



No. T 6058. FENCING, with Four Lines of Wire. All pales full height of fence.

PRICES PER YARD, INCLUDING POSTS.

Height of Fence.	Distance apart of Pales.			
	5 Ins.	3 Ins.	2 Ins.	1 1/2 Ins.
3 ft. 6 ins.	1 1/16	2 2/16	2 6/16	2 10/16
4 " 0 "	2 1/16	2 5/16	2 9/16	3 1/16
4 " 6 "	2 3/16	2 8/16	3 1/16	3 5/16
5 " 0 "	2 7/16	3 2/16	3 5/16	3 11/16
5 " 6 "	2 10/16	3 4/16	4 1/16	4 7/16
6 " 0 "	3 1/16	3 10/16	4 6/16	5 4/16

PRICES PER YARD, WITHOUT POSTS.


Height of Fence.	Distance apart of Pales.			
	5 Ins.	3 Ins.	2 Ins.	1 1/2 Ins.
3 ft. 6 ins.	1 6/16	1 10/16	2 2/16	2 6/16
4 " 0 "	1 8/16	2 0/16	2 5/16	2 9/16
4 " 6 "	1 9/16	2 3/16	2 8/16	3 1/16
5 " 0 "	2 1/16	2 6/16	3 1/16	3 5/16
5 " 6 "	2 4/16	2 10/16	3 6/16	4 1/16
6 " 0 "	2 7/16	3 3/16	3 10/16	4 5/16

This makes a particularly strong and rigid fence, the four lines of wire holding the pales tightly at short intervals. It can be confidently recommended against heavy stock, and it also makes an excellent boundary fence provided the pales are placed sufficiently close to afford no foothold between them.

Pales with blunt tops instead of points can be supplied without extra charge if specially ordered.

\* These prices include round Posts for placing 9 ft. apart, and one square Straining Post and Strut per 100 yards.

No. T 6055. FENCING FOR SHEEP FOLDING, with Three Lines of Wire. All pales full height of fence.



PRICES PER YARD

Height of Fence.	In Rolls of 25 Yards.		In Rolls of 20 Yards.	
	2 Ft. 6 Ins.	3 Ft.	3 Ft. 6 Ins.	4 Ft. 6 Ins.
Pales apart about 6 ins.	1 10/16	1 11/16	1 1/16	1 4/16
" " 5 " "	1 11/16	1 10/16	1 2/16	1 5/16
" " 3 " "	1 3/16	1 4/16	1 6/16	2 1/16
Chestnut Stakes, .. per doz.	7 6	8 3	9 6	10 6
Strong Angle Iron Stakes, with Thrust Plate, ..	12 9	14 3	15 9	17 3
				18 9


Every Pale in this Fence, in addition to being very tightly stranded, is securely stapled to both top and bottom wires, so that the Fence can be readily taken up and refixed without injury, thus making it greatly superior to wooden hurdles or wire netting.

This pattern can also be recommended for enclosing building plots, or for any purpose where a cheap and easily removable fence is required.


# Picture and Dado Rail Mouldings

SUPERIOR QUALITY AMERICAN WHITE WOOD


FULL SIZE SECTIONS.



No. Pa 530. American White Wood, 7/- per 100 ft.  
 „ Pa 208. White Enamelled, 12/- „  
 „ GE 8947. Moulding Hooks, Polished Brass, 23 per doz.  
 „ GE 8945. Moulding Hooks, lighter pattern, 16 „




No. Pa 534.  
 American White Wood  
 63 per 100 ft.



No. Pa 532. American White Wood, 8/- per 100 ft.  
 „ Pa 204. White Enamelled, 15/- „  
 „ GE 8950. Moulding Hooks, Polished Brass, 30 per doz.




No. Pa 531.  
 American White Wood,  
 66 per 100 ft.




No. Pa 535.  
 American White Wood, 86 per 100 ft.




No. Pa 528. American White Wood, 10/- per 100 ft.



No. Pa 533.  
 American White Wood, 11/3 per 100 ft.



No. Pa 527.  
 American White Wood,  
 113 per 100 ft.



No. Pa 514. American White Wood, 15/- per 100 ft.

Panel and Room Mouldings, both Gilt and Black, also kept in Stock.

A larger selection of Designs sent upon application.

1

Telephone:  
Stratford No. 1 (4 Lines).

Telegraphic Address: "Yemart, London."  
Cable: A B C Code, 5th Edition.

9

# YOUNG & MARTEN

.. LIMITED ..

## IRONMONGERY SECTION

COMPRISING

SCREWS, NAILS, BOLTS, SHEET & BAR  
IRON, LOCKS, HANDLES, FASTENINGS  
FURNITURE, AND FITTINGS (IN BRASS  
AND IRON), FOR DOORS, WINDOWS,  
- - CASEMENTS, AND FANLIGHTS - -

ART BLACK GARDEN CITY  
- - - FURNITURE - - -

WIREWORK, WIRE FENCING,  
- - - AND NETTING - - -

EXPANDED METAL LATHING & BRICKWORK REINFORCEMENT

HINGES, SPRINGS, VENTILATORS, BLIND  
FURNITURE & OPENING GEAR, SLIDING  
DOOR FITTINGS, AND PANIC BOLTS  
CONTRACTORS' AND BUILDERS' PLANT  
TOOLS FOR BRICKLAYERS, JOINERS,  
CARPENTERS, SMITHS, AND SLATERS  
- - - IRONMONGERY SUNDRIES - - -



CALEDONIAN  
WORKS

### STRATFORD

LONDON,  
ENGLAND

1

3

# "Standard" Gross List of Patent Pointed Iron Wood Screws

## COUNTERSUNK HEADS

PRICES, PER GROSS.

4, 2, & 1/2 inch.	1/2 inch.	3/4 inch.	1 inch.	1 1/4 inch.	1 1/2 inch.	1 3/4 inch.	2 inch.
No. 1 — 8/8 2 — 8/8 3 — 8/8 4 — 8/8 5 — 9/8 6 — 9/8 7 — 1/1 8 — 1/1 9 — 1/1 10 — 1/2 11 — 1/3	No. 2 — 9/8 3 — 9/8 4 — 9/8 5 — 1/10 6 — 1/11 7 — 1/1 8 — 1/1 9 — 1/2 10 — 1/3 11 — 1/4 12 — 1/5	No. 3 — 1/10 4 — 1/10 5 — 1/11 6 — 1/1 7 — 1/1 8 — 1/1 9 — 1/2 10 — 1/3 11 — 1/4 12 — 1/5 14 — 1/10	No. 4 — 1/10 5 — 1/1 6 — 1/1 7 — 1/2 8 — 1/3 9 — 1/3 10 — 1/4 11 — 1/6 12 — 1/7 13 — 1/10 14 — 2/- 16 — 2/6	No. 5 — 1/3 6 — 1/4 7 — 1/5 8 — 1/5 9 — 1/6 10 — 1/7 11 — 1/8 12 — 1/11 14 — 2/4 16 — 3/- 18 — 3/7	No. 6 — 1/6 7 — 1/6 8 — 1/7 9 — 1/8 10 — 1/9 11 — 1/11 12 — 2/1 13 — 2/4 14 — 2/8 16 — 3/4 18 — 4/-	No. 7 — 1/10 8 — 1/11 9 — 1/11 10 — 2/- 11 — 2/2 12 — 2/4 13 — 2/8 14 — 3/- 15 — 3/4 16 — 3/8 18 — 4/5	No. 8 — 2/- 9 — 2/1 10 — 2/2 11 — 2/4 12 — 2/8 13 — 3/- 14 — 3/4 16 — 4/- 18 — 4/9 20 — 5/6 22 — 6/4
2 1/2 inch.	2 3/4 inch.	3 inch.	3 1/2 inch.	4 inch.	4 1/2 inch.	5 inch.	6 inch.
No. 9 — 2/5 10 — 2/6 11 — 2/8 12 — 3/- 13 — 3/4 14 — 3/8 16 — 4/5 18 — 5/2 20 — 5/11	No. 10 — 2/8 11 — 3/- 12 — 3/4 13 — 3/8 14 — 4/- 16 — 4/9 18 — 5/6 20 — 6/4 22 — 7/4	No. 12 — 4/- 13 — 4/5 14 — 4/9 15 — 5/2 16 — 5/10 18 — 7/3 20 — 8/7 22 — 10/2 24 — 11/8	No. 14 — 5/10 16 — 7/2 18 — 9/- 20 — 10/8 22 — 12/4 24 — 13/8 26 — 15/6 28 — 17/6 30 — 22/-	No. 16 — 8/1 18 — 9/10 20 — 11/6 22 — 13/- 24 — 14/4 26 — 16/6 28 — 18/6 30 — 24/- 32 — 32/-	No. 16 — 10/- 18 — 11/6 20 — 13/6 22 — 15/6 24 — 17/6 26 — 19/6 28 — 22/6 30 — 27/- 32 — 32/-	No. 18 — 13/8 20 — 15/8 22 — 18/- 24 — 20/- 26 — 22/- 28 — 26/- 30 — 30/- 32 — 35/- 36 — 45/-	No. 20 — 20/- 22 — 22/6 24 — 25/- 26 — 30/- 28 — 35/- 30 — 40/- 32 — 45/- 36 — 55/- 40 — 75/-

## JAPANNED ROUND HEADS

PRICES, PER GROSS.

1/2 inch.	3/4 inch.	1 inch.	1 1/4 inch.	1 1/2 inch.	1 3/4 inch.
No. 1 — 11 2 — 11 3 — 11 4 — 11 5 — 1/- 6 — 1/1 7 — 1/2 8 — 1/3 9 — 1/4	No. 3 — 1/- 4 — 1/- 5 — 1/1 6 — 1/1 7 — 1/2 8 — 1/3 9 — 1/5 10 — 1/6 11 — 1/7	No. 6 — 1/6 7 — 1/7 8 — 1/8 9 — 1/9 10 — 1/11 11 — 2/1 12 — 2/4 14 — 3/- 16 — 4/-	No. 7 — 1/9 8 — 1/10 9 — 1/11 10 — 2/1 11 — 2/4 12 — 2/8 13 — 3/- 14 — 3/4 16 — 4/5	No. 8 — 2/- 9 — 2/2 10 — 2/4 11 — 2/8 12 — 3/- 13 — 3/4 14 — 3/8 16 — 4/9 18 — 5/6	No. 8 — 2/2 9 — 2/4 10 — 2/8 11 — 3/- 12 — 3/4 13 — 3/8 14 — 4/- 16 — 5/2 18 — 5/11
2 inch.	2 1/2 inch.	2 3/4 inch.	3 inch.	3 1/2 inch.	4 inch.
No. 9 — 2/8 10 — 3/- 11 — 3/4 12 — 3/8 13 — 4/- 14 — 4/5 15 — 4/9 16 — 5/6 18 — 6/4	No. 11 — 4/- 12 — 4/5 13 — 4/9 14 — 5/2 15 — 5/9 16 — 7/- 18 — 8/- 20 — 9/6 22 1/2 grs. 12/6	No. 12 — 4/9 13 — 5/2 14 — 5/10 15 — 6/6 16 — 7/11 18 — 9/4 20 — 11/- 22 in 13/6 24 1/2 grs. 16/3	No. 14 — 7/2 15 — 8/- 16 — 9/8 18 — 11/10 20 — 13/- 22 — 15/6 24 — 17/6 26 — 22/- 28 — 30/-	No. 16 — 10/8 18 — 12/4 20 — 13/8 22 — 16/6 24 — 18/6 26 — 24/- 28 — 32/- 30 — 37/- 32 — 44/-	No. 16 — 12/6 18 — 14/6 20 — 16/6 22 — 19/6 24 — 22/6 26 — 27/- 28 — 32/- 30 — 40/- 32 — 60/-

NOTE. Round Head Screws are measured from under the head.

## COUNTERSUNK HEADS

1, $\frac{1}{2}$ , & $\frac{1}{4}$ inch.			$\frac{1}{2}$ inch.			$\frac{3}{4}$ inch.			1 inch.			1 $\frac{1}{4}$ inch.			1 $\frac{1}{2}$ inch.		
No.			No.			No.			No.			No.			No.		
4	...	1/6	4	...	1 8	4	...	1 10	6	...	2 9	6	...	3 3	6	...	4 7
5	...	1 7	5	...	1 10	5	...	2 .	7	...	3 .	7	...	3 7	7	...	4 4
6	...	1 9	6	...	2 .	6	...	2 3	8	...	3 4	8	...	4 .	8	...	4 8
7	...	2 .	7	...	2 3	7	...	2 6	9	...	3 8	9	...	4 5	9	...	5 2
8	...	2 3	8	...	2 5	8	...	2 8	10	...	4 1	10	...	4 11	10	...	5 9
9	...	2 6	9	...	2 8	9	...	3 .	11	...	4 6	11	...	5 5	11	...	6 4
10	...	2 9	10	...	3 .	10	...	3 4	12	...	5 .	12	...	6 .	12	...	7 .
11	...	3 4	11	...	3 4	11	...	3 10	13	...	5 7	13	...	6 8	13	...	7 9
12	...	3 8	12	...	3 8	12	...	4 4	14	...	6 3	14	...	7 5	14	...	8 7
			14	...	5 9	14	...	5 9	16	...	7 10	16	...	9 2	16	...	10 6
1 $\frac{3}{4}$ inch.			2 inch.			2 $\frac{1}{4}$ inch.			2 $\frac{1}{2}$ inch.			2 $\frac{3}{4}$ inch.			3 inch.		
No.			No.			No.			No.			No.			No.		
7	...	5 3	8	...	6 3	8	...	7 .	10	...	10 .	12	...	13 .	12	...	14 6
8	...	5 6	9	...	6 9	9	...	7 6	11	...	10 6	13	...	13 9	13	...	15 .
9	...	5 11	10	...	7 5	10	...	8 3	12	...	11 .	14	...	14 5	14	...	15 7
10	...	6 7	11	...	8 2	11	...	9 1	13	...	12 1	15	...	15 9	15	...	17 .
11	...	7 3	12	...	9 .	12	...	10 .	14	...	13 3	16	...	17 2	16	...	18 6
12	...	8 .	13	...	9 11	13	...	11 .	15	...	14 6	17	...	18 10	17	...	20 3
13	...	8 10	14	...	10 11	14	...	12 1	16	...	15 10	18	...	20 6	18	...	22 .
14	...	9 9	16	...	13 2	16	...	14 6	18	...	19	20	...	24 2			
															20	In 4 grs.	25 10

## PRICE, PER GROSS.

1 1/8, 1, & 1 1/4 inch.			1 1/2 inch.			1 3/4 inch.			2 inch.			1 inch.		
No.			No.			No.			No.			No.		
4	...	1/7	4	...	1/10	4	...	2/-	4	...	2/6	6	...	3/7
5	...	1/9	5	...	2/-	5	...	2/3	5	...	2/9	7	...	4/-
6	...	2/-	6	...	2/3	6	...	2/6	6	...	3/-	8	...	4/5
7	...	2/3	7	...	2/5	7	...	2/8	7	...	3/4	9	...	4/11
8	...	2/6	8	...	2/8	8	...	3/-	8	...	3/8	10	...	5/5
	Wrapped in grosses.		9	...	3/-	9	...	3/4	9	...	4/1	11	...	6/-
			10	...	3/4	10	...	3/10	10	...	4/6	12	...	6/8
						11	...	4/4	11	...	5/-	14	...	8/3
						12	...	4/10	12	...	5/7	16	...	10/4

1 1/4 inch.			1 1/2 inch.			1 3/4 inch.			2 inch.			2 1/4 inch.		
No.			No.			No.			No.			No.		
6	...	4/4	7	...	5/6	8	...	6/9	8	...	7/6	12	...	13/9
7	...	4/8	8	...	6/-	9	...	7/6	9	...	8/3	13	...	14/6
8	...	5/2	9	...	6/6	10	...	8/3	10	...	9/-	14	...	15/9
9	...	5/9	10	...	7/3	11	...	9/-	12	...	11/-	15	...	17/3
10	...	6/4	11	...	8/-	12	...	10/-	14	...	13/3	16	...	18/9
11	...	7/-	12	...	8/9	14	...	12/-	16	...	16/-	18	...	22/3
12	...	7/9	14	...	10/9	16	...	14/6	18	...	19/-			
14	...	9/6	16	...	13/3	18	...	17/6	20	...	24/6	20	...	28/3
16	...	11/9	18	...	16/-	20	...	22/9	24	...	36/-	22	...	32/9
	In grosses.			In grosses.			In grosses.			In grosses.			In grosses.	
												24	...	40/-

341

# NET PRICES.

Subject to Market Fluctuations.

## Cut Steel, Wire, and Wrought Nails, &c.

### CUT STEEL CLASP

In 1-cwt. Bags.



Sizes, 1 1/2, 2, 2 1/2, 3, 3 1/2, 4, 5, 6 ins.  
Prices, 13 9 12 9 12 3 11 9 11 9 11 9 11 9 cwt.

The above Prices are Delivered within our Van Delivery Radius. Carriage is paid beyond on Minimum Lots of 5 cwt., at 6d. per cwt. extra, to ANY RAILWAY STATION or, in 2-ton Lots direct from Works, at 3d. per cwt. LESS.

The above Terms apply only to Cut Steel Clasp, Cut Steel Floor Brads, and Patent Steel Flat Point Rose Nails.

### CUT STEEL FLOOR BRADS

In 1-cwt. Bags.



Sizes, 2, 2 1/2, 2 3/4, 3, 3 1/2 ins.  
Prices, 12 9 11 9 11 6 11 6 11 6 per cwt.

### PATENT STEEL FLAT POINT ROSE


In 1-cwt. Bags.



Sizes, 1 1/2, 2, 2 1/2, 3, 3 1/2, 4, 5, 6 ins.  
Prices, 17 3 16 3 15 - 14 6 14 6 14 3 14 - 14 - cwt.  
Do., Galv. 25 6 25 6 22 6 22 - 21 - 21 - 21 - 21 - ..

### WIRE NAILS

In 1-cwt. Bags.




Sizes, 1 1/2, 2, 2 1/2, 3, 3 1/2, 4, 5, 6 ins.  
Gauge, 13 11 10 10 8 6 5 4 W.G.  
Prices, 13 3 12 9 12 3 11 9 11 3 10 9 10 9 cwt.

WIRE NAILS are DELIVERED within our Van Radius, and Carriage is paid to ANY RAILWAY STATION in 3-cwt. Lots.

### BRIGHT OVAL WIRE BRADS

In 1-cwt. Bags.



Sizes, 1 1/2, 2, 2 1/2, 3, 3 1/2, 4, 5, 6 ins.  
Prices, 17 9 15 6 14 - 12 9 12 - 11 6 11 6 11 6 11 6 cwt.

### WIRE SLATE NAILS



Sizes, 1 1/2, 2, 2 1/2, 3, 3 1/2 ins.  
Prices, Bright, 15 - 14 6 14 6 14 6 14 6 per cwt.  
Do., Galvanized, 22 6 22 - 22 - 22 - 22 - ..

### WIRE LATH NAILS



Sizes, 1 and 1 1/2 ins. x 14 W.G.  
Price, Bright, 14 6 per cwt.  
Do., Galvanized, 22 - ..

### WROUGHT SPIKES

Hand Made.



Sizes, 4, 5, 6, 7, 8 ins.  
Prices, 17 - 16 - 16 - 15 - 14 6 per cwt.

### CAST GARDEN WALL NAILS

In 1-cwt. Bags only.



Size, 1 and 1 1/2 ins.  
Price, 11 - per cwt.


### ESCUTCHEON PINS



Sizes, 1, 1 1/2 and 2 inch.  
Price, Brass, 1 - per lb.  
Do., Brass, 7 1/2 - ..

### NEW WIRE FLOOR BRADS

In 1-cwt. Bags.




Round or Oval.

Sizes, 2, 2 1/2, 3 ins.  
Prices, 12 - 12 - 12 - 12 - per cwt.

25 per cent. cheaper in actual use than the ordinary Steel Floor Brad. WRITE FOR SAMPLES.

### WIRE CLOUT NAILS



Sizes, 1 1/2, 2, 3, 4, 5 ins.  
Prices, Blue, 18 - 17 6 - - - per cwt.  
Do., Bright, 16 - 15 - 14 6 - ..

### COUNTERSUNK TOWN CLOUT

Nettelford's. Strong.



Sizes, 1 1/2, 2, 3 ins.  
Prices, 40 - 35 6 32 - 26 - 24 - 23 - per cwt.

### FINE CUT TACKS



Sizes, 1, 2, 3, 4, 5, 1 inch.  
Prices, Blue, 10 1/2, 1 - 13 14 16 18 per 10,000  
Do., Tinned, 13 14 16 17 110 26  
Do., Copper, 2 - 19 16 13 13 1 - per lb.

### HORSE NAILS

BRANDS—"Star," "Lion," or "Capewell."

Length.	Weight, per Nominal Thousand.	Price, per Nominal Thousand.	Price, per Box of 25 Lbs.
1 1/2 inches,	4 lbs.,	2 7/8	15 6
2 "	5 "	2 9	13 -
2 1/2 "	6 "	2 9 1/2	11 6
2 3/4 "	7 "	2 11 1/2	10 6
2 7/8 "	8 "	3 2 1/2	9 4 1/2
3 "	9 "	3 4 1/2	9 1 1/2
3 1/8 "	10 "	3 7 1/2	8 10 1/2
3 1/4 "	12 "	4 1 1/2	8 4 1/2
3 1/2 "	14 "	4 7 1/2	7 10 1/2

### SLATING NAILS ZINC and COPPER



Sizes, 1 1/2, 2, 2 1/2 and 3 ins.  
Zinc, Prices, 42 - per cwt; 5d. per lb.  
Copper, 112 - 13 -

### BEST WROUGHT HURDLE NAILS

Hand Made.



Sizes, 2, 2 1/2, 3 ins.  
Prices, 55 - 51 - 49 - 44 - per cwt.


### FINE WROUGHT CLASP

Hand Made.



Sizes, 1 1/2, 2, 2 1/2, 3 ins.  
Prices, 66 - 50 - 46 - 40 - 38 - per cwt.

### CAST TILE PEGS



Sizes, 1 and 2 ins.  
Black, 12 - per cwt.  
Galvanized, 18 - ..

### BRIGHT WIRE PANEL PINS




Sizes, 1, 1 1/2, 2, 2 1/2, 3, 3 1/2, 4 ins.  
Prices, 6d. 6d. 4d. 3 1/2d. 3d. 3d. 3d. 3d. per lb.

# NET PRICES.

Subject to Market Fluctuations.

## Wall Ties, Chimney Bars, Corbels, &c.


### Wall Ties, Wrought (Light)



	Per 1 cwt.	56 lbs.	28 lbs.
Black, ...	13/6	7/3	4/-
Galvanized,	20/-	11/-	6/-


Either pattern Tared and Sanded, 15/- per cwt.

### Wall Ties, Wrought (Heavy)






	Per 1 cwt.	56 lbs.	28 lbs.
Black, ...	13 6	7/3	4/-
Galvanized,	20 -	11 -	6/-

### Chimney Bars



Sizes for	24	26	28	30 in. openings
Prices,	4/3	4/6	4/9	5/- per doz.
Sizes for	36	42	48 in. openings.	
Prices,	5/-	6/-	6/6	per doz.


### Builders' Corbels

No. 1.	No. 2.	No. 3.
Sizes, 6 or 7 x 2 1/2 ins.	Sizes, 9 10 or 12 x 2 1/2 ins.	Sizes, 12 or 14 x 2 1/2 ins.
Prices, 2/- per doz.	Prices, 2/3 2/6 2/9 per doz.	Prices, 3/3 3/9 per doz.

These Corbels are supplied in Self Color, rough finished.


### Timber Dogs



Self Color.

Sizes.	7 x 3 in.	10 x 5 in.	12 x 6 in.
Price,	15/-	per cwt.	

### Bolts and Nuts (Cup Head)




PRICES, per Gross.

Length, up to 2 1/2	3	3 1/2	4	5	6	7	8	9	10	12 ins.
Size, 1/2 in.,	2/3	2/6	3/2	3/4	3/6	4/6				
.. 3/4 in.,	3/-	3/3	3/8	3/10	4/3	4/9	5/3			
.. 1 in.,	4/-	4/3	4/9	5/-	5/3	6/-	6/9	7/6	9 -	
.. 1 1/4 in.,	7 -	7/6	8 -	8/6	9 -	10/3	11/6	13/6	14/9	16 6
.. 1 1/2 in.,	12/-	12/6	13/6	14/3	15/3	16/-	17/6	18/6	20 -	23 6
.. 1 3/4 in.,	21/-	21/-	22/-	23/-	24/-	27 -	29 -	31 6	34 -	36 6
.. 2 in.,										39 -
.. 2 1/2 in.,										42 -

All Bolts are measured from UNDER head to point.

### Bolts and Nuts (Square Head)



PRICES, per Gross.

Length, up to 2 1/2	3	4	5	6 ins.
Size, 1/2 in.,	4/-			
.. 3/4 in.,	5/-	5/6	6/-	
.. 1 in.,	6/-	6/6	7/-	7/6
.. 1 1/4 in.,	8/-	9/-	9/6	10/6
.. 1 1/2 in.,	20/-	19/-	19/-	18/9
.. 1 3/4 in.,	19/6	18/9	18/9	18/6
.. 2 in.,				


Hexagon Head Bolts, 1 1/2 in. and 2 in., 6d. per gross extra.  
" " " " larger than 2 in., 1/6 " " "

### Best Iron Washers



Sizes, 1/2 3/4 1 1 1/4 1 1/2 in.
Prices, 5d. 6d. 8d. 1 3 2 6 3 6 p. gross.
HEAVY WASHERS (Square Plate).
Price, ... 18/- per cwt.
GALVANIZED ROOFING WASHERS.
Price, ... 6d. per gross.


### Bright Handrail Screws (Best)



Length, ...	4	4 1/2	5	6 ins.
Prices, 1/2 in., two Nuts,	18/-	20/-	21 -	24/- per gross.
.. 3/4 in.,	24/-	26 -	30/-	36 -


With one Nut only, 2/- per gross less.

### Galvanized Cone Head Screws



Length, 1 1/2	2	2 1/2	3 ins.
Prices, 1/8	2/-	2/-	2/6 per gross
Patent Drive Screw, with Washer,	2/6		
For Gutters, (Length, 5	6	7 ins.	
Prices, 6/-	7/-	8/-	per gross.


### Galvanized Cone Head Nails



For Roofing.


Length, 1 1/2	2	2 1/2 ins.
Prices, 18/-	18/-	18/- per cwt.
.. 10d.	1/3	1/6 per gross.

### Galvanized Hook Bolts



Length, 2	2 1/2	3	4	5	4	5 ins.
Diam., 1	1 1/4	1 1/2	1 3/4	2	2 1/4	2 1/2
Prices, 4/-	4/6	5/6	6/6	7/6	10/-	12/- p. gross.

### Steel Rivets




Best Quality.

Measured under head.

Sizes stocked.	
1/2, 3/4, 1 in.,	3 1/2 d. per lb.
1 1/4, 1 1/2, 1 3/4 in.,	3d. "
2, 2 1/4, 2 1/2 in.,	3d. "
2 3/4, 3, 3 1/4 in.,	3d. "
3 1/2, 4, 4 1/2 in.,	3d. "


### Galvanized Round Head Rivets



For Roofing.


Size, ...	1/2 x 1/4 in.
Price, ...	3d. per lb.

### Galvanized Roofing Bolts and Nuts



Sizes, 1/2 x 1/4	1 x 1/4 in.
Prices, 2/-	2/3 per gross.

### Coil Chain (Black)



Common, Twisted or Straight Link.

	Price, per Lb.,	Price, per Lb.,	Price, per Lb.,
	Smaller	Gal	Smaller
Sizes,	Price,	vanized,	Quantities
8 oz.,	45/-	6d.	54/-
12 "	42/-	5 1/2 d.	50/-
16 "	32/-	4 1/2 d.	40/-
1 1/2 lbs.,	28/-	4d.	36/-
1 3/4 "	27/-	3 1/2 d.	33/-
2 "	26/-	3 1/4 d.	33/-
3 "	26/-	3 1/2 d.	33/-




# NET PRICES.

Subject to Market Fluctuations.

## Galvanized Corrugated Iron Sheets

Sizes Stocked, 4 ft. to 10 ft. long, in 24 and 26 W.G.

[No. Y 4603.



Curved to any Radius, to order only.

### GALVANIZED RIDGE CAPPING



					Approximate Weight per Sheet.									
					4	5	6	7	8	9	10 ft.			
					20 gauge,	17	21	25½	30	34	38	42½ lbs.		
Prices, 4 ft. to 8 ft., ..	20	22	24	26 gauge	20 gauge,	17	21	25½	30	34 <td>38</td> <td>42½ lbs.</td>	38	42½ lbs.		
..	15 3	15 6	15 6	17 1/2 per cwt.	22 ..	13½	17	20	23½	27	30	33½ ..		
..	15 3	15 6	15 6	17 6 ..	24 ..	11	13½	16	18½	21½	24	28 ..		
..	16 3	16 6	16 6	18 6 ..	26 ..	8½	10½	12½	14½	16½	18½	21 ..		
Corrugated Sheets, Curved, 15 1/2 per ton.					Smaller Lots than one ton, 6d. per sheet.									

Corrugated Sheets, Curved, 15 1/2 per ton. Smaller Lots than one ton, 6d. per sheet.

No. Y 4603.

### GALVANIZED RIDGE CAPPING


Supplied in 6 ft. lengths ONLY.

18 ins. width 26 gauge, .. Price, 1 6 per length. 18 ins. width 24 gauge, .. Price, 2 6 per length.  
The Prices quoted above are for delivery within our Van Delivery Radius. **One Ton** lots from Country Works direct, carriage paid to nearest Railway Station, at same price. **Two Ton** lots at 5/- per ton less.  
GALVANIZED SCREWS, with Washers, 2 6 per gross. GALVANIZED NAILS, with Washers, 1 6 per gross.

No. Y 4601.

### GALVANIZED CORRUGATED ROOF LIGHT

TO OPEN.



Width covers 2 ft. when laid.

Prices each (Unglazed).

Length,	5	6	7	8	9	10 ft.
24 gauge, 16 6	17 3	18 9	19 6	21	22 6	
22 ..	18	19	19 6	21	22 6	24

Size of opening for glass, about 36 x 48 ins.

Stock size, 24 gauge.

### BUILDERS' HOOP IRON

In 1/2-cwt. bundles. Prices per cwt.

Sizes, ..	1 1/2	1 3/4	1 1/2	1 3/4	1 1/2	1 3/4	1 1/2	1 3/4	1 1/2	1 3/4	1 1/2	1 3/4	1 1/2	1 3/4
Black, ..	11	11	11	11	11	11	11	11	11	11	11	11	11	11
Galvanized, 21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2	21 1/2

### BAR IRON

Usual sizes and lengths.


Best Crown Quality, .. 12 per cwt.

EXTRAS.

Sizes, .. 1/2 1 1/2 2 1/2 3 1/2 4 1/2 5 1/2 6 1/2 7 1/2 8 1/2 9 1/2 10 1/2 11 1/2 12 1/2 13 1/2 14 1/2 15 1/2 16 1/2 17 1/2 18 1/2 19 1/2 20 1/2 21 1/2 22 1/2 23 1/2 24 1/2 25 1/2 26 1/2 27 1/2 28 1/2 29 1/2 30 1/2 31 1/2 32 1/2 33 1/2 34 1/2 35 1/2 36 1/2 37 1/2 38 1/2 39 1/2 40 1/2 41 1/2 42 1/2 43 1/2 44 1/2 45 1/2 46 1/2 47 1/2 48 1/2 49 1/2 50 1/2 51 1/2 52 1/2 53 1/2 54 1/2 55 1/2 56 1/2 57 1/2 58 1/2 59 1/2 60 1/2 61 1/2 62 1/2 63 1/2 64 1/2 65 1/2 66 1/2 67 1/2 68 1/2 69 1/2 70 1/2 71 1/2 72 1/2 73 1/2 74 1/2 75 1/2 76 1/2 77 1/2 78 1/2 79 1/2 80 1/2 81 1/2 82 1/2 83 1/2 84 1/2 85 1/2 86 1/2 87 1/2 88 1/2 89 1/2 90 1/2 91 1/2 92 1/2 93 1/2 94 1/2 95 1/2 96 1/2 97 1/2 98 1/2 99 1/2 100 1/2 101 1/2 102 1/2 103 1/2 104 1/2 105 1/2 106 1/2 107 1/2 108 1/2 109 1/2 110 1/2 111 1/2 112 1/2 113 1/2 114 1/2 115 1/2 116 1/2 117 1/2 118 1/2 119 1/2 120 1/2 121 1/2 122 1/2 123 1/2 124 1/2 125 1/2 126 1/2 127 1/2 128 1/2 129 1/2 130 1/2 131 1/2 132 1/2 133 1/2 134 1/2 135 1/2 136 1/2 137 1/2 138 1/2 139 1/2 140 1/2 141 1/2 142 1/2 143 1/2 144 1/2 145 1/2 146 1/2 147 1/2 148 1/2 149 1/2 150 1/2 151 1/2 152 1/2 153 1/2 154 1/2 155 1/2 156 1/2 157 1/2 158 1/2 159 1/2 160 1/2 161 1/2 162 1/2 163 1/2 164 1/2 165 1/2 166 1/2 167 1/2 168 1/2 169 1/2 170 1/2 171 1/2 172 1/2 173 1/2 174 1/2 175 1/2 176 1/2 177 1/2 178 1/2 179 1/2 180 1/2 181 1/2 182 1/2 183 1/2 184 1/2 185 1/2 186 1/2 187 1/2 188 1/2 189 1/2 190 1/2 191 1/2 192 1/2 193 1/2 194 1/2 195 1/2 196 1/2 197 1/2 198 1/2 199 1/2 200 1/2 201 1/2 202 1/2 203 1/2 204 1/2 205 1/2 206 1/2 207 1/2 208 1/2 209 1/2 210 1/2 211 1/2 212 1/2 213 1/2 214 1/2 215 1/2 216 1/2 217 1/2 218 1/2 219 1/2 220 1/2 221 1/2 222 1/2 223 1/2 224 1/2 225 1/2 226 1/2 227 1/2 228 1/2 229 1/2 230 1/2 231 1/2 232 1/2 233 1/2 234 1/2 235 1/2 236 1/2 237 1/2 238 1/2 239 1/2 240 1/2 241 1/2 242 1/2 243 1/2 244 1/2 245 1/2 246 1/2 247 1/2 248 1/2 249 1/2 250 1/2 251 1/2 252 1/2 253 1/2 254 1/2 255 1/2 256 1/2 257 1/2 258 1/2 259 1/2 260 1/2 261 1/2 262 1/2 263 1/2 264 1/2 265 1/2 266 1/2 267 1/2 268 1/2 269 1/2 270 1/2 271 1/2 272 1/2 273 1/2 274 1/2 275 1/2 276 1/2 277 1/2 278 1/2 279 1/2 280 1/2 281 1/2 282 1/2 283 1/2 284 1/2 285 1/2 286 1/2 287 1/2 288 1/2 289 1/2 290 1/2 291 1/2 292 1/2 293 1/2 294 1/2 295 1/2 296 1/2 297 1/2 298 1/2 299 1/2 300 1/2 301 1/2 302 1/2 303 1/2 304 1/2 305 1/2 306 1/2 307 1/2 308 1/2 309 1/2 310 1/2 311 1/2 312 1/2 313 1/2 314 1/2 315 1/2 316 1/2 317 1/2 318 1/2 319 1/2 320 1/2 321 1/2 322 1/2 323 1/2 324 1/2 325 1/2 326 1/2 327 1/2 328 1/2 329 1/2 330 1/2 331 1/2 332 1/2 333 1/2 334 1/2 335 1/2 336 1/2 337 1/2 338 1/2 339 1/2 340 1/2 341 1/2 342 1/2 343 1/2 344 1/2 345 1/2 346 1/2 347 1/2 348 1/2 349 1/2 350 1/2 351 1/2 352 1/2 353 1/2 354 1/2 355 1/2 356 1/2 357 1/2 358 1/2 359 1/2 360 1/2 361 1/2 362 1/2 363 1/2 364 1/2 365 1/2 366 1/2 367 1/2 368 1/2 369 1/2 370 1/2 371 1/2 372 1/2 373 1/2 374 1/2 375 1/2 376 1/2 377 1/2 378 1/2 379 1/2 380 1/2 381 1/2 382 1/2 383 1/2 384 1/2 385 1/2 386 1/2 387 1/2 388 1/2 389 1/2 390 1/2 391 1/2 392 1/2 393 1/2 394 1/2 395 1/2 396 1/2 397 1/2 398 1/2 399 1/2 400 1/2 401 1/2 402 1/2 403 1/2 404 1/2 405 1/2 406 1/2 407 1/2 408 1/2 409 1/2 410 1/2 411 1/2 412 1/2 413 1/2 414 1/2 415 1/2 416 1/2 417 1/2 418 1/2 419 1/2 420 1/2 421 1/2 422 1/2 423 1/2 424 1/2 425 1/2 426 1/2 427 1/2 428 1/2 429 1/2 430 1/2 431 1/2 432 1/2 433 1/2 434 1/2 435 1/2 436 1/2 437 1/2 438 1/2 439 1/2 440 1/2 441 1/2 442 1/2 443 1/2 444 1/2 445 1/2 446 1/2 447 1/2 448 1/2 449 1/2 450 1/2 451 1/2 452 1/2 453 1/2 454 1/2 455 1/2 456 1/2 457 1/2 458 1/2 459 1/2 460 1/2 461 1/2 462 1/2 463 1/2 464 1/2 465 1/2 466 1/2 467 1/2 468 1/2 469 1/2 470 1/2 471 1/2 472 1/2 473 1/2 474 1/2 475 1/2 476 1/2 477 1/2 478 1/2 479 1/2 480 1/2 481 1/2 482 1/2 483 1/2 484 1/2 485 1/2 486 1/2 487 1/2 488 1/2 489 1/2 490 1/2 491 1/2 492 1/2 493 1/2 494 1/2 495 1/2 496 1/2 497 1/2 498 1/2 499 1/2 500 1/2 501 1/2 502 1/2 503 1/2 504 1/2 505 1/2 506 1/2 507 1/2 508 1/2 509 1/2 510 1/2 511 1/2 512 1/2 513 1/2 514 1/2 515 1/2 516 1/2 517 1/2 518 1/2 519 1/2 520 1/2 521 1/2 522 1/2 523 1/2 524 1/2 525 1/2 526 1/2 527 1/2 528 1/2 529 1/2 530 1/2 531 1/2 532 1/2 533 1/2 534 1/2 535 1/2 536 1/2 537 1/2 538 1/2 539 1/2 540 1/2 541 1/2 542 1/2 543 1/2 544 1/2 545 1/2 546 1/2 547 1/2 548 1/2 549 1/2 550 1/2 551 1/2 552 1/2 553 1/2 554 1/2 555 1/2 556 1/2 557 1/2 558 1/2 559 1/2 560 1/2 561 1/2 562 1/2 563 1/2 564 1/2 565 1/2 566 1/2 567 1/2 568 1/2 569 1/2 570 1/2 571 1/2 572 1/2 573 1/2 574 1/2 575 1/2 576 1/2 577 1/2 578 1/2 579 1/2 580 1/2 581 1/2 582 1/2 583 1/2 584 1/2 585 1/2 586 1/2 587 1/2 588 1/2 589 1/2 590 1/2 591 1/2 592 1/2 593 1/2 594 1/2 595 1/2 596 1/2 597 1/2 598 1/2 599 1/2 600 1/2 601 1/2 602 1/2 603 1/2 604 1/2 605 1/2 606 1/2 607 1/2 608 1/2 609 1/2 610 1/2 611 1/2 612 1/2 613 1/2 614 1/2 615 1/2 616 1/2 617 1/2 618 1/2 619 1/2 620 1/2 621 1/2 622 1/2 623 1/2 624 1/2 625 1/2 626 1/2 627 1/2 628 1/2 629 1/2 630 1/2 631 1/2 632 1/2 633 1/2 634 1/2 635 1/2 636 1/2 637 1/2 638 1/2 639 1/2 640 1/2 641 1/2 642 1/2 643 1/2 644 1/2 645 1/2 646 1/2 647 1/2 648 1/2 649 1/2 650 1/2 651 1/2 652 1/2 653 1/2 654 1/2 655 1/2 656 1/2 657 1/2 658 1/2 659 1/2 660 1/2 661 1/2 662 1/2 663 1/2 664 1/2 665 1/2 666 1/2 667 1/2 668 1/2 669 1/2 670 1/2 671 1/2 672 1/2 673 1/2 674 1/2 675 1/2 676 1/2 677 1/2 678 1/2 679 1/2 680 1/2 681 1/2 682 1/2 683 1/2 684 1/2 685 1/2 686 1/2 687 1/2 688 1/2 689 1/2 690 1/2 691 1/2 692 1/2 693 1/2 694 1/2 695 1/2 696 1/2 697 1/2 698 1/2 699 1/2 700 1/2 701 1/2 702 1/2 703 1/2 704 1/2 705 1/2 706 1/2 707 1/2 708 1/2 709 1/2 710 1/2 711 1/2 712 1/2 713 1/2 714 1/2 715 1/2 716 1/2 717 1/2 718 1/2 719 1/2 720 1/2 721 1/2 722 1/2 723 1/2 724 1/2 725 1/2 726 1/2 727 1/2 728 1/2 729 1/2 730 1/2 731 1/2 732 1/2 733 1/2 734 1/2 735 1/2 736 1/2 737 1/2 738 1/2 739 1/2 740 1/2 741 1/2 742 1/2 743 1/2 744 1/2 745 1/2 746 1/2 747 1/2 748 1/2 749 1/2 750 1/2 751 1/2 752 1/2 753 1/2 754 1/2 755 1/2 756 1/2 757 1/2 758 1/2 759 1/2 760 1/2 761 1/2 762 1/2 763 1/2 764 1/2 765 1/2 766 1/2 767 1/2 768 1/2 769 1/2 770 1/2 771 1/2 772 1/2 773 1/2 774 1/2 775 1/2 776 1/2 777 1/2 778 1/2 779 1/2 780 1/2 781 1/2 782 1/2 783 1/2 784 1/2 785 1/2 786 1/2 787 1/2 788 1/2 789 1/2 790 1/2 791 1/2 792 1/2 793 1/2 794 1/2 795 1/2 796 1/2 797 1/2 798 1/2 799 1/2 800 1/2 801 1/2 802 1/2 803 1/2 804 1/2 805 1/2 806 1/2 807 1/2 808 1/2 809 1/2 810 1/2 811 1/2 812 1/2 813 1/2 814 1/2 815 1/2 816 1/2 817 1/2 818 1/2 819 1/2 820 1/2 821 1/2 822 1/2 823 1/2 824 1/2 825 1/2 826 1/2 827 1/2 828 1/2 829 1/2 830 1/2 831 1/2 832 1/2 833 1/2 834 1/2 835 1/2 836 1/2 837 1/2 838 1/2 839 1/2 840 1/2 841 1/2 842 1/2 843 1/2 844 1/2 845 1/2 846 1/2 847 1/2 848 1/2 849 1/2 850 1/2 851 1/2 852 1/2 853 1/2 854 1/2 855 1/2 856 1/2 857 1/2 858 1/2 859 1/2 860 1/2 861 1/2 862 1/2 863 1/2 864 1/2 865 1/2 866 1/2 867 1/2 868 1/2 869 1/2 870 1/2 871 1/2 872 1/2 873 1/2 874 1/2 875 1/2 876 1/2 877 1/2 878 1/2 879 1/2 880 1/2 881 1/2 882 1/2 883 1/2 884 1/2 885 1/2 886 1/2 887 1/2 888 1/2 889 1/2 890 1/2 891 1/2 892 1/2 893 1/2 894 1/2 895 1/2 896 1/2 897 1/2 898 1/2 899 1/2 900 1/2 901 1/2 902 1/2 903 1/2 904 1/2 905 1/2 906 1/2 907 1/2 908 1/2 909 1/2 910 1/2 911 1/2 912 1/2 913 1/2 914 1/2 915 1/2 916 1/2 917 1/2 918 1/2 919 1/2 920 1/2 921 1/2 922 1/2 923 1/2 924 1/2 925 1/2 926 1/2 927 1/2 928 1/2 929 1/2 930 1/2 931 1/2 932 1/2 933 1/2 934 1/2 935 1/2 936 1/2 937 1/2 938 1/2 939 1/2 940 1/2 941 1/2 942 1/2 943 1/2 944 1/2 945 1/2 946 1/2 947 1/2 948 1/2 949 1/2 950 1/2 951 1/2 952 1/2 953 1/2 954 1/2 955 1/2 956 1/2 957 1/2 958 1/2 959 1/2 960 1/2 961 1/2 962 1/2 963 1/2 964 1/2 965 1/2 966 1/2 967 1/2 968 1/2 969 1/2 970 1/2 971 1/2 972 1/2 973 1/2 974 1/2 975 1/2 976 1/2 977 1/2 978 1/2 979 1/2 980 1/2 981 1/2 982 1/2 983 1/2 984 1/2 985 1/2 986 1/2 987 1/2 988 1/2 989 1/2 990 1/2 991 1/2 992 1/2 993 1/2 994 1/2 995 1/2 996 1/2 997 1/2 998 1/2 999 1/2 1000 1/2 1001 1/2 1002 1/2 1003 1/2 1004 1/2 1005 1/2 1006 1/2 1007 1/2 1008 1/2 1009 1/2 1010 1/2 1011 1/2 1012 1/2 1013 1/2 1014 1/2 1015 1/2 1016 1/2 1017 1/2 1018 1/2 1019 1/2 1020 1/2 1021 1/2 1022 1/2 1023 1/2 1024 1/2 1025 1/2 1026 1/2 1027 1/2 1028 1/2 1029 1/2 1030 1/2 1031 1/2 1032 1/2 1033 1/2 1034 1/2 1035 1/2 1036 1/2 1037 1/2 1038 1/2 1039 1/2 1040 1/2 1041 1/2 1042 1/2 1043 1/2 1044 1/2 1045 1/2 1046 1/2 1047 1/2 1048 1/2 1049 1/2 1050 1/2 1051 1/2 1052 1/2 1053 1/2 1054 1/2 1055 1/2 1056 1/2 1057 1/2 1058 1/2 1059 1/2 1060 1/2 1061 1/2 1062 1/2 1063 1/2 1064 1/2 1065 1/2 1066 1/2 1067 1/2 1068 1/2 1069 1/2 1070 1/2 1071 1/2 1072 1/2 1073 1/2 1074 1/2 1075 1/2 1076 1/2 1077 1/2 1078 1/2 1079 1/2 1080 1/2 1081 1/2 1082 1/2 1083 1/2 1084 1/2 1085 1/2 1086 1/2 1087 1/2 1088 1/2 1089 1/2 1090 1/2 1091 1/2 1092 1/2 1093 1/2 1094 1/2 1095 1/2 1096 1/2 1097 1/2 1098 1/2 1099 1/2 1100 1/2 1101 1/2 1102 1/2 1103 1/2 1104 1/2 1105 1/2 1106 1/2 1107 1/2 1108 1/2 1109 1/2 1110 1/2 1111 1/2 1112 1/2 1113 1/2 1114 1/2 1115 1/2 1116 1/2 1117 1/2 1118 1/2 1119 1/2 1120 1/2 1121 1/2 1122 1/2 1123 1/2 1124 1/2 1125 1/2 1126 1/2 1127 1/2 1128 1/2 1129 1/2 1130 1/2 1131 1/2 1132 1/2 1133 1/2 1134 1/2 1135 1/2 1136 1/2 1137 1/2 1138 1/2 1139 1/2 1140 1/2 1141 1/2 1142 1/2 1143 1/2 1144 1/2 1145 1/2 1146 1/2 1147 1/2 1148 1/2 1149 1/2 1150 1/2 1151 1/2 1152 1/2 1153 1/2 1154 1/2 1155 1/2 1156 1/2 1157 1/2 1158 1/2 1159 1/2 1160 1/2 1161 1/2 1162 1/2 1163 1/2 1164


# Rim Locks

No. Y 2020.  
**Japanned Case, Wrought-steel Interior**




Brass bolts.  
Complete with Brass Furniture.  
Size, 5½ ins. . . . . Price, **17/3** per doz.  
Suitable for Cottage Property.

No. Y 5152.  
**Japanned Steel Case, Wrought-steel Interior**




Heavy brass bolts, nickel-plated key.  
Complete with full size Brass Furniture.  
Size, 6 ins. . . . . Price, **22/6** per doz.

No. Y 2300.  
**Double Hand, Steel Case**




Brass bolts, malleable interior fittings.  
Complete with full size Brass Furniture.  
Size, 6 ins. . . . . Price, **24/-** per doz.

No. Y 2112.  
**Best Quality, Double Hand**




A **thoroughly** reliable Lock.  
Complete with Brass drilled through Furniture.  
Size, 6 ins., Price, **33/-** per doz.

No. Y 2035.  
**YOUNG & MARTEN'S Standard Rim Lock**




Heavy brass bolts, Scotch springs.  
Complete with full size Brass Furniture.  
Size, 6 ins. . . . . Price, **33/-** per doz.  
" 7 " Extra Strong. . . . . **6/6** each.  
" 8 " " " " " **9/-**

No. Y 1913  
**Narrow Steel Case Rim Lock**




Finished ART BLACK.  
Suitable for Garden City Interior Doors.  
Complete with full size Brass Furniture.  
Size, 6 ins. . . . . Price, **19/6** per doz.

No. Y 2004.  
**The "Crown" Patent Rim Lock**




Brass bolts.  
Complete with full size Brass Furniture.  
Size, 6 ins., Price, **39/-** per doz.

No. Y 1800. **Cheap Rim Lock, with Iron Bolt**




Size, 6 inches.  
No. Y 1800, Brass Bushed. . . . . Price, **21/-** per doz.  
" Y 1801, Not Bushed. . . . . **17/3** "  
Complete with Furniture.

No. Y 950. **BEST Quality Lever Rim Lock**




Brass bolts, fully bushed, palace motion.  
Size, 6 x 4 ins. . . . . Price, **45/-** per doz.  
" 7 x 4½ " " " " " **60/-** "  
Complete with Brass Furniture.

No. Y 1912. **"New Era" Rim Lock**



Specially designed for Garden Cities.  
Finished in ART BLACK, extra strong, and of the  
very best quality throughout.  
Size, 6 ins., Price, without Furniture, **31/6** per doz.


No. Y 1916.  
**Polished Brass, Best Quality Moulded  
Rim Lock**



Gun-metal key, lever action.  
Size, 6 ins., Price, without Furniture, **10/6** each.


No. Y 1920.  
**Upright  
Rim Lock**

Size,  
4½ x 2½ ins.  
Price,  
Without  
Furniture,  
**3/3** each.




# Mortice Locks

No. Y 428.



**Stevens' Patent Tubular Mortice Lock**  
Size, 6 ins., Price, 33/- per doz.

No. Y 3929.




**Japanned Narrow Steel Case Mortice Lock**

Made specially thin. One wide brass bolt to shoot out when locked.

Size, 5 1/2 ins., Price, 27/- per doz.

No. Y 349 (with two bolts), 21/-

No. Y 2021.




**Bright Steel Case One-Lever Mortice Lock**

Brass bolts, nickel-plated key.

Size, 6 ins., Price, 33/- per doz.

No. Y 2017.




**Half Rebated Mortice Lock**

Japanned case, two lever brass bolts.  
Size, 6 ins., Price, 48/- per doz.


No. Y 2018. Size, 5 ins. (Sash Ward), 39/-

No. Y 424.



**Letheren's Patent Mortice Lock**  
Size, 6 ins., Price, 30/- per doz.

No. Y 5045.



**Upright Mortice Lock**

Measurement back to front over all.

Y 2044. Japanned Case, Sash Ward.

Sizes, 1 1/2 2 2 1/2 3 4 ins.  
Prices, 36/- 36/- 39/- 45/- doz.

Y 5045. Best quality; Hand made, as illustrated. (Two Levers.)


Sizes, 2 2 1/2 3 4 ins.  
Prices, 7/6 7/6 7/6 8/3 each.

## NOTE

All Locks on this page are drawn LEFT HAND. Any pattern can be made half or full rebated to order.


Two and Four Lever Locks can be supplied in Suites, with Master Key.

No. Y 431.




**Japanned Case Mortice Lock**  
Brass bolts, wrought-steel interior.  
Size, 5 ins., Price, 19/6 per doz.

No. Y 5158.




**Best Quality Japanned Case, Wrought-steel Interior**  
Strong brass bolts (reversible), nickel-plated key.  
Sizes, 5 ins. or 6 ins., Price, 25/6 per doz.

No. Y 4044




**Best Quality Four-Lever Mortice Lock**  
As supplied to H.M. Office of Works.  
Solid brass interior, phosphor-bronze springs, palace motion, fully bushed.  
Size, 6 ins., Price, 11/3 each.

No. Y 2024 B.



**Strong Plain Two-Lever Mortice Lock**  
Of good quality.  
As supplied to the London School Board.  
Size, 6 ins., Price, 60/- per doz.

No. Y 5157.




**Double-handed Full Rebated Mortice Lock**  
Japanned case, strong brass bolts.  
Size, 6 ins., Price, 9/9 each.

# Oak-Cased, Dead, and Pad Locks

## OAK-CASED PLATE LOCKS


No. Y 2013.



Strong Plain Oak Case Stock Lock.

Sizes, ..	7	8	9	10 ins.
No. Y 2012,	21/-	24/-	30/-	33/- per doz.
.. Y 2013,	30/-	33/-	36/-	39/- ..
Steel Bound,				


No. Y 2373.



Patent Double Hand Oak-cased Stock Lock, brass fore-end, solid brass wards, brass bushed.

Sizes, ..	8	9	10 ins.
Prices, ..	4/10	5 3	6 each.

No. Y 2376.



Strong Gothic Stock Lock, solid brass wards, brass bolt, varnished case, mounted as illustrated.

Sizes, ..	8	9	10 ins.
Prices, ..	5 3	6 6	7 6 each.

## JAPANNED CASE DEAD LOCKS


No. Y 2008.



Japanned Case Dead Lock.

Sizes, ..	4	5	6 ins.
No. Y 2008, Unbushed,	15/-	18/-	21/- per doz.
.. Y 2009, Bushed, ..	24/-	27/-	30/- ..

No. Y 2010.



Strong Brass Bushed Dead Lock. Full wards.

Sizes, ..	4	5	6	7	8 ins.
Prices, ..	2 6	2 9	3 3	4 10	6 4 each.

No. Y 2011.




Two lever Brass Bolt Dead Lock.

Sizes, ..	4	5	6	7	8 ins.
Prices, ..	4 6	5 3	6/-	7 6	9/ each.

## IRON AND BRASS PADLOCKS

No. Y 1070.



Strong Solid Steel Frame Padlock, Gun-metal interior. Two Keys. Size, 2 ins. Price, 1/10 each.

No. Y 2433, Brass Padlock,	1 1/2 ins.	9 - per doz.
.. Y 2169, Brass Padlock,	Sizes, 2 2 1/2 ins.	
2 Lever, ..	3/-	4/- each.
4 Lever, ..	4 6	5 9 ..

No. Y 2436.



CHUBB'S Galvanized Iron Padlock. Size, 2 1/2 ins. Price, 6/- each.

### SUITE LOCKS for Estate Work

No. Y 2440.

In Sets of 6 Locks, with 1 Master Key. Price, .. 21/- per set.


No. Y 2437. Strong Iron Padlock.



Sizes, ..	2 1/2	2 1/2	3 ins.
No. Y 2437, Strong Japanned,	15/-	18/-	21/- doz.
.. Y 2438, Strong Galvanized,	18/-	22 6	36/- ..
Extra Keys, 3d. each.			
.. Y 2436, 2 Lever, Japanned,	24/-	30/-	36/- ..

# Night Latches


No. Y 2028.  
**Double Hand Night Latch**



No. Y 2028.  
Heavy Brass Bolt, two Keys.  
Price, **25 6** per doz.

No. Y 2027.  
CHEAPER QUALITY Double, Hand ditto,  
Price, **19 6** per doz.


No. Y 1402.  
**Strong 2-Lever Night Latch**



No. Y 1402.  
Strong Brass Bolt, two Nickel  
plated Pin Keys. Price, **42** per doz.  
1 Lever ditto, ditto, „ **51 6** „


No. Y 1400.  
CHEAPER QUALITY, same design, two Keys,  
2 Lever Brass Bolt, Price, **27 6** per doz.

No. Y 1406.  
**Special 6-Lever Burglar-proof Night Latch**




With extra strong Bolt, constructed to throw forward over  
joint of door and to double lock from outside.  
Price, **11 3** each.

No. Y 2083.  
**Two-Keyed Lever Mortice Front Door Latch**



Price, without Knob, **6 9** each.  
Milled Edge, Brass Knob, as illustrated, **1 6** extra.

No. Y 2310.  
**Genuine Yale Night Latch**




This is the ORIGINAL YALE LATCH, of which many  
thousands are in use. Three small Gilt Keys are supplied  
with each Latch, and EVERY LATCH DIFFERS.

## PRICES.


No. Y 2318. Best quality, Real Bronze Case, . . . **7 6** each.  
„ Y 2310. Cheaper quality, Japanned Case, **5 3** „

No. Y 080.  
**Mortice Cylinder Night Latch**



Size,  $3\frac{1}{2}$  - 4 ins. Brass Front Cylinder,  
Brass Bolt and Knob, Reversible  
Bolt, Three Gilt Corrugated  
Keys. Suitable for Doors from  $1\frac{1}{2}$   
to 2 $\frac{1}{2}$  ins. thick. Price, **14 3** each.


No. Y 07. **Cylinder Night Latch (British Made)**



Size,  $3\frac{1}{2}$  - 2 $\frac{1}{2}$  ins. Reversible Bolt, Brass Cylinder Bolt and Knob, Three  
Corrugated Keys, Finished Enamel Black. Put up one in a box,  
complete, with full instructions for fixing. Changes Unlimited.

No. Y 07. . . . . Price, **5 3** each.  
„ Y 03, Similar Design, Cheaper Finish, „ **4 6** „

No. Y 00. **Cylinder Night Latch (British Made)**




Size,  $3\frac{1}{2}$  - 2 $\frac{1}{2}$  ins. Reversible Bolt, real bronze Cylinder. Bolt and Knob,  
Three Corrugated Keys, Finished Antique Copper. Put up one in a  
box, complete, with full instructions for fixing. Changes Unlimited.

No. Y 00. . . . . Price, **6 9** each.  
„ Y 11, Similar Design, Polished Brass, „ **12** - „


# Shop Door and other Latches, &c.

No. Y 5149.  
**SHOP DOOR LATCH**




No. Y 5149. Plain Iron, with  
Black Wood Handles, .. 5/3 each.  
No. Y 6149. Nickel Plated,  
with Black Wood Handles, 7/6 ..

No. Y 4900.  
**SHOP DOOR LOCK**



No. Y 4900. Japanned Case, Brass Bolts,  
Black Wood Handles (2 Keys), .. 5 3 each.  
No. Y 2192. Bronzed Iron ditto, .. 8 3 ..  
.. Y 4500. Nickel-plated ditto, .. 15 ..


No. Y 2190.  
**SHOP DOOR LATCH**  
(Best Quality).



No. Y 2190. Best Quality, Nickel Plated on  
Brass, Ebony Handles, .. Price, 13, 6 each.  
No. Y 2194. Same Quality and Finish, to  
Lock (2 Keys), .. Price, 21/- ..

All the above Locks and Latches are shown LEFT HAND.


No. Y 2172.  
**MORTICE DEAD LOCK**  
Japanned Case.



No. Y 2176. Sash Ward.  
Sizes, 2 2½ 3 4 ins.  
Prices, 2/6 3/- 3/- 3/6 each.

No. Y 2178. Two Levers.  
Sizes, 2 2½ 3 4 ins.  
Prices, 5/3 6/- 6/- 6/6 each.


No. Y 2173.  
**MORTICE SASH LATCH**



No. Y 2173.  
Sizes, .. 2 2½ 3 ins.  
Prices, .. 2/- 2 3 2/6 each.


No. Y 2226. EXTRA STRONG,  
for Entrance Gates.  
Size, 4 ins., Price, 6/- each.

No. Y 2143.  
**STEEL CASE RIM OR W.C.  
LATCH**




Improved Square Steel Cased  
Rim Latch.  
Fully bushed, brass bolts.  
Complete with Furniture.  
Price, .. 15/- per doz.

No. Y 2954.  
**CUPBOARD CATCH**




Size, 2½ x 1½ ins.  
No. Y 2954. Polished Brass, 8/3 doz.  
.. Y 2955. Antique Bronzed  
on Steel, .. 6/6 ..  
.. Y 2956. Art Black, .. 6/6 ..

## INDICATING LATCHES



No. Y 2207. Polished Brass, .. .. Price, 6/9 each.  
.. Y 2208. Nickel Plated, .. .. " 7/6 ..

No. Y 1908.  
**YOUNG & MARTEN'S Improved Office or Lavatory Latch**




The Strongest and Simplest made.  
Polished Brass, .. .. Price, 6/9 each.


# Kicking Plates, Gate Locks, &c.

ART. BLACK.

No. Y 1625.



No. Y 1626.



Size, 8 ins. wide 24 ins. to 32 ins. long 14 gauge thick.

Either Pattern, .. .. 12 - each.

Sizes, .. ..	24	27	30	32 inches.
Prices, Polished Brass, .. ..	18/-	20/3	22/6	24/- each.

Kicking Plates are made to order only. Any other Plain Pattern same price.


No. Y 2042. **GATE LOCK**



No. Y 2042. Plain Self-color Draw back Iron Gate Lock, .. 27 per doz.  
No. Y 20421. Ditto, with Follower, .. 42 "

Stock sizes—  
No. Y 2042, .. 5 1/4 5 3/4 5 1/2 ins.  
" Y 20421, .. .. 5 1/4 "


No. Y 2044. **GATE LOCK**



Flanged Drawback Iron Gate Lock, Japanned Case, .. 33/- per doz.

Stock sizes—  
1/2 in. Flange .. .. 4 1/4 4 ins.  
3/4 in. " .. .. 4 1/2 4 3/4 3 3/4 "


No. Y 2044. **GATE LOCK**



Flanged Gate Lock, Brass Bolt and Follower, Japanned Case, .. 42 per doz.

Stock sizes—  
1/2 in. Flange, .. .. 4 1/4 4 ins.  
3/4 in. " .. .. 4 1/2 3 3/4 3 3/4 "


No. Y 2044. **DRAWBACK LOCK**



Drawback Lock and Night Latch combined, very strong, handsomely bronzed.

Two Nickel plated Keys, size, 6 ins., 63 per doz.  
Extra Keys always in stock, 1/- each.


No. Y 2047. **DRAWBACK LOCK**



Drawback Lock, Extra Strong, Covered Plate, Double Staple, Fully Bushed, with Brass Slide Catch.

Sizes, .. 7 8 9 10 ins.  
Prices, .. 54/- 60/- 72/- 99/- per doz.


No. Y 2045. **BOW LATCH**



No. Y 2044. Plain, with Brass Furniture, 9/9 per doz.

No. Y 2045. Bolted (as illustrated), with Brass Furniture, 12/- per doz.


No. Y 2170. **PULPIT LATCH**



Brass, with Brass Furniture.

Sizes, .. 3 1/4 4 ins.  
Prices, .. 42 54 per doz.


No. Y 1230. **FANLIGHT CATCH**




Best quality, Polished.

Size, .. 2 1/4 1 1/2 ins.  
Price, .. 22 6 per doz.

No. Y 1232. **FANLIGHT CATCH**



Size, .. 2 1/4 1 1/2 ins.  
Price, .. 22 6 per doz.



No. Y 1233.

**FANLIGHT CATCH**

To work with Cords.

Polished Brass.

Price, 3/9 each.

# Cupboard Fittings and Locks


No. Y 2067.  
**CUPBOARD KNOB**



No. Y 2066. Japanned Iron.  
Sizes, .. 1½ 1½ ins.  
Prices, .. 12/- 15/- per gross.

No. Y 2067. Polished Brass.  
Sizes, .. 1½ 1½ ins.  
Prices, .. 21/- 36/- per gross.

No. Y 2068.  
**CHINA CUPBOARD KNOB**




Sizes, .. 1½ 1½ ins.  
Prices, White, 18/- 21/- per gross.  
" Black, 21/- 24/- "

No. Y 2404.  
**CUPBOARD CATCH**



Iron. Brass.  
Size, 1½ ins. 4/- 9/9 per doz.


No. Y 3012.  
**Brass.**



Sizes, .. 1½ 2 2½ ins.  
Prices, .. 4 6 5 7½ 6 6 per doz

No. Y 3013. With Thumb Bit.  
Sizes, .. 1½ 2 2½ ins.  
Prices, .. 5 7½ 6 7 7 7 per doz.

No. Y 2442.  
**BRASS CUPBOARD TURN**



Sizes, .. 1½ 1½ ins.  
Prices, .. 4/1½ 5/3 per doz.


No. Y 3011.  
**BRASS CUPBOARD BUTTON**



No. Y 3010. Japanned Iron.  
Sizes, .. 2 2½ 2½ ins.  
Prices, .. 3 9 4 6 6 per gross.

No. Y 3011. Polished Brass.  
Sizes, .. 2 2½ 2½ ins.  
Prices, .. 18/- 24/- 30/- per gross.

No. Y 2443.  
**OVAL CUPBOARD TURN**



No. Y 2443. Polished Brass.  
Size, 1½ ins. 6/- per doz.


No. Y 2444. Antique Copper Bronzed.  
Size, 1½ ins. 7 6 per doz.

No. Y 3865. **IMPROVED CUPBOARD FASTENER**




Size, 2 ins. Price, 4/6 per doz.

**BRASS DOUBLE-HAND CUPBOARD LOCK**




Prices per dozen.  
Sizes, .. 2 2½ 3 ins.  
No. Y 2132. 2 Lever, .. 21/- 24/- 30/-  
" Y 2133. 4 " .. 24/- 30/- 36/-

**BRASS CUT CUPBOARD LOCK**




Prices per dozen.  
Sizes, .. 2 2½ 3 ins.  
No. Y 2135. 2 Lever, .. 21/- 24/- 30/-  
" Y 2179. 4 " .. 24/- 30/- 36/-

**IRON CUPBOARD LOCK**




Prices per dozen.  
Sizes, .. 3 3½ 4 ins.  
No. Y 2046. Japanned, .. 4/6 4/6 5/3  
" Y 2047. Do., Strong, .. 6/- 7/6 8/3  
" Y 2048. Bright, .. 9/9 10/6 11/3  
" Y 2049. Do., Strong Brass Bolt, .. 13/6 15/-

No. Y 2162. **BRASS TILL LOCK**




Prices per dozen.  
No. Sizes, .. 2½ 2½ 2½ ins.  
Y 2160. Brass, .. 8/3 9/- 9 9  
Y 2161. Do., 1 Lever, 11/7½ 12/9 13/10½  
Y 2162. Do., 2 " .. 18/- 18/9 19/6  
Y 2163. Do., 4 " .. 24/- 27/- 30/-

No. Y 5133. **BRONZED IRON CUPBOARD CATCH**



Size, 2½ x 2 ins. Price, 6/- per doz.  
No. Y 5134. Polished Brass.  
Size, 2½ x 1½ ins. Price, 13/6 per doz.



No. Y 6639.  
**CHUBB'S Patent Lever DRAWER LOCK**

Brass.  
Dead Finish.


Sizes, 2½ 2½ 3 ins.  
Prices, 4/- 4/6 5/3 ea.

These locks have one key each, and every lock differs.




# Cabinet Furniture

No. Y 3870.  
Cupboard Catch




No. Y3870. Antique Bronze, 3 41 per doz.  
" Y3871. Polished Brass, 5 3 "

No. Y 2410.  
Flush Ring Catch




Sizes, 1 1/2 1 1/4 1 1/2 1 3/4 ins.  
Prices, 12 13 6 15 18 - p. doz.

No. Y 2406.  
Cabinet Ball Catch




Sizes, 1 1/2 2 in.  
Prices, 3 3 9 4 6 per doz.  
Illustration is full size of 1/2 inch.

No. Y 2176.  
Mortice Cupboard Lock



Sizes, 2 2 1/2 3 ins.  
No. Y2176. 2 Lever, 24 - 27 - 30 - per doz.  
" Y2177. 1 " 31 6 34 6 37 6 "


No. Y 2181. Brass Box Lock



BRASS BOX.  
Prices, per Dozen.


Sizes, 2 2 1/2 3 4 in.  
No. Y2180. Tumbler, 9 - 10 6 12 - 22 6  
" Y2181. 2 Lever, 16 6 18 - 21 33 -  
" Y2182. 1 " 21 - 24 - 27 - 36 -

No. Y 2412.  
Rayner's Patent Cupboard Catch



Price, Small-Size, 6 6 per doz.  
" Large " 9 - "

No. Y 2424. Patent Cupboard Catch



Position of Spring and Fastener when door is closed.

The "Gripper" is one of the simplest automatic catches made, can be readily fixed without cutting away woodwork, and can be used in almost any position.

Price, with Screws, complete, 6 9 per doz.  
The illustration shows the action exactly.


IRON BOX LOCK

Sizes, 2 1/2 3 4 in.  
No. Y2183. Prices, 6 - 7 6 9 - per doz.  
" Y2184. Strong, 15 18 21 "

SPRING LOCK CHEST LOCK.

Sizes, 3 4 5 ins.  
No. Y2185. Prices, 18 24 - 36 - per doz.


No. Y 2294. Sliding Sash Catch



As used in tram cars, railway carriages, &c.  
Price, 15 - per doz.

## BEST QUALITY BRASS CABINET HANDLES

No. Y 2584.



Price, per Dozen.

Small Drawer, 2 1/2 ins., 4 6 | Large Drawer, 4 ins., 8 3  
Wardrobe, 4 1/2 " 9 9 | Pedestal, 3 1/2 " 6 9


No. Y 2585.



Price, per Dozen.

Small Drawer, 2 1/2 ins., 4 6 | Large Drawer, 4 ins., 8 3  
Wardrobe, 4 1/2 " 9 9 | Pedestal, 3 1/2 " 6 9

No. Y 2586.



Price, per Dozen

Small Drawer, 2 1/2 ins., 12 - | Large Drawer, 4 1/2 ins., 15 -  
Wardrobe, 4 1/2 " 13 - | Pedestal, 3 1/2 " 14 3


No. Y 2587.



Price, per Dozen

Small Drawer, 2 1/2 ins., 10 6 | Large Drawer, 4 ins., 13 6  
Wardrobe, 4 1/2 " 13 6 | Pedestal, 3 1/2 " 12 9

No. Y 2588.



Price, per Dozen

Small Drawer, 2 1/2 ins., 14 3 | Large Drawer, 4 1/2 ins., 15 9  
Wardrobe, 4 1/2 " 15 9 | Pedestal, 3 1/2 " 15 -

Above Prices of Cabinet Handles is for Polished Brass. If in Antique Copper Finish, 1 3 per dozen net extra.

## Lock Furniture and Finger Plates



No. Y2150.

### Plain Polished Brass Latch and Rim Furniture.


Size for Locks, ...	4	5	6	7	ins.
.. of Knobs, ...	1½	1½	1½	1½	..
Prices, per doz. sets, 6-	6	6	6/4	7/6	
Size for Locks, ...	8	9	10	ins.	
.. of Knobs, ...	2	2½	2½	..	
Prices, per doz. sets, 9-	12	15			



No. Y2152.

### Mace Rim and Mortice Furniture.

	Price, per dozen sets.			
Size, ...	6	7	8	10 ins.
Rim, ...	10 6	13 6	16 6	18 9
Mortice, ...	20 3	21 9	24	



No. Y1104.

### Pitt's Mortice Furniture.

Plain. Flat Roses. Blued Steel Spindle.  
For use with best quality locks.  
Size of Knobs, 2½ ins. Price, 3 9 per set.



No. Y2128.

Mace's spindles. Best quality. Reeded knobs.  
Rim, Knobs, 2 ins., 3/-; 2½ ins., 3 9 per set.  
Mortice, .. 2 .. 4/-; 2½ .. 5 3 ..



No. Y2070.

Octagon. Best quality Cast Brass.  
No. Y2069. Rim, Knobs, 2½ ins., 5 3 per set.  
.. Y2070. Mortice, .. 2½ .. 6 ..



No. Y2059.


Cushion Top. Best quality. Cast Rose.  
Size of Knobs, .. 2 .. 2½ ins.  
No. Y2057. Rim, .. 2 3 .. 2 9 per set.  
.. Y2059. Mortice, 3 .. 3 6 ..



No. Y2053.

### China Mortice and Rim Furniture.

	Price, per dozen sets.			
	White.	Black.	White and Gold.	Black and Gold.
Mortice, 14/3	18/-	24/9	27/9	
Rim, 13/6	16/6	21/9	24/-	




No. Y2210.

### China Mortice Furniture.

#### Pitt's Brass Roses.

	Price, per dozen sets.			
	White.	Black.	White and Gold.	Black and Gold.
	19 6	22 6	27 9	30/-




No. Y2212.

### Cream China Mortice Furniture.

Price, .. 19 6 per dozen sets.


## CHINA AND BRASS FINGER PLATES



No. Y2071. China.

Price per dozen.  
White, ... 6 6  
Black, ... 7 6  
White and Gold, 15 -  
Black .. 16 6


Long or short—same price.



No. Y2220. - China.

Price per dozen.

Cream, ... 9  
Black, ... 10 6



No. Y2240.

Polished Brass.


Price per dozen.

Light—

Long, 7 6; Short, 6 6

Strong—

Long, 12/-; Short, 10 6



No. Y2224. - Brass.

Price per dozen.

Polished Brass—

Long, 7 6; Short, 6 6

Antique Copper

Bronzed—

Long, 10/-; Short, 9 -



No. Y2227.  
Brass.



No. Y2230.  
Brass.



No. Y2232.  
Brass.


2 ins. wide, for narrow stiles.

Either pattern—long or short—same price.

Price per dozen.

Polished Brass, 10/-; Antique Copper, 13 6  
Oxidised Silver, 22 6


# Brass Mortice Furniture and Finger Plates




No. Y 4464  
No. Y 4464. Polished.  
Long, 7 6 per doz.  
Short, 6 6 ..  
No. Y 4465. Antique.  
Long, 9/- per doz.  
Short, 8/3 ..




No. Y 4501  
No. Y 4501. Polished.  
Long, 1 4 each.  
Short, 1 3 ..  
No. Y 4502. Antique.  
Long, 1 9 each.  
Short, 1 7 1/2 ..



No. Y 3741  
No. Y 3741. Polished Brass.  
Long, 10 6; Short, 9 9 doz.  
No. Y 3742. Antique Finish.  
Long, 13 6; Short, 11 3 doz.  
No. Y 3749. Oxidised Silver.  
Long, 21/-; Short, 18/- doz.



No. Y 5176  
No. Y 5176. Polished  
Brass or Antique Finish.  
same price.  
Long, 9/- per doz.  
Short, 7 6 ..




No. Y 4520  
No. Y 4520. Polished Brass  
Long, 15/- per doz.  
Short, 12/- ..  
No. Y 4521. Antique Finish.  
Long, 18/- per doz.  
Short, 15/- ..



No. Y 4488  
No. Y 4488. Polished Brass.  
Price, 1 10 1/2 per set.  
No. Y 4489. Antique Finish.  
Price, 2 7 1/2 per set.




No. Y 4483  
No. Y 4483. Polished Brass.  
Price, 4 6 per set.  
No. Y 4484. Antique Finish.  
Price, 6 9 per set.  
No. Y 4485. Oxidised Silver.  
Price, 7 6 per set.




No. Y 3740  
No. Y 3740. Polished Brass.  
Price, 4 1 1/2 per set.  
No. Y 3739. Antique Finish.  
Price, 5 3 per set.  
No. Y 3738. Oxidised Silver.  
Price, 6/- per set.




No. Y 5181  
No. Y 5181. Plain Oval  
Mortice Furniture,  
Cast Rose.  
Polished Brass, 21/- per doz.  
Antique Finish, 22 6 ..



No. Y 4522  
No. Y 4522. Polished  
Brass.  
Price, 3 3 per set.  
No. Y 4523.  
Antique Finish.  
Price, 4 6 per set.



No. Y 4810.



No. Y 4816


## Mortice Furniture

No. Y 4816. Polished Brass, ... 6/- per set.  
.. Y 4817. Athenian Bronzed, ... 6 9 ..

## Finger Plates (Long only)

Size, 11 1/2 x 2 1/2 ins.

No. Y 4810. Polished Brass, ... 2 3 each.  
.. Y 4811. Athenian Bronzed, ... 3/- ..



No. Y 4819

## Mortice Furniture

No. Y 4819. Polished Brass, ... 6/- per set.  
.. Y 4820. Athenian Bronzed, ... 6 9 ..

## Finger Plates (Long only)


Size, 12 x 2 1/2 ins.

No. Y 4813. Polished Brass, ... 2 3 each.  
.. Y 4814. Athenian Bronzed, ... 3/- ..



No. Y 4818.


# Brass Mortice Furniture and Finger Plates




No. Y 4804 Best Finish, Each  
No. Y 4804, Polished Brass, 2 3  
" Y 4805, Antique Finish, 2 9  
MADE IN LONG ONLY.




No. Y 4838 Best Finish, Each  
No. Y 4838, Polished Brass, 3 6  
" Y 4839, Antique Finish, 4 4  
" Y 4840, Oxidised Silver, 5 3  
MADE IN LONG ONLY.




No. Y 4813 Best Finish, Each  
No. Y 4813, Polished Brass, 2 3  
" Y 4814, Antique Finish, 3  
" Y 4815, Oxidised Silver, 4 6  
MADE IN LONG ONLY.



No. Y 4807 Strong Quality  
No. Y 4807, Polished Brass, Long, 1 10 1/2, Short, 1 6 each  
No. Y 4808, Antique Finish, Long, 2 3, Short, 1 10 1/2 each  
No. Y 4809, Oxidised Silver, Long, 3 4 1/2, Short, 3 1 each




No. Y 4510 Best Finish, Each  
No. Y 4510, Polished Brass, 2  
" Y 4511, Antique Finish, 2 3  
" Y 4512, Oxidised Silver, 3 3  
MADE IN LONG ONLY.



No. Y 4633 Per Set  
No. Y 4633, Polished Brass, 4/-  
" Y 4634, Antique Finish, 5/3




No. Y 4541 Per Set  
No. Y 4541, Polished Brass, 4/-  
" Y 4542, Antique Finish, 4/6  
" Y 4543, Oxidised Silver, 5/3




No. Y 4525 Per Set  
No. Y 4525, Polished Brass, 4/10  
" Y 4526, Antique Finish, 5/7 1/2  
" Y 4527, Oxidised Silver, 6/9




No. Y 4544 Per Set  
No. Y 4544, Polished Brass, 3/-  
" Y 4545, Antique Finish, 3/9  
" Y 4546, Oxidised Silver, 4/6



No. Y 4528 Per Set  
No. Y 4528, Polished Brass, 5/3  
" Y 4529, Antique Finish, 6/-  
" Y 4530, Oxidised Silver, 7/6



No. Y 5629



No. Y 5626

## Oval Mortice Furniture

No. Y 5626, Polished Brass, 3/- per set  
" Y 5627, Antique Copper Finish, 3/9



## Finger Plates

No. Y 5629, Polished Brass, 10 1/2 each  
" Y 5630, Antique Copper Finish, 1/3

LONG OR SHORT—SAME PRICE



No. Y 5635

## Oval Mortice Furniture


No. Y 5635, Polished Brass, 3/- per set  
" Y 5636, Antique Copper Finish, 3/9  
" Y 5637, Old Gold Finish, 3/9



## Finger Plates


No. Y 5638, Polished Brass, 10 1/2 each  
" Y 5639, Antique Copper Finish, 1/3  
" Y 5640, Old Gold Finish, 1/6

LONG OR SHORT—SAME PRICE




No. Y 5638


## Wood Furniture and Finger Plates




**MORTICE**, 2½ ins. (Two Escutcheons.) Price, **18** per doz. sets.  
**RIM**, 2 ins. (One Escutcheon.) Price, **16 6** per doz. sets.  
**LATCH**, 2 ins. (No Escutcheon.) Price, **10** per doz. sets.  
 DRILLED THROUGH SPINDLE. WOOD ROSES.




**MORTICE**, 2½ ins. (Two Escutcheons.) Price, **22** per doz. sets.  
**RIM**, 2 ins. (One Escutcheon.) Price, **18** per doz. sets.  
**LATCH**, 2 ins. (No Escutcheon.) Price, **16 6** per doz. sets.  
 CAST BRASS SCOLLOPED ROSES.




**MORTICE**, 2½ ins. (Two Escutcheons.) Price, **27** per doz. sets.  
**RIM**, 2 ins. (One Escutcheon.) Price, **25 6** per doz. sets.  
**LATCH**, 2 ins. (No Escutcheon.) Price, **22** per doz. sets.  
 CAST BRASS SCOLLOPED ROSES.




**MORTICE**, 2 ins. (Two Escutcheons.) Price, **30** per doz. sets.  
**RIM**, 2 ins. (One Escutcheon.) Price, **27** per doz. sets.  
**LATCH**, 1½ ins. (No Escutcheon.) Price, **22 6** per doz. sets.  
 CAST BRASS PLAIN ROSES.



**MORTICE**, 2½ ins. (Two Escutcheons.) Cast Scolloped Brass Rose. Price, **27** per doz. sets.  
**RIM**, 2 ins. (One Escutcheon.) Stamped Scolloped Brass Rose. Price, **19 6** per doz. sets.  
**LATCH**, 2 ins. (No Escutcheon.) Stamped Scolloped Brass Rose. Price, **16 6** per doz. sets.




**MORTICE**, 2½ ins. (Two Escutcheons.) Price, **30** per doz. sets.  
**RIM**, 2½ ins. (One Escutcheon.) Price, **25 6** per doz. sets.  
**LATCH**, 2 ins. (No Escutcheon.) Price, **21** per doz. sets.  
 CAST BRASS SCOLLOPED ROSES.



Plan.  
 Long, **10 6**; Short, **9 9** doz.



Plan, with Buttons.  
 Long, **16 6**; Short, **16 6** doz.



Plan.  
 Long, **10 6**; Short, **9 9** doz.



Plan Buttons.  
 Long, **16 6**; Short, **16** doz.



Reeded Buttons.  
 Long, **17 3**; Short, **17 3** doz.




Reeded.  
 Long, **15**; Short, **14 3** doz.

COCUS WOOD ONLY STOCKED. EBONY, OAK, OR WALNUT, SAME PRICE, SUPPLIED TO ORDER IN TEN DAYS.

# Lever Handles for Mortice Locks


## LEVER LOCK OR LATCH HANDLES



No. Y 3398.  
Polished  
Brass,  
2/6 each.


No. Y 3399.  
Polished  
Brass,  
3/6 each.

## No. Y 2053O. CRANKED LATCH FURNITURE (7-in. Splindles).



No. Y 2053O. White China, .. 21 - doz. sets  
" Y 2051C. Plain Brass, 5 ins., .. 10 ..  
" Y 2051M. Mace's Spindle, best quality, 19 6 ..  
" Y 2051R. Reeded Brass, .. 36 ..

## No. Y 3383.




No. Y 3383.  
Polished Brass,  
Price 3/- each.

No. Y 3384  
Antique Finish  
Price 3 9 each

No. Y 3385.  
Oxidised Silver.  
Price 4 6 each.




No. Y 3386.



No. Y 3389.

## No. Y 3302.




No. Y 3302. Brass, .. 3/9  
" Y 3303. Bronze Metal,  
Antique, .. 4/6  
" Y 3304. Oxidised Silver, 5/


No. Y 3386. Polished Brass, Price, 3 9 each.  
" Y 3387. Antique Finish, .. 4/6 ..  
" Y 3388. Oxidised Silver, .. 5/3 ..

No. Y 3389. Polished Brass, Price, 4 6 each.  
" Y 3390. Antique Finish, .. 5/3 ..  
" Y 3391. Oxidised Silver, .. 6 9 ..


It on Long Cast Plate.  
6 1/2 in. 8 in.  
Brass, .. 4 10 1/2 .. 6/- ea.  
Bronze Metal,  
Antique, .. 6 9 .. 7/6 ..  
Oxidised Silver, 7 6 .. 9/- ..



No. Y 3395.



No. Y 3606.



No. Y 3611.

No. Y 3395. Brass, .. Price, 7/6 each.  
" Y 3396. Bronze Metal,  
Antique, .. 8/3 ..  
" Y 3397. Oxidised Silver, .. 9/- ..

No. Y 3606. Hammered  
Brass, .. 5/6 each.  
No. Y 3607.  
Bronze Metal, Antique.  
Price, .. 6/9 each.  
Larger is No. Y 3609.  
Plate, 4 1/2 x 4 1/2 ins.  
Ring, 3 1/2 ins.  
Brass, .. 9/9 each.  
Bronze Metal,  
Antique, .. 12/- ..  
No. Y 3611. Brass, .. Price, 6/- each.  
" Y 3612. Bronze Metal, Antique, 6/6 ..  
" Y 3613. Oxidised Silver, .. 7/6 ..  
ESCUTCHEONS EXTRA—Brass, 7 1/2 d.; Antique, 9 d.; Oxidised Silver, 1/- each.  
Illustrations half size.

## Brass and Iron Front Door Furniture



No. Y2101, 9 1/2 x 3 1/2 ins.


Japanned Iron.

Price, 12 - per doz.

No. Y2102, 8 1/2 x 2 1/2 ins.

Japanned Iron.

Price, 9 9 per doz.



No. Y2550,

Enamel Bronzed Iron

Price, 13 6 per doz.

Specially made to match  
No. Y2251 Postal Handle.




No. Y2554,

New Design.

Bronzed Iron.

Price, 16 6 per doz.



No. Y8045,

Adamantine Bronzed Iron.

Price, 12 - per doz.




No. Y2103,

Adamantine Bronzed Iron.

6 1/2 ins. over all.

Price, 12 9 per doz.



No. Y2251, Iron Postal Handle,  
Size, 9 1/2 ins. Bronzed and Relieved.

Price, 18 - per doz.




No. Y5325,

Registered Design.

Iron Combination Postal Handle, Size 8 1/2 x 3 1/2 ins.

Copper Bronzed and Relieved. Price, 24 - per doz.



No. Y5186, New Design.

Iron Combination Postal Handle.

Size, 10 ins. Green Bronzed and Relieved.

Price, 21 - per doz.



No. Y3039, Bronzed Iron, Size, 7 1/2 ins.

Price, 9 9 per doz. Upright, same price.

No. Y3781, Kahala Bronzed, Size, 11 x 4 ins.

Aperture, 8 x 2 1/2 ins. Price, 2 3 each.



No. Y3043,

Polished Brass, Plain or Lettered.

Sizes, 6 x 2 1/2, 7 x 3, 8 x 3 1/2, 10 x 4 ins.

Aperture, 4 1/2 x 1 1/2, 6 x 1 1/2, 8 x 2 ..

Prices, 2 6, 3 9, 4 6, 7 6 each.




No. Y2824,

Letter Plate (Vertical or Horizontal).

No. Y2824, Polished Brass, 2 3 each.

Y2825, Antique Bronzed, 3 ..




No. Y2076,

Gothic Centre Knob, Size, 2 1/2 ins.

Bronzed Iron, 1 - each.


Polished Brass, 4 6 ..



No. Y2077,

Polished Brass Centre Knob,

Size, 2 1/2 ins. Price, 6 - each.




No. Y2078, Bronzed Iron

Centre Knob, Kahala Bronze.

To match No. Y2103 Kicker,

Size, 2 1/2 ins. Price, 13 6 per doz.




No. Y2129, Handsome

Polished Brass Hall-Door Knob.

To match Nos. Y2128 or Y5000

Brass Knockers. Price, 7 6 each.

No. Y5162.



Polished Brass, 2 6 each.


## Polished Brass Knockers

No. Y5185.



Polished Brass, 4 6 each.

No. Y5187




Polished Brass, 3 - each.

No. Y2118.



No. Y2115. Light, 3 3  
Y2118 Heavy, 5 3

No. Y4115.



Polished Brass, 8 3 each.

## Best Quality and Finish Door Knockers

No. Y4263




Polished Brass, 6 9 each.

No. Y4260.




New Design.  
Polished Brass, 10 6 each.

No. Y4242



Polished Brass.  
8 inches, 10 6 each.  
9 " 11 3 "




No. Y2805.  
Polished Brass, 6 6 each.  
No. Y2806.  
Athenian Bronze, 9 9 each.



No. Y2813.  
Polished Brass, 8 3 each.  
No. Y2814.  
Athenian Bronze, 10 6 each.

No. Y4235.



Size, 8 1/2 inches.  
Polished Brass, 6 9 each.

## Polished Brass Combination Postal Knockers

No. Y2822.



Size, 8 1/2 inches.  
Plain, as illustration.  
Polished Brass, 4 6 each.  
Antique Bronzed, 5 3 "

## Bedroom Door Knockers

No. Y4278.



No. Y4278. Size, 3 1/2 inches  
Polished Brass, 4 6 each

No. Y4279.




No. Y4279. Size, 3 1/2 inches  
Polished Brass, 5 9 each.

No. Y4232



Size, 8 inches.  
Polished Brass, 4 6 each.

No. Y4234.




Size, 7 1/2 inches.  
Flap lettered in black.  
Polished Brass, 5 3 each.




# Brass Postal Handles

No. Y 2807.




No. Y 2807. Polished Brass, highly finished, 8 1/2 ins., Price, 10 6 each.  
 .. Y 2808. Athenian Bronzed, 8 1/2 .. .. 12 ..

No. Y 2815



No. Y 2815. Polished Brass, highly finished, 8 1/2 ins., Price, 11 3 each.  
 .. Y 2816. Athenian Bronzed, 8 1/2 .. .. 13 6 ..

No. Y 3408.




No. Y 3408. Polished Brass, best finish, 9 inches, Price, 6 6 each  
 .. Y 3409. Athenian Bronze Finish, 9 .. .. 8 3 ..

No. Y 3782.




No. Y 3782. Polished Brass, 10 1/2 inches, ... .. Price, 15 - each.  
 .. Y 3783. Antique Finish, 10 1/2 .. .. 18 ..

No. Y 3404.




No. Y 3404. Polished Brass, 10 inches, .. .. Price, 9 - each.  
 .. Y 3405. Antique Finish, 10 .. .. 12 ..

No. Y 2826.




No. Y 2826. Polished Brass, 8 inches, ... .. Price, 4 - each.  
 .. Y 2827. Antique Finish, 8 .. .. 5 3 ..

No. Y 2578. (Registered Design.)




No. Y 2578. Polished Brass, 8 1/2 inches, ... .. Price, 6/- each.  
 .. Y 2579. Antique Finish, 8 1/2 .. .. 6 9 ..

No. Y 3764.




No. Y 3764. Polished Brass, 9 1/2 inches, ... .. Price, 6 6 each.  
 .. Y 3765. Antique Finish, 9 1/2 .. .. 8 3 ..

No. Y 3788.



No. Y 3788. Polished Brass, 11 1/2 inches, ... .. Price, 6 each.  
 .. Y 3789. Antique Finish, 11 1/2 .. .. 9 ..

No. Y 3772.



No. Y 3772. Polished Brass, 10 inches, ... .. Price, 5 7 1/2 each.  
 .. Y 3773. Antique Finish, 10 .. .. 6 9 ..

# Best Quality Front Door Suite


ILLUSTRATIONS ARE HALF SIZE.

SUITE No. Y 4560

No. Y 4560A.

ILLUSTRATIONS ARE HALF SIZE.

No. Y 4556.



No. Y 4556. Polished Brass.  
Price, **3/-** each.

No. Y 4557. Polished Gun Metal.  
Price, **3 9** each.

No. Y 4558. Antique Bronze.  
Price, **4 6** each.

No. Y 4559. Oxidised Silver.  
Price, **6/-** each.




No. Y 4560A. Polished Brass.  
Price, **5 6** each.

No. Y 4561. Polished Gun Metal.  
Price, **7 -** each.

No. Y 4562. Antique Bronze.  
Price, **8 3** each.

No. Y 4563. Oxidised Silver.  
Price, **10 6** each.

No. Y 4564.




No. Y 4564. Polished Brass.  
Price, **5 3** each.

No. Y 4565. Polished Gun Metal.  
Price, **6 6** each.

No. Y 4566. Antique Bronze.  
Price, **7 6** each.

No. Y 4567. Oxidised Silver.  
Price, **10 6** each.

No. Y 4568.



No. Y 4568.	Polished Brass,	Price, <b>4 6</b> each.
" Y 4569.	Polished Gun Metal,	" <b>6 -</b> "
" Y 4570.	Antique Bronze,	" <b>6/9</b> "
" Y 4571.	Oxidised Silver,	" <b>9/-</b> "

# Best Quality Front Door Suite

ILLUSTRATIONS ARE HALF SIZE.


SUITE NO. Y4576

ILLUSTRATIONS ARE HALF SIZE.

No. Y4576A.

No. Y4580.

No. Y4572.



No. Y4572. Polished Brass.  
Price, **3 9** each.

No. Y4573. Polished Gun Metal.  
Price, **4 6** each.

No. Y4574. Antique Bronze.  
Price, **6** each.

No. Y4575. Oxidised Silver.  
Price, **7 6** each.




No. Y4576A. Polished Brass, Price, **6 6** each.

„ Y4577. „ Gun Metal, „ **8 3** „

„ Y4578. Antique Bronze, „ **9 9** „

„ Y4579. Oxidised Silver, „ **12 -** „



No. Y4580. Polished Brass.  
Price, **5 3** each.

No. Y4581. Polished Gun Metal.  
Price, **6 6** each.

No. Y4582. Antique Bronze.  
Price, **7 6** each.

No. Y4583. Oxidised Silver.  
Price, **9 9** each.

No. Y4584



No. Y4584. Polished Brass, Price, **6 -** each.

„ Y4585. „ Gun Metal, „ **8 6** „

No. Y4586. Antique Bronze, Price, **9 9** each.

„ Y4587. Oxidised Silver, „ **12 -** „

POSTAL HANDLE, to match.

No. Y4588. Polished Brass, Price, **9 9** each.

„ Y4589. „ Gun Metal, „ **12 -** „

No. Y4590. Antique Bronze, Price, **13 6** each.

„ Y4591. Oxidised Silver, „ **19 6** „

# Best Quality Front Door Suite


ILLUSTRATIONS ARE HALF SIZE.

SUITE No. Y 4091

ILLUSTRATIONS ARE HALF SIZE.

No. Y 4091A.

No. Y 4087.



No. Y 4087. Polished Brass.  
Price, 9/- each.

No. Y 4088. Polished Gun Metal.  
Price, 12/- each.

No. Y 4089. Antique Bronze.  
Price, 12/- each.

No. Y 4090. Oxidised Silver.  
Price, 18/- each.



No. Y 4095.



No. Y 4095. Polished Brass.  
Price, 9/- each.

No. Y 4096. Polished Gun Metal.  
Price, 10 6 each.


No. Y 4097. Antique Bronze.  
Price, 12/- each.

No. Y 4098. Oxidised Silver.  
Price, 18 - each.

No. Y 4091A. Polished Brass, .. Price, 10 6 each.  
.. Y 4092. .. Gun Metal, " " 13/6 "

No. Y 4093. Antique Bronze, .. Price, 15 - each.  
.. Y 4094. Oxidised Silver, .. " 21 - "

No. Y 4099.



No. Y 4099. Polished Brass, .. Price, 10 6 each.  
.. Y 4100. .. Gun Metal, " " 13/6 "


No. Y 4101. Antique Bronze, .. Price, 15 - each.  
.. Y 4102. Oxidised Silver, .. " 21 - "

POSTAL HANDLE, to match is Y 4103 (size, 12 inches).

No. Y 4103. Polished Brass, .. Price, 21/- each.  
.. Y 4104. .. Gun Metal, " " 22 6 "

No. Y 4105. Antique Bronze, .. Price, 25/6 each.  
.. Y 4106. Oxidised Silver, .. " 42 - "

No. Y 5077



**Latch Handle.**

No. Y 5077.

Polished Brass, 12/- per pair.

No. Y 5078.

Antique Bronzed, 16/6 per pair.  
This Handle can be supplied  
with sunk key hole for weighted  
mortice locks at 1/6 per pair extra.

No. Y 5065.



For Weighted Mortice Locks.

No. Y 5065.

Polished Brass, 15/- per pair.


No. Y 5066.

Antique Bronzed, 21/- per pair.

# Swing Door and Lever Lock Handles

BEST QUALITY AND FINISH.

No. Y 5068.



Size, 12 inches.


No. Y 5068.

Polished Brass, 15/- per pair.

No. Y 5069.

Antique Bronzed, 21/- per pair.

No. Y 5061.



Size, 10 1/2 inches.

Solid cast. Very strong.  
Polished Brass (reversible).

Price, 15/- per pair.

No. Y 5071.



Size, 12 inches.


No. Y 5071.

Polished Brass, 12/- per pair.

No. Y 5072.

Antique Bronzed, 18/- per pair.


No. Y 5104.



Polished Brass.

Sizes, 8 10 12 14 x 1 1/2 ins.  
Prices, 6/- 6/9 7/6 10/6 per pair.

No. Y 5074.



Size, 15 1/2 inches.

Polished Brass, 33/- per pair.

No. Y 5080.



Size, 9 inches.

No. Y 5080.


Polished Brass, 6/9 per pair

No. Y 5081.

Antique Bronzed, 10/6 per pair

# Vestibule and Bank Door Handles


BEST FINISH AND QUALITY.




No. Y 5083. Polished Brass.  
Price, 33 - per pair.  
No. Y 5084. Antique Finish.  
Price, 45 - per pair.




No. Y 5089. Polished Brass.  
Price, 24 - per pair.  
No. Y 5090. Antique Finish.  
Price, 33 - per pair.




No. Y 5092. Polished Brass.  
Price, 18 - per pair.  
No. Y 5093. Antique Finish.  
Price, 21 - per pair.



No. Y 5095. Polished Gun Metal.  
Price, 63 - per pair.  
No. Y 5096. Antique Finish  
on Gun Metal.  
Price, 72 - per pair.



Solid Cast Brass. Very strong. Polished.  
Size, 10 1/4 inches. Price, 12 - per pair.




Solid Cast Brass. Very strong. Polished.  
Size, 10 3/4 inches. Price, 15 - per pair.

Where not otherwise stated, the illustrations are ONE-THIRD size.

# Art Black Garden City Furniture

Stock size is 12x3 ins.

No. Y 4825.



Price, 15 - per dozen.


No. Y 4826.



Price, 16 6 per dozen

## FINGER PLATES

No. Y 4827.



Price, 15 9 per dozen.

No. Y 4828



Price, 16 6 per dozen.


Any size made to order in about 28 days.

No. Y 4829.



Price, 22 6 per dozen.


No. Y 4830.



Price, 21 - per dozen.

## MORTICE FURNITURE

No. Y 4832



Price, 3 - per set.

No. Y 4833.




Price, 3 3 per set

No. Y 4834



Price, 3 3 per set.

No. Y 4835




Price, 3 3 per set.

No. Y 4836.



Price, 4 6 per set.

No. Y 4837.



Price, 4 6 per set.

No. Y 4838.




Price, 4 6 per set.

No. Y 4839.




Price, 5 3 per set.

No. Y 4840.




Price,  
4 6 per set.

No. Y 4841.



Price,  
4 6 per set.

No. Y 4842.




Price,  
4 - per set

RIM OR MORTICE FURNITURE SAME PRICE.  
Time required to supply, Seven Days.  
Price includes suitable Escutcheons.


# Art Black Garden City Furniture

No. Y 4844. CUPBOARD TURN




Price, .. .. 10/- per dozen.

No. Y 4845. CUPBOARD TURN




Price, .. .. 10/- per dozen.

No. Y 4846. CUPBOARD TURN




Price, .. .. 10/- per dozen.

No. Y 4847. CUPBOARD TURN




Price, .. .. 10/- per dozen.

No. Y 4848. CUPBOARD CATCH




Price, .. 12/- per dozen.

No. Y 4849. FANLIGHT CATCH



Price, .. 15/- per dozen.

No. Y 4850. WARDROBE HANDLE




Price, .. 10/- per dozen

No. Y 4853.  
BEDROOM DOOR KNOCKER




Price, .. 1/6 each.

No. Y 4851. LEVER LOCK HANDLE




Price, complete, with Escutcheon, .. 3/9 per set.

No. Y 4644. LEVER LOCK HANDLE




Price, complete, with No. Y 4645 Escutcheon, 7/6 per set.

No. Y 4852. LEVER LOCK HANDLE



Price, complete, with suitable Escutcheon, 5/3 per set.

No. Y 4854.  
BEDROOM DOOR KNOCKER



Price, .. 1/6 each.

No. Y 4645.

ART BLACK  
ESCUTCHEON




Price, 8d. each.

These Illustrations are approximately half size.  
Time required to supply, seven days.




# Art Black Garden City Furniture

No. Y 4642.



No. Y 4643.



No. Y 4641.




No. Y 4640. Set complete, consisting of  
1 Polished Brass Handle, No. Y 4642  
1 Art Black Handle, .. " Y 4641  
1 Mortice Lock, .. " Y 4643  
Price, complete, 9/-

## SEPARATELY.

No. Y 4642. Polished Brass Handle, ..	4/6 each.
" Y 4641. Art Black Handle, ..	2/3 "
" Y 4643. Lapped Case Mortice Lock, ..	2/6 "

No. Y 4291.




## BEST FINISH STRONG DOOR LATCH

Art Black.

Size of Plate, 9 1/2 x 2 3/4 ins. Price, 4/- per set.

No. Y 4864. HAT AND COAT HOOK




Special Design.

Best Finish. Wrought Iron.

Price, .. 6/- per dozen.

No. Y 4865. HAT AND COAT HOOK



Special Design.

Best Finish. Malleable Iron.

Price, .. 12/- per dozen.  
This Hook is made to fold back close to wall.


No. Y 4869. POSTAL HANDLE



Size, 8 1/2 ins. Price, 4/6 each.  
If with Bolts and Nuts at back, 4/10 1/2 each.

No. Y 4870.

## COMBINATION POSTAL HANDLE



Size, 8 1/2 ins. Price, 6/- each.

No. Y 4867. ESPAGNOLETTE BOLT




Length, 6 to 8 feet. Shoot, 1/2 inch. Price, 6/- each.

# Art Black Garden City Furniture

No. Y 4855.


## ENTRANCE GATE LATCH



Size, .. .. 6 inches.  
Price, .. .. 13/6 per dozen.

No. Y 4858.


## GARDEN CITY DOOR BOLT



Sizes, .. .. 6 .. 8 inches.  
Prices, .. .. 16 6 .. 18 .. 19 6 per dozen.

No. Y 4856.


## ENTRANCE GATE LATCH



Size, .. .. 6 inches.  
Price, .. .. 2/- each.

No. Y 007.

## PATENT COMBINED CASEMENT STAY AND FASTENER



## THE "STAYFAST" PATENT

Casement stay and fastener combined.  
Strongly made and well finished.  
Gives greater security than the ordinary fastener.  
Gann or tongue cannot be forced with a knife or similar instrument.

It practically works as a fastener on a Mullin Plate.  
The swivel is worked in a barrel joint and secured by a good rivet behind a strong washer, and the back plate has three screw holes, and thus out of line secure a good hold with the screws and the back plate is recessed and no cutting away of the woodwork required.


It is fixed in the centre of the casement, and offer very great advantages over the ordinary stay

Made in Malleable Iron or Art Black, Brass or Gun Metal.

		10	12	15 inch
Malleable,	.. ..	16 6	18 -	24/- do.
Brass,	.. ..	36/-	42/-	45/- ..

No. Y 4857.


## ENTRANCE GATE LATCH



Size, .. .. 6 inches.  
Price, .. .. 2/3 each.

# Art Black Garden City Furniture

No. Y 1938.  
**POSTAL HANDLE**



Size, 9 $\frac{1}{2}$  x 6 inches.  
Price, .. **15/9** each.

No. Y 1937.  
**BELL PULL**




Length over all 36 inches.  
Price, .. **21/-** each.

No. Y 1941.  
**ELECTRIC PUSH**




Size, 5 x 3 $\frac{1}{4}$  inches.  
Price, .. **10/6** each

No. Y 1940.  
**CENTRE KNOB**



2 $\frac{1}{2}$  inches across Knob.  
Price, .. **10/6** each.


No. Y 1939.  
**KNOCKER**



Size, 10 $\frac{1}{2}$  x 4 inches.  
Price, .. **15/9** each.


# Sash Fasteners

No. Y 3052.




No. Y 3052. Bronzed Wrought Steel, with Brass Knob, 4/6 per doz.  
 „ Y 3053. Strong, All Iron, Brown Bronzed, .. 3/3 per doz.

No. Y 1860.




Polished Brass, Oval Knob, Solid Cast, Best Finish, 7/6 per doz.

No. Y 1859.




Polished Brass, Reeded Knob, Strong Cast Solid Catch 8 7/8 per doz.

No. Y 1891.




No. Y 1891. Strong Cast Brass Polished Sash Fastener, with Hopkinson's Arm, .. 10 6 per doz.  
 No. Y 1892. Very strong do., 15 - p. doz.

No. Y 2117.




Machine Made.  
 Price, .. 8/3 per doz.  
 Finished Dead, Dipped and Relieved.

No. Y 3055.



Polished Cast Brass, with Self-acting Drop Catch, With Brass Knob, 16/6 per doz.

No. Y 1899.




Polished Brass, Registered Design, Best Finish, 3 ins. Sizes, .. 27 3 ins. Prices, .. 10 6 15/9 per doz.

No. Y 3311.  
 Patent "Eclipse" Sash Fastener




Automatic in Action. Absolutely Secure.  
 No. Y 3311. Machine Made, Polished Brass, very strong, .. 21/- per doz.  
 „ Y 3312. Cast ditto, .. 30/-  
 This Fastener is steel guarded, and cannot be opened from the outside.

No. Y 304. Ives' Patent




Ornamental Iron, Bronzed.  
 Price, .. 2/- per doz.

No. Y 5050. Ives' Patent




Plain Electro-brassed.  
 Price, .. 5 3 per doz.

No. Y 4646.



No. Y 4646. Plain Iron, Bronzed, .. 3/3 per doz.  
 „ Y 4647. Ditto, with Brass Knob, 6/-  
 „ Y 4648. Plain Brass, Polished, .. 18/-

No. Y 3333. The "Fitch" Sash Fastener




No. Y 3333. Bronzed Iron, .. 1/4 per doz.  
 „ Y 3334. Polished Brass, .. 8/-  
 „ Y 3332. Antique Bronzed Iron, 2/6

No. Y 3335.



Strong.  
 No. Y 3335. Plain Bronzed Iron, .. 6/- per doz.  
 „ Y 3338. Polished Brass, 15/-  
 These two patterns are similar in action to Ives' Patent, but stronger.


No. Y 3336.



Extra Strong.  
 No. Y 3336. Plain Bronzed Iron, .. 10/6 per doz.  
 „ Y 3339. Polished Brass, .. 30/-


# Sash Lifts, Drawer Handles, &c.

No. Y 4200.  
**Polished Brass Sash Lift**




Strong, made out of No. 13 W. G. Metal.  
 Sizes, .. 1 1/2 2 3 4 ins.  
 Prices, .. 2 6 3 9 4 10 1/2 per doz.  
 No. Y 3064 Lapped Iron, 16 6 per doz.

No. Y 4201.




Polished Brass, 4 per doz.  
 Antique Finish, 5 3 ..  
 This Sash Lift will not catch the Venetian blind or curtain.

No. Y 2354. **Flush Drawer Handle**




Strong, machine made, with Cast Handle.  
 Sizes, .. 2 1/2 3 3 1/2 4 ins.  
 Prices, .. 5 3 6 6 9 9 per doz.

No. Y 2355.




Best quality and finish. Polished Cast Brass.  
 Sizes, .. 3 3 1/2 4 ins.  
 Prices, .. 13 6 15 19 6 per doz.

No. Y 3072.



No. Y 3072 Lapped Iron  
 Sizes, .. 2 1/2 3 3 1/2 4 ins.  
 Prices, .. 1 9 2 6 3 3 6 per doz.  
 No. Y 3073 Polished Brass  
 Sizes, .. 3 3 1/2 3 1/2 4 ins.  
 Prices, .. 6 6 7 6 9 12 9 per doz.

No. Y 4206. **Patent Drawer Pull**



Size, 4 ins.  
 By a simple process in the manufacture the strength of this Pull is not equalled.

No. Y 4206 Strong, 6 per doz.  
 No. Y 4207 Lighter, 3 6 ..

No. Y 3302. **Brass Sash Handle**



Sizes, .. 3 3 1/2 3 1/2 4 ins.  
 No. Y 3061 Lapped Iron, 1 9 2 2 7 1/2 4 per doz.  
 No. Y 3065 Cast Brass, very strong, 5 3 6 9 8 3 10 6 ..  
 Sizes, .. 2 1/2 3 3 1/2 ins.  
 No. Y 3302 Stamped Brass, doz., 4 6 5 3 6 per doz.

No. Y 3074.

**Hot Bed Handle**



Measured over all


Sizes, .. 6 7 ins.  
 Prices, Lapped, 8 2 6 9 per doz.

No. Y 3121.  
**Brass Dresser Hook**



Strong, machine made.  
 Sizes, .. 1 1/2 1 1/2 1 1/2 1 1/2 ins.  
 Prices, .. 4 6 6 7 6 9 9 9 gross.  
 Brass, 3 4 6 5 3 6 9 ..  
 Iron, 3 4 6 5 3 6 9 ..

No. Y 3124.  
**Brass Cup Hook**



Strong, machine made, per gross.  
 Sizes, .. 1 1/2 1 1/2 1 1/2 1 1/2 ins.  
 Prices, .. 4 6 6 9 9 9 10 6 11 2 ..  
 Brass, 4 3 5 3 6 6 7 6 ..  
 Iron, 4 3 5 3 6 6 7 6 ..



No. Y 3042.  
**Lifting Handle**

Prices, per Dozen Handles  
 Sizes, .. 2 1/2 3 3 1/2 4 ins.  
 No. Y 3042, Lapped, 1 7 1/2 4 6 ..  
 No. Y 2351, Polished Brass, 4 10 1/2 6 3 8 3 10 6 ..  
 No. Y 2353, Polished Brass, very strong, 4 ins. only, 18 ..  
 Measurement is between Studs.


**Indiarubber Door Stops**

No. Y 4108.



No., 1 2 3  
 Sizes, 1 1 1/2 1 1/2 ins. deep.  
 Prices, 2 6 2 6 3 per doz.



No. Y 4109.



Best Solid Rubber,  
 Assorted Colors,  
 4 6 per doz.

No. Y 2020. **Improved Door Slam and Stop**


Polished Brass.



Size, 7 1/2 ins.

By means of an oval slot, the Stop can be fixed in any position, and thus suit any thickness door.  
 Made to use with an ordinary Solid Rubber Stop (as illustrated) or without.  
 Price, complete, with Rubber Stop, 4 6 each; without Stop, 4 .. each.

No. Y 2024. **Improved Door Stop (Patent)**



As will be seen from the illustration, the socket is let into the floor, the Indiarubber Stop drops loosely into it, and, being removable, can be used either to keep the door open, or to prevent it opening beyond the required distance. Price, 1 6 each.

# Ironmongery Sundries

## PUSH AND PULL PLATES

Polished Brass.

No. Y 2618.


No. Y 2619.



WAXED LETTERS.

Size,  $2\frac{1}{2} \times 1\frac{1}{2}$  ins. | Size,  $4 \times 1\frac{1}{2}$  ins.  
Price, .. 9d. each. | Price, .. 1/3 each.

## No. Y 3293. GLASS PLATE



No. Y 3293. Stamped Brass.  
Sizes, .. 1 1 1 inches.  
Prices, .. 3/- 4/6 7/6 per gross.

No. Y 3294. Strong Cast Brass.  
Sizes, .. 1 1 1 inches.  
Prices, .. 7/6 10/6 13/6 per gross.

## No. Y 3288. BRASS CHAIR NAIL



In boxes containing about 1000.  
Best quality only.  
Polished head, steel pin.

Sizes, ..  $\frac{1}{2}$   $\frac{3}{4}$   $\frac{1}{2}$   $\frac{7}{8}$  inch.  
Prices, .. 3/9 4/6 6/- 9/- per box.

## No. Y 2086. DOOR NUMBER

Size,  $3\frac{1}{2} \times 2\frac{1}{2}$  ins.



No. Y 2086. Black Figures on White Ground, .. 6/6 8/3  
Y 2087. Gold Figures on Black Ground, .. 11/3 15/-  
No. Y 2086 only is stocked. No. Y 2087 supplied to order.

## No. Y 3068. SHUTTER SCREW



Sizes, .. 1 1 2 2 3 4 5 6 ins.  
No. Y 3068. Iron, 2/9 3/- 3/3 3/6 4/6 5/3 6/- doz.  
" Y 3069. Brass, 4/- 4/6 5/3 6/- 7/6 — — "


## No. Y 3105. DOOR CHAINS



No. Y 3105. Japanned Iron, 9/9 10/6 13/6 15/ p.doz.  
Y 3106. Brass Faced, .. 10/6 12/9 14/3 16/6 "  
Y 3108. All Brass (strong), 5/3 6/- 6/9 8/3 each.

## No. Y 3128. HAND RAIL BRACKET

Japanned, Malleable.



Sizes, 2 1 3 4 inches.  
Prices, 6/- 9/- 10/6 per doz

## No. Y 3273. PATENT POINTED SCREW EYES



Suit B  
No. Y 3273. Iron.  
Nos. .. 2 3 4 5 6 7 8  
10 11 12 13 14 15 16 17 18 19 20  
Nos. .. 10 12 14 16 18 20  
3/9 4/10 7/6 10/6 13/- 17/3 p.gross.

No. Y 3279. Brass.  
Nos. 2 3 4 5 6 7 8 9 10  
1 6 2/- 2/3 3/9 5/3 6/- 7/6 9/- 11/3 p. gross.

## No. Y 3281. PICTURE RING

Brass. Strong.






Illustration is full size of  $\frac{1}{2}$  inch.  
Measured outside ring.  
Sizes,  $\frac{1}{2}$   $\frac{3}{4}$   $\frac{1}{2}$  1 in.  
Prices, 4/6 5/3 6/- 7/6 8/3 p. gross.

## No. Y 3406. BRASS SASH STOP



No. Y 3406 With Chain, 7/6 per doz.  
" Y 3405 Without " 6/- "

## No. Y 3574. SASH PIVOT



No. Y 3574. Japanned.  
Sizes, 2 2 2 3 ins.  
Prices, .. 3/- 3/3 4/- 4/10 doz. pairs.  
No. Y 3575. Brass.  
Sizes, .. 2 2 3 ins.  
Prices, .. 13/6 21/- 30/- doz. pairs  
One dozen pairs consists of 48 pieces.  
Illustration represents half a pair.

## No. Y 3298. BRASS HEAD NAIL



No. Y 3297.—Stamped Head, Wire Spike, 1- 1/8 1/6 2- 2/6 3/9 4- 7/3 p.gross.  
Y 3298.—Cast Head, Wrought Spike, — — — 3/6 4/10 7/11 9/- 9/9 "

## No. Y 3129. BRASS SCREW CUPS



Patent Machine-made Screw Cups or Collars.  
Warranted to gauge.  
Nos. .. 5 6 7 8 9 10 11 12 14  
Prices, .. 2/3 2/6 2/7 3/6 3/6 3/9 4/6 5/3 6/6 per gross.

# Brass and Iron Casement Stays

No. Y 4852.




**Wrought-iron Curl Tail Casement Stay, Finished in Art Black**

Size, 10 ins., .. 4 6 per dozen.

This is a thoroughly well-made Stay and sufficiently strong for all ordinary Casements.

No. Y 4471.



**Best Quality, Double Jointed Stay**


Sizes, ..	10	12	14	ins.
No. Y 4471. Wrought Iron, finished in Art Black, ..	6	7	6	per doz.
.. Y 4471B. Polished Brass, Best Finish, ..	20	24	..	..

No. Y 5002C.



No. Y 5002C. Wrought Iron, Art Black, ..	Price, 7 6	per doz.
.. Y 5130. Polished Brass, ..	21	..
.. Y 5131. Antique Copper Bronzed Iron Brass, ..	25 6	..
.. Y 5132. .. .. .. .. Iron, ..	12	..

No. Y 3091B.



Sizes, ..	10	12	14	ins.
No. Y 3091. Japanned Cast Iron, ..	4 10	6	7 10	per doz.
.. Y 3091. Malleable Iron, ..	9	9 9	11 3	..
.. Y 3091B. Polished Brass, very strong, ..	18	24	36	..

No. Y 5208.



**Polished Brass Girder Wedge Casement Stay**

Size, 12 ins., .. 24 - per doz.

No. Y 1250.




**A Very Strong Art Black Wedge Casement Stay, Best Finish**

Made out of 3/4 x 1/2 inch steel bar.


Sizes, ..	12	15	ins.
Prices, ..	21 -	24 -	per doz.

No. Y 5145.



Very Strong, Wrought Steel, Finished in Art Black.  
Size, 10 ins., 4/6 per dozen; 12 ins., 5/3 per dozen.


No. Y 4478.



**Patent Telescopic Casement Stay**

Polished Brass. Combines in itself any length Stay up to 12 ins., and DOES NOT PROJECT INTO THE ROOM.  
Size, 8 1/2 ins. closed, 12 ins. extended. .. Price, 4/- each.


No. Y 5213.



**Polished Brass Patent Wedge Casement Stay. Extra Strong**

No cutting away of wood necessary.  
Length, 12 ins., .. Price, 4/6 each.

No. Y 5196.



**Polished Brass Girder Casement Stay. Extra Strong**

Size, 12 ins., .. 27/- per doz.


No. Y 5140.



**Strong Wrought-iron Casement Stay, Finished Art Black**

Size, 12 ins., .. 9/- per doz.

No. Y 5202.




**Strong Brass Casement Stay**

Sizes, ..	10	12	ins.
No. Y 5202. Polished Brass, ..	24 -	27 -	per doz.
.. Y 5203. Antique Bronzed, ..	30 -	33 -	..

# Casement Fasteners


BRASS AND IRON.

No. Y 3086.



Per doz.  
Japanned Iron, .. 2/9  
Strong Malleable  
Iron, .. 8/7½  
Polished Brass, .. 10/6

No. Y 3240.



Malleable Iron, Square  
Handle—Strong.

Per doz.  
No. Y 3240. Hook  
Plate, .. 5/3  
No. Y 3241. Mortice  
Plate, .. 4 10½


No. Y 5135.




No. Y 5135. Japanned Iron.  
Hook Plate, .. 4 1½ per doz  
Mortice Plate, 3 4½ ..

No. Y 3087. Polished Brass.  
Hook Plate, .. 13 6 per doz.  
Mortice Plate, 12 9 ..

No. Y 3089.



Japanned Iron, 5/3 per doz.  
Strong Malle-  
able Iron, .. 6/6 ..  
Strong Brass,  
Polished, .. 18/- ..



No.  
Y 5000.

Malleable  
Iron.  
Finished  
Art Black.

Per doz.  
No. Y 5001. Hook Plate, 4/10½  
" Y 5000. Mortice Plate, 4/6  
" Y 5024. Antique Bronzed  
on Iron Hook Plate, .. 6/9  
No. Y 5025. Ditto,  
Mortice Plate, .. 6/-



No. Y 3211.


Malleable  
Iron.  
Best Finish

No. Y 3244. Hook Plate, 4/6 per doz.  
No. Y 3245. Mortice  
Plate, .. 3 10½ ..  
No. Y 3248. Polished  
Brass Mortice Plate, 13/6 ..  
No. Y 3249. Polished  
Brass Hook Plate, .. 15/- ..



No. Y 5195.

Polished Brass.  
Per doz.  
No. Y 5195. Hook  
Plate .. 21 -  
No. Y 5197. Mortice  
Plate, .. 18 -




No. Y 3267.


Malleable  
Iron,  
11/3  
per doz.  
Polished  
Brass,  
22/6  
per doz.

Hinged Handle. Suits either hand  
If with Mortice Plate—  
Iron, 9d. per dozen less.  
Brass, 1/6 per dozen less.

No. Y 5218.




Malleable Polished  
Iron Brass  
No. Y 5218. Hook  
Plate, .. 12/- 24/-  
No. Y 5219. Mor-  
tice Plate, .. 11/- 21/-  
Extra Strong, Best Quality  
and Finish.



No. Y 5207.  
Patent Level Wedge  
Fastener.  
Suits either Hand  
Casement.  
The STRONGEST and  
most secure Case-  
ment Fastener made.

No. Y 5207. Polished Brass, .. 13 6 per doz.  
" Y 5208. Antique Bronzed, 17/3 ..  
" Y 5209. Malleable Iron, .. 9/- ..



No. Y 5223.

Malleable Polished  
Iron Brass  
No. Y 5223. Hook  
Plate, .. 6/6 16/6  
No. Y 5224. Mor-  
tice Plate, .. 6/- 15/-  
Best Finish.



# Improved Panic Bolts

As required to be used by L.C.C.

No. Y 4750. **Rebated Doors.**



FOR REBATED DOORS.

No. Y 4750.

Malleable Iron. Price, **45/-** per set.

No. Y 4751.

Polished Brass. Price, **67/6** per set.

No. Y 4746. FOR SINGLE DOOR.

Malleable Iron. Price, **31/6** per set.

No. Y 4747.

Polished Brass. Price, **54/-** per set.

FOR SWING DOORS.

No. Y 4749.

Malleable Iron. Price, **60/-** per set.

No. Y 4752.

Polished Brass. Price, **105/-** per set.

Bolts fitted with Screw Key and Escutcheon to operate from the outside.

Iron, **6/-**; Brass, **10/6** extra.

Brass Dust-proof Sockets, **2/3** each extra.


No. Y 4749. **Swing Doors.**



When ordering state height of door from floor to underside of frame and width of each door.  
Time required to make, 4 clear days.

No. Y 4756.

## NEW PATENT AUTOMATIC PANIC ARM



FOR SINGLE DOORS. OPENING OUT.  
USED IN FACTORIES, SCHOOLS, FLATS, AND  
ALL PUBLIC BUILDINGS.  
ABSOLUTE SECURITY, CAN ONLY BE  
OPENED FROM OUTSIDE WITH KEY.

Japanned Iron. .. .. . Price, **13/6** each.

Polished Brass. .. .. . „ **27/-** „


When ordering, state width of door and if hung on Right or Left side, looking from the **inside** of door.

No. Y 4758.

## PATENT DIRT-EXCLUDING SOCKETS

For Panic Bolts.

FLUSH WITH FLOOR AND GUARANTEED  
NOT TO CHOKE.



### ADVANTAGES :

Increased Security—Bolts always shooting to full depth.

No Dirt to Clean out.

Always efficient, convenient, easy to fix, simple and cheap.

Size of Holes, .. .. . 1/2 1/4 3/8 1/2 in.  
Prices, .. .. . **1/6 1/9 2/- 2/3** each.

# New Model Automatic Panic Bolt

(BRIGGS' PATENT).

LOCKING IN AN AUDIENCE IS IMPOSSIBLE.

This Bolt has been designed to meet the new requirements of the L.C.C. It embraces the maximum of mechanical efficiency in its working parts, with the minimum projection of about 1 inch, which no other Bolt on the market can approach.

Doors fitted with this apparatus when closed are absolutely secure from unauthorised entry; at the same time, pressure from the inside instantly releases them.

**NO KNOB TO TURN,  
OR ANY OTHER FITTINGS  
NECESSARY.**

Suitable for any class of door, swing or folding, single or double.

APPROVED BY THE  
LONDON COUNTY  
COUNCIL  
AND OTHER PUBLIC  
AUTHORITIES.

MADE TO ORDER ONLY.



A. Bolt Secured. B. Bolt Withdrawn.  
INSIDE VIEW.]

By a novel device, any attempt to open the door from without by shaking, &c., causes the Bolts to **shoot further into the Sockets**; at the same time, the Bolt Rod Ends are so constructed that they fit the Sockets perfectly, and prevent any rattling in stormy weather; this arrangement also allows the Bolts to enter the Sockets freely, even if the door be warped.

The sizes required are widths from centre to centre of stiles, and height from floor to underside of door frame, as shown by dotted lines on drawing.

MADE TO ORDER ONLY.

MR. FRANK MATCHAM, the eminent Theatre Architect, of London, says:—


"I have examined and thoroughly tested your Panic Bolt, and, to my idea, it is the best in the market. I cannot show my appreciation of its worth better than by telling you I have specified it for various buildings now in hand."

## PRICES, per Set.

	No. Y 4609, Malleable Iron.	No. Y 4610, Polished Brass, with Gun-metal Working Parts.
For Single Doors: One Bolt and one Arm necessary. . . . .	£1 7 0	£2 14 0
For Swing Doors: One Bolt and one Cross Arm necessary for each Flap, ..	2 12 0	5 6 6
For Pair Folding Rebated Doors: One Bolt and two Cross Arms for Pair Doors, ..	2 2 9	3 7 6


# Hatfield's Patent Rollers for Sliding Doors

No. Y 2931.  
**WROUGHT-IRON  
HANGING ROLLERS**



Diam. of Bowl	Length of Run	Price, Wrought Iron.
Ins.	Feet	Each.
2	2	26
2½	2½	36
3	3	46
4	4	66
5	5	96
6	6	106
6½	7	159
7	8	216
8	10	276
8	12	486

No. Y 2933 **SIDE ROLLERS**  
For Side of Door, Plain Pattern.



Diam. of Bowl.	Length of Run	Dimensions.			Price, Japaned.
		A	B	C	
Ins.	Feet	Ins.	Ins.	Ins.	Each.
2	2½	6½	2½	1	26
2½	3	7½	2½	1	29
3	4	10½	3½	1	46
3½	5	11½	3½	1	66
4	6	13½	4½	1	710
5	8	16½	5½	1	1010
6	10	18½	6½	1	186
8	12	21½	8½	1	246

These Side Rollers are designed for thin doors, and avoid the necessity of mortising; they possess all the advantages of other patterns of Hatfield Rollers.

## FIXTURES FOR HANGING ROLLERS.

Consisting of Wrought iron Pail, Bolts, Nuts, and Washers, and Cast iron Brackets.

For	2	2½	3	4	5	6	7	8	10	feet doors				
Prices	15	16	6	19	6	24	9	30	48	49	6	66	120	per set



A SECTION.



B SECTION.

## Running Rail for Bottom and Side Rollers

A Section for Rollers up to 4-inch Bowls, 10½ per foot.

A Section for Rollers, 6 to 8 inch Bowls, 110½ per foot.

B Section for Rollers up to 8 feet run and over, 23 per foot

No. Y 2932. **PLAIN BOTTOM ROLLERS**  
To Mortice into Doors.



Diam. of Bowl.	Length of Run.	Size of Mortice Required Length.	Depth.	Thickness.	Groove in Bowl.	Price.
Ins.	Feet	Ins.	Ins.	Ins.	Ins.	Each.
2	2	8½	1½	1	1	13
2½	3	7½	2	1	1	17
3	4	9	3	1	1	26
3½	5	11	3½	1	1	46
4	6	13	4	1	1	410
4½	8	16	4½	1	1	66
6	7	18½	6	1	1	89
6	9	17½	6	1	1	129
6	10	18½	6	1	1	153
6	12	21	6	1	1	219
8	16	24	8	2	2	286
8	20	28	8	2	2	

When ordering Hatfield Rollers the following particulars are necessary: -


Width of doors, thickness of doors, and the thickness of walls of beam.

The length of run is usually the same as width of doors. When this is not so, a sketch should be sent.

Hatfield Rollers are only intended to run the distance specified above. If required for intermediate distances, the next size larger should be used; thus for a 5 ft. 6 in. door a 6 ft. roller is best.

No. Y4453. **ANTI-FRICTION BOTTOM ROLLER**

▲ To Run Any Distance.




Sizes of Wheel and Prices: 4 in., 3 6; 5 in., 4 10; 6 in., 8 3 ea.

## HANGING ROLLERS AND RAILS FOR BARN AND WAREHOUSE DOORS

TO RUN ANY DISTANCE.

No. Y 2935.  
**"NONE BETTER"  
ROLLER**




These Hanging Rollers are made in steel throughout, with roller bearing wheels, and are suitable for light doors from 2 to 6 feet wide.

Price, .. 26 each.  
Rail for ditto, 9d. per foot.

No. Y 2936. **Wrought-steel Rail for "None Better" Rollers**



No. Y 2937. **Wrought-steel Rail for No. Y 2957 Roller**




No. Y 2938. **Channel Guide Rail for Hanging Rollers**



- No. Y 2937. Wrought steel Hanging Rail,
- " Y 2938. Brackets with Bolts complete for Wrought Rail,
- " Y 2939. Channel Guide,
- " Y 2940. Distance Pieces,
- " Y 2941. Guide Pins for Bottom of Door,

No. Y 2939. **Distance Piece**




No. Y 2940. **Guide Pin**



2. per foot.  
3. each.  
9d. per foot.  
9d. each.  
7d. "

No. Y 2957.  
**WROUGHT-IRON  
HANGING ROLLER**



For .. 5 6 in. wheels.  
Price, 8 - 10 6 each.

Above Prices include Bolts for fixing. When ordering, the Thickness of Door and of Wall or Beam must be given.

# Mountings for Sliding Doors

FOR GARAGE, BARN, WAREHOUSE, AND PRIVATE HOUSE DOORS.

## THE "COBURN-YEMART" SYSTEM (All British)


### SPECIAL ADVANTAGES.

THE SHAPE OF THE STEEL TRACKWAY is mechanically correct. the parallel runways ensure a dead true running line, free from the possibility of spreading or lateral movement. The section entirely envelopes the working parts, and protects it from dust, snow or ice. The Door when in use cannot possibly "jump" the track, which is a continual trouble with some systems. All sections are made to the full specified gauge of best steel.

OUR TROLLEY from which the Door is suspended, is fitted with SPECIALLY HARDENED roller bearings running in an unbreakable body; wheels are turned and properly centred to ensure smooth action. All parts have been made to anticipate hard wear and tear. With a few exceptions all patterns are now fitted with either a vertical or lateral ADJUSTMENT, which can be brought into action AFTER THE DOOR IS IN POSITION.

ADAPTABILITY. Single, or any number of doors filling one opening can be fitted by this system, the variation in the suspension brackets being stocked to suit all positions. When in any doubt, kindly give us a rough sketch shewing the proposed application, when we will quote for suitable fittings for the job. The variety in sizes are made to form a correct proportion when the work is in position.

INSIST on THE "COBURN-YEMART" and ensure good workmanship.




Full size of Track No. Y 5912.


No. Y 5910. Steel Track is used for light cupboard doors only. It is stocked in lengths up to 4 ft. . . . per foot 8d.

No. Y 5912. Steel Track is made from 16 Gauge (full) material. It is stocked in lengths up to 5 ft., and is suitable for doors weighing up to about 3 cwt. . . . 10d.

No. Y 5914. Steel Track (16 Gauge full) is stocked up to 8-ft. lengths, and is suitable for loads up to 4 cwt., . . . 1/3



Full size of Track No. Y 5910.



Full size of Tracks Nos. Y 5916 and Y 5918.  
No. Y 5916, made of 16 Gauge Steel.  
No. Y 5918, made of 13 Gauge Steel.

No. Y 5916. Steel Track (16 Gauge full) is stocked up to 6-ft. lengths, and is suitable for loads up to 7 cwt., per foot 1/8


No. Y 5918 Steel Track is made from 13 Gauge material. It is stocked in lengths up to 6 ft. and is suitable for any type of heavy door, . . . 2/1

### SPECIAL NOTE.

We have recently added to the lengths of Trackways, the 4-ft. No. Y 5910, and 6-ft. Nos. Y 5916 and Y 5918 being a new length for the section. The advantage lies in the saving of joints in a long run.

Any length of Track can be made by butting end on end, inside the suspension bracket, provided for attachment work.

The end of a run is stopped with brackets provided for the purpose.




Full size of Track No. Y 5914.

# Mountings for Sliding Doors

THE "COBURN-YEMART" SYSTEM—continued.

The Illustrations are for the purpose of showing the various types of Suspension Brackets in use.


Measurements for setting out purposes can be had from us on receipt of specification.



# Mountings for Sliding Doors

## THE "COBURN-YEMART" SYSTEM—continued.


NOTE.—Any width of door can be suspended on this system. To enable you to approximate the cost of the system, we give below the cost of applying various types to a door 4 ft. 6 ins. wide, complete with track and brackets



No. Y 5930 Trolley is used in connection with No. Y 5910 Track only. It is suitable for light internal cupboard doors not exceeding 50 lbs. in weight.

Price per pair, 7/3


Price per set, for Track, Brackets and Trolleys, for a door 4 ft. 6 ins. wide, 16/7



No. Y 5932 Trolley is used with No. Y 5912 Track. It is suitable for doors weighing up to 2 cwt. It is fitted with roller bearings and malleable parts.

Price per pair, 8/4

Price per set, for Track, Brackets and Trolleys, for a door 4 ft. 6 ins. wide, 20/-



No. Y 5934 Trolley is fitted with a vertical adjustment, Roller bearings and malleable fittings. It is used with Nos. Y 5912 and Y 5914 Track.


For No. Y 5912 Track, per pair 18/9

" " Y 5914 " " 24/9

Price per set, for Track, Brackets and Trolleys, for a door 4 ft. 6 ins. wide.

For No. Y 5912 Track, 30/6

" " Y 5914 " 43/6



No. Y 5936 Trolley is similar in all respects to No. Y 5934, with the addition of the face, as well as top fixing. Both types are used when doors run over the face of each other.

For No. Y 5912 Track, per pair 16/-


" " Y 5914 " " 18/-

Price per set, for Track, Brackets and Trolleys, for a door 4 ft. 6 ins. wide.

For No. Y 5912 Track, 27/9

" " Y 5914 " 36/9

Illustration shows a door hung in position with apron fixing. The hanger is fitted with a vertical adjustment. The No. Y 5920 Bracket is shown in position.



Read carefully the descriptive matter with advantages, shown on page 37.

No. Y 5938.	Trolley similar to Illustration.	for Doors weighing up to 2 cwt., per pair,	9/2	For a Door 4 ft. 6 ins. wide, set complete,	20/10
" Y 5940.	" " " " " " " "	3 " "	11/6	" " " " " "	23/2
" Y 5942.	" " " " " " " "	4 " "	14/7	" " " " " "	33/4
" Y 5944.	" " " " " " " "	6 " "	20/7	" " " " " "	46/-
" Y 5946.	" " " " " " " "	10 " "	22/8	" " " " " "	58/-
" Y 5950.	" " " " " " " "	30 " "	26/10	" " " " " "	62/-

NOTE.—The prices for complete sets given above are on the assumption that No. Y 5920 Bracket would be used. Any other type of Bracket would cost approximately the same. In calculating the cost of a pair of doors filling an opening, say, 9 ft. wide, you should nearly double the above figures. Doors of greater width—single, double, or treble—cost very little more, as the hangers are calculated at the same rate in all cases. When time permits, please give us details of the doors to be hung and let us send you an Estimate for suitable gear.

### No. Y 5952. HANGER

Is used exclusively for Sliding Accordion Screens. They are largely used to give temporal partitions of schools and public buildings. Very little space is occupied by the partition when not in use, i.e., the width of the leaves and the total thickness of the leaves folded back. The action is fitted with ball bearings, so that all friction is obviated. This pattern contains special race cap.

To carry 200 lbs., Hanger for No. Y 5912 Track, ... each, 16/8


" 300 " " " Y 5914 " ... " 20/7

### DIRECTIONS FOR APPLYING No. Y 5952 STYLE HANGER.

Select size of Carrier and Track suitable for the thickness and weight of doors to be hung.


Track should equal full width of openings.

Any number of doors can be used, beginning with a half door, hinged to a strip attached to the jamb on one or both sides, according to the proposed way of folding the doors. The half door must be exactly one-half the width of the full-sized doors, less the thickness of the strip to which they are attached. The full-sized doors must be of an exact width top and bottom, and edges perfectly parallel. Hinge the doors together, fold them and strike a centre line across them all. Attach carriers on the centre of this line, having the centre of the pendant on the exact centre of the door, considering both width and thickness. Attach one carrier to each full-sized door if the thickness of door equals or exceeds the diameter of the carrier wheel (trolley); if less in thickness, then apply carriers to every other door. In case of very light screens carriers need only be applied to every other leaf.



# Mountings for Sliding Doors

## THE "COBURN-YEMART" SYSTEM—continued.



No. Y 5954 **Hanger** is fitted with a wrought iron fixing strap. This type shows little or no fixing work when in position. It can be fitted into the wood-work flush if desired. Customers should give us thickness of wood and say if they desire to fix into door flush.

### Prices per Pair :

No. Y 5954, for No. Y 5912 Track, ..	<b>20/7</b>
.. Y 5956 .. Y 5914 .. ..	<b>24/9</b>
.. Y 5958 .. Y 5918 .. ..	<b>31/-</b>

Price for Complete Set for a Door 4 ft. 6 in. wide with Brackets and Track :

Y 5912, **32/3** ; Y 5914, **43/6** ; Y 5918, **65/-**


No. Y 5960 **Hanger** is similar to No. Y 5954, but is fitted with double wrought-iron fixing straps, and a vertical adjustment. In ordering please state thickness of wood.

### Prices per Pair :

No. Y 5960, for No. Y 5912 Track, ..	<b>26/10</b>
.. Y 5962 .. Y 5914 .. ..	<b>31/-</b>
.. Y 5964 .. Y 5916 .. ..	<b>41/2</b>


Price for Complete Set for a Door 4 ft. 6 in. wide with Brackets and Track :

Y 5912, **38/6** ; Y 5914, **49/9** ; Y 5918, **76/2**




NOTE:- Prices given for sets are intended as a guide only. It should be understood that any width, thickness, or weight can be carried by the "Coburn-Yemart." Architects should insist on the "Coburn-Yemart" and ensure satisfaction.

GUIDES for the bottom of doors. No guide should carry any weight of the door ; the joiner should see that the door is "pendent" from the hanger, the guide is only required to save a lateral move at the bottom.



Square Section

No. Y 5963. Channel, Plain per ft. 7d.	
.. Y 5965. Drilled and Csk. ..	<b>1/-</b>
.. Y 5966. With Lugs for Concrete .. ..	<b>1/6</b>
.. Y 5976. Special Flanged Channel for wood .. ..	<b>6d.</b>




No. Y 5968. Malleable Guide to fix on bottom of Door and run in Channel.

Price, **7d.** each.



No. Y 5970. Roller Guide used with Iron Channel. The Roller takes up friction on sides.

Price, **2/-** each.



No. Y 5972. Roller Guide. It is screwed to face of wall or wood-work, the door sliding between fixing plate and wheel.

Price, **9d.** each.

No. Y 5974. Roller Guide to fix into stone or concrete in front of Door.

Price, **3/-** each.



Consider the saving of Floor Space by using Sliding Doors fitted with "Coburn-Yemart" fittings.

Bear in mind the fact that all positions can be fitted easily.


The Door cannot "jump" the trackway, and the Trolley is weatherproof.

Ensure long life of gear, and easy running all the time.

When you want to Hang a Sliding Door let us quote you.

# Ball-Bearing Rollers for Cupboard and Thin Doors

No. Y 2975.



Wrought Steel throughout; Hardened Steel Balls; Thickness of Case, 3/16 in. Light Running. Price, 9 per dozen.

Illustrations are Full Size

No. Y 2977.



FOR HEAVY DOORS.  
Wrought Steel throughout; Hardened Steel Balls; Thickness of Case, 1/2 inch. For No. 1-6 Screw; Light Running. Price, 15 per dozen.

No. Y 2976.



Copper Plated; Solid Wrought steel Sliding Door Track; in 10-foot lengths. For use in combination with No. Y 2975 Sheave. Price, 34 per foot.

No. Y 2978.



Copper Plated; Solid Wrought steel Sliding Door Track. In 10 foot lengths, for use in combination with No. Y 2977 Sheave. Price, 44 per foot.




FIG. Y 59.

FIG. Y 62.

## Improved Lever and Spiral Bolts

AS USED FOR ALL KINDS OF SINGLE OR DOUBLE ENTRANCE AND COACH-HOUSE GATES, MAIN DOORS OF PUBLIC BUILDINGS, THEATRES, FIRE STATIONS, AND GOVERNMENT OFFICES, &c.

It will be seen in our illustration Fig. Y 59, by the simple operation of moving the handle to an angle of about 45 degrees, it is possible for a child to fasten or release the three bolts, a great improvement from the old style of releasing gates.

The dotted lines A show an extension of the Top Bar for the purpose of further securing a pair of gates, and it will be seen that this addition gives both a vertical and horizontal grip to the second gate.

The Top and Bottom Bar can be cranked to any angle either way, to suit any make of doors, and should it be required only to shoot one or two ways, middle bolt on the top one from B could be omitted.

The construction is very simple, and the bolt also forms a strong binding stay for weak door or gate.

### PRICES OF LEVER BOLTS

Made in three Flat Sizes, 1, 2, 3, 4, and 1 1/2, 2 1/2, and 3 1/2, and in three Round Sizes, 1 inch, 1 1/2 inch, and 2 inch.

No.	Description	To Shoot Three Ways.	To Shoot Two Ways.
No. Y 59.	One Bolt, with Iron Case, Guides, Levers, and Polished Handle, ...	£3 0 0	£2 12 6
.. Y 59A.	One Bolt, exactly same as No. Y 59, but Box and Guides thickly Gilt, ...	3 15 0	3 12 0
.. Y 60.	One Bolt, with Brass Case, Guides and Handle, All Bright, ...	3 18 9	3 15 0
.. Y 61.	One Bolt, exactly same as No. Y 60, only highly Polished, ...	4 10 0	4 1 0

### EXTRAS.

Curious instead of Straight Handles, Iron, 7 6; Brass, 10 each.  
Locking Attachment and Two Keys, 13 6 ..

### PRICES OF SPIRAL BOLTS

No. Y 62

All Iron, ...	£2 8 0
All Brass, ...	4 7 6
All Brass except Rods, ...	3 6 0
To Lock, extra, ...	1 2 6

Full size mounted sample will be sent for inspection, if desired.



# Espagnolette or Casement Bolts


Prices are for Bolts up to 7 ft.—Above 7 ft., extra per foot at proportionate price.



No. Y 6056.

No. Y 6056.  
All Iron,  
Self Color,  
Price, 3/- each.

Oxidised Silver  
on Iron.  
Price, 13/6 each.



No. Y 6060.

No. Y 6060.  
All Iron,  
with  
Polished Brass  
S Handles.  
Price, 4/6 each.

Antique  
Copper Finish.  
Price, 8/3 each.



No. Y 5444.

No. Y 5444.  
Art Black  
Mounts and Shoot,  
Brass Knob.  
Price, 12/- each.

No. Y 5445.  
Art Black  
Mounts and Shoot,  
Brass  
Lever Handle.  
Price, 12/- each.



No. Y 5445. No. Y 5446.

No. Y 5446.  
Polished Brass.  
Price, 24/- each.

No. Y 5447.  
Antique Copper  
on Brass.  
Price, 27/- each.

No. Y 5448.  
Oxidised Silver  
on Brass.  
Price, 30/- each.



No. Y 5449



No. Y 5449.  
Hospital and  
Public Hall Pattern,  
Polished Brass.  
Price, 27/9 each.

No. Y 5450.  
Antique Copper  
on Brass.  
Price, 30/- each.

No. Y 5451  
Oxidised Silver  
on Brass.  
Price, 33/- each.



No. Y 5452.

No. Y 5452.  
Polished Brass.  
Price, 33/- each.

No. Y 5453.  
Antique Copper  
on Brass.  
Price, 36/- each.

No. Y 5454.  
Oxidised Silver  
on Brass.  
Price, 39/- each.



No. Y 5455.

No. Y 5455.  
Polished Brass.  
Price, 33/- each.

No. Y 5456.  
Antique Copper  
on Brass.  
Price, 36/- each.

No. Y 5457.  
Oxidised Silver  
on Brass.  
Price, 39/- each.

No. Y 5458.  
Polished Brass.  
Cut Crystal Glass  
Lever.  
Price, 42/6 each.

No. Y 5458.




No. Y 5460.

No. Y 5460.  
Polished Brass.  
Price, 31/- each.

No. Y 5461.  
Antique Copper  
on Brass.  
Price, 36/- each.

No. Y 5462.  
Oxidised Silver  
on Brass.  
Price, 45/- each.



Nos. Y 6056 and Y 6060 only Stocked.—Other Patterns to Order.

# Cabinet and Door Bolts and Latches

No. Y 3004.

## BRIGHT SPRING CUPBOARD BOLT



Sizes, 3 3½ 4 ins.  
Prices, 29 3- 36 per doz.  
Necked or Straight, same price.

No. Y 3009.

## BRONZED CABINET BOLT




Sizes, 3 3½ 4 5 6 ins.  
Prices, 33 36 4- 46 53 per doz.  
Necked or Straight same price.

No. Y 3001. TOWER BOLT




Prices, per dozen.  
SIZES, 4 5 6 7 8 9 10 ins.  
Straight, 23 3- 34 41 410 57 69  
Necked, 26 33 39 46 53 6- 76

No. Y 3003. BARREL BOLT




Per dozen.  
SIZES, 4 5 6 7 8 9 10 ins.  
Prices, 33 4- 410 57 64 73 89  
SIZES, 12 14 16 18 24 ins.  
Prices, 113 129 136 16- 219

No. Y 4007. BRASS BARREL BOLT




A very strong machine-made Bolt, steel-back. Blued steel shoot.  
No. Y 4006, 3 x 1 in., 69 per doz.  
" Y 4007, 4 x 1½ ins., 83 per doz.; 5 x 1½ ins., 99 per doz.; 6 x 1½ ins., 12- "

No. Y 3005. BRASS BARREL BOLT



1½ ins. wide, Cast.  
SIZES, 3 4 5 6 7 8 9 10 12 ins.  
No. Y 3005, Straight, 12- 15- 17 3 18 9 24- 27- 33- 39 42- per doz.  
SIZES, 3 4 5 6 ins.  
" Y 3007, Necked, 14 3 17 3 21 24 19 1-

No. Y 3021. SQUARE SPRING BOLT




Strong.  
3 in. Square Bolt, 8 10 12 15 18 ins.  
Prices, 14 26 33 4- 410½ each.  
Square Plate Sockets for ditto, 4- per dozen.

No. Y 3006. BRASS FLUSH BOLT



Length, 3 4 5 6 7 8 10 12 ins.  
Width, 1 in., 49 6 73 86 10 12- per doz.  
" 53 73 86 10 12-  
" 64 9 99 12- 136 16 20- 24-  
" 710 106 136 166 186 22 27 30  
No. Y 3008 With Knob Slide, same price.

No. Y 1005 IMPROVED IRON TOWER AND BARREL BOLT  
ADJUSTABLE SOCKET



The ONLY Bolt that will shoot easily into its socket when the door is warped or has dropped.  
SIZES, 4 5 6 7 8 9 10 12 14 16 18 24 ins.  
No. Y 1001, Tower, 29 3 4- 46 53 6 66 710½  
" Y 1005, Barrel, 36 46 53 6- 73 8 96 12 136 146 166 24- "


No. Y 3022. MONKEY-TAIL BOLT



3 in. Square Bolt, 16 18 24 30 36 42 48 ins.  
Prices, 33 39 53 57 76 9 106 each  
Square Plate Sockets for ditto, 4- per dozen.


## NORFOLK and SUFFOLK LATCHES and CANADIAN STORE DOOR LATCHES

No. Y 3016. NORFOLK LATCH




Nos., 1 2 3 4  
Japanned, 3- 4- 410 57½ doz.  
Best, Japanned, 33 64 83 9- "

No. Y 3017. SUFFOLK LATCH



Nos., 1 2 3 4  
Japanned, 46 57½ 69 83 doz.  
Best, Japanned, 66 76 99 "

No. Y 3018. SUFFOLK LATCH



Nos., 5 6  
Best Wrought, extra Strong, Japanned, 136 15- per doz.


No. Y 3038. STORE DOOR LATCH



Best Quality, Japanned.  
Price, 6- per doz., complete.


# Best Quality Malleable Gothic Latches and Handles

No. Y 4312.




Length of Latch, .. 5 inches.  
Price, Berlin Black, Malleable, 12/- per dozen.

No. Y 4317.



Length of Latch, .. 7 inches.  
Price, Berlin Black, complete, with two Drop Handles, .. 3/3 per set.

No. Y 4315.



Length of Latch, .. 10 inches.  
Price, Berlin Black, Malleable, 27/- per doz.

No. Y 4324.




Handle, .. 3 1/2 ins. 13/6 48/- p. doz.  
Y 4325. 4 1/2 .. 24/ 78/- ..

No. Y 4326.




Handle, .. 3 ins. 3 1/2 ins. 15/- per doz.

No. Y 4319.



Length of Latch, .. 6 inches.  
Price, Berlin Black, 9/9 per doz.

No. Y 4320.



Length of Latch, .. 6 inches.  
Price, Berlin Black, 9/9 per dozen.

## THE "CITADEL" PATENT DOOR FASTENER

MADE IN

**Solid Brass, Sanded.**


No. Y 2560, 18/- per doz.

**Solid Brass, Polished.**

No. Y 2561, 22/6 per doz.


**Malleable Iron, Berlin Black.**

No. Y 2562, 9/- per doz.



OPEN, FIXED IN DOOR POST


This Fastener marks a distinct advance in the interior fastenings of doors. It is very much stronger than a bolt, is simpler in action, cheaper, and is fixed in one half the time; as will be seen, ONE screw only is required.



CLOSED OVER DOOR.


It is the **BEST** Fastener made for bedroom and all interior doors, whether they be **HEAVY** or **LIGHT**. The drawings do not adequately indicate these specially good features: we therefore solicit an order for a sample.

## No. Y 4321. PLAIN IRON SURFACE LATCH Suitable for Small Hand Gates.



Price, .. 4/- per dozen.


No. Y 3213. GOTHIC IRON BOLT



Malleable. Width of Plate, 2 1/2 inches.

Length, ..	8	10	12	15	18	24	30 ins.
Prices, ..	2 3	3-	4/1	4/6	5/3	6-	7/6 each.


No. Y 3214. GOTHIC IRON BOLT



Malleable. Width of Plate, 2 1/2 inches.


Length, ..	10	12	15	18	24 ins.
Prices, ..	3/4	4/6	5/3	6/9	7/6 each.

No. Y 3217. REVERSIBLE HASP BOLT



Size of Plate, .. 10 x 2 1/2 ins.  
Berlin Black, .. 5/3 each.


No. Y 3215. BRENTON'S PATENT PADLOCK BOLT



Sizes, .. 6 8 10 12 14 16 inches.  
Galvanized Iron, 12/- 12/9 16/6 18/9 21/- 24/- per dozen.

# Butt and other Hinges

No. Y 5803. Solid Steel Butt




Sizes, 1 1/2 2 2 1/2 3 3 1/2 4 ins.

In Gross Lots.

Prices, 7 6 9 - 11 3 18 - 30 - 39 - gross pts.

" 9 1 - 13 19 3 4 doz. "

No. Y 200. Strong Cast Butt



We have made improvements in this Butt, and it is now the strongest CAST BUTT at the price on the market.


Sizes, 2 2 1/2 3 3 1/2 4 ins.

In Gross Lots.

Prices, 21 27 9 36 - 54 63 - gross pts.

" 2 26 36 53 6 - doz. "

No. Y 401. Wrought-steel Butt



This Hinge is equal in strength to the best wrought iron Butt, and is stronger than any other steel Butt made.


RECOMMENDED FOR BEST WORK.

Sizes, 2 2 1/2 3 3 1/2 4 ins.

Prices, 33 4 53 69 - doz. pts.

" 3 4 5 6 ins. Price, 83 156 219 - doz. pts.

No. Y 3028. Wrought-iron Butt



No. 1 Best Quality.

Sizes, 2 2 1/2 3 3 1/2 4 ins.


Prices, 6 7 10 10 6 12 - doz. pts.

Sizes, 4 5 6 ins.

Price, 16 6 27 - 36 - doz. pts.

No. Y 3026. Light Brass Butt


Polished.



Sizes, 1 1/2 2 2 1/2 3 3 1/2 4 ins.

Prices, 23 39 6 - 83 18 24 - doz. pts.

No. Y 3268. Strong Brass Butt




The Original "Arrow" Butt.

Sizes, 1 1/2 2 2 1/2 3 3 1/2 4 ins.

Prices, 46 6 83 129 196 316 - doz. pts.

No. Y 3200. Strong Cast Brass Butt




Sizes, 2 2 1/2 3 4 ins.

Prices, 9 11 3 16 6 28 - doz. pts.

No. Y 3261, Extra Strong.

Prices, 10 6 16 6 27 51 - doz. pts.

No. Y 3262. Steel Washered Brass Butt




Size when open.

Sizes, 4 x 2 1/2 4 x 3 1/2 4 1/2 x 4 5 x 4 1/2 ins.

Prices, 4 6 6 7 6 9 9 - per pair.

No. Y 4000. Ball Bearing Butt



Sizes when open—

3 x 2 3 x 3 3 1/2 x 3 1/2 4 x 3 ins.


Prices, 4 6 4 10 53 53 - per pair.

4 x 4 4 1/2 x 4 1/2 5 x 5 6 x 6 ins.

Prices, 6 - 6 6 7 6 9 - per pair.

This Hinge is specially suitable for heavy doors. It is made of strong steel, heavily brass plated. Fitted with ball bearings and loose pin.

No. Y 4001. Parliament Hinge



Polished Brass, best quality.


Sizes, when open—

4 x 4 5 x 5 5 x 6 6 x 6 6 x 7 1/2 ins.

Prices, 6 - 7 6 9 9 12 9 18 - per pair.

The first measurement given is indicated by the dotted line in the illustration.

No. Y 2000. Counter Flap Hinge



Polished Brass.

Sizes, 4 4 1/2 4 1/2 ins.


Prices, 39 46 6 - per pair.

Black Iron, Strong—

Sizes, 4 4 1/2 5 ins.

Prices, 1 10 2 23 - per pair.

No. Y 5804. Steel Back Flap



Sizes, 1 1 1/2 1 1/2 2 2 1/2 ins.

Prices, 10 1 13 1 6 2 33 - doz. pts.

No. Y 3030.

Best Wrought Lancashire Back Flap

Sizes, 1 1 1/2 1 1/2 2 ins.

Prices, 34 39 53 76 99 - doz. pairs.

No. Y 3032. Cast Brass Back Flap

Sizes, 1 1 1/2 1 1/2 2 ins.

Prices, 4 6 69 99 113 166 - doz. pairs.


No. Y 3348. Machine Made Brass Back Flap

Sizes, 1 1 1/2 1 1/2 2 ins.

Prices, 3 4 6 6 9 - doz. pairs.

# Hinges

## PATENT SINGLE and DOUBLE ACTION REGULATING SPRING HINGES




**SINGLE-ACTION SPRING HINGES** (Two Spring Hinges to a pair).

For Doors up to	1 1/2	1 3/4	2	2 1/4	2 1/2	ins. thick.
Size of Hinge,	3 1/2	4	5	6	7	ins.
No. Y2278 Japanned Iron Hinges,	2	23	36	46	6	each.
" Y2281 Polished Brass Hinges,	4	53	66	76	12	"

**DOUBLE-ACTION HINGES.**

For Doors up to	1 1/2	1 3/4	2	2 1/4	2 1/2	ins. thick.
Size of Hinge,	3 1/2	4	5	6	7	ins.
No. Y2279 Japanned Iron Spring Hinge and Blank,	53	66	9	106	166	per pair.
" Y2279C " " " " only,	36	4	56	7	113	each.
" Y2280 Polished Brass Spring and Blank,	106	119	166	21	27	per pair.
" Y2280C " " " " Hinge only,	76	9	129	15	21	each.

These well known Hinges have recently been greatly improved, and possess advantages over the original pattern which will at once recommend themselves to the practical mechanic. By the introduction of a regulator to each Spring, the Hinge can now be fixed as easily as an ordinary butt, an improvement that will be appreciated by all who have fixed the old pattern. In addition to this, the power of the Spring can be adjusted to exactly close the door with any desired force. A pair of Double-action Hinges consists of one Hinge with Spring, and one Hinge without Spring (blank). In fact the Blank Hinge is made much smaller than the Spring Hinge.



### BOMMER SPRING BUTT HINGES


Two Spring Hinges per pair

#### REQUIREMENTS

The Thickness of Door

Width of Door	If the Earrels of the Hinge are partly embedded into the wood	If the Earrels of the Hinge are to clear the face of the door	Size of Hinge required	Thickness of Hanger Strip required
2 ft.	1 to 1 1/2 ins.	1 to 1 1/2 ins.	3 ins.	1/2 in.
2 1/2 "	1 1/2 to 2 "	1 1/2 to 2 "	4 "	3/4 "
3 "	2 to 2 1/2 "	2 to 2 1/2 "	5 "	1 "
3 1/2 "	2 1/2 to 3 "	2 1/2 to 3 "	6 "	1 1/4 "
4 "	3 to 3 1/2 "	3 to 3 1/2 "	7 "	1 1/2 "
4 1/2 "	3 1/2 to 4 "	3 1/2 to 4 "	8 "	1 3/4 "
5 "	4 to 4 1/2 "	4 to 4 1/2 "	10 "	2 "
5 1/2 "	4 1/2 to 5 "	4 1/2 to 5 "	12 "	2 1/4 "

Always select the largest size Hinge which the thickness of the door will permit




#### PRICE, DOUBLE ACTION.

Length of Flanges.	Japanned Steel.		Highly Polished Brass.	
	No.	Per Pair	No.	Per Pair.
3 ins.	29	68	129	30 10
4 "	30	84	130	35 5
5 "	33	103	133	42 6
6 "	36	147	136	52 1
7 "	39	189	139	66 3
8 "	42	27 1	142	85
10 "	45	37 6	145	113 4
12 "	48	50	148	153 4

#### PRICE, SINGLE ACTION.

Length of Flanges.	Japanned Steel.		Highly Polished Brass.	
	No.	Per Pair	No.	Per Pair.
3 ins.	0	34	100	16 8
4 "	5	42	101	18 9
5 "	6	55	105	22 11
6 "	9	76	109	28 4
7 "	13	97	113	35 5
8 "	17	139	117	45 5
10 "	21	189	121	61 3
12 "	25	25	125	82 6

### CAST-IRON PARLIAMENT HINGE



Measurement is across joint and from A to B  
 Sizes, 2-4 2 1/2-4 1/2 3-5 3 1/2-6 ins.  
 Prices, 10 10' 12 9 16 19 6 per doz. pairs


### TRESTLE JOINT

No. Y4001

Malleable Iron

Size	Price
8 ins.	2 6
10 "	3 3
12 "	4 6
14 "	5 7 1/2

Per pair



No. Y4005

Wrought Iron

Size	Price
10 ins.	4 6
12 "	6
14 "	7 6

Per pair

### STRAP AND CHEST HINGES




No. Y1238




Sizes, 6 8 10 12 ins.  
 No. Y1237, Machine Made, 3 6 5 3 8 9 6 per doz. pairs.  
 Measure full length when open.  
 Sizes, 6 8 10 12 ins.  
 No. Y1238, Wrought, 4 6 5 3 7 6 10 6 per doz. pairs.  
 Measure length from joint

### IMPROVED FIELD GATE HINGES

24 INCH



13 INCH 3 INCH INSIDE



9 INCH BOTTOM HINGE.

Size of Iron,	2 1/2 inch.
Weight per pair,	17 1/2 lbs
Price,	9


No. Y2754 can be specially made to suit any thickness gate and with Straps of any length to order

Price, 48 per set.

### JAPANNED SPRING OR DROP LATCHES

No. Y2755.

No. Y2756



Complete with Head Loops and Catches.

No. 1. Very Strong, 24 x 1/2 inch.  
 Price, 6 per set.

No. 2 Strong, Price, 4 6 per set.

No. 3 For Wicket Gates, Price, 3

# Door, Gate and Coach-House Hinges


No. Y 3033. **JAPPANED CROSS GARNET**



Sizes, .. 8 10 12 14 16 18 20 24 inches.  
Prices, 3/- 3/6 4/1 6/- 7/1 9/9 12/- 18/- per doz. pairs


No. Y 3034. **JAPPANED WATER JOINT**

With Return Strap Knuckle.



Sizes, .. 8 10 12 14 16 inches.  
Prices, .. 6/- 6/9 9/- 11/3 15/- per dozen pairs.  
Special. Extra Strong, 8 ins., Galvanized, for Greenhouse work.  
15/- per dozen pairs.

No. Y 4034. **EXTRA STRONG JAPPANED SCOTCH TEE HINGE**




This Hinge is made out of 10 gauge ( $\frac{1}{8}$ -inch) steel, and is recommended when a strong cheap Hinge is required.

Sizes, .. 12 14 16 18 24 inches.  
Prices, .. 8/- 12/9 15/- 16/10 25/- per dozen pairs.

No. Y 4035B.


**BEST FINISH WROUGHT-IRON LANCASHIRE TEE HINGE**

Bright Hinge Joint, Filed edges.



Sizes, .. 12 14 16 18 inches.  
Prices, .. 18/- 27/- 36/- 42/- per dozen pairs.

No. Y 3035. **WROUGHT WEIGHTY CROSS GARNET HINGES**




Sizes. 12 to 16 ins., 49/6 per cwt.  
" 18 " 36 " 48/- "

Approximate Weight per dozen pairs.

Sizes, .. 12 14 16 18 20 22 24 26 28 30 33 36 ins.  
Weight, 27 32 44 57 66 104 113 144 150 180 266 280 lbs.

No. Y 3077. **THE "PERFECT" HINGE**

Wrought-iron Strap.



Malleable-iron Socket and Chilled Bearings. Ornamental and very strong. We specially recommend this Hinge for Coach House and Barn Doors.

Sizes, 6 8 10 12 14 16 18 20 24 30 36 42 48 inches.  
Prices, 7/d. 9/d. 10/d. 1/- 1/6 2/6 3/- 3/6 4/6 7/6 10/6 13/6 15/- per pair.

No. Y 2982. **COLLINGS'S HINGES**



BOTTOM STRAP.

TOP STRAP.

Length of Strap.	Best Quality.	No. 2 Quality.	Length of Strap.	Best Quality.	No. 2 Quality.
2 ft. 0 ins.	9/-	7/6 per pair.	4 ft. 0 ins.	21/9	18/- per pair.
2 " 6 "	12/9	9/9 "	4 " 6 "	24/-	21/- "
3 " 0 "	15/9	12/9 "	5 " 0 "	28/6	24/- "
3 " 6 "	19/6	15/9 "	5 " 6 "	33/-	27/- "

3/- per pair extra for Hooks for Stone. Spanner for above, 1/3 each.

Special Bolts and Nuts for ditto, 4/6 per dozen.

No. Y 3036.

**HEAVY WROUGHT HINGES, with Hooks to Drive**



Sizes, .. 18 to 36 ins., 36/- per cwt.

Approximate Weight per dozen pairs.

Sizes, .. 18 20 22 24 26 28 30 33 36 ins.  
Weight, .. 80 100 127 156 206 212 296 333 348 lbs.

No. Y 3037.

**HEAVY WROUGHT HINGES, with Hooks on Plate**




Sizes, .. 18 to 36 ins., 45/- per cwt.

Approximate Weight per dozen pairs.

Sizes, 18 20 22 24 26 28 30 33 36 ins.  
Weight, 90 112 168 216 236 262 336 390 402 lbs.

No. Y 4035.

**SELF COLOR. STRONG LONDON TEE HINGE**




This Hinge is much stronger than the ordinary Jappaned Cross Garnet, and not so heavy as our Extra Strong Scotch Tee. Where a good medium strength Hinge is required this will be found very useful.

Sizes Stocked and Prices.

Sizes, 12 14 16 18 20 24 inches.  
5/3 6/6 8/3 12/- 15/- 21/- per dozen pairs.

# Door Checks and Springs

No. Y 4800. **"THE BRITON"**  
A NEW LIQUID DOOR CHECK AND SPRING (PATENT).



A principle has been introduced into this Check and Spring which has made it the most perfect and reliable Door Closer on the market.

## SOME OF ITS ADVANTAGES.

It is British made by British workmen.  
Every item of the material used in its construction is produced in England.  
It is made in sizes to suit any door—light or heavy.  
It suits either hand, right or left, without alteration of any part.  
Every Spring is tested before leaving our works.  
It can be fixed in five minutes by any ordinary workman.  
It can be adjusted to close the door quietly and slowly by simply turning a screw with the fingers.  
It is ornamental. It is cheap. It is warranted.

## PRICES.

Size A	For Light Doors,	1 1/2 inches thick,	.. .. .	21	each.
" B	" Ordinary Doors,	2 "	" "	24	"
" C	" Heavy Doors,	2 1/2 "	" "	30	"
" D	" very Heavy Doors,	2 1/2 "	" "	39	"

No. Y 1444. **A PERFECTLY SIMPLE SPRING**



Specially designed for fixing to the iron gates of ordinary railings. Suits any pattern, and can be fixed in a few minutes, requiring no other tool than a small spanner or screw wrench. It is made in one size only, but is adjustable in strength to close any weight gate.

Price, .. .. . 2 6 each.


No. Y 3148. **IMPROVED COIL DOOR SPRING**



Malleable Ends. No Loose Parts.

Size, 9 ins., for Light Doors,	.. .. .	6 9	per dozen.
" 11 " " Medium Doors,	.. .. .	9 9	"
" 13 " " Heavy Doors,	.. .. .	15 -	"
" 14 " " very Heavy Doors,	.. .. .	21 -	"

No. Y 3699. **IMPROVED "NORTON" SPRING AND CHECK**




One of the most popular Springs made. It is now supplied with nickel-plated cylinder and relieved gold mounts.

No. Y 3699.	For Light Doors,	.. .. .	Price, 18/9 each.
" Y 3698.	" Medium Doors,	.. .. .	22/6 "
" Y 3697.	" Heavy Doors,	.. .. .	24 9 "

Each Spring packed in box, complete, with screws.

No. Y 3141. **SMITH'S PATENT FLOOR SPRING**




Sizes made, 1 1/2, 1 3/4, 1 7/8, 2, 2 1/4, 2 1/2, 2 3/4 ins., measured outside shoe.


Price, for Light Doors, to 2 ins. thick,	.. 5 1/2 x 5 1/2 ..	21 - each.
" " Medium Doors, to 2 ins. thick,	.. 7 1/2 x 6 1/2 ..	22 6 "
" " Heavy Doors, to 2 1/4 ins. thick,	.. 8 1/2 x 7 1/2 ..	31 6 "
" " very Heavy Doors, to 2 1/2 ins. thick,	.. 9 1/2 x 8 1/2 ..	54 - "

If with Adjustable Top Centre, 3/9 each extra.

No. Y 3136.  
**"HELICAL" DOOR SPRING**



No. Y 3136R.  
**PATENT REGULATING SPRING**




No. Y 3136.  
Japanned Iron.

No. Y 3136R.  
Japanned Iron.

3	3 1/2	4	5	6	7	8 ins.	Sizes,	4	5	6	7	8 ins.
1 9	1 10 1/2	2 3	3 7/8	3 9	5 3	7 6 ea.	Prices,	3 3	3 6	4 6	6 7	9 - ea.

No. Y 3137. Polished Brass.	No. Y 3137R. Polished Brass.
3 3 3 6 4 6 6 - 7 6	10 6 12 6 ea.
Sizes,	4 5 6 7 8 ins.
Prices,	5 3 6 9 8 3 11 3


No. Y 3141. **TAIL DOOR SPRING**



Sizes,	12	14	16	18	20	24	28	30 ins.
XX Strong,	.. 1 -	1 1 1/2	1 3	1 4 1/2	1 6	1 9	-	- ea.
XXX Stronger,	.. 1 4 1/2	1 6	1 7 1/2	1 9	1 9	2 -	2 3	2 6 "
XXXX Extra Strong,	1 9	2 -	2 3	2 6	2 9	3 -	3 3	3 6 "
XXXXX For Heavy Doors,	-	-	-	-	-	5 3	6 7	6 9 "

# Iron and Brass Pulleys and Sash Lines

No. Y 4137. **SINGLE SCREW PULLEY**



PRICE, per Dozen.

Sizes, ..	1	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	5 1/2	6	8
Iron, Single, ..	17	22	29	33	41	101	6	83				
.. Double, ..	36	46	66	69	99	12	166					
Brass, Single, ..	39	66	83	99	15	21						


No. Y 4147. **UPRIGHT PULLEY**



Price, per Dozen.

Sizes, ..	1	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	5 1/2	6	8
Iron, Single, ..	2	29	33	41	101	6	83					
.. Double, ..	46	66	69	99	12	166						
Brass, Single, ..	76	113	15	21	33							


No. Y 4143. **SIDE PULLEY**



Price, per Dozen.


Sizes, ..	1	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5	5 1/2	6	8
Iron, Single, ..	17	22	29	33	41	101	6	83				
.. Double, ..	33	46	66	69	99	12	159					
Brass, Single, ..	76	99	113	12	196							

No. Y 3078. **AXLE PULLEY**



Sizes, ..	1 1/2	2	2 1/2	ins.
No. Y 3078. All Iron, Painted Face, ..	16	18	27	gross.
.. Y 3077. Iron Wheel, Brass ..	36	37	6	48
.. Y 3078. Brass ..	54	60	78	


No. Y 3070. **FRAME PULLEY**



All Iron.

Sizes, ..	1	1 1/2	2	2 1/2	ins.
YOUNG & MARTEN'S	10	6	13	6	gross.


No. Y 3090. **KENRICK'S "SECRET" AXLE PULLEY**



Sizes, ..	1 1/2	2	2 1/2	ins.
All Iron, ..	22	6	27	36 gross.
Iron Wheel, Brass Face, ..	45	54	72	
Brass Wheel, ..	72	85	6	126

No. Y 3098. A Special Cheap "SECRET" AXLE PULLEY, 1 1/2 ins. Iron, 19 6; Iron, with Brass Wheel, 36 per gross.

No. Y 3875. **FRAME PULLEY**



Solid WROUGHT STEEL, very strong.

Size of Face Plate, ..	4 ins.
.. Wheel, ..	1 1/2 "

Price, 15/- per gross.

No. Y 3876. **AXLE PULLEY**




KENRICK'S PATENT "ANTI-FRICTION."

Size of Wheel, ..	1 1/2	2	2 1/2	ins.
No. Y 3876. Varnished	5	7 1/2	6	66 p. doz.
Ornamental Iron Face				
and Iron Wheel, ..				
No. Y 3877. Cast Brass	12	9	15	18
Face and Brass Wheel, ..				

## FLAX SASH LINE

Illustrations show exact size



PRICE, per Gross Yards.


No. ..	2	3	4	5	6	7	8	9	10
No. Y 3081. YOUNG & MARTEN'S SPECIAL Flax Sash Line, ..	83	83	99	113	136	166	18		
.. Y 3082. AUSTIN'S Patent Flax Sash Line (Yellow Label), ..	76	9	113	15	166	196	22	6	24
.. Y 3083. Fine Twine Sash Line (Green Label), ..	12	15	9	196	24	30	34	6	48
.. Y 3084. Extra Super Flax Sash Line (Green Label), ..	18	24	27	31	6	36	45	48	54

"SAMSON" SASH LINE (Genuine).

Sizes, ..	1	1 1/2	2	2 1/2	ins.
Prices, ..	21	25	6	31	6
				39	4
				52	6
				72	




## Blind Furniture and Fittings

No. Y 4929. **BLIND ROLLER ENDS**

		Sizes,	..	1 $\frac{1}{2}$	2	inches.
No. Y 4045.	Bronzed Iron,	..	..	1 $\frac{1}{2}$	..	per dozen pairs.
" Y 4020.	Stamped Brass,	..	..	3/-	4/6	" "

No. Y 4021. **BLIND ROLLER ENDS, Strong, all Brass**




For ..	1	1½	1½ in. Roller.
.. ..	8/3	10/6	— per dozen.
.. ..	—	12/9	14/3 „

Brackets, No. Y 6024, extra.

## BRASS RACK PULLEYS

No. Y 4022.



No. Y 4023.



No. Y 4072.




**Patent Adjustable.**

**Strong, Cast.**

	4½	5 ins.	
Polished Brass,	6 6	8 3 per dozen.	6 ins., 13 6 per dozen.
China Knob, ..	7 6	9 9 "	7 " 18 "

No. Y 6028.


## YOUNG'S, CORD HOLDER



Per gross.


No. Y 6026.	Light, ..	<b>11/3</b>
.. Y 6027.	Medium, ..	<b>15/-</b>
.. Y 6028.	Strong, ..	<b>18. -</b>
.. Y 6030.	Electro ..	<b>9/9</b>
	Brassd., ..	

No. Y 6023.



No. Y 6023. Bronzed Iron,	Per gross pairs.	13/6
„ Y 6024. Cast Brass, Strong,	Per dozen pairs.	7/6

No. Y 6078. "HARTSHORN" SHADE ROLLER



42 ins. long	× 1 inch	Roller, complete with Brackets, ..	..	..	..	..	11 3/4 per dozen sets.
48 "	"	" "	"	"	"	"	18 "
54 "	"	" "	"	"	"	"	21 "
60 "	"	" "	"	"	"	"	39 "


## VENETIAN BLIND CORD

	Sizes, ..	2	2½	3 lbs.
YOUNG & MARTEN'S Special, White or Duck,	.. ..	4 6	6 -	7 6 per gross yards.
AUSTIN'S "Anchor," White or Duck, ..	.. ..	6 9	8 3	9 9 " "

Supplied in half-gross coils.

**GLACIE LINES** White, Red or Green.

	Size Nos., . . .	2	3	4	5	6	7	8	
Best Quality,	..	3 9	4 10	6 9	8 -	9 9	11 3	12 9	per gross yards.
		In half-gross boxes.							



## VENETIAN LADDER TAPE

		Distance between Laths.	Length of Strap.	
Letter C represents	..	1½	×	2½ inches.
" D "	..	2	×	2½ "
" E "	..	2½	×	2½ "
" F "	..	2½	×	3 "

In Coils of 72 yards ONLY.


	Per 72 yards.
YOUNG & MARTEN'S Special.	.. 13/6
CARR'S STAMPED Quality,	.. 27/-

Prices are for Duck (half bleached), White,  
Green, or Buff. 3/3 per 72 yards extra.

**Original Coils, uncut, only supplied.**

# Brass and Iron Castors and Sash Rollers


No. Y 4177  
**BRASS SOCKET CASTOR**



Strong Quality.

Prices, per Set of Four.  
 Sizes of Sockets, 1 1/2 1 3/4 1 1/2 1 1/4 ins.  
 No. Y 4177, Brown Bowl, 3 36 39 46 53  
 No. Y 4187, Brass Bowl, 4 11 47 57 69 83


No. Y 4177  
**BRASS SCREW CASTOR**  
VITRIFIED BOWLS.



Strong.

Prices, per Set of Four.  
 Sizes of Bowls, 1 1/2 1 3/4 1 1/2 1 1/4 ins.  
 Brown Bowl, 2 7 3 39 6


No. Y 4182.  
**STRONG PIVOT CASTOR**



Best

Prices, per Set of Four.  
 Sizes, 1 1/2 1 3/4 1 1/2 1 1/4 ins.  
 Iron, Wood Bowl, 2 9 36 46

No. Y 4198.  
**BRONZED IRON**  
**ROLLER BEARING CASTOR**



Prices, per Set of Four.

Sizes, 1 1/2 1 3/4 1 1/2 1 1/4 3 4 ins.  
 13 16 2 29 6 9 15

No. Y 3453.  
**BRASS SASH HOOK**




For 1 inch Stick.  
 Price, 10 6 per dozen.

No. Y 3454.  
**LONG-ARM HOOK**



No. Y 3454. Brass, 18 per dozen  
 Y 3454. Iron, 5


No. Y 3452.  
**LONG-ARM HOOK**



Extra Strong  
 Brass, 18 per dozen

No. Y 3457.  
**BRASS CLEAT HOOK**

Size	Price
1 1/2 ins.	5 3 per dozen
1 3/4 "	7 6 "
2 "	9 "
2 1/2 "	10 6 "




No. Y 3178.

Japaned Iron (Malleable)

Size	Price
1 1/2 ins.	1 9 per dozen
2 "	2 "
2 1/2 "	3 "

**TURNED ASH HANDLES** for above, 12 ins. Diameter, 8 ft. 2 1/2 9 ft. 2 6 10 ft. 3 each


No. Y 4195.  
**SASH ROLLER**



No. Y 4195. Iron.	Price.
Size of Plate, 1 1/2 x 1/2 in.	9d. per doz.
1 1/2 x 1 in.	1 "
2 x 1 in.	1 6 "
2 1/2 x 1 in.	2 "
3 x 1 in.	3 9 "
4 x 1 1/2 in.	6 "


No. Y 4196. Brass.	Price.
Size of Plate, 1 1/2 x 1/2 in.	3 per doz.
1 1/2 x 1 in.	4 "
2 x 1 in.	5 "
2 1/2 x 1 in.	6 6 "
3 x 1 1/2 in.	10 6 "

No. Y 2404.  
**ECCENTRIC CUPBOARD CATCH**



Size, 12 ins. wide.  
 Price, Iron, 4 6; Brass, 9 9 per doz.

No. Y 2409. **BALE'S BALL LATCHES**




Size of Plate.	Price.
1 1/2 x 1 in.	5 3 per doz.
1 1/2 x 1 1/2 in.	6 "
2 x 1 in.	10 6 "
2 1/2 x 1 in.	13 6 "
2 1/2 x 1 1/2 in.	16 6 "
3 x 1 1/2 in.	21 "
3 x 2 in.	27 "

**DOUBLE LIP STRIKERS** can be supplied if required at 3d. each extra.

# Fanlight and Skylight Openers

## LEGGOTT'S SYSTEM


### No. Y 5416. FANLIGHT OPENER



Size No. 2. Malleable Iron, .. .. .	3/9 each.
.. 2. Gun Metal, Polished, .. .. .	6 ..
Size No. 2 opens 10 ins., and is suitable for windows about 2 ft. square, or similar area.	
Size No. 6. Malleable Iron, .. .. .	4 6 each.
.. 6. Gun Metal, Polished, .. .. .	8 3 ..
Size No. 6 opens 18 ins., and is suitable for windows about 3 ft. square, or similar area.	
Size No. 8. Malleable Iron, .. .. .	9 ..
.. 8. Gun Metal, Polished, .. .. .	18 ..
Size No. 8 opens 18 ins., and is suitable for large heavy windows.	

These are made to fix in almost any imaginable position, and are always locked when opened or closed.

### No. Y 5418. SKYLIGHT OPENER




Size No. 3. Malleable Iron, .. .. .	4 6 each.
.. 3. Gun Metal, Polished, .. .. .	9 ..
Size No. 3 opens 10 ins., and is suitable for skylights 2 ft. long and 1 ft. 3 ins. wide.	
Size No. 5. Malleable Iron, .. .. .	6 6 each.
.. 5. Gun Metal, Polished, .. .. .	10 6 ..
Size No. 5 opens 15 ins., and is suitable for skylights 3 ft. long and 2 ft. wide.	
Size No. 7. Malleable Iron, .. .. .	10 6 each.
.. 7. Gun Metal, Polished, .. .. .	21/- ..
Size No. 7 opens 18 ins., and is suitable for skylights 5 ft. long and 3 ft. wide.	

For Roof Lights above this size we make a specially powerful opener.

### Endless Cords for above Measured Double.

Sizes, 6 7 8 10 12 feet.
Prices, 7½d. 7½d. 7½d. 1 1 3 each.

## CARTLAND'S PATENT "INVISIBLE" FANLIGHT OPENER



No. Y 5424 (Half size).

The advantages of this invention will be appreciated by Architects, Builders, and others, and recognised as being a perfect Fanlight Opener.

There is no unsightly projection into the room, and its action is simple, easy, and certain.

All the fixing required is a hole bored into the side frame, large enough for the screw to work freely, and when the Fanlight is closed the Opener is entirely out of sight.

	Brass.	Iron.
No. Y 5424. For Fanlight hinged at bottom, opening IN, ..	8 3	6 - each.
.. Y 5426. .. .. hinged at top, opening OUT, ..	8 3	6 - ..
.. Y 5428. For Pivot Sashes, .. .. .	8 3	6 - ..
.. Y 5430. Side Adjustments, as illustrated, .. .. .	2 9	1 6 ..


Endless Cords for above (same as for Leggott's System).

For Heavy Fanlights a Larger Screw is used, at ONE-THIRD increased cost.

## PULLEYS AND FITTINGS

To be used with above Openers.

### No. Y 5422.



No. Y 5420.



No. Y 5421.




No. Y 5420. Double Swivel Pulley, Brass, .. .. .	3 - each.
.. Y 5421. Double Upright Pulley, Brass, .. .. .	3 - ..
.. Y 5422. Weighted Sliding Handle, Brass, for endless cords, .. .. .	4 4 ..

### No. Y 4311.

## MALLEABLE-IRON FANLIGHT OPENER

Suitable for a Sash hung at Top or Centre, and opening outward at Bottom. Berlin Black.



Sizes, 12 14 16 18 21 24 inches.
Prices, 12 9 15 9 19 6 22 6 25 6 36 - per dozen.


### No. Y 4008. SKYLIGHT IRON Wrought Iron.



Length, 6 8 9 10 12 15 18 inches.
Prices, 6/- 6/- 6/9 6/9 7/6 9/- 10 6 per dozen.

# Fanlight Openers and Fasteners

No. Y 5335.  
For Sashes opening OUTWARDS.




Showing Nos. 1 and 2.

## THE "FITALL" PATENT FANLIGHT OPENER

The "Fitall" Fanlight Opener, as its name implies, is suitable for Sashes hinged at **Top** or **Bottom**, or hung on **Central Pivots**; it is supplied in Malleable Iron, Black finish, or in solid Brass. We do not recommend it for very heavy Fanlights, but for small and medium Sashes. It is the best and simplest Opener on the market **AND THE CHEAPEST.**

Nos. Y 5335 and Y 5339.  
For Sashes opening INWARDS.



Showing Nos. 3 and 4.

No. Y 5335. IRON.				No. Y 5340. BRASS.			
No. 1.	For Sashes Opening Outwards	(Right Hand), ..	Price, ..	No. A.	For Sashes Opening Outwards	(Right Hand), ..	Price, ..
" 2.	" " " "	(Left Hand), ..	complete	" B.	" " " "	(Left Hand), ..	complete
" 3.	" " " " Inwards	(Right Hand), ..	with Cords	" C.	" " " " Inwards	(Right Hand), ..	with Cords,
" 4.	" " " " " (Left Hand), ..	" 1 9 each.	" D.	" " " " " (Left Hand), ..	" 4 1½ each.		

No. Y 5339. IRON. In One Hand only, for Larger Sashes. Price, 3/9 each

## THE PATENT FACILE FANLIGHT OPENERS

This System of Opening and Closing Fanlights can be applied in almost every conceivable position, and for one or more lights.

The two illustrations show the simplest form, but we shall be pleased to forward upon application our complete List of Fanlight Gear, in which every combination is fully dealt with.

PRICES, WITH IRON AND GUN-METAL FITTINGS.


All the Vertical Rods are of Smooth Blued Steel.

Gear Box in Gun Metal.



		Iron Fittings.	Gun metal Fittings.
No. Y 6070.	For ONE Light, OPENING INWARDS, hinged at bottom, .. .. .	18/-	33/- per set.
" Y 6071.	For TWO Lights, OPENING INWARDS, hinged at bottom, .. .. .	22/6	36/ "
" Y 6072.	For ONE Light, OPENING OUTWARDS, hinged at top or on pivots, .. .. .	18/-	33/ "
" Y 6073.	For TWO Lights, OPENING OUTWARDS, hinged at top or on pivots, .. .. .	22/6	36/ "

Above are priced with 6-ft. Steel Vertical Rod; if longer, 7½d. per foot is charged.

No. Y 6079.	Stay Arm, with Spring, to be used at side of heavy Lights, .. .. .	6/-	12/- "
-------------	--	-----	--------



No. Y 6070.  
For Fanlight hinged at bottom and opening in.



No. Y 6072.  
For Fanlights hinged at top or on centres, and opening out at bottom

# Locking Bars, Greenhouse Stays, &c.

No. Y 3521.  
**WROUGHT CABIN HOOK**



Sizes, 6 8 10 12 14 ins.  
Prices, 6/- 6/6 8/3 9/9 12/- per doz.

No. Y 3223.  
**LOCKING STAPLE**




To take Bar  
3 - 2 1/2 4 - 2 1/2 ins.  
1 9 2 6 each.

No. Y 3522. **CABIN HOOK**




No. Y 3521. Japanned, 2/6 2/9 3/6 4/- 4/6 5/3 per doz.  
Y 3522. Malleable, 3/3 3/6 4/- 5/6 7/6 8/-  
Y 3523. Brass, .. 6/- 6/6 7/6 9/9 11/3 13/6 ..

No. Y 3526.  
**WROUGHT-STEEL JAPANNED HASP AND STAPLE**



Sizes, .. 4 4 1/2 5 5 1/2 6 ins.  
Prices, .. 1/9 2/- 2/6 4/6 6/9 per doz.  
Galvanized, 3/9 4/- 5/3 9/- 13/6 ..

No. Y 3219. **LOCKING BAR (Malleable)**




Berlin Black.

12 - 17 11 17 10 2 18 - 2 1/2 20 2 1/2 24 2 1/2 30 2 1/2 36 2 1/2 ins.  
3/- 3/9 4/- 6/- 7/6 9/- 10 6 11 3 each.


The 24-inch size and larger have two Hooks.

No. Y 4299. **EXTRA STRONG LOCKING HASP**




Sizes, .. 10 x 1 1/2 12 x 1 1/2 14 x 1 1/2 16 x 2 ins.  
Prices, Black, .. 1/10 2/3 2/9 3/9 each.  
Galvanized, 2/3 3/- 3/9 4/6 ..

No. Y 3100. **MALLEABLE-IRON GREENHOUSE STAY**



Sizes, .. 12 15 18 21 24 27 30 inches.  
Prices, .. 10/6 13 6 16/6 17 3 18/9 24/- 27/- per dozen.

No. Y 4010. **SHAD BOLT STAY**



Size, 10 1/2 inches. Price, Hardened Copper, 18 - per dozen.

No. Y 4308. **STRONG SLOTTED QUADRANT STAY**




Sizes, .. 18 21 inches.  
Prices, .. 24 - 30 - per dozen.

No. Y 4303. **STRONG SKYLIGHT STAY**



Sizes, .. 15 18 21 24 27 inches.  
Prices, .. 16/6 18/- 21/- 24/- 30/- per dozen.

No. Y 3125.  
**MALLEABLE QUADRANT STAY**




Sizes, 7 10 12 ins.  
Prices, 6/- 9/- 10/6 per doz.

No. Y 2989.

Strong Polished Brass.

Sizes, 6 7 8 ins.  
Prices, 3/9 4/- 4/6 per pair.

No. Y 1228.  
**ROLLER STAY for Fanlights.**




Malleable Iron.

Size, 8 ins., .. 12/- per doz.

# Greenhouse Ventilating Fittings and Gear


MALLEABLE IRON.

No. Y 650. **SPRING LEVER**



Price, .. .. 19 6 each.


No. Y 662. **QUADRANT LEVER**



To fix on Horizontal Bar.


Price, .. .. 12 each.

No. Y 653. **JOINTED ARM**




16 inch full length,	..	2/-	each
18 " " " "	..	2/3	"
20 " " " "	..	2/6	"
22 " " " "	..	2/9	"

No. Y 652.  
**STRONG BEVEL WHEEL GEAR FOR  
HEAVY TOP LIGHTS**



Price, .. .. 30 - each.

No. Y 660. **PATENT SCREW GEAR**



This Patent Gear is neat, noiseless,  
powerful, and easily fixed.

Price, .. .. 21, each.

No. Y 654. **STRONG LEVER**




11 inch,	..	1/7½	each.
15 " " " "	..	1/9	"
18 " " " "	..	2/-	"

No. Y 655  
**CARRIER**



Price, .. 1/- each.  
Projects 3 ins. to centre

No. Y 656.  
**PLATE CARRIER**




Price, .. 1/3 each.  
Projects 3 ins. to centre

No. Y 663. **WROUGHT-IRON STAY AND STUD**



24 inch,	..	3/-	each.
30 " " " "	..	3/3	"

No. Y 651.  
**MALLEABLE-IRON QUADRANT LEVER**



Price, .. .. 15/- each.  
Connecting Tube NOT included.

Iron Tube suitable for above Gearing, 4½d. per foot; smaller ditto, for Nos. Y 651 and Y 658 Connections, 3d. per foot.

No. Y 657.  
**COLLAR**




Price, 9d. each.

No. Y 658.  
**CONNECTING JAW**  
Price, 1/10½ each.



To suit ½-in. and ¾-in.  
Tube.


No. Y 661.  
**COUPLING FOR ¾-in. TUBE**



Price .. .. 2/9 each.


# Ventilators

No. Y 3160. **MICA FLAP VENTILATOR**  
Outlet.



Size of Front, Inches.	Size of Box, Inches.	Price, each.
11 x 5 ins.	9 x 3 ins.	3 3
11 x 7 "	9 x 5 "	4 10
11 x 9 "	9 x 7 1/2 "	6
11 x 11 "	9 x 9 "	7 6
16 x 11 "	14 x 9 "	11 3
24 x 11 "	21 x 9 "	18 6

No. Y 3167. **MICA FLAP VENTILATOR**  
Outlet.




HIT AND MISS FRONT.

Fitted with Iron Hit and Miss Front, complete.

Size of Front, Inches.	Size of Box, Inches.	Price, each.
11 x 5 ins.	9 x 3 ins.	7 6
8 x 8 "	6 1/2 x 6 1/2 "	9 9
11 x 7 "	9 x 5 "	9 9
11 x 9 "	9 x 7 1/2 "	15 1/2
16 x 11 "	14 x 9 "	24 1/2

No. Y 3180. **SLIDING VENTILATOR**




Varnished Bronzed Iron.  
To screw on woodwork.

Size, 6 3/4 ins.	9 - per doz.
9 3/4 "	12 1/2
9 9/16 "	19 6
10 9/16 "	27 1/2
12 9/16 "	33

Nos. Y 3180 and Y 3184 can be supplied for brickwork if required.


No. Y 3184. **SLIDING VENTILATOR**



Varnished Bronzed Iron.  
To work with cords.


Size, 6 3/4 ins.	11 1/3 per doz.
9 3/4 "	27 1/2
12 9/16 "	36 1/2

No. Y 3164. **SILK FLAP VENTILATOR**  
Outlet.



Size of Front, Inches.	Size of Box, Inches.	Price, each.
11 x 5 1/2 "	9 x 3 "	4 6
11 x 8 1/2 "	8 1/2 x 6 "	7 6
11 1/2 x 11 1/2 "	9 x 9 "	9
15 1/2 x 11 1/2 "	13 1/2 x 9 "	12 1/2

No. Y 3168. **SHERINGHAM'S VENTILATOR**  
Inlet.




BALANCE

Price includes weight

Size of Front, Inches.	Size of Box, Inches.	Price, Plain.	Price, Galv.
11 1/2 x 5 1/2 "	9 x 3 "	4 6	6/- each.
16 x 8 1/2 "	13 1/2 x 6 "	7 6	10/6
11 x 8 1/2 "	9 x 6 "	6	9/-
10 1/2 x 10 1/2 "	9 x 9 "	7 6	10/6


No. Y 3170. **AIR BRICK**  
Specially made to suit Ventilators.




FOR OUTER WALL.

Sizes.	Price, Plain.	Price, Galvanized.
9 x 3 ins.	4 6	7 6 per doz.
9 x 6 "	9	15
9 x 9 "	13 6	27
13 x 6 "	13 6	27 1/2
17 x 12 "	27	45

**IMPROVED WROUGHT-STEEL LOUVRE VENTILATOR**



This Ventilator is a distinct advance upon anything in Louvre action at present on the market. It is made of WROUGHT STEEL throughout, and is unbreakable. It can be used either with cords or long arm, and acts as inlet or outlet as desired. Finished in Enamelled BLACK or WHITE.




SIZES AND PRICES.	Y 3181. Black.	Y 3182. White.
Size Box 8 x 6 ins.	5 - each.	6 - each
" 10 x 8 "	5 6	6 6
" 12 x 10 "	7	8 9

Front of Ventilator measures 3/4 inch larger all round than Box.  
Cord and Knobs suitable for above, 4/6d. each net.


**BRASS VENTILATING GRATINGS**  
FOR SHOP FRONTS.

No. Y 3901.



Sheet Brass, Dead Dipped.  
Width—  
2 1/2 3 3 1/2 4 5 6 ins.  
18 16 16 15 15 14 W.G.  
2 3 2 7 1/2 3 4 1/2 3 9 6 7 6 per ft.  
Made up to 6 ft. long.

No. Y 3902.



Cast Brass, Sanded.  
Width, 3 3 1/2 4 ins.  
Prices, 6 9 8 3 9 9 per ft.


No. Y 3903.



Cast Brass, Polished.  
Width—  
2 2 1/2 3 4 5 6 ins.  
6 - 6 9 7 6 9 - 13 6 18/- per ft.

No. Y 3527.


**DROP GATE STOP**



Wrought Iron.  
Size, 12 x 1/2 inch.  
Price, 16/6 per dozen.


# Wrought-Iron School Board Hat and Coat Hooks, &c.

No. Y 1886.  
Hat and Coat Hook



A very Strong Plain Japanned Hook.  
Price, 1 7½ per dozen.

No. Y 3112.  
Hat and Coat Hook




Polished Brass  
Size, 6 ¾ 7 ½ ins.  
Brass, 10 6 12 18 per doz.  
No. Y 3511. One size only.  
Brass Plated, 4 6 per doz.

No. Y 3118.  
Wardrobe Hook




Sizes, 2 2½ 2¾ ins.  
Japanned, 6 7 6 9 per pt.  
Polished Brass, 3 6 5 3 7 6 per doz.  
Brass, 7 6 9 9 13 6 per pt.  
Brass Plated, 7 6 9 9 13 6 per pt.

No. Y 3431  
Double  
Wardrobe  
Hook



No. Y 3431 Polished Brass 9 per doz.  
No. Y 3126 Japanned 6 6 per pt.  
One Hole, 6 6 per pt.  
No. Y 3126 Coppered 9 9  
Two Holes

No. Y 3433.




Young & Marten's  
Patent Automatic  
Hat or Muff Hook

This Hook has been designed for use in the Pews of Churches, Theatre Stalls, Railway Carriages, Ship Cabins, Lavatories, Bath Rooms, &c., and is specially useful where space is limited.

In use the Hook automatically springs back into position B, as soon as the Hat or Muff is removed, and is quite out of the way.


Polished Brass, 30 per doz.  
Antique Copper, 36  
Nickel Plated, 39  
Oxidized Silver, 39

No. Y 226.




Ordinary School Board Pattern.  
Price, 13 6 per gross.

No. Y 2270.



Strong Barrack Pattern.  
Size, 4 W.C.  
Price, 2 6 per doz.

No. Y 2275.



With Number Plates.  
Price, complete, 4 6 per doz.

No. Y 2277.




With Malleable Raised Number Plate.  
Price, complete, 5 3 per doz.

## Special School Board Hat and Coat Hook

No. Y 2384.

TO FIX ON  
WROUGHT-IRON TUBE.



No. Y 2385.



Japanned, with Raised Figures painted White.

To fix on 1 inch Gas Tube, .. .. . Price, 2/- per pair.  
" " 1½ " " " .. .. . " 2/3 "  
" " 1½ " " " .. .. . " 2/6 "


The set screws shown are included in price of hook.

To fix on 1 inch Gas Tube, .. .. . Price, 1/8 each.  
" " 1½ " " " .. .. . " 1/10 "  
" " 1½ " " " .. .. . " 2/- "




# Shelf Brackets, Umbrella Holders, and Stair Treads

No. Y 4360.  
Fine Cast, Ornamental (Strong)




Size	Price, per doz.
6 x 4 in.	3 3
7 x 5 "	3 6
8 x 6 "	5 3
10 x 8 "	6
12 x 10 "	9
14 x 12 "	11 3

No. Y 1985.  
Wrought-iron Shelf Bracket



Size	Price, per doz.
4 x 3 in.	1 1 1
5 x 4 "	1 6
6 x 5 "	2 6
8 x 6 "	3 3
10 x 8 "	5 3
12 x 10 "	7 6
14 x 12 "	10 6


No. Y 2460. Polished Brass



Strong Brass,  
for either  
wood or glass  
shelves.


Size	Price, per doz.
3 ins.	10 6
4 "	15
5 "	18
6 "	19 6
7 "	24

No. Y 2459.  
Malleable-iron Bracket



Size	Price, per doz.
1 1/2 ins.	1 1 1/2
2 "	1 7 1/2
2 1/2 "	1 9
3 "	2 9
3 1/2 "	3 3
4 "	3 6

No. Y 1987. Folding Steel Shelf Bracket




The exceedingly simple action of the folding arm, whereby the table leaf, shelf, shop-assistant's seat, greenhouse stage, &c., will drop flat against the wall, makes this Bracket a very useful article indeed.

A PAIR OF EITHER SIZE  
WILL SUPPORT  
400 LBS.

Size	Price
8 x 8	2
12 x 12	3
16 x 16 ins.	5 3 per pair

No. Y 1461. Patent Ladder Brackets



INSTANTLY FORMING A PLATFORM AT ANY  
HEIGHT, FOR SUCH PURPOSES AS  
PAINTING, SIGN WRITING,  
POINTING, FIXING  
GUTTERS, &c.




Bracket closed up.

These Brackets are made of thoroughly tested steel, and are ABSOLUTELY RELIABLE.  
The hooks engage TWO rounds of each ladder and on either side of ladders.

SAFE, COMPACT, AND NO SIDE MOTION.

Weight per pair, 26 lbs. Price, per pair, 37 6

No. Y 4164. Stair and Threshold Tread




Polished Brass, 11 pairs

Sizes (measured over all), 3 4 5 6 7 8 9 10 ins. wide.  
Plain Polished or Checkered Brass,  
for Entrance Doors, 3 4 4 6 5 3 6 6 7 6 9 9 9 11 3 per lin. ft.

Sizes, 1 1/2 2 2 1/2 2 1/2 ins. wide.  
Brass Stair Tread, Checkered, with  
Nosing, 2 3 3 9 4 per lin. ft.

No. Y 4153. Mason's Patent Steel and Lead Stair Tread



No. Y 4155.

2 in. Filling.

No. Y 4159.

3 1/2 in. Nosing.


This Patent Combined Steel and Lead Stair Tread is now almost universally used in railway stations, public buildings, ships' stairs, &c., and is the most durable and reliable Non-slipping Tread made.

Sizes	Price
No. Y 4159. Plain Iron and Steel,	2 6
" Y 4183. With Polished Brass Nosing,	5 3
" Y 4185. Filling in Strips to widen Tread,	1 1/2 ins., 1 1/2; 2 ins., 1 4


No. Y 4160. Umbrella Rail

Polished Brass.

2 in. Twisted Tube, 1 1/2 ins. overall, 36 per doz.  
Suitable Bronzed Iron Pans for ditto, 1 6 each.



Wrought-steel Stair Tread



Specially suitable for omnibus steps, warehouse stairs, &c.

No. Y 1462. 1 1/2 ins. wide, 3 1/2d. per ft.	No. Y 1464. 2 1/2 ins. wide, 10 1/2d. per ft.
" Y 1463. 2 1/2 " " 6d.	" Y 1465. 3 1/2 " " 1 1 1/2 "

Nos. Y 1464 and Y 1465 with Nose.

# Carpenters' and Joiners' Tools

No. Y 1500. **BRAD AWL**



Improved FAST Tang.

Price, .. 2/6 per dozen.

No. Y 1530. **COMPASSES**



Quality - Best Bright Rule Joint.

Sizes, 6 7 8 9 10 ins.

Prices, 10/d. 1 1 1/6 1/9 2/3 p. pair.

No. Y 1527. **FLAT-NOSE PLIERS**



Quality—Best Black Lancashire.

Sizes, 4 5 6 7 8 ins.

Prices, 8/d. 10/d. 1/- 1/4 3/- p. pair.

No. Y 1540. **CARPENTER'S Mallet**



Oiled Beech.

Sizes, .. 6 6 1/2 7 ins.

Prices, .. 2/3 2/9 3/- each.


No. Y 1589. **SMOOTHING PLANE**



Sizes, 2 2 1/2 2 1/2 ins.

Prices, 4/6 5/3 6/9 each.


No. Y 1502. **GIMLET**



Twist. Best Quality.

Nos. Small, 1 and 2 Medium, 3, 4, and 5 Large, 6  
Prices, 3/6 4/6 5/3 per doz.  
Per set of six, 2/6

No. Y 1528. **TOWER PINNERS**



Best Lancashire.

Sizes, 7 7 1/2 8 9 10 ins.

Prices, 1 3 1 3 1 9 2 2 6 per pair.

No. Y 1515. **SPOKESHAVE**



Sizes, .. 2 1/2 3 3 1/2 4 ins.

No. Y 1515. Beech, Plain, .. 1/3 1/6 1/9 2/3 each.

.. Y 1516. Box, Plated, .. 2/- 2 6 3/- 3 4/-

No. Y 1517. **SPIRIT LEVEL**




Sizes, .. 8 10 12 ins.

No. Y 1517. Plated top, .. 1/6 1/9 2/- each.

.. Y 1518. Plated top and Tipped bottom, 2 6 3 3 6 ..

No. Y 1507. **JACK PLANE**




Length, .. 17 in.

Irons, .. 2 1/2 ..

Price, .. 6/9 each.

No. Y 1566. **CAST-STEEL HAND SAW**




Hand, Panel, and Ripping, same price.

Sizes, .. 16 18 20 22 24 26 28 ins.

No. Y 1566, .. 4/6 4/10 5/3 6/- 6/9 7/6 8/3 each.

Y 1567. Disston's D8 Skew Back, 8/3 9/- 9/9 10/6 11/7 1/2 ..

No. Y 1503. **TURN SCREW**



Length of Blade, .. 4 5 6 7 8 ins.

No. Y 1503. London Pattern, Flat Blade, Flat Handle (as illustrated), 1 1 1/3 1/6 1/10 1/10 ea.

.. Y 1504. Cabinet, Round Blade, Best Oval Box Handle, .. 1 6 1 9 2/3 2/6 2/9 ..


No. Y 1505. **HANDLED FIRMER CHISEL**



Sizes, .. 1 2 3 4 5 6 7 8 10 12 ins.

Beech Handled, 9/d. 9/d. 1/- 1 1/4 1 3/4 1 3/4 1 4/4 1 5/6 ea.

No. Y 1199. **DRAW KNIFE**




Carpenter's London Pattern.

Sizes, .. 8 9 10 12 ins.

Prices, .. 3 3 6 3 9 4 6 each.

No. Y 1537. **"EXETER" OR "LONDON" HAMMER**




Turned Oval Ash Handles.

Size No., .. 2 3 4 5 6 7 8 ins.

Weight of Head 6 8 10 12 14 16 18 oz.

Prices, .. 1 3 1 9 1 9 2 2 3 2 7 1 3/- ea.

No. Y 1530. **SOLID STEEL "WARRINGTON" HAMMER**




Best Turned Ash Handle.

Size No., .. 2 3 4 5 6 7 8 ins.

Prices, .. 1 3 1 9 1 9 2 2 3 2 7 1 3/- each.

No. Y 1568. **BACK SAW**



Sizes, .. 10 12 14 16 ins.

No. Y 1568. Iron Back, .. 5/3 5/7 1/2 6/- 7/6 each.

.. Y 1569. Brass Back, .. 6/- 7/6 8/3 9/- ..

All the Tools illustrated above are of best quality and English made, except No. Y 1567.

# Felling Axes, Adzes and Hatchets

No. Y 1423.  
**STEEL POLLED KENT AXE**



Weight, 4 4½ 5 5½ 6 lbs.  
Prices, 1/3 1/3 1/3 1/3 1/1½ per lb.

No. Y 1424.  
**CARPENTER'S ADZE**  
Half Bright and Blued.



Sizes, A B C D  
Prices, 3/3 3/6 3/9 4/6 each.

No. Y 1425.  
**STEEL POLLED FELLING AXE**




Weight, 4 4½ 5 5½ 6 lbs.  
Prices, 1/3 1/3 1/3 1/3 1/1½ per lb.

No. Y 1426. **WEDGE AXE**  
"Bull" Brand.



Weight, 3 lbs. Price, 1/9 per lb.  
" 3½ " " 1/9 "  
" 4 " " 1/6 "  
" 4½ " " 1/6 "  
" 5 " " 1/6 "  
" 5½ " " 1/6 "  
" 6 " " 1/6 "  
" 6½ " " 1/6 "  
" 7 " " 1/6 "

No. Y 1428. **KENT BILL HOOK**



"Bull" Brand.


Sizes, .. 8 9 10 ins.  
Prices, .. 3/3 3/9 4/6 each.

No. Y 1429. **CLUB HAMMER**



Heads, Weight, .. 2 2½ 3 3½ 4 lbs.  
Prices, .. 9d. 9d. 8½d. 8½d. 7½d. per lb.  
If fitted with 10-inch Handles.  
Prices, .. 1/9 2/3 2/6 2/9 3/ each.


No. Y 1430. **HOUSEHOLD HATCHET**



"Oxford" Brand.

Sizes, A B C D E  
Prices, .. 1/10½ 1/10½ 2 2/3 2/6 each.

No. Y 1431. **CANADIAN HATCHET**  
Bright and Blued.



"Bull" Brand

Sizes, .. A B C  
Prices, .. 3/4½ 3/9 4/ each


No. Y 1432.  
**STEEL POLLED CARPENTER'S AXE**



"Bull" Brand

Sizes, .. A B C D E F G H  
Heads, .. 1½ 2 2½ 2½ 3 3½ 3½ lbs.  
Handles, .. 16 16 17 17 18 18 20 20 ins.  
Prices, .. 3/6 3/9 4/ 4/6 4/6 4/9 5/3 5/9 each.


No. Y 1433. **SPECIAL WEDGE AXE, Bright and Blued**



Handled with 30-inch Best Hickory Handle.

Heads, Weight, 3 3½ 4 4½ 5 5½ 6 6½ 7 lbs.  
Prices, .. 6/6 7/6 8/3 8/9 9/9 10/ 10/6 12/ 12/9 each.


No. Y 1435. **STEEL POLLED KENT FELLING AXE**



"Bull" Brand.

Heads, Weight, .. 4 4½ 5 5½ 6 lbs.  
Straight Handles, .. 32 32 32 34 36 ins.  
Prices, .. 6/ 6/6 7/ 7/6 8/3 each.  
If Bent Handles, 1/- per dozen extra.

No. Y 1434. **STEEL POLLED FELLING AXE**



"Bull" Brand.

Heads, Weight, 4 5 6 7 8 lbs.  
Straight Handles, 30 34 36 36 36 ins.  
Prices, .. 6/ 7/6 8/3 9/ 10/6 each.  
If Bent Handles, 1/- per dozen extra.


No. Y 1436. **CLAWED RAILWAY or PLATELAYER'S BAR**



Best Quality, .. .. 6d. per lb.


All the Tools illustrated above are of **BEST QUALITY** and **ENGLISH MAKE**.

# Bricklayers' and Masons' Tools



No. Y 1631.  
**BRICKLAYER'S HAMMER**

ASH HANDLE.  
Price, .. 3/4 each.



No. Y 1632.  
**SLATER'S HAMMER**

WITH CLAW. ASH HANDLE.  
Price, .. 3/9 each.



No. Y 1633.  
**SCAFFOLDING HAMMER**

ASH HANDLE.  
Weight of Head, 3 lbs.  
Price, .. 3/9 each.

No. Y 1453. **CAULKING TOOL**



No. Y 1454. **YARNING TOOL**



Sizes, 1/4, 1/2, 3/4, 1, 1 1/4 in. thick.  
Price, .. 1/6 per lb.

No. Y 1636  
**STONE-BREAKER'S HAMMER**



Usual size, 1 1/2 lbs.  
Solid Cast Steel, 9d. per lb.  
Handles for doz., 3/- per doz.

No. Y 1637.  
**SLATER'S IRON**




Price, .. 2/3 each.

No. Y 1638. **BRICK CLEANING AXE**



10-inch Blade, strong.  
Price, .. 3/- each.



No. Y 1639. **LATH HAMMER**

Nos., ..	1	2	3	4
Prices, ..	1 9	2/-	2 3	2 7 1/2 each.



No. Y 1640. **SLATER'S SAXE**  
Best Quality.

Sizes, ..	9	10	11 in.
Prices, ..	3/-	3/6	3 9 each.

No. Y 1641.  
**POINTING TROWEL**



Best Cast Steel.


Sizes, ..	5	6	7	8 ins.
Prices, ..	1/3	1 6	1 9	2/- each.

No. Y 1642. **GAUGING TROWEL**  
Best Cast Steel.



Sizes, ..	8	9	10 ins.
Prices, ..	2 3	3/-	3 3 each.

No. Y 1643. **BRICKLAYER'S TROWEL**




Best Quality (W.H.S.)  
No. Y 1643. Right Hand, 3 3/4 3/6 3 9 each.  
Y 1644. Left Hand, 3 3/4 3/6 3 9 ..

No. Y 1646.  
**PLASTERER'S TROWEL**



Best Quality, Single tang.  
10 ins., .. 2/9 each.




No. Y 1647. **SLATER'S RIPPER**

Warranted Best Cast Steel, every Blade Tested. 30 inches long.  
Price, .. 5 3 each



No. Y 1648. **BRICKLAYER'S JUMPER OR AUGER BIT**

Sizes, ..	1/2	3/4	1 inch.
Prices, ..	2/3	2/6	3/4 1/2 each.



No. Y 1649.  
**MORTAR SERVER**

Nos., ..	1	2	3	4
Prices, ..	1 4 1/2	1 6	1 9	1 10 1/2 ea.
Handle, 9d. each.				




No. Y 1650.  
**HAIR HOOK**

Prongs, 2 3  
Prices, 2 7 1/2 3 9 ea.  
Handle, 1/3 each.



No. Y 1651.  
**MORTAR LARRY**

Larry, .. 2 7 1/2 each.  
Handle, .. 1/6 ..




No. Y 1653. **NAVY BARROW**

No. Y 1653. Strong Ash Frame, with Strays, .. 16/6 each.  
" Y 1654. Do., with Extra Strong Iron Leg Strays, and Double Bolted, .. 23/3 ..

# Flooring and Joiners' Cramps


No. Y 2698. **JOINER'S IMPROVED CRAMP**  
Measurement is over all.



We guarantee this to be the strongest and best Cramp of this pattern in the market.


No. Y 2698, Length over all,	42	48	54	60	66	72	78
Prices,	18	19 6	21	22/6	24	25/6	27

No. Y 2698. **JOINER'S ORDINARY CRAMP**  
Measurement is over all.



Length,	42	48	54	60	66	72	78
Prices,	14 3	15	16/6	18	20	21/	23


No. Y 2610. **CRAMPTON'S PATENT JOINER'S CRAMP**



1 section steel bar. Measurement is over all.


Length	42	48	54	60	66	72	78
Prices,	14 3	15	16/6	18	20	21/	23

No. Y 2644. **WOOD BENCH SCREW**



Best Quality. Size, 2 1/2 ins.  
Price, 2 3 each.

No. Y 2646. **KIMBERLY'S PATTERN FLOOR CRAMP**



Best Quality.  
Price, 12/- each.

No. Y 2699. **CRAMP HOLDER**



Price, 3/9 each.

No. Y 2700. **LENGTHENING PIECE**



For Y 2638, .. .. .	2/3 per foot
" Y 2700, .. .. .	3/- "
" Y 2640, .. .. .	3/8- "

No. Y 2639. **JOINER'S ORDINARY SASH CRAMP**




Size to take in .. .. .	24	30	36 ins.
Prices, .. .. .	15/-	16/6	18/- per pair.

No. Y 2641. **CRAMPTON'S PATENT JOINER'S SASH CRAMP**  
(Parallel Action).




Bar, $1\frac{1}{4} \times \frac{1}{2}$ in.	Jaw, $1\frac{7}{8}$ ins. deep.
Size to take in .. 24	30 36 ins.
Prices, .. .. 18/-	21/- 24/- per pair.

No. Y 2645. **JOINER'S STEEL BENCH SCREW**



Best quality and finish.			Bright.	
Length, ..	18	20	22	24 ins.
Diameter, ..	1½	1½	1½	1½ "
Prices, ..	9/-	10/6	15/-	19/6 each.

No. Y 2647. **BISSELL'S PATTERN FLOOR CRAMP**



Price, 18/- each.

No. Y 2648. **CROWN PATTERN FLOOR CRAMP**




This is one of the strongest and best Floor Cramps made.


Price, 21/9 each.

# Wood Working Machinery and Drilling Machines


No. Y 2902.  
Centre Motion  
Mortising, Boring, and  
Tenoning Machine



No. Y 2903. Boring Apparatus



No. Y 2904.  
Venetian Blind  
Punch and Die




No. Y 2905.  
Tenoning Tool




In the above Patent Centre motion and Direct action Mortising Machine, the lever (swung from its directly over the chisel, so that a large additional power is obtained, and the wear and tear consequent upon the usual side crank pinion wheels and toggle movement is entirely done away with. We have every confidence in recommending it as the simplest, cheapest, and best Mortising Machine made.

No. Y 2902.	Including 1/2, 3/4, 1, 1 1/2, and 2 inch Best Cast Steel Chisels, two Core Drifts, and two Screw Keys.	Price, £12 15 0
No. Y 2903.	Boring Apparatus, complete with 1/2, 3/4, and 1 inch Augers, 1/2 and 3/4 inch Cast Steel Drills, .. extra,	2 8 0
No. Y 2904.	Venetian Blind Punch and Die, .. .. .	0 18 0
No. Y 2905.	Tenoning Tool, .. .. .	3 3 0

No. Y 2910.  
PORTABLE DRILLING MACHINE  
For Fixing to Bench or to Wall.




Weight, 28 lbs.	
Price, .. .. .	48 each.
Vice to suit ditto, .. .. .	33 "



No. Y 2672.  
SMITH'S  
LEG VICE  
Best Quality.


Sizes of Jaw, .. .	3 3 1/2 4 4 1/2 5 6 ins.
Approx. Weight, ..	30 35 45 60 85 115 lbs.
Price, .. .. .	67 6 per cwt.
Vices weighing under 45 lbs. are charged as 45 lbs.	

No. Y 2652. WOOD WORKER'S VICE




Size Nos., .. .	10A	10	11
Width of Jaws, ..	7	9	10 1/2 ins.
Opens, .. .. .	6	12	12 "
Prices, each, .. .	16 6	22 6	27 "

No. Y 2680. ENGINEER'S VICE  
Instantaneous Grip.




Size Nos., .. .	1	5	6	7
Width of Jaw, ..	3	3 1/2	3 1/2	4 1/2 ins.
Depth, .. .. .	2	2 1/2	3	3 1/2 "
Opening, .. .. .	3 1/2	4	5	6 "
Weight, .. .. .	14	33	42	59 lbs.
Prices, .. .. .	30	36	45	54 "

No. Y 2681. ENGINEER'S VICE  
Self adjusting Jaws. Instantaneous Grip.



Size Nos., .. .	7	8	8A
Width of Jaw, ..	4	5 1/2	6 ins.
Depth, .. .. .	3 1/2	3 1/2	4 1/2 "
Opening, .. .. .	6	7	8 "
Weight, .. .. .	66	84	100 lbs.
Prices, .. .. .	66	75	84 "

No. Y 2682. PARALLEL VICE




Size Nos., .. .	0A	1A	1	2	3
Width of Jaw, ..	2 1/2	2 1/2	3	3 1/2	4 ins.
Depth, .. .. .	1 1/2	1 1/2	1 1/2	2 1/2	2 1/2 "
Opening, .. .. .	2	2 1/2	3	3 1/2	4 "
Weight, .. .. .	5 1/2	7	10 1/2	18 1/2	27 lbs.
Prices, .. .. .	10 6	12	15	21	30


Every Vice shown above is WARRANTED to be of the BEST QUALITY ENGLISH MAKE.

# Forges, Anvils, and Smiths' Tools

No. Y 2734.  
**CIRCULAR PORTABLE FORGE**




No. Y 2462.  
**SMITH'S ANVIL**



London Pattern, Best Quality.  
84 lbs. and upwards.  
Price, .. 54/- per cwt.

No. Y 2464.  
**SMITH'S SWAGE BLOCK**



Price, .. 27/- per cwt.

No. Y 3603  
**SOLID STEEL SLEDGE HAMMERS, Cross Pane**



Stock size, 4 lbs. to 10 lbs.  
Price, 9d. per lb.  
Double-faced, same price.

## ENGINEERS' BEST CAST-STEEL HAMMERS

No. Y 3600. **Ball Pane**



No. Y 3601. **Straight Pane**



No. Y 3602. **Cross Pane**



Price, .. under 2 lbs., 1/6 per lb.; above 2 lbs., 1/3 per lb.

## BEST QUALITY FILES (Warranted)




No.	Height	Diam. of Hearth	Diam. of Bellows	Price
Y 2731.	28 ins.	16 ins.	14 ins.	54/- each
Y 2735.	20 "	18 "	16 "	60/- "
Y 2736.	20 "	20 "	18 "	67/6 "
Y 2737.	30 "	22 "	20 "	78/ "

Sizes, .. ..	5	6	7	8	9	10	12	14	16 inches.
Flat Bastard, .. ..	4/10½	5/7½	6/9	8/6	9/3	12/-	17/3	24/-	34/6 per doz
Half-Round Bastard, ..	4/10½	5/7½	6/9	8/6	9/3	12/-	17/3	24/-	34/6 "
Round Bastard,.. ..	4/10½	5/7½	6/9	8/6	9/3	12/-	17/3	24/-	34/6 "
Square Bastard,.. ..	4/10½	5/7½	6/9	8/6	9/3	12/-	17/3	24/-	34/6 "
Three Square Bastard, ..	4/10½	6/9	8/3	9/3	12/-	13/6	19/10	30/-	39/- "
Hand Bastard, .. ..	5/3	6/9	8/3	9/3	12/-	13/6	19/10	30/-	39/- "
Flat Smooth, .. ..	6/6	7/6	9/-	10/6	12/6	15/-	21/-	30/-	39/- "
Half-Round Smooth, ..	6/6	7/6	9/-	10/6	12/6	15/-	21/-	30/-	39/- "
Half-Round Wood Rasp,	4/10½	5/7½	6/9	8/6	9/3	12/-	17/3	24/-	34/6 "
Horse Rasps, .. ..	—	—	—	—	—	—	17/3	24/-	34/6 "
Sizes, .. ..	3	3½	4	4½	5	6 inches.			
Tapel Saw Files, .. ..	3/6	3/6	4/-	4/10½	4/10½	6/- per dozen			

NOTE. A Cheaper Quality File can be supplied if required.

No. Y 2720. **IMPROVED FAN FORGE**

Specially Recommended.



No. Y 2720. Size, 20 ins. Pan. Price, 84/- each

" Y 2721. " 24 " " 98/- "

No. Y 2480. **ROAD PICK**



Warranted Quality, as used by the London Corporations,  
7 lbs. and upwards. Price, 42/- per cwt.

No. Y 2483. **ROAD WEDGES**



Best Cast-steel Breaking-up Wedge.  
Size, 18 x 1 1/2 ins.  
Price, .. 42/- per cwt.

## HANDLES (Various).



Sizes, .. .. .	16	18	20 inches.		
Smiths' Hand Hammer Handles, .. .. .	3/-	3/-	3/6 per dozen.		
„ Sledge Hammer Handles, Hickory, 36 ins., .. .. .	..	..	9/- „		
„ Pick Shafts, Hickory, 36 ins. (Best), .. .. .	..	..	12/- „		
Sizes, .. .. .	48	54	60	66	72 inches.
Turned End Best Ash Rake Handles,.. 6/9	7/6	7/6	9/-	9/9	per dozen
Extra Stout ditto, 1½ ins. diameter, .. 8/9	9/9	10/-	11/3	13/6	„

No. Y 2758. Best Quality File Handles, Best Gun-metal Ferrules, 12/- Small. Medium. Large. 15/- 18/- per gross.

# Builders' Plant and Materials

**SCREENS (Best Make) for Gravel, Sand, Lime, Rubbish, Cinders, Coal, Malt, &c.**

No. Y 1234. **EXTRA STRONG LACED SCREENS**





Well made and very strong, the sides, backs, toes and corners of frame are strongly clamped with iron, and strong iron bars at back. The frames are of yellow deal.

Size of Mesh, ..  $\frac{1}{2}$  ..  $\frac{3}{4}$  ..  $1\frac{1}{4}$  ..  $1\frac{1}{2}$  in. and larger.  
Prices, .. .. 25/6 .. 22/6 .. 21/- .. 21/- .. 21/- each.

N.B. Can also be had with galvanized wire work and sheet iron, at an advance of 6/6, 6/6, and 7/6 each, according to size of Screen. This increases their durability in a high degree, and is much recommended.

No. Y 1235. **EXTRA STRONG LOCKET SCREENS**




These Screens will be found very much more durable than the laced ones, as in their construction the upright wires are lapped round the crossbars.

The mesh is determined by the thickness of wire used and the number of laps, see illustration above. These Screens have a smooth sifting surface, and are the strongest and best screens made. The frames are of  $1\frac{1}{2}$ -inch yellow deal.

Size of Mesh, ..  $\frac{1}{2}$  ..  $\frac{3}{4}$  ..  $1\frac{1}{4}$  ..  $1\frac{1}{2}$  ..  $1\frac{3}{4}$  ..  $2$  inch.  
Prices, .. .. 27/- .. 27/- .. 26/- .. 24/- .. 24/- .. 24/- each.


No. Y 1235. **GRAVEL SIEVE**



Extra Strong Oak Rims.

Size of Mesh, 1 to  $\frac{1}{2}$  ..  $\frac{3}{4}$  ..  $1\frac{1}{4}$  ..  $1\frac{1}{2}$  ..  $1\frac{3}{4}$  ..  $2$  m.  
20 ins. diam., 3/4 3/9 4/- 4/3 4/10 4/10 1/2 ea.  
22 " " 4/1 4/6 4/10 5/3 5/7 5/7 1/2 " "  
24 " " 5/3 5/6 6/- 6/- 6/6 " "

No. Y 1236. **PLASTERER'S SIEVE**




Rims  $\frac{1}{2}$  ins. deep inside, wove wire bottoms.

Diameter, 18 20 ins.  
4 to 16 holes to the inch, 3/- 3/6 each.  
18 " 20 " " 3/6 4/3 "  
20 " 24 " " 4/- 4/10 "

If with Oak Rim, extra strong, 9d. each extra.


No. Y 2690.

**IMPROVED TREADLE GRINDSTONE**



Fitted in cast-iron frame, complete, with wrought iron treadle and handle. Best quality stone, suitable for carpenter's and general use.

**BUILDERS' SCAFFOLD CORD**




In Coils weighing about 56 lbs. each.  
Price, 48/- per cwt.

In 16-ft. lengths, whipped, ready for use.  
Price, 54/- per cwt.

NOTE.—For the convenience of our Customers, we are now supplying this Cord in coils of  $\frac{1}{2}$  cwt., whipped at every 16 feet, but NOT CUT OFF, at same price as cut and whipped lengths.  
The average number of Cords in 1 cwt. is 48.

No. Y 2688. **YORKSHIRE GRINDSTONE**



Size.	Price.
12 ins.	3/3 each.
14 "	3/9 "
16 "	4/10 1/2 "
18 "	6/9 "
20 "	7/6 "
22 "	8/3 "
24 "	9/9 "
26 "	12/- "
28 "	14/3 "
30 "	18/- "
36 "	27/- "
42 "	48/- "

Best quality, suitable for all general purposes.

NOTE.—Grindstones are always sent carriage forward at Purchasers' risk.

Sizes, .. 18 x 2 1/2 24 x 4 ins.  
Prices .. 45/- 66/- each.




# Scaffold and Spike Chains--Cement Rollers




No. Y 3960.  
**ORNAMENTAL SPIKE CHAIN**

For Fore Courts of Entrance Gates.  
Size of Link, .. ..  $\frac{1}{2}$  in.  $\frac{3}{4}$  in.  $\frac{7}{8}$  in.  $1\frac{1}{2}$  in.  
Prices, .. .. 6d. 7d. 8d. per foot.  
Stock size,  $\frac{1}{2}$  in.



No. Y 3950.  
**SCAFFOLD CHAIN**

Ring at one end, Hook at other.  
No. 8 W.G. Length, .. 12 14 16 18 feet.  
Prices, .. 19/6 22/6 23/3 27/- per dozen.




No. Y 4354.  
**GALVANIZED MANURE GUARD**

VERY STRONG.

Width.	Price.
4 ft. 0 ins., ..	£2 5 0
4 " 6 " ..	3 3 0
5 " 0 " ..	4 4 0
5 " 6 " ..	4 15 0
6 " 0 " ..	5 5 0

No. Y 3952.  
**FLEXIBLE STEEL WIRE SCAFFOLD LASHES**




Size,  $\frac{1}{4}$  inch diameter.  
Length, 18 feet.  
Price, .. 27/- per dozen

Used by the Principal Contractors.


## CEMENT PAVEMENT ROLLERS

No. Y 3954. **Ordinary Pattern.**



$\frac{1}{8}$ -in. Centre to Centre of Teeth.  
Teeth and Body of Roller is made in Brass and cast in one solid piece. Weight, about 11 lbs. Price 57/- each.


No. Y 3955. **Corrugated Pattern**



Corrugated and Stable Rollers by cross rolling can make various sizes, Squares, Oblongs, and Diagonals, and are also suitable for Pavements, Stairs, and Hearths. Made in Solid Brass.

Weight, about  $11\frac{1}{2}$  lbs.  
Price, 54/- each.

No. Y 3956. **Stable Roller**




All Rollers screwed for Extension Rod. Any Bead can also be supplied to any Roller at same price. Made in Solid Brass. Beads,  $3\frac{1}{8}$ -in. centre to centre  $\times$   $\frac{1}{4}$ -in. deep. Weight about 10 lbs.

Price, .. 54/- each.

**EXTENSION ROD or HANDLE** to Fit all Rollers, 42 ins. long. Price, 6/- each.  
ANY SIZE OR DESIGN MADE TO ORDER.

## Contractors' Sundries


No. Y 2234.  
**Light Galvanized Bucket**



Seamed sides, for Painters' use and light Housework.

Sizes, .. 11 12 ins.  
Prices, .. 11/3 13/6 per doz.


No. Y 2235.  
**Light Galvanized Bucket**



Rivettted sides, forged ears and bail; specially made for Painters' use.

Sizes, 11 12 13 ins.  
Prices, 16/6 18/- 21/- per doz.


No. Y 2237.  
**Strong Well-made Bucket**



With extra stout bottom, half round forged top guard, forged hoop at bottom, rivettted sides, solid forged ears and balls; specially made for Builders' use.


Weight of 12-in., 96 lbs. per doz.  
Sizes, 11 12 13 14 ins.  
Prices, 33/- 36/- 37/6 42/- per doz.

No. Y 2239.  
**Extra Strong Contractor's Bucket**




Wrought-iron hoop, top and bottom, wrought strapped sides, forged ears and bail.  
Sizes, 12 13 11 ins.  
Weight, 126 142 118 lbs. per doz.  
Prices, 48/- 51/- 60/-

No. Y 2168.  
**Cane Rubbish Baskets**



Half Bushel, .. 3/9 each.  
One .. 6/-


No. Y 2169.



**Contractor's Rubbish Wheel**

For Weights under 1 cwt.	For Weights above 1 cwt.
Size, 6 ins., .. 3/- each.	Size, 12 ins., 12/6 each.
" 7 " .. 3/9 "	" 14 " 14/3 "
" 8 " .. 5/3 "	" 16 " 16/6 "

No. Y 2505.  
**Workman's Hard-wear Tool Basket**



These Baskets are very strongly made of tanned waterproof canvas, and are specially recommended.


Nos. .. 1 2 3 4 5  
Prices, .. 2/- 2/7½ 3/3 3/9 4/6 each

No. Y 2486.  
**Lifting Jack**



Power.	Height when down.	Price.
1½ tons.	12 ins.	12/- ea.
2½ "	15 "	13/6 "
4 "	18 "	16/6 "
5 "	21 "	19/6 "
6 "	24 "	25/6 "
8 "	24 "	30/- "
10 "	24 "	36/- "


No. Y 2471. **Basket Chains**



Price, .. 3/6 per pair.

Illustration shows One Pair.


No. Y 2512. **Engineer's Oil Feeder**



With Patent Valve and Copper Spout.

Sizes, .. 1/8 1/6 1/10½ 1 1½ 2 pints.  
Prices, .. 1/6 1/6 1/10½ 2/6 3/- 4/3 each.

No. Y 2506. **Carpenter's Tool Basket**



Nos. .. 1 2 3 4 5  
Y 2506. Plain Bound, 10½ d. 1/- 1 3 1 6 1 10½ ea.  
Y 2507. Canvas Lined, 1/3 1/6 1/9 2/- 3/-  
Y 2508. Leather " 4/6 6/- 6/6 7/6 9/-

No. Y 2511. **Glue Pots**  
With Improved Inner Tinned Iron Pans.



Size.	Price, each.	Size.	Price, each.
No. 00,	1/9	No. 5,	4/6
" 0,	2/-	" 6,	5/3
" 1,	2/1½	" 7,	6/-
" 2,	2/9	" 8,	7/6
" 3,	3/3	" 9,	9/-
" 4,	4/3		

# Hoisting Gear and Pulley Blocks

No. Y 2893.

## WESTON'S IMPROVED DIFFERENTIAL PULLEY BLOCKS

### PRICES

Tested to	Per Set, without Guide.	Per Set, with Guide.
5 cwt., ..	7 6	10 6
10 " ..	9 9	15
15 " ..	12 9	18
20 " ..	15	21
30 " ..	31 6	37 6
40 " ..	39	48
60 " ..	57	67 6
80 " ..	81	97 6

### BRIGHT B.I.R. HAND CHAIN.

For	5	10	15	20 cwt.
Prices,	7 1/2	7 1/2	8 1/2	10 1/2 per foot
For	30	40	60	80 cwt.
Prices,	13	16	19	23 per foot

Length of Chain required Four times the Fall size.

### NOTE.

Every Block is carefully tested before leaving Works, but we do not hold ourselves responsible for any accident that may occur from breakage in use, or any other cause.




No. Y 2892. QUICK CHAIN HOIST

A very useful and reliable Hoist for weights up to 1/2 ton.

The 2 1/2 cwt. size is DIRECT in action as in illustration. Above that weight the action is GEARED.

By simply slipping the chain into the catch at side of frame the load is made safe at any point.

When ordering, state Weight required to be raised and Height of Lift.



### PRICE OF HOIST.

Tested to	
2 1/2 cwt., ..	18 -
5 " ..	21 -
10 " ..	24 -
20 " ..	30 -

Chain extra.

### PRICE OF CHAIN.

#### Per Foot of Lift.

2 1/2 cwt., ..	2 3
5 " ..	2 3
10 " ..	3 3
20 " ..	3 9

If required the larger sizes can be fitted with Band Brake at a cost of 15/-

## WROUGHT-IRON PULLEY BLOCKS

No. Y 2897  
Snatch Block



No. Y 2898



No. Y 2899



No. Y 2900



### PRICES, EACH.


Diam. of Sheave, ins.	2 1/2	3	4	4 1/2	5	6	7	8
Width of Groove, "	1	1 1/2	2	2 1/2	3	4	5	6
No. Y 2897 Snatch,	4 6	4 6	5 3	6	9	10 6	13 6	18
Weight, lbs.,	2	4	5	8	11	14	21	31
No. Y 2898 One Sheave,	3	3	4 6	6	7 6	9	10 6	16 6
Weight, lbs.,	1	4	5	9	12	16	22	35
No. Y 2899 Two Sheaves,	4 6	6	6 6	9	10 6	13 6	18	30
Weight, lbs.,	2	5	8	13	20	26	37	58
No. Y 2900 Three Sheaves,	5 3	6 6	9	10 6	16 6	18	24	33
Weight, lbs.,	3	7	10	18	26	36	51	78
Spare Iron Sheaves,	4 1/2	6 1/2	9 1/2	16	1 10	2 3	3 9	5 3

For Galvanized Sheaves, add 25 per cent.

No. Y 2916.

## SINGLE PURCHASE CRAB


Cast-iron Sides. Ordinary Lever Brake.



To lift direct from Barrel, ..	8	12	16	20 cwt.
To lift with 2 and 3 Sheave Blocks, }	2	3	4	5 tons.
Price, with Brake, }	84	90	105	114

No. Y 2884.

## FLOOR PILLAR CRAB




For weights up to 5 cwt.

### PRICE OF PILLAR ONLY.

Size, 2 1/2 cwt., ..	67 6
" 5 " ..	101 3
Tested CHAIN, ..	9d. per foot.
Top Pulley, ..	7 6 each.

# Safes, Lavatory Lock, and Umbrella Holders

No. Y 4. FIRE-RESISTING SAFE




This Safe is now supplied in solid bent steel, with  $\frac{3}{8}$ -inch solid door,  $2\frac{1}{2}$ -inch fire-resisting chambers, and powder and acid-proof lock; well finished throughout.

Outside Measure.					Price.
H.	W.	D.			
Ins.	Ins.	Ins.			
20	13	12	One Drawer,	..	£4 10 0
22	15	13	" "	..	4 19 0
24	17	15	" "	..	5 5 0
26	19	17	" "	..	6 0 0
28	20	18	" "	..	6 18 0
30	21	20	" "	..	7 10 0
32	21	20	Two Drawers,	..	8 5 0
34	22	22	" "	..	9 0 0
36	22	22	" "	..	10 10 0
38	23	23	" "	..	12 0 0
40	24	24	" " and Shelf,	..	12 15 0

INSIDE MEASURES 6 inches less in width and depth, and 10 inches less in height above drawers.

No. Y 5. FIRE-RESISTING SAFE




Made in solid steel with extra steel bands,  $\frac{3}{4}$ -inch solid door, 3-inch fire-resisting chambers; handle throws three bolts; a very strong and reliable Safe.

Outside Measure.					Price.
H.	W.	D.			
Ins.	Ins.	Ins.			
20	14	14	One Drawer,	..	£6 15 0
22	16	16	" "	..	7 10 0
24	18	18	" "	..	8 5 0
26	20	20	Two Drawers,	..	9 9 0
28	22	22	" "	..	10 10 0
30	24	24	" "	..	11 15 0
32	24	24	" "	..	12 0 0
34	24	24	" "	..	13 0 0
36	24	24	" "	..	15 0 0
38	24	24	" "	..	16 10 0
40	25	24	" " and Shell.	..	17 10 0
44	26	24	" "	..	18 15 0
48	28	25	" "	..	21 0 0

Extra Shelves or Divisions, 12/- extra.

INSIDE MEASURES  $6\frac{1}{2}$  inches less in width and depth, and 11 inches less in height above drawers.

No. Y 22 B.S.  
FIRE AND THIEF RESISTING SAFE



Made from  $\frac{3}{8}$ -inch toughened steel plates, solid and jointless at all corners;  $\frac{1}{2}$ -inch solid steel door, thickened up to  $\frac{3}{4}$  inch, with drill-proof steel over lock; fitted with  $3\frac{1}{2}$ -inch fire-resisting chambers.

Outside Measure.			Inside Measure Over Drawers.				Price.
H.	W.	D.	H.	W.	D.		
Ins.	Ins.	Ins.	Ins.	Ins.	Ins.		
26	20	20	13	12	12	..	£15 0 0
28	22	22	15	14	14	..	16 10 0
30	24	24	17	16	16	..	17 5 0
32	24	24	19	16	16	..	19 10 0
34	24	24	21	16	16	..	21 0 0
36	24	24	23	16	16	..	22 10 0
42	26	26	29	18	18	..	25 0 0
48	28	26	35	20	18	..	32 0 0
54	30	26	41	22	18	..	36 0 0
60	30	28	47	22	20	..	39 0 0


Above Safes have two drawers each.

Sizes above 42 inches have one shelf in addition to drawers.

Extra Shelves or Divisions, 15/- extra.

No. Y 2380.

## IMPROVED PENNY-IN-SLOT LAVATORY LOCK



Made in polished or bronzed brass, with either knob or lever handle: size over all,  $11 \times 4\frac{1}{2} \times 1\frac{1}{2}$  inches.

Price, complete with Tablets, Keys, and Spring for Door, .. 60/- each.

These Locks are in general use in the underground Lavatories of the City of London, and most of the large cities throughout the country. We have also supplied them to the Sanitary Authorities of Calro, Gibraltar, Malta, etc., and they are giving complete satisfaction. In ordering, the thickness of the door must be given, on which side it is hinged, and whether it opens INWARDS or OUTWARDS.

Illustration shows a Left-hand Lock.

No. Y 4161. PATENT UMBRELLA HOLDER (Bronzed Iron)



Spaces, ..	1	2	3	4	5	6	8	10	12
Total Length, $5\frac{1}{2}$	$8\frac{1}{2}$	10	12	$14\frac{1}{2}$	$16\frac{1}{2}$	21	25	39	ins.
Prices, ..	1/6	2/6	3/3	4/-	4/10	5/3	8/-	11/3	15/- each

No. Y 4163. Bronzed Pans for ditto, (Size, 9 12 14 18 ins. Prices, 1/6 2/6 2/9 4/- each.

No. Y 3909 PATENT UMBRELLA AND BILLIARD CUE HOLDER



Made in bronzed iron; projects, when fixed, 3 inches; and can be supplied for any number of umbrellas. The rollers are of soft rubber, are quite noiseless, and will not injure the most delicate handles.

No. Y 3909. Bronzed Iron, including Pan.

No. of Holes, ..	1	2	3	4	5	6
Prices, ..	21/-	27/-	33/-	39/-	54/-	60/- per dozen.


# Name Plates, Rules, Letter Boxes, Mats, &c.

HAND-MADE HAMMERED COPPER NAME PLATES for Entrance Gates  
No. Y 1121.



Size, 12 x 3 ins., for any name not exceeding 10 letters, Price, 8/3 each.  
The above and any other size made to order only.


No. Y 1123.



Size, 12 x 3 ins., for any name not exceeding 12 letters, Price, 9/9 each.

No. Y 1125.

THE "YEMART" FOUR-FOLD RULE




The special feature of this Rule is its extreme legibility. The figures are very large and polished black, the divisions are simple and clear, and for practical carpenter's work it is the best Rule made.

Price, .. 1.10½ each.

No. Y 2609.


Japanned Letter Box



Sizes, 9 12 15 ins.  
Prices, 2/7½ 3/9 4/6 each.

No. Y 2610.


Japanned Letter Box



Sizes, 12 15 18 ins.  
Prices, 4/6 6/9 8/3 each.

No. Y 2611.


Wire Letter Cage



No. Y 2611. Galvanized.  
Sizes, 10 13 16 ins.  
Prices, 3/- 3/9 4/6 ea.


No. Y 2612. Lacquered.  
Sizes, 10 13 16 ins.  
Prices, 4/6 5/3 6/9 ea.

No. Y 1127. PATENT HACK SAW HANDLE



The advantages of this Hack Saw Holder over the Adjustable Frame patterns are its extreme simplicity—a blade can be inserted in one second—an increased power in use of 50 per cent.; it takes in any size or make, and broken blades can be used; it is practically unbreakable, and is cheaper than any other Holder. Price, 1/10½ each.

No. Y 1128. "ENOX" HACK SAW BLADE (Warranted)



Sizes, .. 6 8 9 10 12 inches.  
Prices, .. 1.10½ 2/3 2/9 3/- 3/9 per dozen.


No. Y 3050. GALVANIZED FLEXIBLE STEEL WIRE MAT



Sizes, .. 28 x 16 30 x 18 33 x 18 36 x 21 39 x 21 42 x 24 ins.  
Prices (without name), 6/9 7/6 9/- 11/3 12/9 15/- each.  
Any name can be worked in this Mat, as illustrated, 1/6 for each letter.  
Any size made to order.

Sizes, .. 6 8 9 10 12 inches.  
Prices, .. 19/6 24/9 27/- 33/- 39/- in gross lots.

No. Y 3057. GALVANIZED WROUGHT-IRON GARDEN MAT  
VERY STRONG.



This Mat is made of wrought-iron splines rivetted together with transverse rods, with studded divisions, as illustrated, and being galvanized after made, it is exceedingly strong, and specially suitable for out-door work.

Sizes, .. 24 x 14 30 x 18 36 x 21 42 x 24 ins.  
Prices, .. 9/- 13/6 19/6 24/9 each.

# Ironmongery Sundries

## IMPROVED DRIVE SCREWS AND NAILS WITH WASHERS COMPLETE.

No. Y 37.



No. Y 37.

Evenden's Patent Twisted Driving Nail with washer attached. A perfectly secure fixing. One size only, 2½ inches, Price, 2/6 per gross.

No. Y 38.


Improved Drive Screw with washer complete. The Head being flat the niche is not burred over when driving; and the screw can be withdrawn if required.

Sizes, .. 2 2½ 3 ins.  
Prices, .. 3 3 3 9 4/6 per gross.

No. Y 38.



## No. Y 1971. PATENT POST HOLE BORER




Price, .. 12/- each.

With this Tool a boy can bore a clean cut round hole, 24 inches deep by 9 inches diameter, in 20 minutes.

**It will save its Cost in Boring Holes for 12 Posts.**

Made in one size only.

## No. Y 1973. PATENT "BAT" HURRICANE LAMP



Price, .. 4/- each.

This Lamp is made of best tinned STEEL throughout. The reservoir is a solid stamping and has no seams to leak, and we guarantee it

**Absolutely Windproof.**

## No. Y 1988. BUILDERS' BRANDING IRONS



MADE TO ORDER.


Initials or Name cut in solid steel, in any size.

Size of Letters,	3	4	5	6	8	10 letters.
¼ and ⅜ inch.	3 6	4/-	5/3	6/-	7 6	10 6
½ "	4/6	5/6	6/-	9/-	10 6	12/-
¾ "	7/-	9/-	10 6	12/-	14 3	18/-
1 "	9/-	10 6	12/-	13 6	18/-	21/-

No. Y 1989.

## BRANDING IRON FRAME FOR HOLDING MOVABLE LETTERS OR FIGURES


WITH WOOD HANDLE



To hold	2	3	4	5	6	7	8	9	10 letters or figures.
Size, ¼ in.	1/-	1/-	1/3	1/9	2/3	3/3	4/6	6/-	7 6 each.
" ½ "	1/6	2/-	3/-	3/9	4/6	5/3	7/6	9/-	9/9 "

Letters or Figures—¼ inch, 4/- per dozen; ½ inch, 6/6 per dozen extra.


## EXPANDED METAL



This material known as Expanded Metal is made from sheets of rolled steel of various thicknesses, cut and expanded into meshes of different shapes and sizes, varying from ⅛ to 6 inch mesh, embracing a range of nearly 300 variations. The size of sheets extends to 16 x 8 feet, and it is supplied in any size up to those dimensions. If the very large sheets are necessary, consideration must be given to the question of cost of carriage when price is an object, as the large sheets cost more per ton than the medium size sheets, and unless they are crated there is great risk of their getting buckled in transit. Expanded Metal is now being largely used in concrete reinforcement, and is specially suitable for foundations, walls, roofs, arches, bridges, reservoir dams, piers, &c. The lighter gauges are frequently used for encasing steel work. Full particulars upon application.

# Galvanized Wire Netting

GALVANIZED AFTER MADE.




Best Quality. Standard Imperial Gauge. Full Measure.

TABLE OF PRICES FOR ALL WIDTHS. PER ROLL OF 50 YARDS.

Mesh.	Gauge.	12 Inches Wide.	18 Inches Wide.	24 Inches Wide.	30 Inches Wide.	36 Inches Wide.	42 Inches Wide.	48 Inches Wide.	60 Inches Wide.	72 Inches Wide.	Gauge.	Mesh.
* 1/2 inch.	22 20 19	£ s. d. 0 14 6 0 17 7 1 3 6	£ s. d. 1 0 11 1 5 3 1 13 7	£ s. d. 1 7 2 1 12 10 2 3 9	£ s. d. 1 13 2 2 0 0 2 13 4	£ s. d. 1 19 9 2 8 0 3 4 0	£ s. d. 2 6 5 2 16 0 3 14 8	£ s. d. 2 13 0 3 4 0 4 5 4	£ s. d. 3 6 4 4 0 0 5 6 8	£ s. d. 3 19 6 4 16 0 6 8 0	22 20 19	* 1/2 inch.
* 3/8 inch.	22 20 19	£ s. d. 0 11 0 0 13 8 0 18 9	£ s. d. 0 15 9 0 19 7 1 6 9	£ s. d. 1 0 6 1 5 4 1 14 10	£ s. d. 1 5 0 1 11 0 2 2 6	£ s. d. 1 10 0 1 17 2 2 11 0	£ s. d. 1 15 0 2 3 4 2 19 6	£ s. d. 2 0 0 2 9 6 3 8 0	£ s. d. 2 10 0 3 2 0 4 5 0	£ s. d. — — —	22 20 19	* 3/8 inch.
* 3/4 inch.	20 19 18	£ s. d. 0 9 3 0 11 10 0 16 1	£ s. d. 0 13 2 0 17 0 1 3 1	£ s. d. 0 16 10 1 1 6 1 9 5	£ s. d. 1 0 6 1 6 4 1 15 10	£ s. d. 1 4 0 1 10 9 2 2 0	£ s. d. 1 8 0 1 15 11 2 9 0	£ s. d. 1 12 0 2 1 0 2 16 0	£ s. d. 2 0 0 2 11 4 3 10 0	£ s. d. 2 8 0 3 1 6 4 4 0	20 19 18	* 3/4 inch.
1 inch.	20 19 18 17	£ s. d. 0 7 5 0 8 10 0 10 9 0 14 5	£ s. d. 0 10 7 0 12 8 0 15 5 1 0 8	£ s. d. 0 13 5 0 16 1 0 19 7 1 6 3	£ s. d. 0 16 5 0 19 8 1 3 11 1 12 0	£ s. d. 0 19 2 1 3 0 1 8 0 1 17 6	£ s. d. 1 2 4 1 6 10 1 12 8 2 3 9	£ s. d. 1 5 6 1 10 8 1 17 4 2 10 0	£ s. d. 1 11 11 1 18 4 2 6 8 3 2 6	£ s. d. 1 18 4 2 6 0 2 16 0 3 15 0	20 19 18 17	1 inch.
1 1/4 inch.	19 18 17 16	£ s. d. 0 7 1 0 8 8 0 11 4 0 15 3	£ s. d. 0 10 2 0 12 5 0 16 4 1 1 11	£ s. d. 0 12 11 0 15 9 1 0 9 1 8 0	£ s. d. 0 15 7 0 19 1 1 5 1 1 13 9	£ s. d. 0 18 0 1 2 0 1 9 0 1 19 0	£ s. d. 1 1 0 1 5 8 1 13 10 2 5 6	£ s. d. 1 4 0 1 9 4 1 18 8 2 12 0	£ s. d. 1 10 0 1 16 8 2 8 4 3 5 0	£ s. d. 1 16 0 2 4 0 2 18 0 3 18 0	19 18 17 16	1 1/4 inch.
1 1/2 inch.	19 18 17 16	£ s. d. 0 5 7 0 7 1 0 9 3 0 11 9	£ s. d. 0 8 1 0 10 2 0 13 3 0 16 11	£ s. d. 0 10 3 0 12 11 0 16 10 1 1 6	£ s. d. 0 12 4 0 15 7 1 0 4 1 5 11	£ s. d. 0 14 3 0 18 0 1 3 6 1 10 0	£ s. d. 0 16 8 1 1 0 1 7 5 1 15 0	£ s. d. 0 19 0 1 4 0 1 11 4 2 0 0	£ s. d. 1 3 9 1 10 0 1 19 2 2 10 0	£ s. d. 1 8 6 1 16 0 2 7 0 3 0 0	19 18 17 16	1 1/2 inch.
1 5/8 inch.	19 18 17 16	£ s. d. 0 5 2 0 6 4 0 8 3 0 10 4	£ s. d. 0 7 5 0 9 1 0 11 10 0 14 10	£ s. d. 0 9 5 0 11 7 0 15 1 0 18 10	£ s. d. 0 11 5 0 14 0 0 18 2 1 2 9	£ s. d. 0 13 2 0 16 2 1 1 0 1 6 3	£ s. d. 0 15 4 0 18 10 1 4 6 1 10 8	£ s. d. 0 17 6 1 1 6 1 8 0 1 15 0	£ s. d. 1 1 11 1 6 11 1 15 0 2 3 9	£ s. d. 1 6 4 1 12 4 2 2 0 2 12 6	19 18 17 16	1 5/8 inch.
2 inch.	19 18 17 16 15 14	£ s. d. 0 4 5 0 5 7 0 7 3 0 9 5 0 11 10 0 15 3	£ s. d. 0 6 4 0 8 1 0 10 5 0 13 6 0 17 0 1 1 10	£ s. d. 0 8 1 0 10 3 0 13 3 0 17 3 1 1 8 1 7 11	£ s. d. 0 9 8 0 12 3 0 15 9 1 0 7 1 5 10 1 13 3	£ s. d. 0 11 0 0 14 0 0 18 0 1 3 6 1 9 6 1 18 0	£ s. d. 0 12 10 0 16 4 0 18 0 1 7 5 1 14 5 2 4 4	£ s. d. 0 14 8 0 18 8 1 4 0 1 11 4 1 19 4 2 10 8	£ s. d. 0 18 4 1 3 4 1 10 0 1 19 2 2 9 2 3 3 4	£ s. d. 1 2 0 1 8 0 1 16 0 2 7 0 2 19 0 3 16 0	19 18 17 16 15 14	2 inch.
2 1/4 inch.	19 18 17 16	£ s. d. 0 3 9 0 4 8 0 6 2 0 7 9	£ s. d. 0 5 6 0 6 8 0 8 10 0 11 3	£ s. d. 0 7 0 0 8 6 0 11 4 0 14 4	£ s. d. 0 8 4 0 10 3 0 13 7 0 17 0	£ s. d. 0 9 6 0 11 8 0 15 6 0 19 6	£ s. d. 0 11 1 0 13 5 0 18 1 1 2 9	£ s. d. 0 12 8 0 15 7 1 0 8 1 6 0	£ s. d. 0 15 10 0 19 6 1 5 10 1 12 6	£ s. d. 0 19 0 1 3 4 1 11 0 1 19 0	19 18 17 16	2 1/4 inch.
3 inch.	19 18 17 16	£ s. d. 0 3 6 0 4 1 0 5 3 0 6 7	£ s. d. 0 5 0 0 5 10 0 7 7 0 9 6	£ s. d. 0 6 4 0 7 5 0 9 8 0 12 1	£ s. d. 0 7 7 0 8 11 0 11 7 0 14 5	£ s. d. 0 8 8 0 10 2 0 13 2 0 16 6	£ s. d. 0 10 1 0 11 10 0 15 4 0 19 3	£ s. d. 0 11 6 0 13 6 0 17 6 1 2 0	£ s. d. 0 14 5 0 16 11 1 1 11 1 7 6	£ s. d. 0 17 4 1 0 4 1 6 4 1 13 0	19 18 17 16	3 inch.
4 inch.	18 17 16	£ s. d. 0 3 6 0 4 1 0 4 10	£ s. d. 0 5 0 0 5 10 0 6 11	£ s. d. 0 6 4 0 7 5 0 8 10	£ s. d. 0 7 7 0 8 11 0 10 6	£ s. d. 0 8 8 0 10 2 0 12 0	£ s. d. 0 10 1 0 11 10 0 14 0	£ s. d. 0 11 6 0 13 6 0 16 0	£ s. d. 0 14 5 0 16 11 1 0 0	£ s. d. 0 17 3 1 0 4 1 4 0	18 17 16	4 inch.

Orders of £24 net value and upwards Delivered Free in England and Wales, also to Glasgow, Dublin, Belfast, Cork, Waterford, and Wexford.  
Marked \* can be supplied in 25 yard rolls. Original rolls, uncut, only supplied.

N.B. -Special Terms on Application for Orders of 1000 yards and upwards, and your esteemed enquiries are respectfully solicited.



## PATENT MACHINE MADE Mixed Mesh Wire Netting GALVANIZED AFTER MADE.

This Netting is the best and cheapest rabbit fence extant, and is rapidly taking the first place in the Australian Colonies as the only effective means of dealing with the rabbit pest. It is also invaluable for enclosing warrens, plantations, &c., where small ground game have to be fenced against. The lower portion being of 1 1/2-inch mesh affords an absolute protection at the required point, while the upper portion being of 2 1/2-inch mesh gives the required height at a reduction of 20 per cent. on the cost of 1 1/2-inch throughout.

PRICE PER 50-YARD ROLL. (Original Rolls, Uncut, only supplied.)

Width of 1 1/2-inch Mesh in Inches.	Gauge.	COMBINED WITH THE FOLLOWING WIDTHS OF 2 1/2-INCH MESH.										Gauge.	Width of 1 1/2-inch Mesh in Inches.
		2 1/2-inch, 6-inch.	2 1/2-inch, 12-inch.	2 1/2-inch, 15-inch.	2 1/2-inch, 18-inch.	2 1/2-inch, 21-inch.	2 1/2-inch, 24-inch.	2 1/2-inch, 30-inch.	2 1/2-inch, 36-inch.	2 1/2-inch, 42-inch.	2 1/2-inch, 48-inch.		
36 inch.	19	£ s. d. 1 0 9	£ s. d. 1 2 0	£ s. d. 1 2 9	£ s. d. 1 3 6	£ s. d. 1 4 3	£ s. d. 1 5 0	£ s. d. 1 6 6	£ s. d. 1 8 0	£ s. d. 1 9 6	£ s. d. 2 0 0	19	36 inch.
	18	1 5 0	1 6 6	1 7 6	1 8 6	1 9 6	2 0 6	2 1 6	2 2 6	2 3 6	2 4 6	18	
	17	1 12 9	1 15 0	1 16 3	1 17 6	1 18 9	2 0 0	2 1 3	2 2 6	2 3 6	2 4 6	17	
	16	2 3 0	2 6 0	2 7 9	2 9 6	2 11 3	2 13 0	2 16 6	2 18 0	2 19 6	2 21 0	16	
33 inch.	19	0 19 3	1 0 6	1 1 3	1 2 0	1 2 9	1 3 6	1 5 0	1 6 6	1 7 9	1 9 0	19	33 inch.
	18	1 3 3	1 4 9	1 5 9	1 6 9	1 7 9	1 8 9	2 0 3	2 1 6	2 2 9	2 4 0	18	
	17	1 10 6	1 12 9	1 14 0	1 15 3	1 16 6	1 17 9	2 0 3	2 1 6	2 2 9	2 4 0	17	
	16	2 0 0	2 3 0	2 4 9	2 6 6	2 8 3	2 10 0	2 13 6	2 17 0	2 20 0	2 24 0	16	
30 inch.	19	0 17 9	0 19 0	0 19 9	1 0 6	1 1 3	1 2 0	1 3 6	1 5 0	1 6 6	1 8 0	19	30 inch.
	18	1 1 6	1 3 0	1 4 0	1 5 0	1 6 0	1 7 0	1 9 0	2 0 6	2 2 0	2 4 0	18	
	17	1 8 3	1 10 6	1 11 9	1 13 0	1 14 3	1 15 6	1 18 0	2 0 6	2 2 0	2 4 0	17	
	16	1 17 0	2 0 0	2 1 9	2 3 6	2 5 3	2 7 0	2 10 6	2 14 0	2 18 0	2 24 0	16	
27 inch.	19	0 16 3	0 17 6	0 18 3	0 19 0	0 19 9	1 0 6	1 2 0	1 3 6	1 5 0	1 6 6	19	27 inch.
	18	0 19 9	1 1 3	1 2 3	1 3 3	1 4 3	1 5 3	1 7 3	1 9 3	2 1 3	2 3 3	18	
	17	1 6 0	1 8 3	1 9 6	1 10 9	1 12 0	1 13 3	1 15 9	1 18 3	2 0 3	2 2 3	17	
	16	1 14 0	1 17 0	1 18 9	2 0 6	2 2 3	2 4 0	2 7 6	2 11 0	2 15 0	2 21 0	16	
24 inch.	19	0 14 9	0 16 0	0 16 9	0 17 6	0 18 3	0 19 0	1 0 6	1 2 0	1 3 6	1 5 0	19	24 inch.
	18	0 18 0	0 19 6	1 0 6	1 1 6	1 2 6	1 3 6	1 5 6	1 7 6	1 9 6	2 1 6	18	
	17	1 3 9	1 6 0	1 7 3	1 8 6	1 9 9	2 1 0	2 3 6	2 6 0	2 8 0	3 0 0	17	
	16	1 11 0	1 14 0	1 15 9	1 17 6	1 19 3	2 1 0	2 4 6	2 8 0	3 1 0	3 4 0	16	
21 inch.	19	0 13 3	0 14 6	0 15 3	0 16 0	0 16 9	0 17 6	0 19 0	1 0 6	1 2 0	1 3 6	19	21 inch.
	18	0 16 3	0 17 9	0 18 9	0 19 9	1 0 9	1 1 9	1 3 9	1 5 9	1 8 3	2 0 3	18	
	17	1 1 6	1 3 9	1 5 0	1 6 3	1 7 6	1 8 9	2 1 3	2 4 3	2 7 3	3 0 3	17	
	16	1 8 0	1 11 0	1 12 9	1 14 6	1 16 3	1 18 0	2 2 6	2 6 0	3 0 0	3 4 0	16	
18 inch.	19	0 11 9	0 13 0	0 13 9	0 14 6	0 15 3	0 16 0	0 17 6	0 19 0	1 0 6	1 2 0	19	18 inch.
	18	0 14 6	0 16 0	0 17 0	0 18 0	0 19 0	1 0 0	1 2 0	1 4 0	1 6 0	1 8 0	18	
	17	0 19 3	1 1 6	1 2 9	1 4 0	1 5 3	1 6 6	1 9 0	2 1 6	2 4 6	2 7 6	17	
	16	1 5 0	1 8 0	1 9 9	1 11 6	1 13 3	1 15 0	1 18 6	2 2 0	2 6 0	3 0 0	16	

N.B.—From the above table the list price of any of the combinations enumerated can be obtained, for instance:—The price of 36 inches of 1 1/2-inch mesh, combined with 12 inches of 2 1/2-inch mesh in 18 gauge, is 26/6 per 50-yard roll; and of 27 inches of 1 1/2-inch mesh, combined with 21 inches of 2 1/2-inch mesh in 17 gauge, is 32/ per 50 yard roll.

The combinations given in the table are those usually employed; quotations for any other will be sent on application, but no combination may exceed 3 feet wide of either mesh or 6 feet of the two combined.

## EXTRA STRONG Galvanized Wire Sheep Netting WITH 3-PLY SELVAGES.

This Netting can be supplied with or without intermediate strands as desired, and with round or flat draught bars at ends of rolls. These latter very much facilitate handling in erection.

It is generally sent out in 50-yard rolls, but can be made up in 25-yard rolls, if desired, without extra cost.

STANDARD LIST PRICE PER 50-YARD ROLL.


Mesh.	Gauge.	3 ft. wide.	3 ft. 6 ins. wide.	4 ft. wide.	Gauge.	Mesh.
3 inch.	16	£ s. d. 0 17 0	£ s. d. 0 19 10	£ s. d. 1 2 8	16	3 inch.
	15	1 0 6	1 3 11	1 7 4	15	
	14	1 5 0	1 9 2	1 13 4	14	
	13	1 11 0	1 16 2	2 1 4	13	
	12	2 0 0	2 6 8	2 13 4	12	
4 inch.	17	0 11 9	0 13 9	0 15 9	17	4 inch.
	16	0 13 11	0 16 3	0 18 7	16	
	15	0 17 9	1 0 9	1 3 9	15	
	14	1 0 5	1 3 10	1 7 3	14	
	13	1 4 0	1 8 0	1 12 0	13	
	12	1 12 6	1 17 11	2 3 4	12	

### INTERMEDIATE STRANDS.

17, 16 and 15 Gauges,	1/9 per roll each extra to above prices.
14 and 13	2/ "
12 Gauge,	2/6 "
Flat Galvanized Iron Draught Bar at each end of Roll—	
3 x 3 in.,	3 ft., 1/-; 3 ft. 6 ins., 1/2; 4 ft., 1/4 per roll extra net.
Round Galvanized Iron Draught Bar at each end of Roll—	
No. 4,	3 ft., 8d.; 3 ft. 6 ins., 9d.; 4 ft., 1/- per roll extra net.
3 in.,	3 ft., 1/-; 3 ft. 6 ins., 1/3; 4 ft., 1/6 "
2 in.,	3 ft., 1/3; 3 ft. 6 ins., 1/6; 4 ft., 1/9 "

Orders of £4 net value and upwards delivered free in England and Wales also to Glasgow, Dublin, Belfast, Cork, Waterford, and Wexford.

N.B.—Special Terms on Application for Orders of 1000 yards and upwards, and your esteemed enquiries are respectfully solicited.








# Wirework


No. Y 3726. Galvanized Diamond Wirework



PRICES, per Square Foot.						
Gauge, ..	15	14	13	12	11	10
$\frac{1}{2}$ inch Mesh, ..	1 -	1	1 3	1 6		
$\frac{3}{4}$ " " " " "	10 $\frac{1}{2}$ d.	11 $\frac{1}{2}$ d.	1 -	1 4 $\frac{1}{2}$		
1 " " " " "	6d.	9d.	10 $\frac{1}{2}$ d.	11 $\frac{1}{2}$ d.	1 -	
1 $\frac{1}{2}$ " " " " "	5 $\frac{1}{2}$ d.	6d.	7 $\frac{1}{2}$ d.	8d.	9 $\frac{1}{2}$ d.	10 $\frac{1}{2}$ d.
2 " " " " "	-	5d.	7d.	7 $\frac{1}{2}$ d.	8d.	10d.
3 " " " " "	-	-	4 $\frac{1}{2}$ d.	5d.	6 $\frac{1}{2}$ d.	7 $\frac{1}{2}$ d.
4 " " " " "	-	-	-	4 $\frac{1}{2}$ d.	5 $\frac{1}{2}$ d.	7d.


All Wirework is made to order only, and pieces measuring less than 4 feet super are charged as 4 FEET.  
In ordering, care should be taken to state which measurement is HEIGHT and which is WIDTH.  
Time required to make, four clear days.

No. Y 3730. Galvanized Straight Wire Lattice




PRICES, per Square Foot.						
Gauge, ..	16	15	14	13	12	
$\frac{1}{2}$ inch Mesh, ..	1	1 1 $\frac{1}{2}$	1 2	1 3	1 4 $\frac{1}{2}$	
$\frac{3}{4}$ " " " " "	7 $\frac{1}{2}$ d.	9d.	10 $\frac{1}{2}$ d.	1	1 2	
1 " " " " "	7 $\frac{1}{2}$ d.	7 $\frac{1}{2}$ d.	8d.	9d.	10d.	
1 $\frac{1}{2}$ " " " " "	-	7d.	7 $\frac{1}{2}$ d.	8d.	9d.	
2 " " " " "	-	-	5 $\frac{1}{2}$ d.	6d.	7d.	

No. Y 3731. Cathedral Wirework for Gothic Windows



Usual size,  $\frac{1}{2}$  in. x 13 gauge.  
Strong,  $\frac{1}{2}$  in. x 13 gauge.  
Price per foot, same as No. Y 3730.


No. Y 3700. Plain Diamond Archway



Cheap useful Arch. Galvanized after manufacture.  
The outside frame of plain iron and filled in with corrugated diamond lattice.

Height out of Ground.	Span.	Width.	Price, each.
Ft. Ins.	Ft. Ins.	Ft. Ins.	
7 0	4 0	1 0	7 6
7 0	4 0	1 8	9 9
7 0	4 0	2 0	14 3
7 6	4 6	1 6	13 6
7 6	4 6	2 0	22 6
8 0	5 0	2 0	24 -


No. Y 3701. Circular Spiral Archway



Ornamental Arch. Galvanized after manufacture.  
Extra strong and substantial Archway, with plate feet bases, a great advantage, having a firmer hold in the ground than the ordinary pronged feet.

Height out of Ground.	Span.	Width.	Price, each.
Ft. Ins.	Ft. Ins.	Ft. Ins.	Extra Strong.
7 0	4 0	1 0	22 6
7 0	4 6	1 6	30 -
7 6	4 6	1 6	39 -
8 0	5 0	1 6	45 -
8 0	5 0	2 0	48 -
8 0	5 0	3 0	60 -

No. Y 3702. Ornamental Archway



Galvanized after manufacture.  
Made with spiral iron and corrugated diamond lattice.

Height out of Ground.	Span.	Width.	Price, each.
Ft. Ins.	Ft. Ins.	Ft. Ins.	Strong.
7 0	4 0	1 0	10 6
7 0	4 0	1 8	13 6
7 0	4 0	2 0	16 6
7 6	4 6	1 6	18 -
7 6	4 6	2 0	25 6
8 0	5 0	2 0	27 -

No. Y 3736. Galvanized Wire Snow Guard



9 inches wide, 1-inch mesh, 14 gauge.  
Price, 7 $\frac{1}{2}$ d. per lineal foot.  
Stock sizes, 4 ft. to 12 ft. lengths; sizes advance every 6 inches.


No. Y 3737. Galvanized Wrought Brackets for Snow Guards, 10 $\frac{1}{2}$ ¢ per dozen.

No. Y 3738. Ornamental Wire Snow Guard



12 inches wide over all, 1-inch mesh, 14 gauge.  
Price, 10 $\frac{1}{2}$ d. per lineal foot.  
Made in any length to order only.

Wire Gauze




No. Y 36. 36 hole.  
Iron, 7 $\frac{1}{2}$ d. per sq. ft.  
Brass, 2 -  
Copper, 2/3 -  
No. Y 24 is the usual size for mosquito screens.

No. Y 24. 24 hole.  
Iron, 6 $\frac{1}{2}$ d. per sq. ft.  
Brass, 2 -  
Copper, 2/3 -

**NET PRICES.**

# Garden Sundries

**NET PRICES**



No. Y 1240.  
"New Automaton"  
Lawn Mower

We have no hesitation in saying that Ransome's "New Automaton" is equal in every respect to any lawn mower made, and we recommend it for large lawns in preference to any other machine.

Sizes, ..	8	10	12	14	16	18 ins.
Prices, ..	51	70	89 3	108 3	127 6	144 6 each

No. Y 1240 Lawn Mower is sent CARRIAGE PAID.  
No. Y 1243, CARRIAGE FORWARD.



No. Y 1242.  
Ransome's "Lion"  
Lawn Mower

Ransome's "Lion" Mower is an English made machine, and recommended for small lawns.

Sizes, ..	9	11	13 ins.
Prices, ..	21 9	23 3	25 - each.
Grass Box, ..	3 6	3 9	4 3 "


These Light Mowers work far better without a Grass Box, which is really not necessary, but can be supplied if required. **Every Lawn Mower warranted.**



No. Y 1243.  
Young & Marten's  
"Special"  
Lawn Mower

This is a five-blade Canadian Machine and is thoroughly reliable. Over 2000 machines were sold last season, and gave every satisfaction.


Sizes, ..	8	10	12	14 ins.
Prices, ..	12 6	13 6	15 -	16 6 each
Grass Box, ..	3 6	3 6	4 -	4 6 "



No. Y 4030.  
Double Cylinder  
Garden Roller

Solid ends, engine-turned meeting edges and bearings, and of best quality and finish.

Size.	Weight.	Price.
16 ins.	12 cwt. 0 lbs.	40 -
18 "	2 1/2 " 10 "	50 -
20 "	3 " 0 "	60 -
24 "	4 " 0 "	80 -



No. Y 4727. Galvanized Iron Barrow


Frame very strongly made of wrought iron, painted; body, galvanized.

No. ....	1	2	3
Sizes, ..	27 x 22	30 x 25	34 x 28 ins.
Prices, ..	18 -	21 -	24 - each.

No. Y 470.

## GARDEN SEATS


No. Y 477.



The 7-foot Seat has three Standards.

	4 ft.	5 ft.	6 ft.	7 ft.
Painted Green, ..	14 6	16	17 6	22 3
Grained Oak, Varnished, ..	15 6	17 -	18 6	23 3
Pitch Pine, Varnished, ..	18 -	19 -	20 -	25 -
Teak, Oiled, ..	24 6	28 6	31 6	38 6

The 8 foot Seat is made extra strong, for Public Parks, Railway Stations, &c. Arms for 8 or 6 feet Seats, 2 - per pair extra.




The 8-foot Seat has 3 Standards, 3 Elbows, and Intermediate Straps.

	5 ft.	6 ft.	8 ft.
Painted Green, ..	18 6	19 6	37 6
Grained Oak, Varnished, ..	19 9	22 -	39 3
Pitch Pine, Varnished, ..	20 -	23 9	43 6
Teak, Oiled, ..	30 6	35 -	67 6

# Electro-Brassed Iron Goods


The articles illustrated on this page are electro brass plated upon iron. In appearance, finish and strength, they are equal to brass, but considerably lower in price.

No. Y 5728. **CABINET HANDLE**




Solid Brass Plate,  
with  
Brass-plated Drop.  
Polished or Antique  
Copper Bronzed  
3½ ins., 4/6 per doz.  
4½ " 5/3 "

No. Y 5730. **SIDEBOARD HANDLE**



Electro-brassed or  
Antique Copper  
Bronzed.  
Size, 5 ins.  
Price, 5/3 per doz.


No. Y 5732.



**PEDESTAL HANDLES**

Electro-brassed or Antique Copper  
Bronzed.  
Price, 3/9 per doz.

No. Y 5733.




**BRONZED DOOR STATIONER**

Holds the Door in any position,  
and is released instantly.  
Price, 3/9 each.

No. Y 5755.



No. Y 5750.



Brass Polished.  
Long, 5/3 p. doz.  
Short, 4/6 "  
Antique Copper  
Bronzed.  
Long, 6/9 p. doz.  
Short, 6/- "


**FINGER PLATES (Special Cheap Line)**

No. Y 5751.



Antique Copper  
Bronzed.  
4/10½ per doz.  
Long or Short.

No. Y 5752.



Antique Copper  
Bronzed.  
4/10½ per doz.  
Long or Short.

No. Y 5756.




Antique Copper  
Bronzed.  
3/3 per doz.  
Long only.

These Finger Plates will match any Oval or Plain Mortice Furniture.  
NOTE.—Prices are for the quantity mentioned. Smaller quantities, 25 per cent. NET extra.

# Electro-Brassed Iron Goods


The articles illustrated on this page are electro brass plated upon iron. In appearance, finish, and strength they are equal to brass, but considerably lower in price.

No. Y 5737.  
**WARDROBE HOOK**




Electro-brassed.  
Size, .. .. 2 ins.  
Price .. .. 9/9 per gross

No. Y 5739.  
**DOUBLE SUSPENDING HOOK**




Solid Cast. Electro-brassed.  
Size, .. .. 2½ ins.  
Price, .. .. 15/- per gross.

No. Y 5740.




Antique Copper Bronzed.  
Size, .. .. 5½ × 3½ ins.  
Price, 15/- per gross; 1/7½ per dozen.

No. Y 5738.  
**DOUBLE WARDROBE HOOK**




Electro-brassed.  
Size, .. .. 3½ 1½ ins.  
Price, .. .. 21/- per gross.

No. Y 5741.  
**REVOLVING DOUBLE HOOK**



Electro-brassed Steel.  
Price, .. .. 19/6 per gross.

No. Y 5747.




Antique Bronzed.  
Size, .. .. 6 × 4 ins.  
Price, 23/3 per gross; 2/- per doz.

No. Y 5740.  
**TREBLE REVOLVING HOOK**



Solid Cast. Electro-brassed.  
Sizes, .. .. 2 × 2½ 2½ × 3 ins.  
Prices, .. .. 21/- 40/6 per gross.

No. Y 5742.  
**FOUR-WAY REVOLVING HOOK**



Electro-brassed Steel.  
Price, .. .. 31/6 per gross.

No. Y 5748.



Strong Electro-brassed.  
Illustration Half Size.  
Price, .. .. 4/6 per doz.

No. Y 5749. Smaller.  
Size, 5½ ins., Price, 1/3 per doz.

NOTE.—Prices are for the quantity mentioned. Smaller quantities, 25 per cent. NET extra.

# Electro-Brassed Iron Goods

The articles illustrated on this page are electro brass plated upon iron. In appearance, finish, and strength, they are equal to brass, but considerably lower in price.

No. Y 5727. **SASH HANDLE**



Electro-brassed.

Size, .. .. . 3½ ins. hand space.  
Price, .. .. . 2/9 per dozen.

A very strong handle.




No. Y 5721. **HAT HOOK**

Half Size

Price, Electro-brassed, .. .. . 1/10½ per dozen.  
,, Antique bronzed, .. .. . 2/3 ..

No. Y 5735. **BEDROOM DOOR CHAIN**



Electro-brassed.

Size, .. .. . 3½ ins.  
Price, .. .. . 4/6 per dozen.


No. Y 5736. **CUPBOARD BUTTON**



Electro-brassed.

Size, .. .. . 2 ins.  
Price, .. .. . 6d. per dozen.


No. Y 5723. **SASH FASTENER**



Very Strong, Brown bronzed,  
with Electro-brassed Arm and Knob.

Size, .. .. . 2½ ins.  
Price, .. .. . 3/- per dozen.

No. Y 5754. **SCREW CASTOR**



Electro-brassed. Brown Bowl.

Size, .. .. . 1½ ins.  
Price, .. .. . 1/- per set.

No. Y 5734. **DRAWER PULL**



Full Size.

Electro-brassed Stamped Steel.


Price, .. .. . 9/9 per gross.

NOTE.—Prices are for the quantity mentioned. Smaller quantities, 25 per cent. NET extra.

# Electro-Brassed Iron Goods


The articles illustrated on this page are electro brass plated upon iron. In appearance, finish, and strength they are equal to brass but considerably lower in price.

No. Y 5716. **SASH LIFT**




Sizes, ..  $1\frac{1}{2}$  ins. x 17 W.G. 2 ins. x 14 W.G.  
Prices, .. 12/- 15/- per gross.

No. Y 5717. **GLASS PLATE**



Sizes, ..  $1\frac{1}{2}$   $1\frac{1}{2}$  ins.  
Prices, .. 2/- 3 - per gross.

No. Y 5726. **TOWEL RAIL BRACKET**



Electro-brassed or Antique Copper Bronzed.

Price, .. 2/6 per doz. pairs.

Brassed or Bronzed Tube for Towel Rail, to fit Y 5726 Brackets, 16 ins. long,  $1\frac{1}{10}$  per doz.

No. Y 5718. **CORD HOLDER**



Full Size.

Price, .. 9/9 per gross.

No. Y 5719. **LONG ARM HOOK**



Size, ..  $1\frac{1}{2}$  ins.  
Price, .. 5/3 per doz.

No. Y 5724. **CLEAT HOOK**




Full Size of  $2\frac{1}{2}$  ins. Electro-brassed.

Size, ..  $2\frac{1}{2}$  4 ins.


Prices, .. 9d. 1/6 per doz.

No. Y 5720. **FANLIGHT CATCH**



Bronzed Iron.

Size, ..  $2\frac{1}{2} \times 1\frac{1}{2}$  ins.  
Price, .. 6/9 per doz.



No. Y 5712.


**FANLIGHT CATCH**

Wrought Steel.  
Art Black.

Size,  $1\frac{1}{2} \times 1\frac{1}{2}$  ins.

Price, .. 4/6 per doz.

No. Y 5725.  
**CUPBOARD TURN**



Full Size.

Electro-brassed.

Price, .. 3/6 per doz.


NOTE.—Prices are for the quantity mentioned. Smaller quantities, 25 per cent. NET extra.

**YOUNG & MARTEN LTD.**  
 MANUFACTURERS OF  
*Wood & Metal Letters*  
 FOR  
**ADVERTISING PURPOSES**


WHOLESALE & RETAIL DEPT.  
 RETAIL GLASS CUTTING DEPT.  
 REVEILED MILLWORK

FRAMED LETTERS  
 STAINED GLASS LETTERS


ENTRANCE TO STAINED & WINDOW GLASS DEPT.



Incised Facio & Letters Works



Cathedral Light Manufactory




Wholesale Glass  
Cutting Dept.



# Window Glass

## FOREIGN WINDOW GLASS, in Cases

BEST MAKE ONLY STOCKED.



"Cross Keys."



"Three Lances."



D. J. C.



"Lighthouse."



"Marine" or "Caduceus."

We have pleasure in drawing special attention to the above best brands of Foreign Window Glass, which for whiteness, evenness of surface and full weight, is not surpassed by any other make; whilst the prices are as low as ordinary selected brands. Large stocks of the following thicknesses and qualities are kept at our wharf in readiness for immediate despatch. We ask our friends to give us an order for a sample consignment. Once used, they will be appreciated and generally adopted.

Cases contain—15 oz. 300 feet super.; all other substances, 200 feet in each case. 2nd, 15 oz. 200 feet super. in each case.

Quality—	Coarse,	Fourth,	Third,	Best Third,	Seconds,	Substance,	15	21	26	32 ozs.
Coarse,	..	..	..	..	..	..	..	..	..	..
Fourth,	..	..	..	..	..	..	..	..	..	..
Third,	..	..	..	..	..	..	..	..	..	..
Best Third,	..	..	..	..	..	..	..	..	..	..
Seconds,	..	..	..	..	..	..	..	..	..	..

Current quotations will be submitted upon receipt of details of actual requirements.

N.B. The best 3rds in these brands is superior to ordinary 2nds; and the 2nds is equal to 1sts in ordinary makes.

## FOREIGN WINDOW GLASS, Cut to Sizes

FOR ORDERS OF 100 FEET AND OVER.

In Squares, ..	15	21	26	32	15	21	26	32 ozs.
Under 2 feet super.,	2½d.	4½d.	4½d.	6½d.	3d.	4½d.	5½d.	6½d. per foot super.
Larger Sizes,	3d.	4½d.	5½d.	7½d.	3½d.	5½d.	5½d.	8½d. " "

N.B.—Cut Sizes over 60 inches long or 40 inches wide at special prices, upon application.

## HORTICULTURAL GLASS, in Boxes

100 feet boxes—15 oz., ; 21 oz., -- each. 200 feet boxes—15 oz., -- ; 21 oz., -- each.

Current quotations will be submitted upon receipt of details of actual requirements.

A full stock of the following sizes in 21 oz. 200 feet boxes is kept at our wharf:—

12 × 10 ins.	18 × 12 ins.	16 × 14 ins.	18 × 16 ins.	20 × 18 ins.
	20 × 12 "	18 × 14 "	20 × 16 "	22 × 18 "
		20 × 14 "	24 × 16 "	24 × 18 "

## ENGLISH WINDOW GLASS, in Crates

We strongly recommend our friends to give English Window Glass a trial; it is full weight, full measure, and of superior surface quality.

	Substance,	15	21	26	32 ozs.
Fourth,	..	..	..	..	per foot super.
Third,	..	..	..	..	" "
Seconds,	..	..	..	..	" "
Best,	..	..	..	..	" "
Enamelled,	..	..	..	..	" "
Ground,	..	..	..	..	" "
Fluted,	..	..	..	..	" "

Current quotations will be submitted upon receipt of details of actual requirements.

The size of the sheets usually packed in crates as above is 50×35 inches, but may vary from 40×26 inches to 54×38 inches. Larger sizes, as under, are obtainable at an increased cost. Estimates given to specification of precise requirements. The largest sizes that can be made in the various substances of sheet glass are as follows, but the extreme limits of length and width cannot be combined in the same sheet:—

	Substance,	15	21	26	32 ozs.
Extreme Length,	..	..	..	..	75 ins.
" Width,	..	..	..	..	46 "
" Area,	..	..	..	..	20 feet.

The extreme area taken in connection with the extreme length or width required in any particular case will indicate approximately the corresponding limit of width or length.

## ENGLISH WINDOW GLASS, Cut to Sizes

FOR ORDERS OF 100 FEET AND OVER.

In Squares, ...	15	21	26	32	15	21	26	32 ozs.
Under 2 feet super.,	3d.	4½d.	5½d.	7½d.	3½d.	4½d.	5½d.	7½d. per foot super.
Larger Sizes,	3½d.	4½d.	6d.	8½d.	3½d.	5½d.	6½d.	9d. " "

N.B.—Cut Sizes over 60 inches long or 40 inches wide at special prices, upon application.

# Watertight Puttyless Glazing—"Leadglass"


(GREGORY'S PATENT).

**SIMPLE! SOUND!! INEXPENSIVE!!! ACCESSIBLE!!!!**


Also supplied with

**SPECIAL SECTION MILD STEEL BAR, BLACK OR GALVANIZED**


N.B.—The Lead Strips, being independent, are not coated on to the bars; and are of ample and uniform substance, manufactured from pure pig lead, thus ensuring durability.




Section of Steel Bar showing application of Lead Sheath.



Example of Lead Sheathed Bar, and method of fixing with Purlin Staple and Stop-end.



Purlin Staple.



Purlin Staple and Stop-end.

## PRICES (for London only)

### STEEL BARS, Lead Sheathed, Unfixed

In lengths up to 10 feet, .. ..	10d. per foot lineal.
" " " 15 " .. ..	10½d. " " "
" " " 20 " .. ..	11d. " " "

PURLIN STAPLES, Plain, 1½d.; Ornamental, 2½d. each.

STOP-ENDS, 2½d. each.

### STEEL BARS, Lead Sheathed, with Glass Fixed

With $\frac{3}{16}$ inch Plain Rolled Plate, ..	1/3½ per foot super.
" $\frac{1}{4}$ " " " " " ..	1/4 " " "
" $\frac{5}{16}$ " " " " " ..	1/5 " " "
" $\frac{3}{8}$ " " " " " ..	1/8½ " " "

For openings not less than 18 inches wide.

Reference to, or inspection of Works executed with the above, arranged for by request; also Prices, including fixing in country districts, quoted upon receipt of particulars of actual requirements.

Sole Licensees and Manufacturers:

CALEDONIAN  
WORKS

**YOUNG & MARTEN, LTD.**

STRATFORD  
LONDON, E.

# Window Glass

## MUFFLED GLASS

Original Sheets, .. ..	White, 6d.	Tinted, 9d.	per foot super.
Cut Sizes, .. ..	7½d.	10½d.	" "

## CATHEDRAL GLASS

Original Sheets, .. ..	White, 4½d.	Tinted, 5½d.	per foot super.
Cut Sizes, .. ..	5½d.	6d.	" "

## GLASS TILES

No. G 4082.




Pantile Shape.

No. G 4083.



Roman Shape.

No. G 4084.



Corrugated Shape.

Sheet, .. ..	15	21	26	32 ozs.
No. G 4082, Prices, ..	6/-	7/9	9/6	11/6 per doz.
" G 4083, ..	9/-	11/7½	14/3	17/3 "
" G 4084, ..	12/-	15/6	19/-	23/- "
Rolled Plate, ..	½	¾	1	1½ in. thick.
No. G 4082, Prices, ..	9/6	10/6	11/6	17/3 per doz.
" G 4083, ..	14/3	16/3	17/3	25/10½ "
" G 4084, ..	19/-	21/-	23/-	34/6 "

## FLEMISH GLASS

Original Sheets, .. ..	White, 9d.	Tinted, 10½d.	per foot super.
Cut Sizes, .. ..	9½d.	1/-	" "


## CROWN SHEET BULLIONS

These are specially suited for glazing to our 6048 or 6770 Doors, and can be supplied from 6×6 ins. upwards.

Price, .. .. from 1/6 each, according to size.

## GLASS SLATES

No. G 4085.



Rolled Plate, with two peg holes in each.

Thickness, .. ..	¼	⅝	¾	1	inch.
Viscountess, 18×10 ins.,	7/6	8/7½	9/-	11/6	p. doz.
Countess, 20×10 ..	8/-	9/6	9/9	12/9	"
Small Duchess, 22×12 ..	9/6	11/3	12/-	15/9	"
" Imperials, 20×14 ..	9/9	12/-	12/6	17/3	"
Duchess, 24×12 ..	9/9	12/-	12/6	17/3	"

## GLAZING, in London

Sashes Primed and Glazed, .. ..	¾d.	per foot on price of Cut Squares.
Fixed Work Glazed, .. ..	1½d.	" "
Old Work (Ordinary) Glazed, .. ..	4½d.	" "

Glazing in Country Estimated for.

## MEASUREMENT OF LAMP PANES, IRREGULAR SHAPES, &c.

In Lamp or Lantern Panes, which are wider at one end than the other, the width for measurement is taken at two-thirds up from the narrow end for quantities. (Bent and Opal Lamp Panes are charged full size of the extreme dimensions.) This rule, however, applies only to Lamp Panes; all other Panes of irregular shape, not rectangular, are measured as squares from extreme points: and when the shapes are very irregular, a special charge is made to cover risk and loss of time in cutting.

## Glaziers' Diamonds



Diamonds are bought according to their weight and quality, and perhaps some information on the methods adopted in numbering them may be of interest. The Diamonds are divided into six sizes: Nos. 1 and 2, for cutting sheet glass, are lighter than Nos. 3 and 4 for cutting thick sheet and figured rolled, and all glass of a rough and uneven surface, like muffled or Hartley's, the No. 4 being the best "all-round" diamond made, capable of cutting any kind of glass; Nos. 5 and 6 are still heavier and larger stones, and are made for cutting polished plate glass only.

	For Sheet Glass.		For Thick Sheet.		For Plate Glass.	
Grades, .. ..	A 1	A 2	A 3	A 4	A 5	A 6
Prices, .. ..	15/9	20/3	24/9	30/-	37/6	45/-
Grades, .. ..	B 1	B 2	B 3	B 4	B 5	B 6
Prices, .. ..	7/6	11/3	16/6	22/6	18/9	27/-

Customers' own diamonds re-set at 4/1½ each.

"MONCE" or similar Wheel Cutters in boxes of one dozen, at 6/- per dozen cutters.

Price of Putty quoted upon application.

Glaziers' Cutlery illustrated and priced in Colors Section of this Catalogue.

# Polished Plate Glass

Cut to Sizes. Usual Stock Thickness about  $\frac{1}{4}$  inch.

NOTE.—Orders exceeding £5 value and for more than one plate, delivered to buyer's nearest railway station on the mainland in England at the following rates:—

In Squares not exceeding .. ..	2	4	6	12	18	25	50	75	90 feet super.
Plain Plates, .. ..	1/3	1/7½	1/10½	2/3	2/3½	2/4½	2/6	2/7½	2/8½ per foot super.
Silvered Plates, .. ..	1/8½	2/-	2/5½	2/10½	3/-	3/1½	3/4½	3/9	4/3½ " "

No. G 4061.

## MIRRORS IN BLACK BEAD FRAMES



INCLUDING PANELLED  
BACKBOARD.

Plain Edges. Beveling extra.

In sizes not exceeding—

5	12	25 feet super.
3/4½	3/9	4/1½ per foot super.
50	75	90 feet super.
4/6	4/10½	5/3 per foot super.

We can supply every description of Polished and Silvered Plate Glass suitable for shop window fittings, and would submit inclusive estimates to customers' specifications upon application.

## BEVELLING ON POLISHED PLATE GLASS

Width of Bevel, .. ..	½	¾	1	1 inch.
Squares up to 10 feet run,	3d.	3½d.	4½d.	6d. per foot run.
" " 10 " super.,	4½d.	5½d.	6d.	7½d. " "
Width of Bevel, .. ..	1¼	1½	1½	inches.
Squares up to 10 feet run,	8½d.	9d.	1/-	per foot run.
" " 10 " super.,	9½d.	10½d.	1/1½	" "



Prices are for rectangular pieces. We can bevel every description of shape suitable for overmantels, fancy doors, &c. Prices given on receipt of particulars.

## ¾ inch BEVELLED SILVERED POLISHED PLATE GLASS

9 × 7 inches,	1/7½ each.	24 × 18 inches,	7/10½ each.
10 × 8 " "	1/10½ " "	26 × 20 " "	9/9 " "
12 × 10 " "	2/6 " "	28 × 20 " "	10/6 " "
16 × 12 " "	3/9 " "	32 × 24 " "	15/- " "
18 × 14 " "	5/- " "	33 × 21 " "	13/3 " "
20 × 16 " "	6/- " "	36 × 26 " "	19/10½ " "
22 × 18 " "	7/6 " "	42 × 14 " "	12/- " "

## DIAGRAMS FOR BENDING GLASS

FOR EXPLANATIONS AND DIAGRAMS OF OTHER CURVES, SEE SEPARATE AND COMPLETE BENDING LISTS.




Every description of glass bent to customers' specification and diagrams.

Prices and particulars upon application.

# Glass Specialities

## PATENT WIRED GLASS



About  $\frac{1}{4}$  inch thick.


For roofs, windows, and doors in workshops, mills, factories, car sheds, skylights, verandahs, covered ways, &c.

Cut sizes.

Rolled or Cast,  
9d. per foot super.

Polished Plate Glass,  
from  
4/6 per foot super.

## Regd. No. 492005. "ARCTIC" GLASS




For window screens, door panels, partitions, enclosures, &c., &c.

Cut to sizes.

White,  
6 $\frac{1}{2}$ d. per foot super.

Tinted,  
9d. per foot super.

## DAYLIGHT REFLECTORS




Made in frames of well - seasoned wood, painted and made water-tight. Glazed with best silvered fluted glass.

Necessary fixing irons included, ready for placing in position.

From 6/- per foot super.

For reflectors containing not less than 5 feet super.

## PATENT PRISMATIC ROLLED GLASS



Increasing light in dark rooms, shops, cellars, &c.  
The glass must always be glazed with ribs running horizontally and the prisms pointing upwards inside the room.


1/3 per foot super.

## MAXIMUM LIGHT GLASS

This is a daylight increasing window glass, combining lenses and prisms, and is exceedingly useful in increasing the daylight in dark rooms.

Cut Sizes.	Prices.
Under 1 ft. super.,	1/9 per foot super.
" 2 " "	1/10 $\frac{1}{2}$ " "
Larger sizes,	2/- " "

Invaluable for diffusing light into all dark basements, offices, shops, residences, &c.




## "CAT'S EYE" GLASS



A new ornamental window glass of unusual brilliancy, suitable for partitions, door panels, &c., where view is desired to be obscured without detracting from the light.

BRILLIANT AND DECORATIVE  
Day and Night.

Cut to sizes at 1/3 per foot super.



# Polished Plate Glass Shelves and Supports



**SPECIFICATION.**—Stout  $\frac{1}{4}$ -inch Polished Plate Glass, front edge and two ends polished, two corners rounded and polished, back edge ground, similar to PGS8 pattern.

Width, .. .. .	6	8	10	12	14	16	18	20 inches,
Length, 24 inches,	3/3	3/9	4/6	5/-	5/9	6/6	7/-	8/- each Shelf.
30 "	3/9	4/9	5/6	6/3	7/-	8/3	8/9	10/6 "
36 "	4/6	5/3	6/6	7/3	8/6	9/9	11/6	12/- "
42 "	5/-	6/3	7/3	8/9	10/6	12/-	13/6	15/3 "
48 "	5/6	7/-	8/6	9/9	12/3	13/9	15/3	18/- "
54 "	7/-	8/3	10/3	12/-	14/3	16/6	18/9	21/9 "
60 "	8/3	10/3	12/6	14/-	16/3	19/6	23/-	26/- "
66 "	10/-	12/-	14/6	16/9	19/-	24/6	27/3	32/3 "
72 "	13/-	14/3	17/-	19/6	22/-	27/3	32/3	35/3 "

No. F9000.  
Bronzed Iron Standard Bars,  
including Top and Bottom Plates.  
1 $\frac{1}{2}$  x  $\frac{1}{4}$  inch—  
Single, 8d. per foot vertical.  
1 $\frac{1}{2}$  x  $\frac{3}{8}$  inch—  
Single, 9d. per foot vertical.

Extra for Shaped Front to Polished Shelves as follows:—

Shapes PGS1, 2, 6, 7, .. .. . 1/- per foot run of Shelving.  
" PGS8, .. .. . 6d. " " "  
" PGS4, 5, 1/- per foot run of Shelving, plus 2/3 per Shelf for Mitres.

No. F9009.  
Bronzed Brass Shelf Brackets.  
6 8 10 12 inches.  
12/6 15/9 21/- 27/- per doz.

## CIRCLE SHELVES

With all Edges Polished.

4	6	8	10	12	14	16 ins. diam.
1/3	1/9	2/6	3/3	4/-	5/-	6/- each.

## SQUARE SHELVES


With Four Round Corners.

4	6	8	10	12	14	16 ins. sq.
2/-	2/3	2/9	3/3	4/-	4/9	5/6 each.

It without Round Corners at 1/3 less each Shelf.

Holes drilled in centre for Standard—

Up to $\frac{1}{8}$ inch diam.,	9d. each Hole.
" 1 "	1/1 $\frac{1}{2}$ "




## ANGLE SHELVES

With Half-circle Front and all Edges Polished.

9 x 6	10 x 8	12 x 8	12 x 10	12 x 12	14 x 10	14 x 12	14 x 14 inches.
2/6	3/-	3/3	3/6	3/9	4/-	4/3	4/6 each.


It with simple Curved Front and Square Corners or Flat Front and Two Round Corners, 9d. less each Shelf.

It with Flat Front and Square Corners, 1/4 less each Shelf.



Any size Shelf supplied to customers' specification.

# Improved Circular Glass Ventilators




OPEN.

Including Glass.

The circles are about 9 or 10 inches in diameter.

Larger sizes extra.

N.B.—In ordering these Ventilators, the description of glass required and the height and width in rabbets must be distinctly stated; also, if the circles are desired in any particular position, such should likewise be mentioned, as we cannot be answerable for errors in same if such are omitted.





SHUT.

Superticial measurement,	..	..	12	18	24	30	36	48	60	72 inches.
26 oz. Sheet Glass,	..	..	13/6	17/3	21/-	24/-	27/9	33/9	37/6	40/6 each.
32 " " "	..	..	15/-	19/6	23/3	27/-	31/6	37/6	42/-	46/6 ..
Polished Plate Glass,	..	..	16/6	21/9	26/3	30/-	34/6	40/6	46/6	52/6 ..

Intermediate sizes charged in proportion.

Larger sizes quoted for.

## PATENT IMPROVED GLASS LOUVRE VENTILATORS



For church or other windows where lead lights are used, the Ventilators can be made to correspond with remainder of window.

No. 1 QUALITY (for strength and durability).—Brass frames, cast brass levers, improved metal springs (for closing), polished plate glass, edges rounded and polished.

No. 2 QUALITY.—Zinc frames, cast brass levers, improved metal springs (for closing), patent plate glass, edges rough ground.

No. 3 QUALITY (for temporary use only).—Zinc frames, zinc levers, india-rubber springs, sheet glass.

Sizes,	..	..	9 x 6	12 x 10	18 x 12	20 x 14	20 x 16 inches.
1st Quality,	..	..	21/9	27/-	38/3	43/6	46/6 each.
2nd "	..	..	15/-	19/6	27/-	30/-	33/- ..
3rd "	..	..	12/-	15/-	21/-	24/-	25/6 ..

Sizes,	..	..	24 x 18	27 x 18	30 x 18	30 x 20	30 x 24 inches.
1st Quality,	..	..	52/6	58/6	63/-	67/6	72/- each.
2nd "	..	..	37/6	40/6	45/-	48/-	51/- ..
3rd "	..	..	30/-	32/3	34/6	36/-	37/6 ..


Intermediate sizes charged in proportion.

Church quarry ventilators made only of the 1st quality.

When ordering please state clearly if the measures given are in the clear (sight) or including rabbets. Are the rabbets inside or outside of windows? Are they to pull on right-hand side? Are they to be fixed on, under, or between glass? (This question refers to whether the outside of ventilator frame comes into contact with glass. By between glass is meant glass at sides, NOT top and bottom).

No. G 4066.

## PROPAGATING GLASSES



6	8	10	12	14	16 ins. diam.
1/6	2/-	2/6	3/3	5/-	6/6 each.

Also suitable for Wreath Glasses  
or Fern Shades

No. G 4067.

## GLASS AQUARIUMS



8	10	12	14	16	18 ins. diam.
2/3	3/-	4/-	5/9	8/3	11/- each.

Prices of Stands below.

No. G 4068.

## GLASS CAKE COVERS



Suitable for Restaurant Counters.

8	9	10	11	12 ins. diam.
2/3	2/9	3/-	3/6	4/- each.

No. G 4069.

## BLACK POLISHED STANDS

For Aquarium Glasses.



Small Size, 5 ins. diam., 1/1½ each.  
Large Size, 7 ins. diam. 1/9 each.

## Wrought-Iron Casement without Frame

Section No. L4072.

These are strong and substantial Casements, suitable for use in wooden frames, and are fitted with loose iron slips to screw to head, jamb, and cill.

They are hung on strong brass hinges, and provided with wrought-iron handle and stay.

### PRICES.

Prepared for rebates any width not exceeding 2 feet, with square head, and for glass in one pane.

Height.	Price.
Under 3 feet, .. .. .	20/-
3 feet and under 3½ feet, .. ..	21/-
3½ " " 4 " " " " " " " " " "	22/-
4 " " " 4½ " " " " " " " " " "	24/-

Saddle Bars, 1/- each extra.

Section No. L4072.


Reduced size.

Hung at side.

To open outwards.


Fitted with loose clips.

OPENING OF WOODEN FRAME.



ELEVATION OF CASEMENT.

### TRANSOM OR HEAD.



## Wrought-Iron Hopper Casement and Frame

Section No. L4073.

Fall-in Hopper with wings, or top to lift up (Box Hopper).

Made with eye, and pulley for opening and closing.

### PRICES.

Height.	Price.
With screw-hole at sides, not exceeding 18 x 18 ins., square head, and for glass in one pane, ..	26/-
2 feet and under 2½ feet, .. ..	28/-
2½ " " 3 " " " " " " " " " "	32/-

With Gun-metal Spring Catch, 2/- each extra.

With Iron Fixing Fillets at sides for stone grooves, 2/6 extra each hopper.


Saddle Bars, 1/- each extra.

Section No. L4073.

Hopper Casement.


Reduced size.

Made to rock on bottom and to fall in, or top to lift up.



ELEVATION OF CASEMENT.

### TRANSOM OR HEAD.



Sections and Prices for guaranteed Watertight Casements, for fixing in exposed positions, will be forwarded on application.

These are not stock articles, the sizes and details varying to requirements.



# Wrought-Iron Casements and Frames

## Section No. L 4075.

For schools, colleges, larders, and other positions where cheap casements are required. Provided with gun-metal hinges and wrought-iron handle and pin-stay.

Quality No. 1—Brass or gun-metal handle and stay.

„ „ 2 Iron handle and stay.

### PRICES.

For any width not exceeding 2 feet, prepared for rebates, with square head, and for glass in one pane.

Height.	Prices.	
	Quality No. 1.	Quality No. 2.
Under 3 feet, .. .. .	38/-	32/-
3 feet and under 3½ feet. ..	40/-	34/-


Fixing Fillets, 3/- per casement extra.  
Saddle Bars, 1/- each extra.

## Section No. L 4075.

Reduced size.

Hung at side.


To open outwards.



ELEVATION OF CASEMENT.

DETAILS FOR REBATES.


## TRANSOM OR HEAD.



CILL

TO OPEN INWARDS.

## TRANSOM OR HEAD.



CILL

## Section No. L 4077.

Quality No. 1 has gun-metal fittings, polished or bronzed handle, and cabin hook stay.

Quality No. 2 has plain brass fittings, polished or bronzed, or wrought-iron handle, and cabin hook stay.

### PRICES.

For any width not exceeding 2 feet, prepared for rebates, with square head, and for glass in one pane. Hung on strong gun-metal hinges.

Height.	Prices.	
	Quality No. 1.	Quality No. 2.
Under 3 feet. .. .. .	38/-	32/-
3 feet and under 3½ feet, ..	40/-	34/-
3½ „ „ 4 „ ..	42/-	36/-
4 „ „ 4½ „ ..	44/-	40/-

Fixing Fillets, 3/- per casement extra.  
Saddle Bars, 1/- each extra.

## Section No. L 4077.

Reduced size.

Hung at sides.

To open inwards.



ELEVATION OF CASEMENT.

DETAILS FOR REBATES.

## PARTICULARS TO BE GIVEN WHEN ORDERING.


If possible, send sketch of head, cill and jambs, showing rebate or groove, and indicating where measurements have been taken. Height to be given first and so stated. For Casements—Sections L 4072, L 4075 to L 4077—state whether to be hinged on RIGHT or LEFT side, as seen from within. When for lead lights, state the number and position of saddle bars. If Hopper intended for insertion in leaded windows—instruct us to provide a rebate top and bottom. In all cases state whether plain sides with screw-holes or fixing fillets are preferred.

These are not stock articles, the sizes and details varying to requirements.


# Wrought-Iron Sashes

MOULDED SASH BAR, MITRE JOINTS.

No. L 6390.



No. L 6391.




These Sashes are light combined with strength, and can be made any shape, design, or size; also divided into any number of panes, either of which may be made to open as casements, viz., push-out, fall-back, swing (hung on centre), or as hopper.

## FULL-SIZE SECTIONS.



REBATE DETAIL

1½ in.

FLANGE DETAIL



INSIDE




JAMB

INSIDE

DETAIL.

Section 1½ in. showing ¾ in. Fillet for fixing in stone grooves.




JAMB


Or, provided with lugs for building in.

Also made with 1½ in. or 2 in. Sections.

No. L 6392.




No. L 6393.



Prices on application.

# Leaded Stained Glass

Design L.L. 266.



Price, 2/3 per ft.

Design L.L. 267.




Price, 7/6 per ft.

Design L.L. 268.



Price, 2/9 per ft.

Design L.L. 271.



Price, 4/6 per ft.

Design L.L. 272.




Price, 2/4 per ft.

Design L.L. 273.




Price, 3/9 per ft.

Design L.L. 270.



Price, 3/6 per ft.

Design L.L. 269.



Price, 3/6 per ft.

Design L.L. 274.



Price, 2/9 per ft.

Design L.L. 276.




Price, 7/6 per ft.

Design L.L. 275.



Price, 3/9 per ft.

Design L.L. 277.




Price, 3 - per ft.

Manufactured in plain clear sheet glass, or with colored centres, at customer's option.


Wherever desirable, steel-cored lead is used to give strength and rigidity.

When ordering, Height should be given first; also if sizes are Full or Sight. Lights under 3 ft. in area are charged slightly in excess of above rates, and if under 12 in. wide are charged as that width.


# LEADED STAINED GLASS.




Design L.L. 250.  
Price, 1/9 per ft.




Design L.L. 251. Price, 3/- per ft.



Design L.L. 252. Price, 3/- per ft.





Design L.L. 253.  
Price, 3/- per ft.



Design L.L. 254. Price, 3/6 per ft.

Design L.L. 255  
Price, 2/3 per ft.




Design L.L. 257. Price, 2/3 per ft.

ALL work is  
designed and  
executed in our  
Studios. Archi-  
tects' drawings,  
and any scheme  
of decoration  
carefully fol-  
lowed out.



Design L.L. 256,  
Price, 2/3 per ft.



Design L.L. 258. Price, 3/- per ft.


When ordering Height should be given first. Also if sizes are Full or Sight. Lights under 3 ft. in area are charged slightly in excess of above rates, and if under 12 in. wide are charged as that width.

# Wood, Glass, Enamelled Iron and Copper Letters, Figures, Signs, &c.


FOR FIXING ON WINDOWS, SIGNBOARDS, FACIAS, HANGING AND PROJECTING TABLETS, &c.

## WOOD LETTERS

Gilded on face with English Gold (colored sides). To fix on Facias, Signboards, &c.



Bevelled and Shaded, Gilded on face, sides and bevel colored.



Above Prices are for Letters from 3 to 12 inches high only. Larger Sizes quoted for specially. All Wood Letters can be supplied any size.

## OPAL AND GOLD LETTERS

From 2 to 4 inches high. To fix on Glass Windows.



## CRYSTAL GILT LETTERS

From 2 to 4 inches high. To fix on Glass Windows.



## WHITE ENAMELLED COPPER LETTERS



White Enamelled Copper Letters or Figures (Block).

Sizes, 1 & 1½ 2 2½ 3 4 6 7 8 9 10 ins. high.  
Prices, 1d. 1½d. 1½d. 2½d. 3d. 6d. 1/3 1/8 2/3 3/- each.

Can be supplied any size up to 24 inches high. Prices on application.

Prices for "Acme," "Excelsior," "Prismatic" Glass Letters, also Cast-Iron, Brass and Copper Letters on application.

Please quote number when ordering: do not cut illustrations out.

## INCISED LETTERS, FACIAS, &c.

Quoted for on receipt of details of requirements.

## AN ILLUSTRATED LIST OF THESE GOODS

May be had upon application.

## "BRILLIANT" GOLD LETTERS

For Shop Windows. Prices on application.


## ORNAMENTAL ILLUMINATED CANOPIES AND VERANDAHS

Designed and manufactured on our premises and erected on site.

# LEADED STAINED GLASS.




Design L.L. 259. Price, 7 6 per ft.



Design L.L. 260. Price, 7 6 per ft.

All work is designed and executed in our Studios. Architects' drawings, and any scheme of decoration, carefully followed out.




Design L.L. 261. Price, 9/- per ft.



Price, 3/9 per ft.



Price, 3/6 per ft.



Price, 2/- per ft.




Price, 3/3 per ft.

When ordering, Height should be given first. Also if sizes are Full or Sight. Lights under 3 ft. in area are charged slightly in excess of above rates, and if under 12 in. wide are charged as that width.



# Leaded Stained Glass.



Design S.R.  
Price, 2/9 per ft.



Design S.N. Price, 4/3 per ft.




Design S.E.  
Price, 3/9 per ft.

All Work is  
Designed and  
Executed in  
our Studios.




Design S.O. Price, 2/3 per ft.

Architects Draw-  
ings, and any  
scheme of Deco-  
ration, care-  
fully followed out.



Design S.M.  
Price 2/3 per ft.



Design S.Q.  
Price, 2/9 per ft.




Design S.F.  
Price, 4/6 per ft.



Design S.P.  
Price, 2/3 per ft.




Design S.C.  
Price, 3/6 per ft.




Design S.V.  
Price, 2/3 per ft.




Design S.I.  
Price, 3/- per ft.



Design S.H.  
Price, 3/- per ft.



Design S.G.  
Price, 2/3 per ft.



Design R.S.  
Price, 3/- per ft.

We can supply all grades of work from 1/3 per foot upwards.  
Wrought Iron Casements and Ventilators a Speciality.

STRATFORD, E., WALTHAMSTOW, N.E., AND LEYTONSTONE, E., LONDON.





RAIN-WATER, SOIL, & DRAIN GOODS  
 GATES AND RAILINGS  
 MANHOLE COVERS & FRAMES  
 STABLE FITTINGS  
 HOT-WATER APPARATUS  
 AND  
**BUILDERS' CASTINGS**



PHOTOGRAPH OF FOUNDRY DEPARTMENT

**WAREHOUSES AND RAILWAY SIDINGS**

Three Floors, each 430 feet by 60 feet.  
 Delivery Bank, 196 feet by 28 feet.  
 Stables, 196 feet by 28 feet.  
 Forage Mill and Store, 196 feet by 28 feet.


600 feet, with Dock for 40 Goods Trucks.  
 Lay-by and Shunting Spur for 15 Goods Trucks.  
 Lineal Accommodation for 55 Goods Trucks.

The Largest in the Trade; Reserved Exclusively for Stocking every Requisite for Building Construction.

---

**YOUNG & MARTEN, LTD.**  
 CALEDONIAN STRATFORD LONDON  
 WORKS ENGLAND

## Round Rain-Water Pipes and Connections



**CONNECTIONS.**—STANDARD LIST PRICES. Prices of Pipes are given on page 456.

	Diameter.	..	..	..	inches.	2	2½	3	3½	4	4½	5	6
No. C 932.	Heads, flat or angled,	..	..	..	each.	1/3	1/5	1/8	2/-	2/3	3/2	4/-	5/-
" C 4810.	" extra large, flat or angled,	..	..	..	"	2/6	3/-	3/6	3/9	4/6	-	-	-
" C 936.	Shoes,	..	..	..	"	9d.	10d.	1/-	1/4	1/6	2/2	2/8	3/9
" C 937	Boots, 12 inches long over all,	..	..	..	"	1/-	1/2	1/6	1/9	2/2	-	-	-
"	" 15 "	..	..	..	"	1/1	1/3	1/7	1/10	2/3	3/-	3/6	4/9
"	" 18 and 20 inches long over all,	..	..	..	"	1/4	1/6	1/10	2/1	2/6	3/4	4/-	5/3
"	" 24 inches long over all,	..	..	..	"	1/8	1/10	2/2	2/6	3/-	3/9	4/6	5/9
" C 934.	Elbows, square, without door,	..	..	..	"	11d.	1/1	1/4	1/7	1/11	2/8	3/6	4/6
" C 3034.	" obtuse,	..	..	..	"	-	-	-	-	-	-	-	-
" C 305.	" square, with door,	..	..	..	"	-	-	2/9	3/-	3/4	4/2	5/-	6/3
" C 3035.	" obtuse,	..	..	..	"	-	-	-	-	-	-	-	-
" C 938.	Swan Necks, 1½, 2½ and 3 inch projection,	..	..	..	"	1/-	1/1	1/4	1/8	2/-	2/6	3/3	4/6
"	" " 4½ and 6 inch projection,	..	..	..	"	1/2	1/4	1/6	1/10	2/4	3/4	4/-	5/3
"	" " 9 inch projection,	..	..	..	"	1/6	1/8	2/-	2/6	3/-	4/-	4/9	6/-
"	" " 12 "	..	..	..	"	1, 10	2, 1	2, 5	3/-	3/6	4/6	5/6	7/3
"	" " 15 "	..	..	..	"	2/3	2, 6	2, 10	3/6	4/3	5/3	6/6	8/6
"	" " 18 "	..	..	..	"	2/6	2, 10	3, 4	4/-	4/9	6/-	7/6	9/6
"	" " 21 "	..	..	..	"	3/-	3, 3	3, 9	4/6	5/6	8/-	9/6	11/6
"	" " 24 "	..	..	..	"	3/6	4/-	4, 4	5/3	6/6	9/-	10/6	12/9
"	" " 27 "	..	..	..	"	4/-	4/6	5/-	6/-	7/6	10/6	12/-	15/-
"	" " 30 "	..	..	..	"	4/6	5/-	5/6	6/6	8/6	12/-	14/-	17/-
" C 3038	Plinth Bends, 2½ and 3 inch projection,	..	..	..	"	1/1	1/2	1/6	1/10	2/2	2/9	3/6	4/9
"	" " 4½ " 3 "	..	..	..	"	1/3	1/6	1/8	2/-	2/6	3/6	4/3	5/6
"	" " 6 " 5 "	..	..	..	"	1/6	1/9	1/11	2/2	2/8	3/9	4/6	6/-
" C 941.	Union Sockets,	..	..	..	"	6d.	7d.	9d.	11d.	1/1	1/4	1/8	2/-
" C 3037.	T Branch Pieces,	..	..	..	"	-	-	-	-	-	-	-	-
" C 939.	Y " " " " " " " "	..	..	..	"	1/3	1/6	2/-	2/4	2/10	4/-	4/6	7/-
" C 3036	TY " " " " " " " "	..	..	..	"	-	-	-	-	-	-	-	-
" C 940.	Double Y Branch Pieces,	..	..	..	"	2/-	2/6	3/-	3/6	4/3	6/-	6/9	10/6
" C 4034.	Cowl, with socket,	..	..	..	"	2/3	2/3	2/7	3/-	3/5	4/2	5/-	6/9
" C 3039.	Syphon Trap, without door,	..	..	..	"	2/3	2/6	2/9	3/6	4/6	6/-	8/-	10/6
" C 3040.	" " with cleaning door,	..	..	..	"	3/9	4/-	4/3	5/-	6/-	7/9	10/-	12/6

# Half-Round and O.G. Gutters and Connections

No. C942. Half-round Gutter.



No. C946. O.G. Gutter.



No. C944. H.R. Square Angle.  
Right hand external or left hand internal.



No. C944. H.R. Square Angle.  
Left hand external or right hand internal.



No. C3954. H.R. Obtuse Angle.  
Right hand internal or left hand external.



No. C3955. H.R. Obtuse Angle.  
Left hand internal or right hand external.



No. C943. H.R. Nozzle Piece.



No. C3956. H.R. Tee Piece.



No. C948. O.G. External Square Angle.




No. C949. O.G. Internal Square Angle.



No. C3959. O.G. Obtuse External Angle.



No. C3958. O.G. Obtuse Internal Angle.



No. C3960. O.G. Drop Stop End, for Socket.



No. C3960. O.G. Drop Stop End, with Socket.



No. C947. O.G. Nozzle Piece.



No. C3953. H.R. Drop Stop End, with Socket.



No. C3953. H.R. Drop Stop End, for Socket.



No. C945. H.R. Stop End, for Spigot.



No. C945. H.R. Stop End, for Socket.



No. C3957. H.R. Union Clip.



No. C6145. Drop Grating.



No. C951. O.G. Union Clip.



No. C950. O.G. Stop End, for Socket.



No. C950. O.G. Stop End, for Spigot.



## CONNECTIONS.—STANDARD LIST PRICES.

Prices of Gutters are given on page 456.

### HALF-ROUND GUTTER CONNECTIONS.

		Sizes,	..	..	inches,	3	3½	4	4½	5	6
No. C944.	H.R. Angles, square, each,	9d.	10d.	11d.	1/1	1/2	1/8				
" C3954.	H.R. Angles, obtuse, 130 deg.	1/1½	1/3	1/4	1/7½	1/9	2/6				
" C3955.											
" C943.	H.R. Nozzles, ..	9d.	10d.	11d.	1/1	1/2	1/8				
" C3956.	H.R. Tee Pieces, ..	9d.	10d.	11d.	1/1	1/2	1/8				
" C3953.	H.R. Drop Stop Ends, ..	6d.	7d.	8d.	9d.	10d.	1/2				
" C945.	H.R. Stop Ends, ..	2½d.	2½d.	2½d.	3d.	4d.	5d.				
" C3957.	H.R. Union Clips, ..	4d.	4d.	4d.	4½d.	6d.	8d.				


### O.G. GUTTER CONNECTIONS.

		Sizes,	..	..	inches,	3	3½	4	4½	5	6
No. C948.	O.G. Angles, square, each,	1/-	1/-	1/1	1/3	1/5	1/9				
" C949.											
" C3958.	O.G. Angles, obtuse, 135 deg.	1/6	1/6	1/7½	1/10½	2/1½	2/7½				
" C3959.											
" C947.	O.G. Nozzles, ..	1/-	1/-	1/1	1/3	1/5	1/9				
" C3960.	O.G. Drop Stop Ends, ..	9d.	9d.	10d.	11d.	1/-	1/4				
" C950.	O.G. Stop Ends, ..	2½d.	2½d.	2½d.	3d.	4d.	5d.				
" C951.	O.G. Union Clips, ..	6d.	6d.	6d.	8d.	8d.	10d.				

No. C6145. Drop Grating. For Outlet 2 ins., 7½d.; 2½ ins., 9d.; 3 ins., 11½d.; 3½ ins., 1/2; 4 ins., 1/5; 4½ ins., 2/-; 5 ins., 2/6; 6 ins., 3/4 each.  
Gutter Bolts and Nuts, 3/- per gross.

# Straight Back O.G. Gutter

"WYANEM" SECTION.



The advantage of using our Straight Back Gutter is at once obvious, as owing to the increased water carrying capacity, even in time of excessive down-pour, the risk of overflow is reduced to a minimum. The prices we offer this excellent Gutter at are only slightly an advance upon those of the ordinary form, while the weights are in excess of the sections already upon the market.

The drawings give the exact sections and substances of 4 and 4½ inch sizes.

## "WYANEM" STRAIGHT BACK O.G. GUTTERS AND CONNECTIONS.

		Diameter, .. .. . inches,	3½	4	4½	5	6
"Wyanem"	O.G. Gutters, 6 ft. lengths, .. .. . per yard,		1/0½	1/2	1/3	1/5	1/9
"	Short Lengths, .. .. . extra, ..		1½d.	1½d.	1½d.	2½d.	2½d.
"	O.G. Nozzles, .. .. . each,		1/-	1/1	1/3	1/5	1/9
"	" Angles, Square, .. .. . "		1/-	1/1	1/3	1/5	1/9
"	" " Obtuse, .. .. . "		1/6	1/7½	1/10½	2/1½	2/7½
"	" Stop Ends, Plain, .. .. . "		2½d.	2½d.	3d.	4d.	5d.
"	" " Return, .. .. . "		6d.	7d.	8d.	9d.	11d.
"	" Drop Stop Ends, .. .. . "		9d.	10d.	11d.	1/-	1/4
"	" Union Clips, .. .. . "		6d.	6d.	8d.	8d.	10d.

## RAIN WATER AND SOIL GOODS.


6 Feet Lengths by Diameter.		inches,	2	2½	3	3½	4	4½	5	6
No. C 931.	Rain-water Pipes, Fine Cast, with or without Ears, per yard.		1/2½	1/4	1/7	1/10½	2/1	2/9	3/1	3/9
	Galvanized, .. .. . "		2/5	2/8	3/2	3/9	4/2	5/6	6/2	7/6
" C 5610.	Light Soil, or Large Socket R.W. Pipes, Fine Cast, ..		1/5	1/6½	1/9½	2/1	2/2½	3/2	3/6	4/2
	Galvanized, .. .. . "		2/10	3/1	3/7	4/2	4/5	6/4	7/-	8/4
" C 1470.	Medium Soil Pipes, Fine Cast, .. .. . "		1/7	1/9	2/1	2/6	2/8	3/3	3/8	4/9
	Galvanized, .. .. . "		3/2	3/6	4/2	5/-	5/4	6/6	7/4	9/6
" C 5611.	Heavy Soil Pipes, L.C.C. Weights, Fine Cast, .. .. . "		1/8	2/-	2/6	2/9	3/-	3/7	4/3	5/3
	Galvanized, .. .. . "		3/4	4/-	5/-	5/6	6/-	7/2	8/6	10/6
	Short Lengths to above, Fine Cast, extra, .. .. . "		2½d.	2½d.	2½d.	2½d.	2½d.	3½d.	3½d.	3½d.
	Galvanized, .. .. . "		5d.	5d.	5d.	5d.	5d.	7½d.	7½d.	7½d.
" C 942.	H.R.I. Gutters, Fine Cast, Plain, .. .. . "		—	—	9½d.	9½d.	10½d.	11½d.	1/1½	1/6
" C 942 B.	" " Beaded, extra, .. .. . "		—	—	1½d.	1½d.	1½d.	1½d.	3d.	3d.
" C 946.	O.G. " " Plain, .. .. . "		—	—	11½d.	11½d.	1/1	1/2½	1/4	1/8½
" C 946 S.B.	" " Straight Back, extra, .. .. . "		—	—	1d.	1d.	1d.	1d.	1d.	1d.
	Short Lengths to H.R. and O.G. Gutters, .. .. . "		—	—	1½d.	1½d.	1½d.	1½d.	2½d.	2½d.

6 Feet Lengths.		inches,	2½ × 2½ × 2½	3 × 3	3½ × 2½	3½ × 3½	4 × 3	4 × 4	4½ × 3½	5 × 4	6 × 4	6 × 6	7 × 4	
No. C 1781.	Rectangular Rain-water Pipes, Fine Cast, Plain, .. .. . per yard.		2/5	2/8	2/9	2/10	3/6	3/3	3/10	3/11	5/-	5/3	7/6	7/9
" C 1782.	Rectangular Rain-water Pipes, Fine Cast, Ornamental, extra, per yard,		1/-	1/-	1/-	1/-	1/-	1/-	1/-	1/-	1/-	1/-	1/-	
	Short Lengths to R.R.W.P., .. .. . "		5d.	5d.	5d.	5d.	5d.	5d.	7½d.	7½d.	7½d.	7½d.	11½d.	11½d.

# Garden City Gutters and Brackets

## ARTISTIC BRACKETS FOR GARDEN CITY GUTTERS

No. C 6721.




Price, .. 5/- each.

No. C 6722.



Price, .. 2/6 each.

No. C 6723.




Price, .. 2/6 each.

No. C 6721.



Price, .. 2/6 each.

No. C 6725.



Price, .. 5/- each.

The above designs are Hand made in Wrought Iron, for 3, 3½, 4, 4½, 5 and 6 inch Gutters. Prices for "Drive," "Rafter," or "Screw-up" Patterns, to either, are the same.

## GARDEN CITY GUTTERS

No. C 1. Heavy Plain.



Sizes, .. 3 3½ 4 4½ 5 6 inches.


No. C 1. Plain, { ¾ in. Metal, 1/3 1/4 1 4/5 1/6 1 7 2/1 per yard.  
1/4 " " 1/5 1/6 1 7 1/10 2 1 2/8 "

No. C 2. Heavy Beaded Half Round Gutter is 1½d. per yard extra for 3 to 4½ ins.  
" " " " 2½d. " " 5 and 6 "

No. C 2. Heavy Beaded.



No. C 5. Deep H.R. Plain.




Sizes, .. 4 3 5 x 3 5 x 4 6 x 4 inches.

Substance, { Ordinary, .. .. 1 8 1/11 2/1 2/6 per yard.  
¾ in. Metal, .. .. 2/2½ 2/6 2/8½ 2/10½ "  
1/4 " " " " 2 7 3/1 3/5 3/9 "

No. C 6. Deep Beaded Half Round Gutter is 1½d. per yard extra on above prices for No. C 5 Deep Half Round Plain.

No. C 6. Deep H.R. Beaded.



The above prices are at per yard for 6-foot lengths.

Short Lengths and Connections charged by same rule as Moulded Gutters.  
Cutting and Laying-off to Plans, 5 per cent. extra.

## BRACKETS FOR ORDINARY GUTTERS

No. C 4712.  
Wrought-iron  
Bracket.



No. C 1432.  
Wrought-iron  
Bracket.



No. C 1433.  
Wrought-iron Bracket.



No. C 4714.  
Wrought-iron  
Bracket.



No. C B 2.  
Cast-iron  
Bracket.




No. C B 4.  
Cast-iron  
Bracket.




			For Gutters	3	3½	4	4½	5	6 inches
No. C 4712.	H.R. Brackets, to Screw up.	..	..	2/1½	2/3	2 4/5	2/9	3/-	3/6 per dozen.
" C 1432.	" " to Drive,	..	..	3/9	3/9	4/-	4/-	4/6	5/3 "
" C 1433.	" " for Rafter,	..	..	3/9	3/9	4/-	4/-	4/6	5/3 "
" C 4714.	O.G. " to Screw up.	..	..	2/1½	2/3	2 4/5	2/9	3/-	3/6 "
" C B 2.	H.R. " " " " "	..	..	2/6	2/6	3/-	3/-	4/6	6/- "
" C B 4.	O.G. " " " " "	..	..	3/-	3/-	3/-	4/-	5/6	7/6 "

No. C 3720.  
Gutter Cone.



No. C 3720.	Galvanized Wire Cones for Gutters,	..	..	..	..	at 5/- per dozen, 6d. each
" C 3722.	" " Balloons for Pipes,	..	..	..	..	" 5/- " 6d. "
Pipe Nails,	..	..	..	..	..	at 5/- per gross, 6d per dozen.
Gutter Bolts,	..	..	..	..	..	" 3/6 " 4½d. "
Mushroom Head Screws, Galvanized.	..	..	..	..	..	" 3/6 " 4½d. "


No. C 3722.  
Pipe Balloon.




# Moulded Gutters and Connections

EXAMPLES OF OUR NO. C973 SECTION.


External Square Angle.




Internal Square Angle.




External Obtuse Angle.



Internal Obtuse Angle.




Nozzle Piece.



Drop Cast on Back.



Drop Cast on Heel.



Loose Drop, Square.




Union Clip.



Loose Drop, Round.



Drop Stop End, for Socket.



Plain Stop End, Left Hand.



Plain Stop End, Right Hand.



Return Stop End, Left Hand.



Return Stop End, Right Hand.



Plain Reverse Stop End.



Ornamental Reverse Stop End.



Prices of the above Sections are given below.

No. C973. Moulded.




Sizes, .. .. .	3 x 2½	4 x 3	4½ x 3	5 x 3	5 x 4	6 x 4	6 x 4½	7 x 5	8 x 6 Ins.
No. C973, Moulded, Ordinary Substance, }	1/6	1/9	1/10	1/11	2/1½	2/6	2/8	3/7	5/1 p. yd.
.. C972. ..									
.. C975. ..	1/6-in. Metal,	2/2½	2/4	2/7	2/8½	2/10½	3/2	4/2	5/4 ..
.. C976. ..	1-in. ..	2/7	2/10½	3/1	3/5	3/10	4/-	5/2	6/- ..
.. C6. Deep O.G.									

Sizes, .. .. . 4 4½ 5 6 inches.


No. C3814. Notts O.G., .. 1/3 1/4½ 1/9 2/1 per yard.

The above prices are per yard, in 6 ft. lengths.


No. C976. Moulded.



No. C972. Moulded.



No. C6. Deep O.G.



Short Lengths to a Moulded Gutter { up to 2 ft. charged as 1 yard.  
above 2 ft. and up to 4 ft. charged as 1½ yards.  
above 4 ft. and up to 6 ft. charged as 2 yards.

Angles and Nozzles, stock patterns, charged as 1 yard each.

Clips, Stop Ends, Drops on bottom, charged as ½ yard each.

Drops cast on back, charged as ½ yard each.

Drops cast on front, charged as 1½ yards.

Return Ends, charged as ½ yard each.

Drop Ends, charged as ½ yard.

Angles and Nozzles to Boundary Wall and Valley Gutters, charged as 2 yards each.

Galvanized Rain-water and Soil Goods about double the price of Black.

Painting Rain-water and Soil Goods 5 per cent. extra on price of Black.

Coating Rain-water and Soil Goods 5 per cent. extra on price of Black.

Laying out to plan 5 per cent. extra on price of Black.


We shall be pleased to submit prices for the above Sections in intermediate, smaller and larger sizes.

No. C3814. Notts O.G.



# Ornamental Moulded Gutters

No. COM 48.




Width. Depth. Sole.  
 $4\frac{1}{2} \times 4 \times 2\frac{1}{2}$  ins., .. Price. 3/6 per yard.  
 $6 \times 4 \times 3\frac{1}{2}$  „ .. „ 4/6 „  
 $8 \times 6 \times 4 \times \frac{1}{8}$  ins., „ 6/6 „

No. COM 93.




Width. Depth. Sole.  
 $5 \times 4 \times 2\frac{1}{2}$  ins., .. Price. 3/6 per yard.

No. COM 177.



Width. Depth. Sole.  
 $6 \times 4 \times 3$  ins., .. Price. 4/- per yard.  
 $8 \times 5 \times 4 \times \frac{1}{8}$  ins., .. 6/6 „

No. COM 88.




Width. Depth. Sole.  
 $6 \times 4\frac{1}{2} \times 3\frac{1}{2}$  ins., .. Price. 4/4 per yard.

No. COM 74.



Width. Depth. Sole.  
 $6 \times 5 \times 2\frac{1}{2}$  ins., .. Price. 5/- per yard.

No. COM 97.




Width. Depth. Sole.  
 $10 \times 7 \times 4\frac{1}{2} \times \frac{1}{8}$  ins., Price. 7/6 per yard

The above prices are per yard for 6-foot lengths.


Short Lengths and Connections charged by same rule as Moulded Gutters. Cutting and Laying-off to Plans, 5 per cent. extra.

## Patent Gutter Adjuster

Patent No. 10791.




Exact Size.



Ordinary O.G. Gutter when fixed WITHOUT the ADJUSTER.

About one-third actual size.



The same Gutter when fixed WITH the ADJUSTER.

About one-third actual size.

IN the process of moulding it is more difficult, and consequently more expensive, to produce O.G. Gutters with a straight back. Although we offer our "Wyandem" Straight Back Gutter at the prices and weights which will compare favourably with the ordinary form, many of our customers have still stocks on hand of the ordinary section which they desire to utilize. The device we illustrate on this page in use adjusts the ordinary O.G. Gutter so that the front rim is raised to nearly a level with the back top edge, thus giving a smaller size gutter a water-carrying capacity equivalent to a larger size. The adjuster is manufactured of galvanized iron, therefore cannot rust, and is constructed with integral teeth to fix same upon the wooden fascia board in the desired position. A simple tap with a light hammer achieves this object. The gutter is then placed in position against the adjuster, and a fixing screw with a washer bedded in red lead prevents the possibility of water leakage through the screw hole. The screw passing through the interstice in the adjuster fixes the whole permanently in a rigid position.

This appliance is obtainable only from the patentees at the nominal cost of 5/- per gross.




# Box, Boundary Wall and Valley Gutters



## No. C 979. BOX GUTTERS

	Sizes, 4×3	4½×3	4×4	5×4	6×4	6×4½	7×6 inches.
Substance—Ordinary, ..	1/10½	2/-	2/3	2/4½	3/-	3/1½	4/5 per yard.
.. 1½ inch Metal, ..	—	—	2/6	3/-	3/6	—	5/1 ..
.. 1 inch .. ..	2/9½	—	—	3/4½	4/-	—	6/1½ ..

## No. C 978. BOUNDARY WALL GUTTERS



Width,	8	8½	9½	12½	13½	14	16	16	12½	15	19	21	24	inches.
Depth,	4½	5	4½	4½	6½	5	5	6	6	6	6	7¼	6	„
Base,	3	6	6	3¾	5¾	7	8	5	5¾	7	6	9¼	8¾	„
Substance—														
Ordinary, 3/8	4/-	4/2	5/1	5/7	5/3	6/3	6/3	6/3	—	—	—	—	14/-	per yard.
½ in. Metal,	—	—	—	—	—	—	—	—	6/-	7/3	8/9	10/9	—	„

## No. C 3815. VALLEY OR CENTRE GUTTERS



Ordinary Substance.									
Width,	12	15½	16	18	18	18	19	21	24 inches.
Depth,	4	5	6	4	4½	6	5	6	4½ ..
Base,	2½	5½	4	7½	6½	4	4½	9	9½ ..
PRICE,	4/3	5/9	5/9	5/9	5/9	5/11	5/9	6/9	7/7½ per yard.
½ in. Metal.									
Width,	9	12½	14	15	18	19	22	24	inches.
Depth,	5	4½	4	5	5	5	5½	6	..
Base,	6½	6	3	6	5½	6	5	10	..
PRICE,	5/7½	5/7½	5/4½	5/10½	7/1½	7/1½	9/-	10/-	per yard.

The above prices are at per yard for 6 feet lengths.

SHORT LENGTHS—Up to 2 feet charged as 1 yard.

.. Above 2 feet up to 4 feet charged as 1½ yards.

.. .. 4 feet up to 6 feet charged as 2 yards.

ANGLES—Square, charged as 2 yards.

.. Obtuse, charged as 3 yards.

NOZZLE PIECES charged as 2 yards.

UNION CLIPS charged as ½ yard.

STOP ENDS—Loose or cast on, charged as ½ yard.

RETURN ENDS charged as ½ yard.

DROPS—Cast on bottom, charged as ½ yard.

.. Cast on back, charged as 1 yard.

Cutting and Laying off to Plan, 5 per cent. extra.

For quantities, any special sizes of above sections and substances made to order.


FOR ROUND OR SQUARE PIPES.

**No. CE 2. PROJECTING.**

No. CE 4. HOLDERBAUGH.

No. CE 5. HOLDERBAT.

**NO. CE 7. PROJECTING.**



**No. CE 6.**

No. CE 14a.



No. CE 32



No. CE 45.

No. CE 8.


No. CE 10.



No. CE 40.

No. CE 48.

No CE 51.



### PRICES OF EARS -FOR ROUND PIPES.

No. CE 1.	Ornamental Ear, to fit under Socket, projection, 2 ins..	..	each,	1/1	1/2	1/3	1/5	1/6	1/8	1/10	2/-	
	" " " " " 2 1/2 ..	..	..	1/2	1/3	1/4	1/6	1/7	1/10	2/-	2/2	
	" " " " " 3 ..	..	..	1/3	1/4	1/5	1/7	1/8	2/-	2/2	2/4	
" CE 2.	" " projecting, to clip round Socket.	..	..	1/4	1/6	1/7	1/9	1/10	--	—	—	
" CE 4.	Holderbat, Brass Pin, to fit under Socket, ..	..	..	1/8	1/10	2/-	2/2	2/4	2/6	2/9	3/-	
" CE 5.	" Bolt and Nut, to fit under Socket, ..	..	..	1/4	1/6	1/7	1/9	1/10	2/-	2/3	2/5	
" CE 7.	Ornamental Ear, projecting, to clip round Socket,	..	..	1/8	1/10	2/-	2/2	2/4	2/6	2/9	3/-	
	" " Common Pattern, Loose, ..	..	..	1/1	1/2	1/3	1/5	1/6	1/8	1/10	2/-	
Nos. CE 5A to CE 45.	Ornamental Ears, Loose, ..	..	..	1/4	1/4	1/4	1/6	1/6	1/9	2/-	2/2	
" CE 48 to CE 51.	" " " " " " " " ..	..	..	1/8	1/8	1/8	1/10	1/10	2/2	2/6	2/8	

### PRICES OF EARS—FOR SQUARE PIPES.

Nos.	CE 5A. to CE 45.	Ornamental Ears, Loose,	1/4	1/4	1/4	1/4	1/6	1/6	1/7	1/9	2/-	2/2	2/2	2/6	2/6
"	CE 48. to CE 51.	" " "	1/8	1/8	1/8	1/8	1/10	1/10	1/11	2/2	2/6	2/8	2/8	3/2	3/4

# Rectangular Rain-Water Pipes and Connections

No. C 1781.  
Rectangular  
Rain-water  
Pipe.



No. C 960.  
Union Socket.




No. CH 2. Head.




No. CH 3A. Head.




No. CH 3942. Head—Flat.  
London School Board Pattern.



No. CH 10. Head.




No. CH 11. Head.




No. C 1782.  
Ornamental  
Rectangular  
Rain-water  
Pipe.




No. C 3947. Corner Offset.




No. C 3944. Side Offset.




No. CH 3941.  
Head—Angle.  
London School Board  
Pattern.




No. C 963.  
Single Branch Piece.




No. C 964.  
Double Branch Piece.




No. C 3946.  
Corner Plinth Offset.




No. C 3945.  
Front Plinth Offset.



No. C 3949.  
Square Elbow.




No. C 3950.  
Side Square Elbow.




No. C 957.  
Shoe.



No. C 959. Front Offset.




No. C 3948. Side Plinth Offset.




No. C 958.  
Obtuse Elbow.



No. C 3951.  
Side Obtuse Elbow.



No. C 3952.  
Corner Shoe.



## CONNECTIONS - STANDARD LIST PRICES.

Prices of Pipes are given on page 150.

		Diameter,	Inches,	2 1/2 x 2	3 x 2 1/2	3 x 3	3 1/2 x 2 1/2	3 1/2 x 3 1/2	4 x 3	4 x 4	4 1/2 x 3 1/2	5 x 4	6 x 4	6 x 6	7 x 4
No. CH 2.	Heads,	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" CH 3A.	"	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" CH 3941.	"	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" CH 3942.	"	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" CH 10.	"	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" CH 11.	"	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" C 957.	Shoes,	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" C 3949.	Elbows, Square.	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" C 958.	" Obtuse.	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" C 963.	Single Branch-piece.	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" C 964.	Double	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" C 960.	Union Sockets,	..	..	..	..	..	..	..	..	..	..	..	..	..	..
" C 959.	Offsets - 2 1/2 and 3 inch projection.	..	..	..	..	..	..	..	..	..	..	..	..	..	..
	4 1/2	..	..	..	..	..	..	..	..	..	..	..	..	..	..
	6	..	..	..	..	..	..	..	..	..	..	..	..	..	..
	12	..	..	..	..	..	..	..	..	..	..	..	..	..	..
	15	..	..	..	..	..	..	..	..	..	..	..	..	..	..
	18	..	..	..	..	..	..	..	..	..	..	..	..	..	..
	21	..	..	..	..	..	..	..	..	..	..	..	..	..	..
	24	..	..	..	..	..	..	..	..	..	..	..	..	..	..

The above Prices are for FRONT Connections.


SIDE Elbows, Offsets, Shoes, and Plinths, 25 per cent. extra.

CORNER Plinths, Shoes, Offsets, and Bends, 50 per cent. extra.

# Artistic Rain-Water Heads

(Registered Designs.)

FOR ROUND AND SQUARE PIPES.



## SIZES AND PRICES.

Design Nos.	..	CH 3	CH 3	CH 6	CH 8	CH 8	CH 48	CH 29	CH 209	CH 210	CH 202	CH 208	CH 206	CH 204
Width,	.. ins.,	7 $\frac{1}{2}$	10 $\frac{3}{4}$	11	11 $\frac{1}{2}$	13	11	11 $\frac{1}{2}$	26	21	25	26	24	25
Depth,	.. "	5 $\frac{1}{2}$	8 $\frac{1}{4}$	7 $\frac{1}{4}$	7 $\frac{1}{4}$	8	6	8 $\frac{1}{4}$	6 $\frac{1}{2}$	7	6	7	6	7
Height,	.. "	11 $\frac{3}{4}$	15 $\frac{3}{4}$	17	14	14	16 $\frac{1}{2}$	17 $\frac{3}{4}$	16	17	18	16	19	19
For Round Pipes,	..	2 to 3	3 $\frac{1}{2}$ to 4 $\frac{1}{2}$	2 to 4 $\frac{1}{2}$	2 to 2 $\frac{1}{2}$	3 to 3 $\frac{1}{2}$	2 to 4	2 to 4 $\frac{1}{2}$	2 to 4	2 to 4	2 to 4	2 to 4	2 to 4	2 to 4
For Square	.. "	2 $\frac{1}{2}$ x 2 to 3 x 3	3 $\frac{1}{2}$ x 3 to 4 x 3 $\frac{1}{2}$	2 $\frac{1}{2}$ x 2 to 4 x 4	2 $\frac{1}{2}$ x 2 to 3 x 2 $\frac{1}{2}$	3 x 3 to 4 x 3 $\frac{1}{2}$	2 $\frac{1}{2}$ x 2 to 4 x 3	2 $\frac{1}{2}$ x 2 to 4 x 4	2 $\frac{1}{2}$ x 2 to 4 x 4	2 $\frac{1}{2}$ x 2 to 4 x 4	2 $\frac{1}{2}$ x 2 to 4 x 4	2 $\frac{1}{2}$ x 2 to 4 x 4	2 $\frac{1}{2}$ x 2 to 6 x 4	2 $\frac{1}{2}$ x 2 to 4 x 4
Prices,	.. each,	9/6	14/6	18/-	12/6	14/-	15/-	18/-	30/-	30/-	35/-	35/-	40/-	40/-


# Artistic Rain-water Heads

NEW DESIGNS.


No. CH 110.




No. CH 117.



No. CH 60.




No. CH 66.



No. CH 113.



No. CH 67.



## SIZES AND PRICES.

	Design Nos.,	CH 110.	CH 117.	CH 60.	CH 66.	CH 113.	CH 67.	
Width, over	{ Ears,	..	30½	13½	17½	25½	15½	inches.
	{ Body,	..	24½	10	12	20½	10	
Projection,	..	..	{ Ends, 8 }	7½	7	{ Ends, 7½ }	5	"
		..	{ Centre, 10 }			{ Centre, 9 }		"
Height, exclusive of Outlet,	..	12	11½	10	18½	10½	18	"
For Round Pipes,	..	2½	2 to 4	2 to 4	2 to 4	3 to 4	2 to 4	"
For Square	..	—	—	—	—	—	2½ × 2 to 4 × 4	"
Prices, ..	..	7/-	30/-	12/-	25/-	24/-	25/-	each.

Numerals indicating CURRENT YEAR can be substituted for those shown ; or, in lieu of same, Owners' Initials Cast-on.

# Artistic Rain-Water Heads

NEW DESIGNS.


No. CH 107.



No. CH 109.



No. CH 51.



Can have One or Two Outlets Cast-on.


No. CH 53.



No. CH 118.




No. CH 112.



Made 15, 21, 23, 30, 36 and 48 inches wide, with One or Two Outlets.

No. CH 115



## SIZES AND PRICES.

Design Nos.	CH 107.	CH 109.	CH 51.	CH 115.	CH 118.	CH 112.	CH 53.						inches.
Width, over Ears,	12½	35½	—	24½	19	24½	—	—	—	—	—	—	
„ „ Body,	9	30	13½	20	15½	19	15	21	23	30	36	48	„
Projection, ..	6	6½	8½	6½	7½	9½	8	8	8	9	9	9	„
Height, exclusive of Outlet, ..	6	6	15	6	21½	12½	8	8	8	6	6	6	„
For Round Pipes,	2 to 4	2 to 4	2 to 4	2 to 4	—	2 to 4	2 to 6						„
For Square ..	2 x 2 to 4 x 4	2 x 2 to 4 x 4	—	2 x 2 to 4 x 4	3 x 3 to 4 x 4	—	2½ x 2 to 6 x 6						„
Prices, .. ..	5/-	25/-	15/-	15/-	20/-	20/-	20/-	25/-	27/6	30/-	35/-	42/6	each.


Numerals indicating CURRENT YEAR can be substituted for those shown ; or, in lieu of same, Owners' Initials Cast-on.

# Cast-Iron Soil Pipes and Connections


Soil Pipe,  
with or  
without  
Fars.




No. C 5614.  
Square Bend




No. C 5616.  
Obtuse Bend




No. C 2986.  
Long Bend,  
to take Earthenware Pipe.



No. C 5689.  
Connector,  
with Large Socket.



No. C 5634.  
Square Bend,  
with Large Socket.




No. C 5612.  
Union  
Socket




No. C 5745.  
Shoe




No. C 5650.  
Swan Neck




No. C 5680.  
Junction for P Trap




No. C 5828.  
Junction for S Trap




No. C 5682.  
Junction, with Anti-Syphon.



No. C 5653.  
Branch Piece



No. C 5656.  
Tee Branch Piece



## STANDARD LIST PRICES OF CONNECTIONS.

Light. Medium. Heavy.  
Light Soil, Medium Soil, Heavy Soil,  
and Large 1/2" Metal, and 3/4" Metal,  
Socket Rain Water Pipe. L.C.C. Weights.

Diam., ins.,	4	2	3 1/2	4	4
No. C 5614,	2/4	1/8	2/6	2/10	3/4 each.
" C 5616,	2/4	1/8	2/6	2/10	3/4 "
" C 2986,	4/-	—	—	4/8	— "

### No. C 5689—

9 ins. long,	2/-	—	—	2/3	— "
12 " "	2/3	—	—	2/6	— "
15 " "	2/9	—	—	3/-	— "
18 " "	3/-	—	—	3/6	— "
24 " "	4/-	—	—	4/6	— "

### No. C 5634—

12x12 ins.,	4/8	—	4/8	5/-	— "
14x14 " "	5/-	—	5/-	5/6	— "
16x14 " "	6/6	—	6/6	7/-	— "
16x16 " "	6/6	—	6/6	7/-	— "
17x17 " "	7/-	—	7/-	7/6	— "
20x20 " "	8/-	—	8/-	8/6	— "
22x22 " "	9/6	—	9/6	10/-	— "

No. C 5745,	2/-	1/2	2/-	2/4	3/- "
-------------	-----	-----	-----	-----	-------

### " C 5650—

3 in. project.,	2/4	1/6	2/8	3/2	4/4 "
4 1/2 " "	2/9	1/10	3/2	3/8	4/6 "
6 " "	2/9	2/-	3/8	4/3	5/3 "
9 " "	3/6	2/8	4/3	5/-	6/2 "
12 " "	4/-	3/2	5/2	5/8	7/1 "
15 " "	4/11	4/-	5/6	6/6	8/- "
18 " "	5/6	4/9	6/6	7/6	9/6 "
21 " "	6/-	—	7/6	8/6	11/- "
24 " "	7/6	—	8/6	9/6	13/6 "

No. C 5612,	1/4	11d.	1/5	1/8	2/2 "
-------------	-----	------	-----	-----	-------

### Nos. C 5680 and C 5828—

Arm, 9 ins.,	6/-	—	6/-	6/6	— "
" 12 " "	6/6	—	6/6	7/-	— "
" 15 " "	6/9	—	7/-	7/6	— "
" 18 " "	7/3	—	7/6	8/-	— "
" 21 " "	7/9	—	8/-	8/6	— "
" 24 " "	8/3	—	8/6	9/-	— "
" 27 " "	9/-	—	9/6	10/-	— "
" 30 " "	10/-	—	10/6	11/-	— "
" 33 " "	11/-	—	11/6	12/-	— "
" 36 " "	12/-	—	12/6	13/-	— "


### No. C 5682—

Extra on Nos. C 5680 and C 5828,	1/6	—	1/6	1/6	— "
No. C 5653,	3/6	2/-	3/6	4/-	5/- "
" C 5656,	3/6	2/-	3/6	4/-	5/- "


If Coated or Painted, add 5 per cent.: Galvanized, double.

# Cast-Iron Soil Pipes and Connections

No. C 5636.  
**Quadrant Bend**  
Sanitary Socket.



No. C 5639.  
**Sanitary Bend**



No. C 5620.  
**Square Bend, with**  
Heel Rest.




No. C 5623.  
**Obtuse Bend, with**  
Heel Rest.



## STANDARD LIST PRICES OF CONNECTIONS.

	Light. Light Soil, and Large Socket Rain Water Pipe.	Medium. Medium Soil, and L.C.C. Weights.	Heavy. Heavy Soil, and Metal.	
Diam., Ins.,	4	2 3 4	4	
No. C 5636,	—	—	3/8	— each.
" C 5639,	—	2/9	2/11	— "
" C 5620,	3/-	2/1	3/6	4/4 "
" C 5623,	3/-	2/1	3/6	4/4 "

No. C 5627.  
**Square Bend, with**  
Door.



No. C 5630.  
**Obtuse Bend, with**  
Door.



No. C 5626.  
**Square Bend, with**  
Brass Plug.



No. C 5632.  
**Obtuse Bend, with**  
Brass Plug.



No. C 5627,	6/7	5/8	6/9	7/1	7/7	each.
" C 5630,	6/7	5/8	6/9	7/1	7/7	"
" C 5626,	5/1	4/5	5/3	5/7	6/1	"
" C 5632,	5/1	4/5	5/3	5/7	6/1	"

No. C 5667.  
**Tee Branch Piece,**  
with Door.



No. C 5665.  
**Branch Piece,**  
with Door.



No. C 5671.  
**Tee Branch Piece,**  
with Brass Plug.



No. C 5669.  
**Branch Piece,**  
with Brass Plug.



No. C 5644.  
**Increasing**  
**Piece**



No. C 5667,	7/9	6/-	7/9	8/3	9/3	each.
" C 5665,	7/9	6/-	7/9	8/3	9/3	"
" C 5671,	6/3	4/9	6/3	6/9	7/9	"
" C 5669,	6/3	4/9	6/3	6/9	7/9	"
" C 5644,	2/3	1/7	2/4	2/9	3/4	"

No. C 5658.  
**Double Tee**  
**Branch Piece**



No. C 5660.  
**Breeches Piece**



No. C 5662.  
**Double Branch**  
**Piece**




No. C 5647.  
**Diminishing**  
**Piece**




No. C 5658,	4/10	2/7	4/3	4/9	5/11	each.
" C 5660,	4/10	2/7	4/3	4/9	5/11	"
" C 5662,	4/10	3/2	4/10	5/6	6/10	"
" C 5647,	2/3	1/7	2/4	2/9	3/4	"

No. C 5672.  
**Anti-Syphon**  
**Branch A.**



No. C 5674.  
**Anti-Syphon**  
**Branch B.**



No. C 5642.  
**Anti-Syphon**  
**Square Bend**



No. C 5641.  
**Anti-Syphon**  
**Branch**



No. C 5643.  
**Anti-Syphon**  
**Obtuse Bend**




No. C 6039.  
**Cast-Iron**  
**Cowl**



No. C 5672,	3/6	2/-	3/6	4/-	5/-	each.
" C 5674,	3/6	2/-	3/6	4/-	5/-	"
" C 5641,	—	4/-	—	—	—	"
No. C 5642—						
6 inch Tail,	—	1/7	—	—	—	"
9 " " "	—	2/-	—	—	—	"
12 " " "	—	2/10	—	—	—	"
18 " " "	—	3/6	—	—	—	"
24 " " "	—	4/6	—	—	—	"
No. C 5643						
6 inch Tail,	—	1/7	—	—	—	"
9 " " "	—	2/-	—	—	—	"
12 " " "	—	2/10	—	—	—	"
18 " " "	—	3/6	—	—	—	"
24 " " "	—	4/6	—	—	—	"
No. C 6039,	—	2/-	2/4	2/6	—	"

No. C 5676.  
**Anti-Syphon**  
**Branch C.**



No. C 5678.  
**Anti-Syphon**  
**Branch D.**




No. C 6227. **Pipe Clip**  
To fit round Collar; Stems also  
made for bolting to wall.



No. C 5686. **Pipe Clip**



No. C 5609.  
**Roof Syphon**



No. C 5676,	3/6	2/-	3/6	4/-	5/-	each.
" C 5678,	3/6	2/-	3/6	4/-	5/-	"
" C 6227,	2/-	1/6	1/10	2/-	2/-	"
" C 5686,	2/-	1/6	1/10	2/-	2/-	"
" C 5609,	5/6	3/6	5/3	5/8	7/1	"

If Coated or Painted, add 5 per cent.; Galvanized, double.



# Heavy Drain Pipes and Connections

L.C.C. WEIGHTS; COATED WITH DR. ANGUS SMITH'S SOLUTION.

No. C 6230. Pipe



No. C 6230.

Diameter,	2	3	4	5	6 ins.
9 ft. lengths, —	3/9	5/-	6/3	7/6	per yard.
6 ft. „	2/6	4/4½	5/7½	6/10½	8/1½ ..
3 ft. „	3/7½	5/-	6/3	8/1½	10/- ..

No. C 6237.  
Collar



No. C 6231.  
Blank Spigot



No. C 6232.  
Blank Socket



No. C 6305. Short Pipe  
with large Socket for  
Earthenware Pipe



Diameter,	2	3	4	5	6 ins.
No. C 6237.	2/3	3/-	3/9	6/-	7/6 each.
„ C 6231.	6d.	1/-	1/3	2/3	2/6 ..
„ C 6232.	2/-	2/6	2/9	3/9	4/6 ..
„ C 6305.	—	2/9	5/3	7/6	9/- ..

Diminishing Pieces

No. C 6234.



No. C 6236.



No. C 6238.  
Handhole Pipe




Diameter,	4 to 3	5 to 4	6 to 4	6 to 5 ins.
No. C 6234.	5/3	6/9	8/3	9/9 each.
„ C 6236.	5/3	6/9	8/3	9/9 ..

No. C 6239.  
Short Bend



No. C 6244.  
Long Bend



No. C 6240.  
Obtuse Short  
Bend



No. C 6245.  
Obtuse Long  
Bend




Diameter,	2	3	4	5	6 ins.
No. C 6238.	—	—	13/6	15/9	19/6 each.


No. C 6239.	3/9	4/6	6/9	9/-	12/9 each.
„ C 6244.	3/9	5/3	7/6	9/9	15/- ..
„ C 6240.	3/9	4/6	6/9	9/-	12/9 ..
„ C 6245.	3/9	5/3	7/6	9/9	15/- ..

Nos. C 6240 and C 6245 made in 95, 100, 112½, 120, 135, 145, 157 degrees.

No. C 6242.  
Short Bend with  
Heel Rest




No. C 6246.  
Long Bend with  
Heel Rest



No. C 6243.  
Obtuse Short Bend  
with Heel Rest




No. C 6247.  
Obtuse Long Bend  
with Heel Rest



No. C 6242.	4/6	6/-	8/3	10/6	15/9 each.
„ C 6246.	4/6	6/9	9/-	11/3	16/6 ..
„ C 6243.	4/6	6/-	8/3	10/6	15/9 ..
„ C 6247.	4/6	6/9	9/-	11/3	16/6 ..

Nos. C 6243 and C 6247 made in 95, 100, 112½, 120, 135, 145, and 157½ degrees.

No. C 6248.  
Short Bend with  
door



No. C 6249.  
Short Bend with  
door



No. C 6250.  
Long Obtuse Bend  
with door



No. C 6251.  
Long Bend with  
large access door



No. C 6248.	8/3	9/9	11/3	15/-	18/9 each.
„ C 6249.	8/3	9/9	11/3	15/-	18/9 ..
„ C 6250.	9/-	10/6	12/9	15/9	21/- ..
„ C 6251.	—	15/-	18/-	21/9	30/- ..

Nos. C 6249, C 6250 and C 6251 made in 95, 100, 112½, 120, 135, 145 and 157½ degrees.


Nos. C 6248, C 6249 and C 6250 have each three gun-metal set screws and rubber joint to door.

No. C 6251 has four gun-metal set screws and rubber joint to doors, made right or left hand.


# Heavy Drain Pipes and Connections

L.C.C. WEIGHTS: COATED WITH DR. ANGUS SMITH'S SOLUTION.


No. C 6262.  
**Bend, with large  
Access Door.**




No. C 6263.  
**Obtuse Bend, with  
large Access Door.**



No. C 6269.  
**Bend, with large  
Access Door.**



No. C 6270.  
**Bend, with large  
Access Door.**




Diam., .. 2 3 4 5 6 inches.

No. C 6262,	28/6	33/9	38/3	43/6	each.
.. C 6263,	28/6	33/9	38/3	43/6	..
.. C 6269,	-	-	34/6	40/6	45/9 ..
.. C 6270,	-	-	34/6	40/6	45/9 ..

Above are made right or left hand. Nos. C 6263 and C 6270 made 95, 112 1/2 and 135 degrees.

No. C 6252.  
**Branch**



No. C 6253.  
**Branch**



No. C 6254.  
**Branch,  
with Access Door.**




No. C 6255.  
**Branch,  
with Access Door.**



No. C 6252,	6/-	7/6	11/3	15/-	19/6 each.
.. C 6253,	6/-	7/6	11/3	15/-	19/6 ..
.. C 6254,	11/3	12/9	16/6	19/6	25/6 ..
.. C 6255,	11/3	12/9	16/6	19/6	25/6 ..

Nos. C 6253 and C 6255 made 95, 100, 112 1/2, 120, 135, 145 and 157 1/2 degrees.


No. C 6260.  
**Short Pipe, with  
large Access Door.**




No. C 6256.  
**Branch, with  
large Access Door.**



No. C 6257.  
**Branch, with  
large Access Door.**



No. C 6265.  
**Inspection Branch,  
with large Access Door.**




No. C 6260,	-	-	15/9	19/6	26/3 each.
	4x4	5x4	5x5	6x4	6x6
.. C 6256,	21/-	26/3	27/9	33/-	34/6 each.
.. C 6257,	-	-	24/-	30/-	39/- ..
	4x4	5x4	5x5	6x4	6x6
.. C 6265,	39/-	45/6	46/6	55/6	57/- each.

Nos. C 6265 and C 6256 made right or left hand. No. C 6256 made 95, 100, 112 1/2, 120, 135, 145, and 157 1/2 degrees. No. C 6257 made 90, 95, 100, 112 1/2 and 120 degrees.


No. C 6267.  
**Inspection  
Pipe, with  
large Access  
Door.**



No. C 6258.  
**Double Branch**



No. C 6259.  
**Double Branch,  
with large Access Door.**



No. C 6271.  
**Inspection Branch,  
with large Access  
Door.**




Length,	26	27	28	30 inches.
No. C 6267,	24/-	27/9	31/6	34/6 each.
.. C 6258,	—	15/-	21/-	24/- ..
.. C 6259,	..	27/-	33/-	39/9 ..
	4x4	5x4	5x5	6x4 6x6
.. C 6271,	39/9	46/6	48/-	57/9 60/- each.

Nos C 6258 and C 6259 made 90, 95, 100, 112 1/2, and 120 degrees. No. C 6271 made 90, 112 1/2 and 135 degrees; either right or left hand.

# Heavy Drain Pipes and Connections

L.C.C. WEIGHTS: COATED WITH DR. ANGUS SMITH'S SOLUTION.

No. C6261. **Swan-neck**




No. C6288. **Horizontal Trap**



Diam.,	2	3	4	5	6 inches.
No. C6261—					
3 ins. Projection, ..			6/9	9/-	12/- each.
4½ .. ..			7/1½	9/3	12/9 ..
6 .. ..			7/6	9/9	13/6 ..
9 .. ..			8/3	10/6	15/- ..
12 .. ..			9/9	11/3	16/6 ..

No. C6267. **Inspection Shoe**  
with Vertical Inlet.



9½ 5½ ins. Grating, 1/3 each extra.

No. C6289. **Horizontal Trap**  
Fitted with Flanged Access Door.



No. C6267. — 12/6 13/6 — — ..

No. C6288, — — 11/3 — ..

No. C6289, — — 21/- — ..

No. C6282, with—  
P Outlet. — 7/6 10/6 — — ..


Q .. — 8/- 11/3 — — ..

S .. — 8/9 12/- — — ..

No. C6282. **P, Q, or S Trap**



No. C6283. **P, Q, or S Trap**  
Fitted with Flanged Access Door.




No. C6283, with  
P Outlet, 17/6 21/- — — ..

Q .. 18/3 21/9 — — ..

S .. — 18/9 22/6 — — ..


No. C6272.  
**Inspection Branch**  
with large Access Door.



Diam., 4 5 5 ins.  
Prices, 57 - 72 - each.


If with Socket Inlet cast on, 39/- 42/- 49 6 ..

No. C6290.  
**Intercepting Trap**  
with Cover, Bridle and Screw.




4 5 6 ins.  
34 6 37 6 43 6 each.

No. C6285.  
**Trapped Inlet,**  
11 8 inches on Top,  
with P or S Outlet.




4-inch Outlet.  
Price, 21/- each.

No. C6286.  
**Trapped Inlet**  
with 4-inch P or S Outlet




7½ ins. diam. at top.  
Price, 12/- each.

No. C6291.  
**Gulley Inlet**



Diam., 4 5 6 ins.  
Prices, 6/9 8/9 10/9 each.

No. C6292.  
**Gulley Inlet**




4 ins., 8/9 each.

No. C6297.  
**Gulley Inlet**




4 ins., 8/9 each.

No. C6298.  
**Gulley Inlet**



4 ins., 30/- each.

No. C6299.  
**Gulley Inlet**



4 ins., 42/- each.

Branch Inlets may be either 2, 3, or 4 ins. diam.


# Manhole Covers and Frames

**Young & Marten's Patent No. 10825 Locking and Lift-off Manhole Cover**

APPROVED AND ADOPTED BY BOROUGH AND DISTRICT COUNCILS.

No. C 3931.

**Air-tight Manhole Cover, with Flange at Surface.**




## PARAMOUNT ADVANTAGES.


1. Perfectly air tight.
2. Absolute security.
3. Strongly made.
4. Nominal cost.
5. Triple locked.
6. Solid lug hinge.
7. Cover movable; but
8. Immovable without keys.
9. In case of breakage, Cover can easily be replaced without interfering with frame.

No. C 3932.

**Air-tight Manhole Cover, with Flange at Bottom.**



No. C 3932.




Showing method of opening.



This drawing shows the patent hinging arrangement.

No. C 3932.




Showing Cover removed.

Prices (including Two Keys to each Cover).  
Size of Opening, 18 18 24 18 30 24 ins.  
Prices, .. .. 15/- 18/- 30/- each.

Locking arrangement is made with Gun-metal Liners and Wrought-iron Tongues.


The turnbuckle cannot be unlocked without the aid of the key, thus the cover is securely locked and cannot be opened by children or unauthorised persons. The two keys are also applicable for the purpose of raising the cover on hinge, and again for its complete removal. The lower frame has a groove all round, which must be filled with sand, soap or grease, so that when cover is shut and locked it is both air-tight and secure.

Design No. C 4273.  
Showing Locking Arrangement.




**Young & Marten's Patent No. 11146 Locking and Lift-off Manhole Cover**

Design No. C 4273.  
Showing Hinge Fitting in Frame.



Design No. C 4273.  
Showing Cover standing Vertical on Hinge.



## ADVANTAGES.


Cost—NOMINAL. Seal—AIR TIGHT.  
Cover—HINGED. Cover—LOCKING.  
Cover—REMOVABLE (with aid of key only).

Children and unauthorised persons cannot meddle with it.  
Will stand thorough examination.

Size of Opening, .. 24 18 24 24 30 24 ins.  
Prices, .. .. 18/- 22/6 30/- each.


Locking arrangement is made with Gun-metal Liner and Wrought-iron Tongues.

Design No. C 4273.  
Air-tight Manhole Cover showing Cover Locked to Frame.




# Manhole Covers and Frames

## No. C 4840. With Cover, 1, 3, or 4 inches Deep for Concrete




Size of Opening.	Cover Sunk 1 inch.		Cover Sunk 3 inches.		Cover Sunk 4 inches.	
	Weight in Lbs.	Price, Each.	Weight in Lbs.	Price, Each.	Weight in Lbs.	Price, Each.
15 × 15 ins., ..	108	15/-	131	18/-	—	—
18 × 18 „ ..	119	16/6	152	21/9	—	—
24 × 18 „ ..	168	22/6	189	25/6	247	33/-
24 × 24 „ ..	182	25/6	231	31/6	—	—
30 × 24 „ ..	198	28/6	273	37/6	—	—

## No. C 6015. Double Cover Manhole Covers and Frames



Size of Opening.	Weight in Lbs.	Price, Each.
18 × 18 ins., ..	147	19/6
24 × 18 „ ..	175	25/6
24 × 18 „ ..	252	42/-

## No. C 6016. Lock and Hinge Manhole Covers and Frames




Size of Opening.	Weight in Lbs.	Price, Each.
18 × 12 inches, ..	68	15/-
18 × 18 „ ..	112	18/-
24 × 18 „ ..	140	22/6
30 × 18 „ ..	123	21/-
30 × 24 „ ..	166	27/-

See also No. C 6019 for Hinged Covers, with Flange at surface.



## No. C 6017. Double Seal Manhole Covers and Frames




Size of Opening.	Weight in Lbs.	Price, Each.
18 × 18 inches, ..	89	13/6
24 × 18 „ ..	76	12/9
24 × 18 „ ..	110	16/6
24 × 24 „ ..	140	22/6
30 × 24 „ ..	112	19/6
30 × 24 „ ..	152	22/6
36 × 24 „ ..	189	28/6

# Inspection and Manhole Covers


No. C 1455.

## Manhole Covers and Frames




Size of Opening.	SPECIAL.		LIGHT.		MEDIUM.		STRONG.		HEAVY.		EXTRA HEAVY.	
	Weight in Lbs.	Price, Each.	Weight in Lbs.	Price, Each.	Weight in Lbs.	Price, Each.	Weight in Lbs.	Price, Each.	Weight in Lbs.	Price, Each.	Weight in Lbs.	Price, Each.
6 x 6 ins.	0	1/6	—	—	—	—	—	—	—	—	—	—
9 x 6 ..	—	—	21	3/9	—	—	—	—	—	—	—	—
9 x 9 ..	19	3/6	—	—	24	4/1 1/2	30	4/6	—	—	—	—
12 x 12 ..	19	3/9	25	4/1 1/2	35	5/-	53	7/6	—	—	—	—
15 x 15 ..	—	—	35	5/7 1/2	49	6/9	63	9/-	—	—	—	—
18 x 9 ..	23	3/10 1/2	—	—	—	—	—	—	—	—	—	—
18 x 12 ..	31	5/7 1/2	—	—	50	8/3	—	—	—	—	—	—
18 x 18 ..	11	6/-	—	—	50	7/6	86	12/-	—	—	112	15/-
20 x 15 ..	—	—	—	—	50	8/3	—	—	—	—	—	—
20 x 20 ..	—	—	50	7/6	—	—	81	10/6	—	—	—	—
24 x 9 ..	—	—	—	—	48	6/9	—	—	—	—	—	—
24 x 12 ..	—	—	—	—	50	7/6	70	10/1 1/2	—	—	—	—
24 x 18 ..	50	6/3	56	7/1 1/2	70	8/3	84	10/6	112	12/9	168	21/-
24 x 18 ..	—	—	64	8/3	77	10/1 1/2	98	12/9	144	15/9	252	30/-
24 x 24 ..	—	—	72	12/-	94	13/6	112	13/10 1/2	122	16/6	—	—
30 x 18 ..	—	—	84	12/9	115	15/9	144	19/6	—	—	—	—
30 x 24 ..	—	—	103	14/7 1/2	112	16/1 1/2	162	21/-	—	—	—	—

## Manhole Covers and Frames, with Flange at Top for Pavements



Size of Opening.	No. C6018. Cover to Lift off.		No. C6019. Cover with Hinge and Lock	
	Weight in Lbs.	Price, Each.	Weight in Lbs.	Price, Each.
15 x 15 ins.	67	9/9	91	15/9
18 x 18 ..	91	12/9	112	18/9
24 x 18 ..	112	16/6	128	21/-
24 x 24 ..	147	22/6	151	25/6
30 x 24 ..	192	28/6	198	33/-

## Manhole Covers and Frames. Large Sizes and Heavy Castings.



SECTION.

No. C 6013. Large Sizes.			No. C 6014.		
Size of Opening.	Weight in Lbs.	Price, Each.	Extra Heavy, for Cart Traffic.		
28 x 28 ins.	126	18/9	Size of Opening.	Weight in Lbs.	Price, Each.
30 x 30 ..	196	27/-	18 x 18 ins.	168	22/6
32 x 32 ..	151	24/-	24 x 18 ..	221	30/-
36 x 18 ..	144	19/6	24 x 24 ..	266	34/6
36 x 24 ..	196	27/-	30 x 18 ..	252	34/6
36 x 30 ..	235	33/-	30 x 24 ..	301	39/-
36 x 36 ..	290	37/6	36 x 24 ..	370	48/-
42 x 30 ..	324	42/-			
42 x 36 ..	392	51/-			
48 x 24 ..	273	36/-			
48 x 36 ..	432	57/-			

## NOTES AND EXTRAS.

All Weights stated are approximate

Customer's Name and Address cast on in raised letters, without extra charge, for orders of Twelve Manhole Covers of a size.

Prices.—Galvanized about double those of Fine Cast, as quoted herein.


Keyholes, in place of Sunk Lifts, same price. Keys for Lifting, 6/- per dozen

Gun-metal Screws fitted to Covers at 2/- each Screw.

Joints are made air-tight by filling the grooves with sand or grease.

# Street Gulleys and Gratings

No. C4274. Road Manhole Cover




Fitted with Wood Blocks,  
39/- each.

With Solid Cast-iron Top,  
36/- each.

Size at top, 1 ft. 9 ins. diameter.


No. C1145. Heavy Street Grating, Hinged




Frame.	Flange.	Depth.	Prices. Each.
9 x 9 ins.	13 x 13 ins.	2 1/2 ins.	5/3
10 x 10 "	13 1/2 x 13 1/2 "	3 1/8 "	6/6
12 x 12 "	17 x 17 "	4 "	15/-
13 x 13 "	15 1/2 x 16 1/2 "	4 1/2 "	12/9
14 x 12 "	18 1/2 x 16 "	4 1/2 "	12/9
14 x 14 "	21 1/2 x 21 1/2 "	6 "	22/6
16 x 16 "	23 1/2 x 23 1/2 "	6 "	27/9
16 x 18 "	22 x 24 "	6 "	28/6
18 x 18 "	25 1/2 x 25 1/2 "	6 "	40/6
24 x 17 "	30 x 23 "	6 "	46/6

## THE "CALEDONIAN" STREET GULLEY, Double Trapped, with Sludge Box


No. C4716. With Bottom Outlet



SECTION.



No. C4717. With Side Syphon Outlet



Sizes Inches.	Weights. Cwts. Qrs. Lbs.	Price, 10/6 each.
10 x 7	0 1 7	12/9
11 x 7 1/2	0 2 0	18/-
13 1/2 x 10	0 3 4	33/-
18 x 12	1 2 0	51/-
20 x 15	2 1 21	73/6
21 x 16	3 2 14	102/-
30 x 18	5 0 0	

Sizes. Inches.	Weights. Cwts. Qrs. Lbs.	Price, 12/9 each.
10 x 7	0 1 14	16/6
11 x 7 1/2	0 2 15	22/6
13 1/2 x 10	0 3 21	36/9
18 x 12	1 2 16	55/6
20 x 15	2 2 14	78/-
24 x 16	3 3 7	108/-
30 x 18	5 1 0	



No. C6407. Channel Grates and Frames

Unhinged.


Sizes, ..	8 x 4 1/2	8 x 8 ins.
Prices, ..	2/-	3/- each.



No. C1146. Channel Grates and Frames

Hinged.

Sizes, ..	6 x 6	7 x 7	8 x 8	9 x 9	10 x 10	12 x 12 ins.
Light, ..	1/10	2/3	2/9	3/3	3/9	5/6 each.
Heavy, ..	2/6	3/-	3/6	4/6	5/3	7/6 "



No. C1144.

Garden Grates and Frames

4	5	6	7	8	9	10	12 ins. sq.
9d	1-1/4	1/9	2/3	3/4	4/1	6/3	each.

Flat same prices.


No. C4151.



Drain Grates, Round or Square No. C4152.

Sizes, ..	4	5	6	7	8 ins.
Prices, ..	4 1/2d.	6d.	7 1/2d.	9d.	1/- each.

Sizes, ..	0	10	11	12 ins.
Prices, ..	1/3	1/6	2/-	2/3 each.



Dished.

No. C5998.

Wrought-iron  
Gratings

(London School  
Board Pattern).  
Galvanized.


Inches.	Prices, Each.
6 x 6 ..	9/-
9 x 9 ..	12/-
12 x 12 ..	15/-

Larger sizes supplied  
at proportionate  
cost.

No. C1463. Step Irons for Manholes



No. C1461.




No. C1463.	About 15 ins.	Cast-iron U pattern,	18/- per dozen.
" C1463.	" 15 "	Galvanized,	33/- "
" C1461.	" 12 "	Wrought-iron, U pattern,	30/- "
" C1461.	" 12 "	Painted,	48/- "
" C1461.	" 12 "	Galvanized,	48/- "


# Roof Lights

PAINTED FRENCH GREY


No. C1025.  
SKYLIGHT to open.



No. C4342.  
SKYLIGHT, with Quadrant Opener.



No. C1030. DEADLIGHT  
Does not open.




No. C4351.  
CORRUGATED CAST-IRON ROOFLIGHTS  
3-INCH CORRUGATIONS.



These are the only satisfactory Skylights for Corrugated Roofs. They are strong and substantial, and effectively keep the rain. The corrugated part and the under portion of the light is cast in one piece, so that there are no leaky joints.

Daylight	Width,	14	16	16	20	20	24	in
Sizes,	Height,	20	24	30	30	36	36	
No. C4351. To Open,		13/6	15/-	16/6	21/-	27/-	28/6	e
" C4352. Dead,		9/-	10/6	13/6	16/6	21/-	24/-	
does not open,								

No. C4353. DEADLIGHT  
CONTINUOUS.



Made in Plates to fit together, with 5-inch margin top and bottom; 4-inch end margins; Astragals, 12 inch centres.

## PRICES.

Daylight Sizes.		No. C1025.	No. C1030.
Width.	Height.	Skylight.	Deadlight
8 inches.	10 inches.	6/-	4/- each.
10 "	14 "	7/-	4 6 "
12 "	16 "	8/-	5 - "
14 "	20 "	8/6	5/6 "
16 "	24 "	9/6	6/6 "
18 "	24 "	11/3	7/9 "
18 "	30 "	13/-	9/- "
20 "	30 "	14/-	9/6 "
24 "	36 "	18/-	12/- "
30 "	36 "	22/-	15/6 "
30 "	42 "	24/-	16/6 "
36 "	42 "	32/-	21/- "
36 "	48 "	34/6	23/- "

There are wide margins beyond the sizes enumerated above.

No. C4342 is extra on price of No. C1025 Skylight as follows: -

Pulley Attachment fitted, 2/- each.

Patent Opener (Leggots' System).


Quadrant.	Opens.	Suitable for Rooflights	Prices.
12	10 inches.	up to 16 x 24 inches.	6/- each.
16	15 "	" " 24 x 36 "	7/- "
21	18 "	" " 36 x 48 "	10/- "

Daylight Sizes. -Length of Astragals, 30 36 48 54 60 66 inches.  
Measured over Astragals. .. 4/- 5/- 6/- 7/- 8/- 9/- per ft. r  
End Pieces, .. 4/- 5/- 6/- 7/- 8/- 9/- each.  
Thus a complete Light, 60 30 ins. in Clear Opening, costs-  
5-foot run at 4/- per foot, .. .. 21 0 0  
2 End Pieces at 4/- each, .. .. 0 8 0  
21 8 0



# Cast-Iron Window Sashes

All the sizes enumerated below are kept in stock ready for immediate despatch, either at our Country Works or London Stores.



No. C 1263. Measured over all.

Can be supplied in the following sizes, with Casement :—

Width, .. .. .	24	30	36	36	40	42	42	45	48	51	54	60	66	72 inches.
By Heights, .. .. .	36	48	36	48	48	42	48	48	48	48	48	48	48	48 "
" .. .. .	45	60	45	60	60	52 1/2	60	60	60	60	60	60	60	60 "
" .. .. .	54	72	54	72	72	63	72	72	72	72	72	72	72	72 "
" .. .. .	63		63	84	84	73 1/2	84	—	84	84	84	84	84	84 "
" .. .. .	72		72	—	—	—	—	—	96	—	96	96	96	96 "
Pane Sizes about														
Height, .. .. .	9	12	9	12	12	10 1/2	12	12	12	12	12	12	12	12 "
Width, .. .. .	6	7 1/2	6	9	10 1/2	7	10 1/2	11 1/2	8	12 1/2	9	10	11	12 "

No. C 1266. Measured over all.


Can be supplied in the following sizes, with Casement :—

Width, .. .. .	18	24	30	36	36	42	42	48	54	60 inches.
By Heights, .. .. .	32	39	51	54	90	52 1/2	64	60	63	66 "
" .. .. .	39	48	—	66	—	63	78	72	75	78 "
" .. .. .	—	—	—	—	—	73 1/2	—	84	87	90 "
" .. .. .	—	—	—	—	—	—	—	99	102	102 "
Pane Sizes about										
Height, .. .. .	7 1/2	9	12	12	12	10 1/2	15	12	12	12 "
Width, .. .. .	4 1/2	6	7 1/2	9	9	7	9	8	9	10 "

Price, 1/6 per superficial foot.

The pane sizes enumerated are approximate only. We can supply Cut Squares of any class of Window Glass to fit accurately the apertures of either of the above.

## Circular Cast-Iron Windows



No. C 7261. To open.

Diam., 12	18	24	30	36	39	42	48	51	54	60 ins.
Prices, 10/9	16/6	22/-	27/-	33/-	39/-	44/-	55/-	66/-	77/-	ea.

No. C 7262. Does not open.


Diam., 12	18	24	30	36	39	42	48	51	54	60 ins.
Prices, —	8/9	13/6	19/6	26/6	—	33/-	—	—	—	ea.

No. C 1204.



**BULL'S EYE WINDOW**

19 ins. diam., Price, 13/6

24 "	"	"	16/6
32 "	"	"	21/-



## Wrought-Iron Window Sashes



Detail of  
Wrought-iron  
Sash.

Made to Customers' dimensions in 1½ inch **Moulded Mitred Bars and Frames.**

PRICES for Sashes, with square heads, each of 16 feet minimum superficial area :—

Pane Sizes about :—									
Height, .. .. .	15	13	12	11	10 inches,				
Width, .. .. .	12	11	10	9	8				
Prices, .. .. .	1/4½	1/6	1/7½	1/10½	2/1¼ per foot super.				

Camber Head, 1/8 each extra.      Semi-circular Head, 7/- each extra.

Rectangular Swing Casement (for two or four panes), with Eves for Cord, fitted, 20/- each extra.

The pane sizes enumerated are approximate only. We can supply Cut Squares of any class of Glass to fit accurately the apertures of above.

**Drawings and Prices for Wrought-iron Sashes and Casements for any purpose forwarded upon receipt of details of requirements.**

## Cast-Iron Cottage Casement Windows

No. C 7291.



Heights, ..	42	36	Inches.
Widths, ..	19	27	"
Prices, ..	16/6	17/3	each.

No. C 7292.



Heights, ..	35	36	45	26	Inches.
Widths, ..	18½	19	18	22	"
Pane Sizes—	Height, 9	9	9	12½	"
	Width, 6	6	6	7	"
Prices, ..	7/6	7/6	10/-	9/6	each.

No. C 7293.



Height, ..	35	Inches.
Width, ..	18	"
Price, ..	7/6	each.


GLASS EXTRA.

If made to open, and fitted with two Iron Butt Hinges and Cockspur Fastener, 5/6 each extra.

# Pavement Lights, Cellar Flaps and Lenses

## PAVEMENT LIGHTS

No. C 7106. Glazed with No. CL 5 4 x 3 inch Lenses.



PATTERN SIZES, measured over Frame, Rabbet Flange 1 1/4 inches underneath.

Lengths,	13 1/2	18 1/2	22 1/2	27 1/2	32 1/2	36 1/2	41 1/2	45 1/2	50 1/2	55 1/2	60 1/2	64 1/2	69 1/2	73 1/2	78 1/2	82 1/2	87 1/2	92 1/2	inches.
Widths,	11 1/2	13 1/2	15 1/2	17 1/2	19 1/2	21 1/2	23 1/2	25 1/2	27 1/2	29 1/2	31 1/2	33 1/2	35 1/2	37 1/2	39 1/2	41 1/2	43 1/2	45 1/2	"

NOTE. Any intermediate size can be made: to obviate delay pattern sizes should be adopted.  
Either of the lengths enumerated can be worked in conjunction with either of the widths stated.

Glazed with 4 x 3 inch Nos. CL 1 and CL 7 Lenses alternately.	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	8/- per foot super.
" " 4 x 3 " " No. CL 5 Lenses entirely,	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	8 - " "
" " 4 x 3 " " CL 8 " " " "	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	6/- " "
" " 4 x 3 " " CL 7 " " " "	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	5/9 " "
" " 4 x 3 " " Rough Cast Plate " " " "	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	5/3 " "

## FOLDING CELLAR FLAPS

No. C 4842.

Glazed with No. CL 7 4 x 3 inch Lenses.



WITH ALL-ROUND GUTTER FRAME.

PATTERN SIZES, measured over Frames, with all-round Gutter Frame: 1 1/4 inch Flanges, underneath.

Lengths,	38 1/2	43 1/2	48 1/2	52 1/2	57 1/2	61 1/2	66 1/2	71 1/2	75 1/2	-	-	-	-	-	-	-	-	-	inches.
Widths,	30 1/2	33 1/2	36 1/2	39 1/2	42 1/2	45 1/2	48 1/2	51 1/2	54 1/2	57 1/2	60 1/2	63 1/2	66 1/2	69 1/2	72 1/2	75 1/2	78 1/2	81 1/2	"

NOTE. Any intermediate size can be made: to obviate delay pattern sizes should be adopted.  
Either of the lengths enumerated can be worked in conjunction with either of the widths stated.

Prices include Guard Bar and Bolt.

Glazed with 4 x 3 inch Nos. CL 1 and CL 7 Lenses alternately.	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	11/- per foot super.
" " 4 x 3 " " No. CL 5 Lenses entirely,	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	11/- " "
" " 4 x 3 " " CL 7 " " " "	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	10/- " "
" " 4 x 3 " " CL 8 " " " "	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..	10/- " "

Can also be supplied with Open Back, Gutter Frame and Loose Back Bar at same prices.

## LENSES

FOR PAVEMENT LIGHTS AND CELLAR FLAPS.

No. CL 1. Prismatic Lens



Price, 10d. each.

No. CL 5. Prismatic Lens



Price, 8d. each.

No. CL 7. Convex Lens



Price, 5d. each.

No. CL 8. Convex Lens




Price, 5d. each.

Special Prices given for quantities.

# Stall Board and Circular Pavement Lights, and Cellar Flaps


Design No. C 5997.

No. CL 14.  
Prismatic Lens




Price, 10d. each.

No. CL 15.  
Prismatic Lens




Price, 10d. each.



Design No. C 5999.

No. C 5997. **Cast-iron Frame, Flanges, 1½ inches at back, glazed with either No. CL 14 or No. CL 15 Prismatic Lenses, 5¼ × 5¼ inches**

Heights in Inches.	By Widths in Inches.
14	14
19½	19½
25½	25½
31½	31½
37½	37½
43½	43½
49	49



No. C 5999. **Cast-iron Frame, Flanges, 1½ inches at back, glazed with either No. CL 14 or No. CL 15 Prismatic Lenses, 5¼ × 5¼ inches.**

Heights in Inches.	By Widths in Inches.
15	15
20½	20½
24½	24½
32½	32½
38½	38½
44	44
49½	49½
55½	55½
61½	61½
67	67
72½	72½

NOTE.—Either of the heights enumerated can be worked in conjunction with either of the widths stated.  
Prices for either of above, 7/6 per foot super measured over all.

No. C 4844.

## Circular Pavement Light

Glazed with 4 × 3 inches.

Nos. CL 1 and CL 7 Lenses alternately.

Sizes, .. 18 24 30 36 ins diam.  
Prices, .. 21/- 36/- 57/- 81/- each.


No. CL 8 Lenses entirely

Sizes, .. 18 24 30 36 ins diam.  
Prices, .. 18/- 30/- 45/- 67/6 each.

No. CL 7 Lenses entirely

Sizes, .. 18 24 30 36 ins. diam.  
Prices, .. 16/- 28/- 43/6 63/- each.

Illustrations of Lenses shown on page 478.



No. C 4841.

## Improved Folding Cellar Flaps IN GUTTERED FRAMES.



Flaps can be supplied in either chequered Cast or Wrought Iron.

Price, complete with Guard Bar and Bolt, from 11/- per foot super.

# CRESTINGS

Drilled for Screwing to Wood, or to order with Batts for Leading into Stone. Prices given are for Pattern Lengths. Cutting to Plan, also Standards, are charged extra.

No. C 3796.



2½ inches high ; 36-inch lengths, .. .. Price, 9d per foot.

No. C 1977.



3 inches high ; 35-inch lengths, .. .. Price, 9d per foot.

No. C 1979.



5 inches high ; 34 inch lengths, .. .. Price, 10½d. per foot.

No. C 1981.



6 inches high ; 23 inch lengths, .. .. Price, 1 3 per foot.

No. C 1983.




7½ inches high ; 32-inch lengths, .. .. Price, 1 9 per foot.

No. C 1984.



9 inches high ;	33½ inch lengths,	.. ..	Price, 1 6 per foot.
14½ "	45½ "	.. ..	" 2 3 .. "
20 "	35 "	.. ..	" 3 6 .. "
24 "	48 "	.. ..	" 4 3 .. "

No. C 1987.



12 inches high ; 32-inch lengths, .. .. Price, 2 6 per foot.

No. C 3797.



3½ inches high ; 37½ inch lengths, .. .. Price, 1 3 per foot.

No. C 1978.



3½ inches high ; 34-inch lengths, .. .. Price, 10½d. per foot.

No. C 1980.




5½ inches high ; 30-inch lengths, .. .. Price, 1/- per foot.

No. C 1982.




6 inches high ; 32-inch lengths, .. .. Price, 1 6 per foot.

No. C 1986.



7½ inches high ; 30-inch lengths, .. .. Price, 1 9 per foot.

No. C 1985.



7½ inches high ; 32½-inch lengths, .. .. Price, 2/- per foot


No. C 3845.



15 inches high ; 48-inch lengths, .. .. Price, 3/- per foot


# CRESTINGS

Drilled for Screwing to Wood, or to order with Batts for Leading into Stone. Prices given are for Pattern Lengths. Cutting to Plan, also Standards, are charged extra.



No. C 3841.

12 inches high ; 43½-inch lengths, .. .. Price, 1/4½ per foot.  
Standards, 3/- each.



No. C 3847.

20 inches high ; 39½-inch lengths, .. .. Price, 3/6 per foot.  
Standards, 4/6 each.



No. C 3858.

27 inches high ; 40-inch lengths, .. .. Price, 4/3 per foot.



No. C 3862.


31 inches high ; 34½-inch lengths, .. .. Price, 6/- per foot.

No. C 3848.




21 inches high ; 36-inch lengths, .. .. Price, 4/6 per foot.

No. C 3846.



19½ inches high ; 44½-inch lengths, .. .. Price, 3/6 per foot.  
23½ .. .. 44 .. .. .. 4/3 .. ..



No. C 3850.

24 inches high ; 49-inch lengths, .. .. Price, 3/6 per foot.



No. C 3864.

29 inches high ; 45½-inch lengths, .. .. Price, 8/3 per foot.

# Finials and Weather Vanes

MADE WITH SCREW CAST IN FOR WOOD, OR TO ORDER WITH BATT FOR STONE.

No. C1206.



8½ ins. high.  
Arms, two ways, 1 1/3 each.  
" four " 2 3 "

No. C1207.




1 ft. 2½ ins. high.  
Arms, two ways, 2 each.  
" four " 3/6 "

No. C1804.



2 ft. high.  
Arms, two ways, 5 3 each.  
" four " 7/3 "

No. C1806.




3 ft. high.  
Arms, two ways, 14 3 each.  
" four " 21. "

No. C1809.




3 ft. 6 ins. high, 18 each.  
4 " 8 " " 21/ "

No. C1208.



1 ft. 10½ ins. high.  
Arms, two ways, 3 6 each.  
" four " 6. "

No. C1209.




2 ft. high.  
Arms, two ways, 4 10½ each.  
" four " 9/9 "

No. C3821.



Price, 9 - each.

No. C1803.




5 ft. 8 ins. high.  
Arms, four ways, .. 50 - each.

No. C3820.




2 ft. high.  
Arms, two ways, .. 15/- each.  
" four " .. 22/6 "

No. C3816.



3 ft. 3½ ins. high.  
Price, 18/- each.

No. C3818.



3 ft. high.  
Arms, two ways, 13 6 each.

No. C1210.



2 ft. 1 in. high.  
Arms, two ways, 4 6 each.  
" four " 9. "

No. C1802.



1 ft. 6 ins. high.  
Arms, two ways, 7/3 each.  
" four " 9. "

No. C3187.




1 ft. 6 ins. high.  
Arms, two ways, 6/9 each.  
" four " 9/9 "

No. C3819.




2 ft. 3 ins. high.  
Arms, two ways, 20 3 each.

No. C1211.




1 ft. 10 ins. high.  
Arms, two ways, 5/3 each.  
" four " 12/6 "

## Verandah Brackets




No. C 5766

Sizes. Weight. Price.  
42 x 36 ins. 105 lbs. each. 25/6



No. C 5767.

Sizes. Weight. Price.  
24 x 24 ins. 17 lbs. each. 4/6  
20 x 15 " 9 " " 3/-




No. C 5768.

Sizes. Weight. Price.  
22 x 22 ins. 23 lbs. each. 6/-  
32 x 30 " 42 " " 9/-  
45 x 36 " 77 " " 19/6  
54 x 48 " 189 " " 42/-



No. C 5769.

Sizes. Weight. Price.  
48 x 19 ins. 98 lbs. each. 24/




No. C 4823.

### Column and Brackets

Diam. 2½ ins. at Shaft.  
6 ins. at Base.

Height to top of Brackets.	Brackets.	Price p. set, as shown.
8 ft. 0 ins.	18 x 18 ins.	58/6
9 " 0 "	24 x 24 "	63/9
10 " 6 "	24 x 24 "	70/6




No. C 4824.

### Column and Brackets

Diam. 2½ ins. at Shaft.  
6 ins. at Base.

Height to top of Brackets.	Brackets.	Price p. set, as shown.
8 ft. 0 ins.	18 x 18 ins.	58/6
9 " 0 "	24 x 24 "	63/9




No. C 4825.

### Column and Brackets

Diam. 2½ ins. at Shaft.  
4½ ins. at Base.

Height to top of Brackets.	Brackets.	Price p. set, as shown.
7 ft. 6 ins.	18 x 24 ins.	39/9
8 " 0 "	18 x 24 "	42/-
8 " 6 "	18 x 24 "	43/6
9 " 0 "	18 x 24 "	46/6



No. C 4826.

### Column and Brackets


Diam. 3½ ins. to 2½ ins. at Shaft.  
5 ins. at Base.

Height to top of Brackets.	Brackets.	Price p. set, as shown.
7 ft. 6 ins.	20 x 29½ ins.	50/3
8 " 0 "	20 x 29½ "	51/9
8 " 6 "	20 x 29½ "	53/3
9 " 0 "	20 x 29½ "	57/-



# Ornamental Verandahs

No. C.4828.



No. C.4828.

Set of Ironwork for Verandah, 12 ft. wide  $\times$  3 ft. to 4 ft. projection, as shown, fitted ready for re-erection, prepared to receive wood beam and wood astragals for glass.

No. C.4828.

## VERANDAH SET

Comprises:—

- 3 Verandah Columns, 8 ft. 6 ins. high; with Entablatures.
- 3 pairs Brackets for same.
- 1 pair Brackets for wall.
- Frieze, 4½-in.  $\times$  3-in. Moulded Gutter, and Cresting for front and returns.
- 2 Terminals.


Price, £12 0 0 per set.

## Single Set

6 ft. wide; 4 ft. projection.

Price, £8 15 0 per set.


No. C.6676.



No. C.6676. Set of Ironwork for Verandah, 15 feet 9 inches wide over Pilasters  $\times$  6 feet projection  $\times$  2 feet high Roof  $\times$  9 feet 3 inches high to underside of Gutter as drawn; consisting of 5 Pilasters (3 Front and 2 Return); Spandrel Brackets, 4½  $\times$  3½ inch Moulded Gutter, Gutter Ornaments, 1½  $\times$  1½ inch T and L Iron for Roof; fitted ready for re-erection; prepared for Glass.


Price, £31 10 0 per set.

## Cast-Iron Porch or Door Canopies



No. C 6658. Set of Ironwork for Porch, 6 feet wide between centres of Brackets 3 feet 6 inches projection  $\times$  2 feet high Roof as drawn, consisting of 4 $\times$ 3 inch Moulded Gutter, 4 $\times$ 2 $\frac{1}{2}$  inch Angle Beam, 1 $\frac{1}{2}$  $\times$ 1 $\frac{1}{2}$  inch T and L Iron for Roof; fitted ready for re-erection; prepared to receive Glass, which is extra.

Price, .. .. . £11 8 0 per set.




No. C 6659. **DOOR PORCH** Can be made for Single or Double Doorways. Castings fitted ready for fixing in Brickwork, and drilled for screwing to Wood Beam.

Brackets, 24 $\times$ 24 inches, .. .. .	Price, 7/6 each.
9-inch Frieze, in 3 feet 6 inch lengths, .. .. .	„ 2/- per foot.
Corner or Centre Pediments, .. .. .	„ 2/6 each.


Prepared to receive Glass, which is extra.

# Balcony Railings



No. C 3912.


29½ ins. wide × 31½ ins. high, .. .. 6/- per foot.  
Can be made in various lengths.



No. C 3913.

37 ins. wide, centre to centre of Standards, × 36 ins. high over Standard, 22/- each  
49½ .. .. " .. " × 36 .. .. " 28/- ..  
60 .. .. " .. " × 36 .. .. " 30/- ..  
60 .. .. " .. " × 45 .. .. " 48/- ..  
Can be made in various lengths.

## No. C 6410. FINE CAST BALCONY RAILING




No. C 6410.

3 ft. high, with Wrought Top Rail.

SIZES:—Pilasters, 2 ft. wide; Panel, 2 ft. 2 ins. wide.  
Pilasters repeating at about 6 ft. 4 in. centres.  
Cut to plan, fitted ready for fixing.

Price, .. .. 8/- per foot run.  
Corner Standards, Square or Obtuse Angle, 7/6 each.

## No. C 6409. FINE CAST BALCONY RAILING



No. C 6409.

2 ft. 9½ ins. high, with Wrought Top and Bottom Rails.

SIZES:—Pilasters, 2 ft. wide; 1½ in. square cast bars; 4 in. centres.  
Pilasters repeating at about 5 ft. centres.  
Cut to plan, fitted ready for fixing.

Price, .. .. 9/9 per foot run.  
Corner Standards, Square or Obtuse Angle, 7/6 each.

# Balcony Railings


No. C 5723. FINE CAST BALCONY RAILING

3 ft. high, with Wrought-iron Top Rail. Pilasters repeating at about 7 ft. Centres.

Price, 7/6 per foot run.

Railing only, without Pilasters, 5/6 per foot run.

Corner Standards, to suit, 7/6 each.




No. C 5724. FINE CAST BALCONY RAILING

2 ft. 11 ins. high, with Cast Top Rail; Wide Pilasters, 1 ft. 3 ins. wide; Narrow Pilasters, 8 ins. wide; Panel, 2 ft. 8 ins. wide.

Price, 8/- per foot run.

Railing only, without Pilasters, 4/9 per foot run.

Corner Standards, to suit, 8/- each.




No. C 5725. FINE CAST BALCONY RAILING

2 ft. 7 ins. high, with Wrought-iron Top Rail.

Price, 8/6 per foot run.


Corner Standards, to suit, 12/- each.



# Fire Escape Staircase

No. C 6400.

DESIGN APPROVED BY THE LONDON COUNTY COUNCIL.




Stock Sizes, .. .. .	..	2 ft. 6 ins.	3 ft. 0 ins.	3 ft. 6 ins.	4 ft. 0 ins. wide.
Prices per Step, fitted ready for re-erection, .. ..	..	22/-	24/-	25/6	28/6

Landings extra, according to size.

Estimates for supplying and fixing on site, in the London district, any class of Cast and Wrought Iron Staircases  
furnished upon application.

## Straight Stairs



No. C 6417. Light Stair without Risers. Treads, 8 inches wide.  
Fitted ready for re-erection.

---

Stock Sizes,	..	..	..	..	..	..	2 ft. 0 ins.	2 ft. 6 ins.	3 ft. 0 ins. wide.
Prices, Hand Rail both sides,	..	..	..	..	..	..	15/6	17/-	18/- per step.
„ „ one side only,	..	..	..	..	..	..	13/6	15/-	16/3 „


Landings extra, according to size.

---

**Estimates for supplying and fixing on site, in the London district, any class of Cast and Wrought Iron Staircases  
furnished upon application.**

# Spiral Stairs

## WITH NON-SLIPPING TREADS



PLAN OF  
TREAD.

### STOCK SIZES.

Diameter.		Risers.
Ft.	Ins.	Ins.
3	6	7½
4	0	to
4	6	8½
5	0	

Right or Left Hand.

Supplied with one or two  
Balusters on each Step.

No. C 6416. Spiral Stairs with Wrought Handrail. Right or Left Hand Wheeling.  
All fitted ready for re-erection.


Stock Sizes, .. .. .	3 ft. 6 ins.	4 ft. 0 ins.	4 ft. 6 ins.	5 ft. 0 ins. diam.
Prices, with one Baluster on each Step, .. .. .	13/-	14/6	15/6	16/6 per step.
.. .. two Balusters .. .. .	15/-	16/6	17/6	18/6 ..

Quarter-circle Landing with Guard Rail, 40/6 extra.

Guard Rail and Balusters round Well-hole, 3/9 per foot.

Estimates for supplying and fixing on site, in the London district, any class of Cast and Wrought Iron Staircases  
furnished upon application.

## Spiral Stairs



No. C 3811. Spiral Stairs with Wrought Handrail. Right or Left Hand Wheeling.  
All fitted ready for re-erection.

Diam. A to B, 3 ft. 6 ins. ; Rise per Step, 8 to 9 ins. ; Number of Balusters on each Step, 1												.. Price, 15/9 per step.			
..	..	4	..	0	..	..	8	..	9	..	1	..	..	16/6	..
..	..	4	..	6	..	..	8	..	9	..	2	..	..	19/6	..
..	..	5	..	0	..	..	8	..	9	..	2	..	..	21/-	..
..	..	5	..	6	..	..	8	..	9	..	2	..	..	22/6	..
..	..	6	..	0	..	..	8	..	9	..	2	..	..	24/-	..

Quarter-space Landing, 39/- extra.

Railing round Well-hole at top, 54/- extra.



# Balusters and Newels

Made with Screws or Drilled Plates for Wood or Iron; or Batts for Stone, as required, to order.

No. C 3765.



Height. Width. Price.  
36 in. 5 in. 1/9 ea.

No. C 6770.




Height. Width. Price.  
30 in. 7 1/2 in. 1/10 1/2 ea.

No. C 6771.




Height. Width. Price.  
38 in. 5 in. 2/- ea.

No. C 6772.




Height. Width. Price.  
34 1/2 in. 7 1/2 in. 2/- ea.

No. C 6773.



Height. Width. Price.  
36 in. 9 1/2 in. 3/3 ea.

No. C 6774.



Height. Width. Price.  
32 in. 6 1/2 in. 2/3 ea.

## NEWEL BARS.

No. C 6775.



Size. Price.  
36 x 3 1/2 in. 6/3 each.  
39 x 3 1/2 in. 6/6 "

No. C 6776.



Size. Price.  
36 x 3 1/2 in. 4/9 each

No. C 6777.



Size. Price.  
31 x 3 in. 4/6 each.  
34 x 3 in. 4/9 "

No. C 6778.



Size. Price.  
36 x 5 in. 5/3 each.

No. C 6779.



Size. Weight.  
38 1/2 x 4 1/2 in. 84 lbs.  
21/- each.

No. C 6780.




Size. Price.  
35 x 3 in. 5/- each.

# Patent Folding Gates

For Main Entrances, Show Windows, Lifts, &c.

DESIGN No. C 4277.

Showing Gate when not required to go full height of opening. Spearhead pattern, with hinged folding tracks, made in  $\frac{1}{4}$ -inch,  $\frac{3}{8}$ -inch, and  $\frac{1}{2}$ -inch sections, according to size. Also to lift away. In halves or one piece to suit any doorways.



Prices, complete with hangings, best quality locking arrangements, ready for fixing.


Sections.

$\frac{1}{4}$ inch, ..	5/3 per ft. super.
$\frac{3}{8}$ " ..	6/0 " "
$\frac{1}{2}$ " ..	7/6 " "

Measurements all reckoned by height to top of spearhead and width of Gate when fully extended.

DESIGN No. C 4278.

Showing Gate the full height of opening, made in various strengths to suit all apertures, with T fixed top tracks, and recessed channel or hinged folding bottom tracks, as required.



Prices, complete with tracks, locks, latches, &c.

Sections.

$\frac{1}{4}$ inch, ..	3/0 per ft. super.
$\frac{3}{8}$ " ..	4/6 " "
$\frac{1}{2}$ " ..	5/3 " "

Measurements all reckoned by height to top and width of Gate when fully extended.

# Gates and Railings

METAL READY FOR ERECTION, TO DESIGNS SHOWN ON THE FOLLOWING PAGES :-

The data in this Section is compiled with the object of affording at a glance to a prospective purchaser of Gates and Railings definite and inclusive prices ; thus obviating the uncertainty in calculating his cost, by computing same from the weights of the castings at price per cwt. ; for :-

- (a) **Gate Sets.** Single and double for piers or dwarf walls.  
(b) **Carriage Entrance Gates** for piers or independent fixing.

- (c) **Gates and Railings** complete with and without coping for specified frontages.  
(d) The requisite extra for extended frontages.

## SPECIFICATION.

**A frontage of 16 ft. consists of**—(c) One Gate fitted with Latch, one Gate Socket, Hanging Standard with Clip, Latching Standard, one pair of Braces and sufficient Panelling, and, when shown in drawing, wrought-iron horizontal bars.

**A frontage of 32 ft. consists of** (f) Two Gates, handed, fitted with Latches, two Gate Sockets, one double hanging Pilaster fitted with Clips, two Latching Standards, two pairs of Braces and sufficient Panelling, and, when shown in drawing, wrought-iron horizontal bars.

**SINGLE GATE SETS consist of**—(g) One Gate fitted with Latch, Gate Socket, hanging Batt for Brick Pier, fitted with Clip and Latching Batt for Brick Pier ; or (h) One Gate fitted with Latch, Gate Socket, hanging Standard fitted with Clips, Latching Standard and pair of Braces.

**DOUBLE GATE SETS consist of**—(j) Two Gates, handed, fitted with Latches, Gate Sockets, double hanging Pilaster, two Latching Standards, and two pairs of Braces.

**CARRIAGE ENTRANCE GATES consist of** (k) One pair of Gates, fitted with Striking Plate, Latch or Lock, Slip Bolt and Gate Stop, Gate Sockets and Hangings for Brick Piers ; or (l) One pair of Gates, fitted with Striking Plate, Latch or Lock, Slip Bolt and Gate Stop, Gate Socket and heavy Hanging Standards fitted with Clips.

**BUILDING DIMENSIONS.** The Gate spaces enumerated are those for (h) Single Gate with Standards ; (j) Double Gates with Pilaster and Standards ; (k) Carriage Entrance Gates for Brick Piers. Local requirements may necessitate the deviation from the measurements stated ; it is therefore advisable to have the "sets" on site to ensure accuracy in the construction of the brickwork.


**EXTRAS.** Division Fencing, consisting of two wrought-iron horizontal bars  $\frac{1}{2}$ -in. diameter, and cast-iron standard with plate base supplied thus :-

6-ft. set, two horizontal bars and one standard,	7/6 per set.
10-ft. set, " " "	8/- "
12-ft. set, two horizontal bars and two standards,	12/9 "
16-ft. set, " " "	16/6 "

Bent Panels, Corner Standards, Ramps, Circled Corner Pieces, and any alterations from specified details are extra to any pattern railing. We shall be pleased to estimate to plans deviating in any details from foregoing description.


**FIXED RAILING AT SITE.**—Having a staff of experienced men we undertake for the trade the erection of any of our designs within twenty-five miles of the Tower, London. Estimates will be furnished, inclusive of supplying the materials and labour, upon receipt of details of actual requirements.

No. C 7009. **OCTAGON** No. C 7100. **ROUND (He-vy)**



## IRON POSTS OR PILLARS

Height to under Collar, .. .. .	43	46	49	55	60 inches.
No. C 7009. No base, .. .. .	21/9	22/-	23/6	26/-	30/- each.
" C 7009. With base .. .. .	28/-	28/-	30/6	35/6	41/- "
" C 7100. No base, .. .. .	21/9	22/-	23/6	26/-	30/- "
" C 7100. With base, .. .. .	29/-	30/6	34/-	37/-	- "
Hinge Brackets, 1/9 each extra.					Holes for Fencing Bars, 8d. each hole extra.





No. C 4095.  
**GATE STOP,**  
fitted with Hinged  
Cover.

Sizes.	
4 x 3 ins.,	1/9 each.
5 x 4 " "	2/6 "
6 x 5 " "	3/9 "

No. C 5691. **GATE CATCH**

To screw to wood.

Price, 2/6 each.



No. C 5692.  
**GATE CATCH**  
for Stone.  
Price, 5/- each.

No. C 3894.  
**DIVISION**  
**STANDARDS**

With Sole Plate, two  
holes, 42 ins. high,  
2/6 each.

Round wrought-iron  
horizontal bars, in  
cut lengths :-

$\frac{1}{2}$ -in.	$\frac{1}{2}$ -in. diam.
3d.	5d. per ft.

No. C 6036. **GATE STOP**  
Self-acting.

Sizes.	
$3\frac{1}{2} \times 3\frac{1}{2}$ ins.,	3/3 ca.
$7\frac{1}{2} \times 6\frac{1}{2}$ " "	4/6 "
$10\frac{1}{2} \times 7\frac{1}{2}$ " "	9/- "
$12 \times 8\frac{1}{2}$ " "	11/6 "



No. C 3893. **IRON COPING**

9-in. Flat Top O.G. in stock lengths, 1/6 per foot.



## Cast-Iron Railing Bars



No. C 0033.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 48 ins.  
Price, 14/- 17/6



No. C 0034.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 42 48 ins.  
Price, 14/- 17/6



No. C 0035.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 ins.  
Price, 16/6



No. C 0036.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 ins.  
Price, 18/6



No. C 0037.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 30 48 ins.  
Price, 14/- 16/6



No. C 0038.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 48 ins.  
Price, 14/- 17/6



No. C 0039.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 48 ins.  
Price, 14/- 18/6 per doz.



No. C 0040.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 ins.  
Price, 21/-



No. C 0041.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 ins.  
Price, 18/6



No. C 0042.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 46 ins.  
Price, 14/-



No. C 0043.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 ins.  
Price, 23/-



No. C 0044.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 48 50 ins.  
Price, 14/- 18/6 28/-




No. C 0045.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 40 ins.  
Price, 18/6



No. C 0046.  
Size,  $\frac{3}{4}$  in. diam.  
Length, 48 ins.  
Price, 15/6 per doz.

### No. C 3918. CAST-IRON BAR RAILING



Opening for Single Gate, 4 feet; Double Gate, 8 feet.

Metal for 16-feet Frontage, consisting of—  
Gate fitted with Latch, pair of Standards with Braces, Railing Bars and  $2 \times \frac{1}{2}$  inch Top Rail, Punched  
6-inch Centres, .. .. .  
Do., do., .. with Iron Coping, .. .. .  
Extra Panelling, .. .. .  
„ „ and Coping, .. .. .

£4 4 0 per set.  
5 16 0 „  
0 3 6 per foot.  
0 6 0 „

With Dog Bars.  
£6 8 0 per set.  
8 2 0 „  
0 6 10 per foot.  
0 9 6 „

Gates can be made with any Pattern Bars shown above.

## Gates and Railings

No. C 1107. "STRING RING" PATTERN



Space required for Single Gateway, 3 ft. 6 ins.; for Double Gateway, 7 ft. 8 ins. Height from Gate Stone to top of Coping, 1 ft. 7½ ins.

METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage, .. .. .	16 ft.	32 ft.
Castings, .. .. .	£2 12 0	£5 6 0 per set.
Coping, .. .. .	1 0 0	2 0 0 „
	£3 12 0	£7 6 0 per set.

Single Gate Sets—		
With Batts, .. .. .	£0 18 9 per set.	
„ Standards, .. .. .	1 2 6 „	

BEYOND ABOVE FRONTAGES: Panelling and Bars, .. .. .	2/- per ft. run.
Coping, .. .. .	1/9 „ „

## Carriage Entrance Gates

No. C 1107. "STRING RING" PATTERN

TO MATCH ABOVE.




ONE PAIR OF GATES, fitted with Striking Plate, Drop Bolt and Lock, Gate Stop, Gate Sockets:—

With Hangings for Brick Piers; space required, 7 ft. 6 ins.. .. .	Price, £5 0 0 per set
„ Hanging Standards; space required, 8 ft. 9 ins.. .. .	„ 5 5 0 „

# Gates and Railings

No. C 1092. "BUTTERFLY" PATTERN



Space required for Single Gateway, 3 ft. 6 ins.; for Double Gateway, 7 ft. 6 ins.  
Height from Gate Stone to top of Coping, 2 ft.

METAL READY FOR ERECTION. For General Specification, see page 494.


Frontage, ..	..	..	16 ft.	32 ft.	Single Gate Sets--	
Castings, ..	..	..	£2 13 6	£5 10 0 per set.	With Batts, ..	£1 0 0 per set.
Coping, ..	..	..	1 0 0	2 0 0 "	" Standards, ..	1 8 9 "
			£3 13 6	£7 10 0 per set.		

BEYOND ABOVE FRONTAGES—Panelling and Bars, .. .. . 2/1½ per ft. run.  
Coping, .. .. . 1/9 " "

No. C 6002. "BUTTERFLY" PATTERN

EXTRA HEAVY CASTINGS.

This makes a very substantial railing fixed on either Stone or Cement Coping.



Space required for Single Gateway, 3 ft. 6 ins.; for Double Gateway, 7 ft. 6 ins.


METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage, ..	..	..	16 ft.	32 ft.	Single Gate Sets--	
Castings, ..	..	..	£2 16 6	£5 14 6 per set.	With Batts, ..	£1 4 9 per set.
Coping, ..	..	..	1 0 0	2 0 0 "	" Standards, ..	1 13 0 "
			£3 16 6	£7 14 6 per set.		

BEYOND ABOVE FRONTAGES—Panelling, .. .. . 2/- per ft. run.  
Coping, .. .. . 1/9 " "

# Gates and Railings

No. C 6000. "STAMFORD" PATTERN



Space required for Single Gateway, 3 ft. 6 ins.; for Double Gateway, 8 ft. 0 ins.

METAL READY FOR ERECTION For General Specification, see page 494.

Frontage, .. .. .	10 ft.	32 ft.
Castings, .. .. .	£2 10 0	£5 4 0 per set.
Coping, .. .. .	1 0 0	2 0 0 "
	£3 10 0	£7 4 0 per set.

Single Gate Sets—

With Batts, .. .. .	£1 0 0 per set.
„ Standards, .. .. .	1 8 0 ..

Beyond above Frontages


Panelling, .. .. .	2/- per ft. run.
Coping, .. .. .	1/9 " "

CARRIAGE ENTRANCE GATES, TO MATCH ABOVE.

Space required, 7 ft. between Piers.

With Batts for Brick Piers, .. .. .	£3 16 0 per pair.
„ Hanging Standards, .. .. .	4 0 0 „

No. C 6140. BURR WALL RAILING



Opening for Gate, 3 ft. between Piers.

BURR WALL PANEL, BARS AND GATE TO MATCH—

PANEL, 16 x 16 ins. cored for 1/2-in. square Wrought-iron Horizontal Bars, with Batt for Brick Wall, .. .. .	5/3 each.
BARS in cut lengths, .. .. .	6d. per ft.
GATE SET to Match, 33 1/2 ins. wide x 48 ins. high, fitted with Thumb Latch, Gate Socket, Hanging and Latching Batts for Brick Piers, .. .. .	21/- per set.
GATE SET, same Specification, but fitted with Hanging and Latching Pieces for Wood Posts, .. .. .	21/- "

# Gates and Railings

## No. C 4810. THE "BEAULIEU" PATTERN



Height of Wall from Gate Stone to top of Coping, 2 ft. Opening for Single Gateway, 3 ft. 9 ins.,  
for Double Gateway, 7 ft. 9 ins.

METAL READY FOR ERECTION. For General Specification, see page 494.			
Frontage, .. .. .	16 ft.	32 ft.	Single Gate Sets
Castings, .. .. .	£2 12 6	£5 7 0 per set.	With Batts, .. .. .
Coping, .. .. .	1 0 0	2 0 0 ..	.. Standards, .. .. .
	£3 12 6	£7 7 0 per set.	
CARRIAGE ENTRANCE GATES, TO MATCH ABOVE.			
Space required, 7 ft. 6 ins. between Piers.			
Beyond above Frontages			With Batts for Brick Piers, .. .. .
Panelling, .. .. .		1 10 1 per ft. run.	.. Hanging Standards, .. .. .
Coping, .. .. .		1/9 .. ..	
Also made with Extra Heavy Standards, 6/- extra per pair.			

Also made with Extra Heavy Standards, 6/- extra per pair.

## No. C 4276. THE "LOUIS" PATTERN




Height of Wall from Gate Stone to top of Coping, 1 ft. 9 ins.; space required for Single Gateway, 3 ft. 7 ins.; for Double Gateway, 8 ft.

METAL READY FOR ERECTION. For General Specification, see page 494.									
Frontage, .. .. .	16 ft.	32 ft.							
Castings, .. .. .	£2 19 6	£5 19 0 per set.	Single Gate Set .. .. .						
Coping, .. .. .	1 0 0	2 0 0 "	With Batts, .. .. . £1 4 9 per set.						
	£3 19 6	£7 19 0 per set.	" Standards, .. .. . 1 11 6 "						
BEYOND ABOVE FRONTAGES—Panelling, .. .. . 3/- per ft. run.									
		Coping, .. .. .	1/9 " "						



# Gates and Railings

No. C 4271. THE "MARYLAND" PATTERN



Height of Wall from Step to top of Coping, 1 ft. 10½ ins. Opening for Single Gateway, 3 ft. 8 ins.; for Double Gateway, 8 ft. 2 ins.

METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage, .. .. .	16 ft.	32 ft.
Castings, .. .. .	£2 17 0	£5 18 6 per set.
Coping, .. .. .	1 0 0	2 0 0 "
	£3 17 0	£7 18 6 per set.

Single Gate Sets ..

With Batts, .. .. .	£1 1 0 per set.
.. Standards, .. .. .	1 12 6 "


BEYOND ABOVE FRONTAGES—Panelling, .. .. .	1/10½ per ft. run.
Coping, .. .. .	1/9 " "

Also made with Extra Heavy Standards, 7/6 extra per pair.

## Carriage Entrance Gates

No. C 4271. THE "MARYLAND"

TO MATCH ABOVE.




ONE PAIR OF GATES, fitted with Striking Plate, Drop Bolt and Lock, Gate Stop, Gate Sockets:—

With Hangings for Brick Piers; space required, 8 ft. 3 ins., .. .. .	Price, £7 10 0 per set.
.. Hanging Standards; space required, 9 ft., .. .. .	.. 8 17 0 "

# Gates and Railings

No. C6035. THE "MEDALLION" PATTERN



Space required for Single Gateway, 3 ft. 4½ ins.; for Double Gateway, 7 ft. 6 ins. Height from Gate Stone to top of Coping, 2 ft. 2 ins.

METAL READY FOR ERECTION.				
	16 ft.	32 ft.		
Frontage, .. .. .	16 ft.	32 ft.		
Castings, .. .. .	£3 0 0	£6 4 0 per set.		
Coping, .. .. .	1 0 0	2 0 0 ..		
	£4 0 0	£8 4 0 per set.		

Single Gate Sets—

With Batts, .. .. .	£1 4 0 per set
Standards, .. .. .	1 14 0 ..

BEYOND ABOVE FRONTAGES	Panelling, .. .. .	2/4 per ft. run.
	Coping, .. .. .	1/9 .. ..

No. C6047. THE "CLOVA" PATTERN



Space required for Single Gateway, 3 ft. 6 ins.; for Double Gateway, 7 ft. 6 ins. Height from Gate Stone to top of Coping, 2 ft.

METAL READY FOR ERECTION.				
	16 ft.	32 ft.		
Frontage, .. .. .	16 ft.	32 ft.		
Castings, .. .. .	£3 0 0	£6 4 0 per set.		
Coping, .. .. .	1 0 0	2 0 0 ..		
	£4 0 0	£8 4 0 per set.		


Single Gate Sets—

With Batts, .. .. .	£1 3 0 per set.
Standards, .. .. .	1 12 0 ..

BEYOND ABOVE FRONTAGES—	Panelling, .. .. .	2/4 per ft. run.
	Coping, .. .. .	1/9 .. ..

## Gates and Railings

No. C 5716. THE "EARLHAM" PATTERN



Space required for Single Gateway, 3 ft. 6 ins. ; for Double Gateway, 7 ft. 6 ins. Height from Gate Stone to top of Coping, 1 ft. 6 ins.

METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage.	..	..	..	..	16 ft.	32 ft.
Castings,	..	..	..	..	£3 6 0	£6 14 0 per set.
Coping,	..	..	..	..	1 0 0	2 0 0 "
					£4 6 0	£8 14 0 per set.

Single Gate Sets—


With Butts,	..	..	..	..	£1 2 6 per set.
" Standards,	..	..	..	..	1 12 0 "

BEYOND ABOVE FRONTAGES—Panelling.	..	..	..	..	..	2/6 per ft. run.
Coping.	..	..	..	..	..	1/9 " "

## Carriage Entrance Gates

No. C 5717. THE "EARLHAM"

TO MATCH ABOVE.




ONE PAIR OF GATES, fitted with Striking Plate, Drop Bolt and Lock, Gate Stop, Gate Sockets :—

With Hangings for Brick Piers ; space required, 8 ft.,	..	..	..	..	..	..	Price, £6 6 0 per set.
" Hanging Standards ; space required, 8 ft. 9 ins.,	..	..	..	..	..	..	" 6 9 0 "

# Gates and Railings

No. C 1170. "QUEEN ANNE" PATTERN



Space required for Single Gateway, 4 ft. ; for Double Gateway, 8 ft. 6 ins. Height from Gate Stone to top of Coping, 1 ft. 9½ ins.

METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage,	..	..	..	..	16 ft.	32 ft.
Castings,	..	..	..	..	£3 17 0	£7 18 0 per set.
Coping,	..	..	..	..	1 0 0	2 0 0 "
					£4 17 0	£9 18 0 per set.

Single Gate Sets—


With Batts,	..	..	..	..	..	£1 6 0 per set.
„ Standards,	..	..	..	..	..	2 6 0 „

BEYOND ABOVE FRONTAGES—Panelling,	..	..	..	..	..	..	2/6 per ft. run.
Coping,	..	..	..	..	..	..	1/8 „ „

## Carriage Entrance Gates

No. C 1170. "QUEEN ANNE" PATTERN

TO MATCH ABOVE.




ONE PAIR OF GATES, fitted with Striking Plate, Drop Bolt and Lock, Gate Stop, Gate Sockets :—

With Hangings for Brick Piers ; space required, 8 ft.,	..	..	..	..	..	..	..	Price, £7 10 0 per set.
„ Hanging Standards ; space required, 9 ft. 3 ins.,	..	..	..	..	..	..	..	„ 7 15 0 „

# Gates and Railings

## No. C 1094. "OPEN ARCH" PATTERN



Space required for Single Gateway, 3 ft. 9 ins. ; for Double Gateway, 7 ft. 9 ins.

Height from Gate Stone to top of Coping, 1 ft. 6 ins.

METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage, ..	..	..	16 ft.	32 ft.
Castings, ..	..	..	£4 4 0	£8 14 0 per set.
Coping, ..	..	..	1 0 0	2 0 0 "
			£5 4 0	£10 14 0 per set.

Single Gate Sets—				
With Batts, ..	..	..	..	£1 3 0 per set.
" Standards, ..	..	..	..	2 2 0 "

BEYOND ABOVE FRONTAGES—Panelling, ..	..	..	..	..	3/- per ft. run.
Coping, ..	..	..	..	..	1/9 " "

## No. C 1097. "CLOSE ARCH" PATTERN



Space required for Single Gateway, 3 ft. 6 ins. ; for Double Gateway, 7 ft. 9 ins.

Height from Gate Stone to top of Coping, 1 ft. 7 ins.

METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage, ..	..	..	16 ft.	32 ft.
Castings, ..	..	..	£4 6 0	£8 17 0 per set.
Coping, ..	..	..	1 0 0	2 0 0 "
			£5 6 0	£10 17 0 per set.


Single Gate Sets—				
With Batts, ..	..	..	..	£1 8 0 per set.
" Standards, ..	..	..	..	2 10 0 "

BEYOND ABOVE FRONTAGES—Panelling, ..	..	..	..	..	3/- per ft. run.
Coping, ..	..	..	..	..	1/9 " "

# Gates and Railings

No. C 6631. "WINCANTON" PATTERN

AN ARCHITECT'S DESIGN—SIMPLE BUT EFFECTIVE.



Space required for Single Gateway, 3 ft. 10 ins.; for Double Gateway, 8 ft. 5 ins.

METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage, .. .. .	16 ft.	32 ft.
Castings, .. .. .	£6 4 0	£12 14 0 per set.
Coping, .. .. .	1 8 0	2 16 0 "
	£7 12 0	£15 10 0 per set.

Single Gate Sets—


With Butts, .. .. .	£1 17 6 per set.
„ Standards, .. .. .	4 0 0 "

BEYOND ABOVE FRONTAGES—Panelling, .. .. .	3/8 per ft. run.
Coping, .. .. .	2/3 " "

# Carriage Entrance Gates

No. C 6632. "WINCANTON" PATTERN

TO MATCH ABOVE.




GATE METAL, consisting of—

Pair of Gates with Galvanized Lock, Pair of Gate Steps, Pair of Iron Pillars, Gate Stopper, fitted complete, ready for re-erection,	£17 10 0 per pair
Pair of Gates with Galvanized Lock Hangers for Brick Piers, Gate Steps, and Gate Stopper, .. .. .	13 15 0 "
Quadrant Rails of 2 1/4 x 1/2 in. Wrought Iron, and including extra for Rollers on Gates, and Gate Catches, .. .. .	1 17 6 "
PANELLING, Cut to Plan, .. .. .	3/8 per ft. run.

# Gates and Railings

No. C 3342. THE "BLENHEIM" PATTERN



Space required for Single Gateway, 4 ft. 3 ins.; for Double Gateway, 9 ft. 3 ins.

METAL READY FOR ERECTION. For General Specification, see page 494.

Frontage, .. .. .	16 ft.	32 ft.
Castings, .. .. .	£7 6 0	£14 8 0 per set.
Coping, .. .. .	1 6 0	2 12 0 "
	£8 12 0	£17 0 0 per set.


Single Gate Sets—

With Butts, .. .. .	£2 8 0 per set.
" Standards, .. .. .	4 0 0 "

BEYOND ABOVE FRONTAGES—Panelling, .. .. .	5/6 per ft. run.
Coping, .. .. .	2/- " "

No. C 5715. THE "ALBANY" HEAVY PATTERN

Suitable for Mansions and Public Buildings.




Gate, 3 ft. 1 in. wide × 5 ft. high, fitted with Lock and Clip, and pair of Pilasters, with Backstays, .. .. .	Price, £6 6 0 per set.
Railing, 4 ft. 6 ins. high, .. .. .	" 0 11 0 per ft. run.

## Cast-Iron Entrance Gates



Gate, 4 ft. wide  $\times$  7 ft. 7½ ins. high, complete with Hangers and Locking Box for Brick or Stone Piers, Lock and Knob as shown.  
Price, .. .. £13 10 0 per set.




Gate, 6 ft.  $\times$  7 ft. 7½ ins., fitted with good Lock and Sham, Wrought-Iron Hangers and Pivots, Striking Plate, and Slip Bolt, complete, ready for erection, .. .. Price, £22 10 0 per pair.

## Heavy Cast-Iron Railings and Gates

SUITABLE FOR MANSIONS AND PUBLIC BUILDINGS.

No. C 5714.



Gate, 3 ft. wide  $\times$  4 ft. high, fitted with Lock and Clip and pair of Pillars, with Backstays, .. .. £6 0 0 per set.  
Railing, 4 ft. high, .. .. 0 9 6 per foot run.



# Artistic Wrought-Iron Gates

No. C4813.



4 ft. wide  $\times$  4 ft. 6 ins. high to top Horizontal.

Uprights,  $\frac{1}{2}$  in. square, spaced as shown.

Gate Pillars,  $1\frac{1}{2}$  ins. square with  $\frac{3}{4}$ -in. square Backstays.

Price, Gate and Pillars as shown, .. .. £6 5 0 per set.

If fitted with Best Brass Warded Lock, 16/- extra.

No. C4814.



4 ft. wide  $\times$  4 ft. 6 ins. high to top Horizontal.


Uprights,  $\frac{1}{2}$  in. square, spaced as shown.

Gate Pillars,  $1\frac{1}{2}$  ins. square with  $\frac{3}{4}$ -in. square Backstays.

Price, Gate and Pillars as shown, .. .. £6 16 0 per set.

If fitted with Best Brass Warded Lock, 16/- extra.

No. C4815.



4 ft. wide  $\times$  4 ft. 6 ins. high to top Horizontal.


Uprights,  $\frac{1}{2}$  in. square, spaced as shown.

Gate Pillars,  $1\frac{1}{2}$  ins. square with  $\frac{3}{4}$ -in. square Backstays.

Price, Gate and Pillars as shown, .. .. £8 6 0 per set.

If fitted with Best Brass Warded Lock, 16/- extra.

No. C4819.



4 ft. wide  $\times$  4 ft. 6 ins. high to top Horizontal.

Uprights,  $\frac{1}{2}$  in. square, spaced as shown.

Gate Pillars,  $1\frac{1}{2}$  ins. square with  $\frac{3}{4}$ -in. square Backstays.


Price, Gate and Pillars as shown, .. .. £8 6 0 per set.

If fitted with Best Brass Warded Lock, 16/- extra.

Prices for Railings to match these Gates quoted on application, stating quantity required.

# Artistic Wrought-Iron Entrance Gates

No. C4817.



8 ft. wide  $\times$  5 ft. high in centre. Uprights,  $\frac{1}{2}$  in. square. Scrollwork,  $\frac{1}{2} \times \frac{1}{4}$  in.  
Fitted with Best Brass Warded Lock and Sham, Drop Bolt, and hung to  $1\frac{1}{2}$ -in. square Wrought-iron Pillars, with 1-in. square Backstays.

Price, Gates and Pillars, .. .. . £15 15 0 per set.

Price for Railing to match quoted on application, stating quantity required.

No. C4818.




8 ft. wide  $\times$  5 ft. 6 ins. high in centre. Long Uprights,  $\frac{1}{2}$  in. square. Short Uprights,  $\frac{1}{4}$  in. square.  
Fitted with Best Brass Warded Lock and Sham, Drop Bolt, and hung to  $1\frac{1}{2}$ -in. square Wrought-iron Pillars, with 1-in. square Backstays.

Price, Gates and Pillars, .. .. . £21 5 0 per set

Price of Railing to match quoted on application, stating quantity required.

# Wrought-Iron Carriage Entrance Gates


No. C 3740. WROUGHT-IRON VERTICAL GATES AND SIDE GATE



Pair Gates only, 8 ft. wide $\times$ 4 ft. high above ground, fitted with Patent Lock and Sham, Vertical Bars $\frac{1}{2}$ inch diameter, 5-inch apart Centres at top, with Hangings for Wood or Stone, .. .. .	Price, £8 5 0 per pair.
Side Gates only, 3 ft. 6 ins. wide $\times$ 4 ft. high above ground, fitted with Patent Lock and Sham, Vertical Bars $\frac{1}{2}$ inch diameter, 5-inch apart Centres at top, with Hangings for Wood or Stone, .. .. .	Price, 4 8 0 each.
Cast-iron Pillars, with Bases for Stone, including Bolts, each extra, .. .. .	1 5 0
„ „ with Self-fixing Bases, each extra, .. .. .	1 12 0

No. C 3741.


WROUGHT-IRON SELF-SHUTTING CARRIAGE GATE



Gate only, 9 ft. 6 ins. wide $\times$ 4 ft. 6 ins. high to top horizontal, with Hangings for Wood or Stone, .. .. .	Price, £9 15 0 each, complete.
„ 9 „ 6 „ $\times$ 4 „ 6 „ hung to Cast-iron Pillars, for Stone, .. .. .	15 10 0 „ „
„ 9 „ 6 „ $\times$ 4 „ 6 „ „ „ „ with Self-fixing Bases, .. .. .	17 15 0 „ „

# Wrought-Iron Entrance Gates


No. C 4034.



These Gates are made entirely of wrought iron, and present a very handsome appearance. They are 10 ft. wide  $\times$  5 ft. high to top horizontal. The long uprights are  $\frac{7}{8}$  in. diameter at 6 in. apart centres, and short uprights  $\frac{5}{8}$  in. diameter.

Gates only, with Lock and Sham and Hangings for Stone Piers, .. .. .	Price, £30 17 0 per pair, complete.
„ „ hung to Wrought-iron Pillars, as shown, 10 ins. square, for fixing on Stone, .. .. .	„ 45 0 0 „ „

No. C 4035.



These Gates are exceedingly strong, and present a very bold and handsome appearance.

They are 10 ft. wide  $\times$  5 ft. high to top horizontal.

Gates only, with Lock and Sham, and Hangings for Stone Piers, .. .. .	Price, £75 0 0 per pair, complete.
„ „ hung to Ornamental Wrought-iron Pillars, as shown, with Bases for Stone, .. .. .	„ 107 10 0 „ „

# Wrought-Iron Garden Border and Division Railings, and Continuous Unclimbable Railings




No. C 3331.

## Garden Border Hurdles

All painted one coat before being despatched from works.


Bolts and Nuts are included in prices under.



No. C 3332.

6 ft. long. Frame,  $1 \times \frac{1}{2}$  in. Uprights,  $\frac{1}{2}$  in. diameter at 3-in. centres.  
Height above Ground, 9 12 15 18 24 30 36 inches.  
Prices, .. 4/- 4/3 4/6 4/7½ 4/9 5/6 7/- per yard.

6 ft. long. Frame,  $1 \times \frac{1}{2}$  in. Uprights,  $\frac{1}{2}$  in. diameter at 3-in. centres.  
Height above Ground, 9 12 15 18 24 30 36 inches.  
Prices, .. 4/- 4/3 4/6 4/7½ 4/9 5/6 7/- per yard.



No. C 3537.

## Ornamental Game-proof Garden Hurdles


For Flower Gardens, Lawns, &c.

Hurdles are 6 ft. long. End uprights,  $1\frac{1}{2} \times \frac{1}{2}$  in. Horizontals,  $1 \times \frac{1}{2}$  in. Verticals,  $\frac{1}{2}$  in. diameter, placed  $1\frac{1}{2}$  ins. apart.

Height above Ground, 30 36 42 48 inches.  
No. C 3537 or 3538. } 6/8 7/4 8/- 8/6 per yard.

All hurdles under 4 ft. high have only three horizontals.

Gates to match, same prices as No. C 3735, page 513.




No. C 3538

Blunt Points, No. C 3334 B.P.]

No. C 3334. Wrought-iron Continuous Unclimbable Railing

[Spear Heads, No. C 3334 S.H.]

Covered with one coat of black varnish before leaving works.




All necessary Bolts and Nuts are included in prices under.

Railing.	Height above Ground.	Size of Horizontals and Standards. Flat Iron.	Vertical Bars.		Price, per Yard.	If Painted instead of Varnished, extra.	Side Stays, extra.
			Size, Round.	Distance, Centre to Centre.			
No. C 3334	3 ft. 6 ins.	1½ × ½ in.	½ in. diameter.	4 ins.	7/-	3d. per yard.	For Railing up to 4 ft. 6 ins. Price, 2/6 each.
	3 " 9 "	1½ × ½ "	" "	4 "	7/3		
	4 " 0 "	1½ × ½ "	" "	4 "	7/6		
	4 " 6 "	1½ × ½ "	" "	4 "	8/3		
	4 " 0 "	1½ × ½ "	" "	4½ "	10/3	4½d. "	For Railing up to 5 ft. 6 ins. Price, 2/9 each.
	4 " 6 "	1½ × ½ "	" "	4½ "	11/3		
	5 " 0 "	1½ × ½ "	" "	4½ "	12/-		
	4 " 6 "	1½ × ½ "	" "	4½ "	14/-		
	5 " 0 "	1½ × ½ "	" "	4½ "	15/-	6d. "	
	4 " 6 "	1½ × ½ "	" square.	4½ "	12/9		
	5 " 0 "	1½ × ½ "	" "	4½ "	13/9		
No. C 3334 B.P.	Railing, with Blunt Points, same prices as above.						
" C 3334 S.H.	" with Spear Heads, on ½ in. or ¾ in. diameter bars, 9d.; on ½ in. diameter or ¾ in. square, 10½d. per yard extra.						

# Wrought-Iron Gates and Railings

No. C 3735. **ORNAMENTAL GAME-PROOF HURDLES AND GATES.** For the protection of Flower Gardens, Lawns, &c.



In 6 ft. hurdles, end uprights,  $1\frac{1}{2} \times \frac{1}{2}$  in.; horizontals,  $1 \times \frac{1}{2}$  in.; verticals,  $\frac{1}{2}$  in. diameter and placed  $1\frac{1}{2}$  ins. apart between.  
All hurdles under 4 ft. high have only three horizontal bars.

Height above ground,	..	..	..	..	..	..	..	..	..	30	36	42	48	inches.
Hurdles,	..	..	..	..	..	..	..	..	..	6/8	7/4	7/8	8/-	per yard.
											Up to 3 ft. high.	Up to 4 ft. high.		
Hand Gates to match, 3 ft. wide, with Latch and Catch, and hung to Strong Wrought-iron Standards,	..	..	..	..	..	..	..	..	..	..	40/-	42/-	each, complete	
" " hung to Square Cast-iron Pillars with Self-fixing Bases,..	..	..	..	..	..	..	..	..	..	..	60/-	66/-	"	"


No. C 3333. **EXTRA STRONG ORNAMENTAL HURDLES AND GATES**



End uprights and horizontal bars,  $1\frac{1}{2} \times \frac{1}{2}$  in. Uprights,  $\frac{1}{2}$  in. diameter at  $2\frac{1}{2}$ -in. centres.


Height above ground,	..	..	..	..	..	..	..	..	..	30	36	42	48	inches.
Hurdles (those 30 and 36 inches high have only two horizontals),	..	..	..	..	..	..	..	..	..	7/6	8/-	8/9	9/3	per yard.
											Up to 3 ft. high.	Up to 4 ft. high.		
Hand Gates to match, 3 ft. wide, with Latch and Catch, and hung to Strong Wrought-iron Standards,	..	..	..	..	..	..	..	..	..	..	42/-	42/6	each.	
Pair of Gates " 3 " with Brass Warded Lock. " " " " " "	..	..	..	..	..	..	..	..	..	..	62/-	69/-	"	
Pair of Gates " 8 " " " " " " "	..	..	..	..	..	..	..	..	..	..	129/-	140/-	per pair.	

No. C 6530. **ORNAMENTAL WROUGHT-IRON RAILING**




This Railing has a good appearance. It is 2 ft. 3 ins. high above coping, made in 9 ft. lengths, and connected by an Ornamental Cast-iron Pillar, as shown. The Horizontal Bars are  $1\frac{1}{2} \times \frac{1}{2}$  in. flat. The long Uprights are  $\frac{1}{2}$  in. square, flat to view, at 9-in. apart centres, with Ornamental Wrought-iron Heads. The short Uprights between are  $\frac{1}{2}$  in. square, angle to view, with pointed tops. Price, 6/6 per foot run.  
Hand Gates to match, 4 ft. 6 ins. high  $\times$  3 ft. 3 ins. wide, with Best Brass Warded Lock, and hung to Ornamental Cast-iron Pillars,  $2\frac{1}{2}$  ins. square in centre, for stone, with strong Wrought-iron Backstay to each, complete. Price, £9 4 0 each.

# Wrought-Iron Field and Farm-Yard Gates



No. C3737.  
**FIELD GATE**  
 9 ft. wide x 3 ft. 9 ins. high.  
 With Hangings for Wood or Stone,  
 Price, £3 8 0 each.  
 With Pillars to fix on Stone,  
 Price, £4 7 6 each.  
 With Pillars having Self-fixing Bases.  
 Price, £5 5 0 each.

No. C3335. **SHEEP HURDLE**




**SHEEP HURDLES.**

No.	Height above Ground.		Length.	End Uprights.	Centre Uprights.	Diameter of Top Bar.	Lower Bars.	Price, each.
	Ft.	Ins.	Feet.	Ins.	Ins.	In.		
C3335	3	0	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. diam.	5/9
C3336	2	8	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. diam.	6/3
C3337	2	8	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	{ two one " }	6/9
C3338	2	8	6	{ 1 1/2 x 1/2 Angle Iron. }	1 1/2 x 1/2	1/2	1 x 1/2 in. flat.	7/3
C3339	2	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	{ two one " }	7/6
C3340	3	3	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	{ three one " }	7/6
C3341	3	4	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	{ three one " }	8/9

No. C3340 has three uprights and five horizontals. No. C3341 has four uprights and five horizontals. All others have three uprights and four horizontals.

No. C3344. **CATTLE HURDLE**



**CATTLE HURDLES.**


No.	Height above Ground.		Length.	End Uprights.	Centre Uprights.	Top Bar.	Lower Bars.	No. of Uprights.	No. of Horizontal Bars.	Price, each.
	Ft.	Ins.	Feet.	Ins.	Ins.					
C3344	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2 in. diam.	1 in. diam.	3	4	6/9
C3345	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 x 1/2 in. flat.	3	5	7/10
C3346	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. diam.	4	5	8/3
C3347	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 x 1/2 in. flat.	4	5	8/9
C3348	3	7	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	{ four one " }	3	6	9/3
C3349	3	6	6	{ 1 1/2 x 1/2 Angle Iron. }	1 1/2 x 1/2	1/2	1 x 1/2 in. flat.	3	5	9/6
C3350	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 x 1/2 in. flat.	3	5	9/6
C3351	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. diam.	3	5	10/9
C3352	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	{ four one " }	4	6	11/3
C3353	3	9	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2 in. square.	1 x 1/2 in. flat.	3	5	11/9
C3354	3	8	6	1 1/2 x 1/2	1 1/2 x 1/2	{ 1 1/2 x 1/2 in. Half round Iron. }	{ four one " }	3	6	11/6
C3355	3	9	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2 in. diam.	1 in. diam.	3	5	12/3
C3356	4	0	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	{ four one " }	3	6	14/-
C3357	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. diam.	4	5	12/9
C3358	4	0	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. diam.	4	6	15/9

**TUBULAR BAR CATTLE HURDLES.**

No.	Height above Ground.		Length.	End Uprights.	Centre Uprights.	Top Bar.	Lower Bars.	No. of Uprights.	No. of Horizontal Bars.	Price, each.
	Ft.	Ins.	Feet.	Ins.	Ins.					
C3359	3	6	6	1 1/2 x 1/2	1 1/2 x 1/2	2 in. tube.	1 in. tube.	3	5	12/-
C3360	3	9	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. tube.	3	5	12/6
C3361	3	9	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. tube.	4	5	13/6
C3362	4	0	6	1 1/2 x 1/2	1 1/2 x 1/2	1/2	1 in. tube.	3	6	15/-

The above prices include one coat of black varnish and all necessary bolts and nuts. For large quantities special quotation given, including delivery to any part of the country.

## Wrought-Iron Continuous Flat Bar Fencing




This Fencing is made with the top bar of round iron, and lower bars of flat iron, placed edge upwards. The standards are generally placed 3 feet apart, with a joining standard every 15 feet. The flat bars are secured to standards on the notch and wedge principle, which firmly holds the standards in their upright position. All the flat bars are notched and wedged at the joining standards, thus rendering the withdrawal of the horizontal bars impossible.

Fences suitable for	Estimate No.	Height above Ground.	Depth under Ground.	Distance apart of Standards.	Size of Intermediate Standards.	Size of Joining Standards, placed 15 ft. apart.	No. of Bars.	Size of Top Bar, Round.	Size of Lower Bars, Flat.	Price, per Yard.	Extras, per Yard.		Cast-iron Terminal Pillars, with Self-fixing Bases, as shown.
		Ft. Ins.	Ins.	Ft. Ins.	Ins.	Ins.		In.	In.		Additional Flat Lower Bar.	If with Square Top Bar instead of Round.	
Sheep and Light Cattle.	C 10	3 6	12	3 0	1½ × ½	1½ × ½	5	½	1 × ½	3/9	5d.	¾ .. 1½d.	19/- each.
	C 11	3 6	13	3 0	1½ × ½	1½ × ½	5	½	1 × ½	4/6	5d.	¾ .. 1½d.	19/- ..
General Purposes.	C 12L	3 9	14	3 0	1½ × ½	1½ × ½	5	¾	1 × ½	4/10½	5d.	1½ .. 2½d.	19/- ..
	C 12	3 9	14	3 0	1½ × ½	1½ × ½	5	¾	1 × ½	5/3	5d.	1½ .. 2½d.	19/- ..
	C 13	4 0	14	3 0	1½ × ½	1½ × ½	5	¾	1 × ½	5/3	5d.	1½ .. 2½d.	20/- ..
Heavy Stock.	C 14	4 0	14	3 0	1½ × ½	1½ × ½	6	¾	1 × ½	6/-	5d.	1½ .. 2½d.	20/- ..
	C 15	4 6	15	3 0	1½ × ½	1½ × ½	6	¾	1 × ½	6/3	5d.	1½ .. 2½d.	22/- ..

Prices include one coat Black Varnish before leaving works, with Wedges and Rivets, complete.

No. C3743. HAND GATE




3 feet 6 inches wide × 3 feet 6 inches to 4 feet high.

Hung to Strong Wrought-iron Standards, 40/-; Extra Strong, 45/- each.

" Cast-iron Pillars for Stone, .. .. " " 65/- "

" " " with Self-fixing Bases, .. .. " " 73/6 "

No. C3744. FOOTPATH GATE



3 feet 6 inches to 4 feet high.


Hung to Cast-iron Pillar, with Self-fixing Base, .. .. 70/- each.

Do., do., Extra Strong, .. .. 80/- "



## Wrought-Iron Unclimbable Vertical Gates



**No. C 3968.**



**These Gates are 9 feet wide, to match Unclimbable Railings, shown on page 512. Fitted with slip bolt for padlock and drop bolt. Gate Stops, 10/- each extra.**

Sizes.	PRICE, with Hangings for Wood or Stone, per pair.	PRICE, Hung to Cast-iron Pillars, with Bases for Stone, per pair.	PRICE, Hung to Cast-iron Pillars, with Self-fixing Bases, per pair.
3 ft. 6 ins. high; Uprights, $\frac{1}{2}$ in. diameter, at 4 in. Centres, .. .. .	£4 5 0	£6 5 0	£6 15 0
4 " 0 " " " " " " 4 " " " " " " " " " " " "	4 10 0	6 12 0	7 3 0
4 " 6 " " " " " " 4 " " " " " " " " " " " "	4 15 0	6 18 0	7 12 0
4 " 0 " " " " " " 4 " " " " " " " " " " " "	4 18 0	7 3 0	7 15 0
4 " 6 " " " " " " 4 " " " " " " " " " " " "	5 3 0	7 6 0	8 0 0
5 " 0 " " " " " " 4 " " " " " " " " " " " "	5 7 0	7 12 0	8 4 0
4 " 6 " " " " " " or $\frac{1}{2}$ in. square, at $4\frac{1}{2}$ in. Centres,	6 10 0	9 10 0	10 10 0
5 " 0 " " " " " " 4 " " " " " " " " " " " "	6 18 0	10 0 0	11 0 0
5 " 6 " " " " " " 4 " " " " " " " " " " " "	7 6 0	10 10 0	11 14 0

**If fitted with Brass Warded Lock and Sham, 14/- per pair extra.**



No.	Width.	Height above Ground.	Size of Round Vertical Bars.	Distance Centre to Centre.	PRICE, with Hangings for Wood or Stone	PRICE, Hung to Cast-iron Pillars to fix on Stone, including Bolts.	PRICE, Hung to Cast-iron Pillars, with Self-fixing Base.
C 3964.	3 ft. 6 ins.	3 ft. 6 ins.	3 in. diam.	4 inches.	£2 2 0	£4 5 0	£4 13 0
	3 " 6 "	4 " 0 "	"	4 "	2 4 0	4 10 0	4 17 6
	3 " 6 "	4 " 0 "	"	4 "	2 8 0	4 12 0	5 0 0
	3 " 6 "	3 " 6 "	"	3 "	2 9 6	4 8 0	5 2 0
C 3967.	3 " 6 "	4 " 0 "	"	3 "	2 10 0	4 10 0	5 5 0
	3 " 6 "	4 " 0 "	"	3 "	2 15 0	4 15 0	5 10 0

If with Best Brass Warded Lock, 8/- each extra.


# Grave Tablets, Wreath Stands, and Cemetery Bordering

No. C 6745.  
Grave Mark



8½ ins. wide.  
12 ins. above ground.  
Price, .. 4/- each.

No. C 6746.  
Grave Tablet



12 ins. wide.  
14 ins. above ground.  
Price, .. 5/- each.


No. C 6747.  
Grass Tablet



Tablet.	Fork.	Each.	Per Doz.
12 x 8 ins.	8 ins.	2/9	30/-
16 x 10 "	10 "	4/-	42/-
20 x 12 "	12 "	5/-	48/-


Inscription included.

No. C 6748.  
Grave Tablet




14½ ins. wide.  
14 ins. above ground.  
Price, .. 6/- each.

No. C 6749.  
Grass Tablet




14½ ins. wide.  
19 ins. above ground.  
Price, .. 6/- each.

No. C 4802.  
Wreath Stand and Grave Tablet




18 ins. wide. 30 ins. above ground.  
Price, .. 12/- each.  
WREATH STAND ONLY.  
16 ins. wide. 26 ins. above ground.  
Price, .. 10/6 each.

No. C 6750.  
Grave Tablet



20½ ins. wide. 31½ ins. above ground.  
Price, .. 22/6 each.  
20½ ins. wide. 26½ ins. above ground.  
Price, .. 15/- each.


No. C 4801. Grave Tablet



20 ins. wide. 29 ins. above ground.  
Price, .. 38/- each. Inscription included.

Inscriptions, where not included as stated, cast on in Raised Letters at 1/6 per dozen letters.

No. C 6090. Lawn Bordering




In 3-foot lengths. 6 ins. high above ground.  
Price, .. 2/6 per length each; 27/- per doz. lengths.

No. C 6091. Lawn Bordering



In 3-foot lengths. 6 ins. high above ground.  
Price, .. 2/9 per length each; 30/- per doz. lengths.

# Tomb Railings



INFANTS' SIZE.


No. C 6411. **Single Rail**

CASTINGS ONLY.—Four Corner Standards, Two Centre Standards, Eight Twisted Rails.  
Complete, ready for fixing, at .. .. . £0 18 0 per set.

No. C 6412. **Double Rail**

CASTINGS ONLY.—Four Corner Standards, Two Centre Standards, Eight Twisted Rails.  
Complete, ready for fixing, at .. .. . £1 4 0 per set.

This Pattern can also be supplied with open End Standards.




No. C 6413.

CASTINGS ONLY.—Four Corner Standards. Two Centre Standards. Four Dwarf Standards, Eight Twisted Bars.  
Complete, ready for fixing, at .. .. . £1 10 0 per set.


This Pattern can also be supplied with open End Standards.

## Tomb Railings



No. C6414

CASTINGS ONLY.—Four Corner Standards, Two Centre Standards, Four Dwarf Standards, Eight Twisted Bars.  
Complete, ready for fixing, at .. .. . £2 13 0 per set.



No. C6415. Suitable for Double Graves. 6 ft. 2 in. Centres.

CASTINGS ONLY.—Four Corner Standards, Four Centre Standards, Four  $1\frac{1}{2}$  in. diameter Twisted Bars.  
Complete, ready for fixing, at .. .. . £3 10 0 per set.

# Portable Coppers

CAST IRON, SELF-CONTAINED.

SPECIAL FEATURES: REQUIRE NO SETTING. WILL WORK ANYWHERE OCCUPY SMALL SPACE. SMALL FUEL CONSUMPT.

No. C4858. THE "KLENE"



Burns Coke, Coal, or Wood. Quick Heating.  
Efficient and Economical in use. Clean and Simple.

Capacity, .. .. .	6	8	10	12 galls.
Price, with Galvanized or Rustless Boiler,	39/9	45/3	53/3	58/9 each.

No. C4836. THE "CORNER COMFORT"



Fits snugly in a corner. Fire Brick Linings and Cast Sole Plate.

Capacity, .. .. .	6	8	10	12	14 galls.
Price, with Galvanized or Rustless Boiler, .. .. .	57/-	63/-	69/-	75/-	81/- each.

No. C4889. THE "HOMESIDE"



Substantially Constructed. Durable and Economical in use.  
Specially suitable for Artizan Dwellings. Will stand snugly in a corner.

Capacity, .. .. .	6	8	10	12 galls.
Price, with Galvanized or Rustless Boiler,	40/-	46/-	57/-	60/- each.
Smoke Pipe, with Soot Plug, Dumper and Elbow, .. .. .	8/-	8/-	8/-	8/- p. set.
	48/-	54/-	65/-	68/- "

No. C1024. THE "HOUSEHOLD"



Smoke Outlet Nozzle supplied horizontal to order.


Capacity, .. .. .	6	8	10	12	16	20	25 galls.
Price, with Galvanized or Rustless Boiler, ..	42/9	48/-	57/-	63/-	72/-	81/-	96/- each.

Mounted on Wheels, 16/6 each extra.

## Portable Coppers

### THE "COUNCIL" CAULDRON FOR BOILING ASPHALTE AND OTHER LIQUIDS.


No. C6718.



Substantially constructed  
of stout  $\frac{1}{8}$ -in. Steel Plates,  
with strengthening bands,  
to stand hard wear.

Boilers made from  $\frac{5}{8}$ -in.  
Wrought-iron Plates.

No. C6719.




Capacity of Boiler, .. ..	20	25	30	40	50	60	70	80	90	100	galls.
No. C6718. Without Wheels,	£11 5 0	£12 0 0	£12 15 0	£13 17 6	£15 0 0	£16 17 6	£18 7 6	£19 17 6	£21 7 6	£22 17 6	each.
No. C6719. If mounted on 4 Wheels, or 3 Wheels with Handle, .. ..	13 10 0	14 12 6	15 11 3	17 5 0	18 18 9	21 3 9	23 1 3	24 15 0	26 12 6	27 6 3	„

Stirrer and Ladle for same, 13 6 to 21/- extra.

Strong 2-in. Cast-iron Full-way Draw-off Taps can be fitted as shown above for 24/- extra.


### No. C6730. THE "IMPROVED FARMER" CAST IRON.



Will boil liquids quickly in or out doors. The "Farmer" is specially  
constructed for Dairy and Farm purposes. Strong cast-iron throughout;  
brick linings to fire. Base plate to protect floor.

Capacity, .. ..	25	30	40	50	60	galls.
With Galvanized or Rust- less Boiler, .. ..	98/-	102/-	114/-	138/-	162/-	each.
Mounted on Wheels, .. ..	16/6	16/6	16/6	21/-	21/-	„ extra.
Sizes, .. ..			$\frac{1}{2}$	$\frac{1}{2}$	1	inch.
Fitted with Draw-off Cock and Flue- cleaning Doors, .. ..	13/6	16/6	21/-	each	extra.	


### No. C1025. PORTABLE COPPER WROUGHT-IRON CASING.



Capacity, .. ..	6	8	10	12	14	16	18	20	25	30	galls.
With Galvanized } Cast-iron Pan, }	20/-	24/-	28/-	32/-	36/-	42/-	46/-	51/-	66/-	89/-	each.

If supplied with best rivetted Copper Pan, add 2/3 per gallon to the  
above prices, which include an Elbow and 2-foot Flue Pipe.

# Furnace Pans and Fittings



No. C 1163.  
**GALVANIZED CAST-IRON  
FURNACE PAN**



6 to 12 galls.,	..	1/-	per gall.
14 " 20 "	..	1/1½	"
25 " 40 "	..	1/3	"
45 " 100 "	..	1/6	"

Rustless Cast-iron Furnace Pans,  
same prices as above.

No. C 1161.  
**BEST RIVETTED COPPER  
COPPER**

6 to 200 galls.,	..	2/3	per lb.
Average weight, 1½ lbs. per gall.			

If fitted with Copper Draw-off Pipe,  
screwed to receive tap,  
6d. per lb. extra.



No. C 1164.  
**COPPER DOOR AND FRAME**


Size Nos.,	1	2	3
Ordinary,	1/-	1/1½	1/9 each.
Medium, ..	1/6	2/-	2/3 "
Heavy, ..	3/-	3/9	4/6 "

Size Nos.,	4	5	6
Ordinary,	3/-	—	— each.
Medium, ..	3/6	—	— "
Heavy, ..	6/-	7/6	9/- "


No. C 916. **SOOT DOOR**  
With Wrought-iron Fastenings.

Size Nos.,	00	0	1	2
Width, ..	6½	7	7½	9 ins.
Height, ..	5	5½	5½	6½ "
Prices, ..	2/-	2/3	2/6	2/9 each

Size Nos.,	3	4	5	6
Width, ..	10	11	12½	13 ins.
Height, ..	7½	7½	8½	9½ "
Prices, ..	3/3	3/9	4/-	5/3 each.



No. C 1165. **COPPER GRATES**



Size Nos.	Ordinary.	Heavy.	Hearing Bars Per Pair.
1	7½d.	1/3	4½d.
2	10½d.	1/9	6d.
3	1/4	2/3	9d.
4	1/9	3/-	1/-
5	—	4/-	1/6
6	—	4/9	2/-


No. C 925. **DAMPERS AND FRAMES**

No.	Size.	Price.
00	5 × 4	8½d. each.
0	5½ × 5	9d. "
1	6 × 5½	10½d. "
2	7 × 6	1/3 "
3	7½ × 6½	1/6 "
4	9 × 7½	1/7½ "
5	10½ × 9	2/3 "
6	12 × 10	2/6 "
7	14½ × 11½	3/9 "
8	16½ × 12½	5/- "
Outside Sizes.		



No. C 917. **SOOT BOXES**

Sizes,	Nos. 1	2	3	4	5	6
Prices, ..	4½ × 3½	6 × 4	7 × 5	9 × 4½	9 × 6	9 × 9
Prices, ..	2/4½	2/10½	3/4½	3/9	4/6	6/- each.



No. C 4142. **SOOT DOORS (Double)**  
Fitted with Brass Turn Buckle and Cast-iron Key.

Sizes of Frame, ..	9 × 6	9 × 9	12 × 9	12 × 12	18 × 9 ins.
Prices, ..	6/9	8/-	8/9	10/6	13/6 each.
Sizes of Frame, ..	18 × 12	18 × 18	21 × 15	24 × 18	24 × 22 ins.
Prices, ..	16/6	24/-	25/6	36/-	46/6 each.



No. C 1158. **FALSE BOTTOM (Kitchen)**

Sizes, 4 × 5	4 × 6	4 × 7	4 × 8	4 × 9	4 × 10	5 × 8	5 × 9	6 × 8 ins.
Prices, 4½d.	6d.	7½d.	9d.	10½d.	1/-	10½d.	1/-	1/1½ ea.
Sizes, 6 × 9	6 × 10	7 × 9	7 × 10	7 × 12	8 × 10	8 × 12	9 × 12 ins.	
Prices, 1/3	1/4½	1/6	1/7½	2/-	1/9	2/3	2/6 ea.	



No. C 922. **QUICK DRAUGHT FURNACE BARS**


Sizes, ..	..	..	14	16	18	20	22	24 ins. long.
Prices, ..	..	..	10½d.	1/1½	1/4½	1/9	2/1½	2/4½ each.



No. C 921. **SLOW DRAUGHT FURNACE BARS**

Sizes, ..	..	..	12	14	16	18	20	22 ins. long.
Prices, ..	..	..	7½d.	8d.	10½d.	1/3	1/4½	1/7½ each.

No. C 920. **CISTERN AND COVER**



Sizes, 12 × 6½ × 10	No. 2. 13 × 7 × 10	No. 3. 15 × 8 × 11 ins.
Prices, 4/10½	5/9	7/6 each.
Sizes, ..	No. 4. 18 × 8 × 12	No. 5. 21 × 9 × 12½ ins.
Prices, ..	9/9	13/6 each.

**FURNACE PAN OR BOILER TOPS**  
With Galvanized Lid and Copper Hinge.

No. C 6831.

No. C 6832.



No. C 6833.


No. C 6834.



27 ins. to suit	8 and 10 Gallon Boilers,	6/9 each.
30 " "	10 and 12 " "	9/9 "
32 " "	12, 14 and 16 " "	11/3 "
36 " "	16, 18, 20 and 25 " "	18/- "

## Miscellaneous Castings

No. C 6396. **CAST PIPE NOZZLE**  
WITH DAMPER.  
For Regulating Draught in Stove Pipe.




Sizes, ..  $3 \times 2\frac{1}{2}$   $3\frac{1}{2} \times 3$  4  $4\frac{1}{2}$   $4\frac{1}{2} \times 4$   $5 \times 4\frac{1}{2}$   $6 \times 5\frac{1}{2}$  ins.  
Prices, .. 2/- 2/3 2/6 3/- 3/6 4/- each.

No. C 4096. **CAST-IRON STAIR NOSINGS**



Made in 24 30 36 42 48 inch lengths by  
Breadths, 3  $3\frac{1}{2}$  4  $4\frac{1}{2}$  5 6 inches.  
Prices, 1/-  $1\frac{1}{4}$   $1\frac{1}{3}$   $1\frac{1}{4}$   $1\frac{1}{6}$   $1\frac{1}{10}$  per lineal ft.  
Cast-iron Stair Treads to match, at same prices.

No. C 1159.  
**PARTITION BRACKETS**



In.	Price.
12 x 18 ..	1/9 each.
12 x 24 ..	2/6 "
13 x 30 ..	3/3 "
14 x 36 ..	3/9 "
14 x 42 ..	4/3 "
14 x 48 ..	4/6 "

No. C 4159. **SKID IRON**




For .. 2  $2\frac{1}{2}$  3  $3\frac{1}{2}$  4  $4\frac{1}{2}$  5 in. wheels.  
Prices, .. 2/3 2/6 2/9 4/- 4/3 4/9 5/- each.

No. C 6397. **SKID PAN**



For .. 2  $2\frac{1}{2}$  3  $3\frac{1}{2}$  4  $4\frac{1}{2}$  5 in. wheels.  
Prices, .. 2/6 3/-  $3\frac{1}{4}$  4/6 5/-  $5\frac{1}{6}$   $5\frac{1}{9}$  each.




No. C 3761. **WALL TIE PLATE**

Sizes, ..	6	7	8	9 ins.
Prices, ..	9d.	1/-	1/6	2/- each.
Sizes, ..	10	11	12	14 ins.
Prices, ..	2/3	3/-	3/6	6/3 each.

No. C 4165 **EARTH RAMMER**

Sizes, ..	8	10	12	14	16 lbs.
Prices, ..	1/6	1/9	2/3	2/6	3/- each.





No. C 1369. **TRUCK WHEEL**

Sizes, ..	4	5	6	7 ins. diam.
Prices, ..	4½d.	6d.	8d.	10½d. each.
Sizes, ..	8	9	10	12 ins. diam.
Prices, ..	1/3	1/9	2/-	2/3 each.

No. C 7097. **SOLID TRUCK WHEEL**

Sizes, ..	6	7	8 ins. diam.
Prices, ..	1/3	1/9	2/3 each.
Sizes, ..	9	10	12 ins. diam.
Prices, ..	2/9	3/3	5/9 each.




No. C 7096.

**NAVY BARROW WHEEL**

14 ins. diam.,	..	2/9 each.
16 "	..	2/10½ "
17 "	..	3/- "
18 "	..	3/3 "

No. C 1368.  
**GARDEN BARROW WHEEL**

Sizes, ..	11	16 ins.
Prices, ..	2/9	3/3 each.
Sizes, ..	18	20 ins.
Prices, ..	4/-	5/- each.






# Ventilating Air Bricks and Gratings

No. C 1126.  
**ORNAMENTAL  
AIR BRICK**




No. C 6682.  
**SCHOOL BOARD  
AIR BRICK**  
Light.




## CAST IRON.

		Sizes, ..	9x3	9x6	9x9	12x6	12x9	12x12 inches.	
No. C 1126.	Fine Cast,	..	2/3	4/6	9/-	—	—	—	per doz.
	Galvanized,	..	4/6	9/-	16/6	—	—	—	"
No. C 6401.	Fine Cast, Medium,	..	3/4	6/3	10/6	9/9	15/-	16/6	"
	Galvanized, "	..	6/6	12/-	19/6	16/6	27/-	28/6	"
	Fine Cast, Heavy,	..	4/6	9/3	—	12/9	16/6	22/6	"
	Galvanized, "	..	8/3	16/6	—	24/-	31/6	42/-	"
No. C 6682.	Fine Cast,	..	3/9	8/3	12/-	12/9	16/6	18/-	"
	Galvanized,	..	7/6	15/-	22/6	24/-	31/6	34/6	"
No. C 1127.	Fine Cast, Light,	..	9/9	13/6	21/-	21/-	30/-	31/6	"
	Galvanized, "	..	15/-	22/6	37/6	31/6	39/-	51/-	"
	Fine Cast, Heavy,	..	13/6	21/-	30/-	25/6	34/6	42/-	"
	Galvanized, "	..	24/-	35/-	48/-	43/6	60/-	65/-	"

No. C 6401.  
**PLAIN AIR BRICK**  
Medium and Heavy.



No. C 1127.  
**SLIDING AIR BRICK**  
Light and Heavy.



No. C 3788. **SCHOOL BOARD AIR BRICK**

1/2 in. thick, 1 1/2 in. flange, 1/2 in. mesh.


Sizes, ..	9x3	9x6	9x9	12x6	12x9	12x12	15x12	15x15	18x12	18x18	24x12	24x18 inches.
Fine Cast,	6/-	9/9	15/-	16/6	18/-	26/6	34/6	37/6	32/6	45/-	45/-	63/- per doz.
Galvanized,	11/3	18/-	28/6	31/6	34/6	50/6	64/6	72/-	63/-	87/-	87/-	123/- "

No. C 6402. **SCHOOL BOARD AIR BRICK**


With Removable Front and Four Brass Screws.

1/2 in. mesh, 2 in. flange.

Sizes, ..	9x3	9x6	9x9	12x6	12x9	12x12	14x9	14x14	15x15	18x12	18x18	22x22 inches.
Fine Cast, ..	2/-	2/6	3/3	3/3	3/6	4/-	4/-	7/3	7/-	7/6	9/-	12/- each.
Galvanized,	2/9	3/9	4/6	4/6	5/3	6/-	6/3	10/6	11/3	10/9	13/6	19/6 "



No. C 6678.




## VENETIAN VENTILATORS

No. C 6677. Diam. of front, 13 1/2 ins.; diam. of box, 11 1/2 ins.; Price, black enamelled, 18/- each.

" C 6678. " " 17 1/2 " " " 15 " " " " 21/9 "


No. C 6677




No. C 4191. **LOUVRE AIR BRICK**

With Horizontal Webs.

Sizes, ..	9x6	9x9	12x6	12x9	12x12	14x12 inches.
Fine Cast, ..	3/-	4/-	3/9	5/3	6/-	9/9 each.
Galvanized, ..	4/6	6/-	6/-	8/3	10/6	13/6 "



No. C 5693.




		No. C 5693. AIR GRATING.		Circular.			
Sizes, ..	9	12	14	16	18	20	22
Fine Cast, ..	10 1/2 d.	1/6	2 1/4	2/9	3/6	4/3	5/3
Galvanized, ..	1/9	3/-	4/-	5/3	6/9	8/-	9/9

		No. C 1131. AIR GRATING.		Hit and Miss.			
Sizes, ..	6	8	9	10	12	14	15 inches.
No. C 1131. Square, ..	2/-	2/6	3/-	3/3	3/9	6/-	6/6 each.
" C 1132. Round, ..	2/-	2/6	3/-	3/3	3/9	6/-	6/6 "

Including one Key to each.

No. C 1131




# Ventilating Air Bricks and Gratings

## THE "LOCO" AIR BRICK


APPROVED BY THE LEADING ENGINEERS FOR RAILWAY STORES AND LARGE BUILDINGS.

- ADVANTAGES:—(a) Door hinged in frame and to lock, excluding dust.  
(b) Hit-and-miss in door for ordinary ventilation.  
(c) Free current of air available when door fully opened.  
(d) Door can only be opened with key provided.

No. C6680. For inside face of wall.




No. C6681. For outside face of wall.



Sizes, ..	9x6	9x9	12x9	15x9	18x9	12x12	15x12	18x12	18x18 inches.
No. C6680. Galvanized, ..	6/-	7/6	9/-	10/6	12/-	13/6	15/-	16/6	24/- each.
No. C6681. Painted, ..	1/-	1/6	2/-	2/6	3/-	3/3	3/6	3/9	4/6 "

## COWELLS' PATENT AIR BRICKS OR VENETIAN VENTILATORS

Design No. C 3930.



THIS Air Brick is far and away superior to any of the ordinary designs, and at but very nominal extra cost. It needs only to be used once to ensure its continuity of adoption for all classes of buildings. Hitherto the main difficulty with air bricks has been the moisture driven through the interstices by the wind, damaging the fabric; this defect has been overcome by this invention. The above drawings very lucidly show this advantage. The louvres act upon the suction principle and induce a current of air. Strongly made of cast iron. Cheap, durable, and effective.



Elevation of 12x6 Inch Ventilator.


Sizes, ..	9x3	9x6	9x9	12x6	12x9	12x12 inches.
Fine Cast, ..	8/-	16/-	24/-	24/-	27/-	48/- per doz.
Galvanized, ..	13/6	27/-	37/6	37/6	49/6	75/- "

Section and Adaptation to Brick Work of 9x6 and 12x6 Inch Ventilators.


Arrangements can be made to pay carriage on quantities to any Railway Station in the British Isles.

## AIR INLET, VENTILATOR AND WINDOWS

No. C 7239. With Square Head.



No. C 7238. With Camber Head.




Sizes outside, ..	16 1/2 x 11 1/2	26 x 20	33 x 13 ins.	Sizes outside, ..	38 x 17 x 19	36 x 18 x 22	30 x 18 x 20 ins.
" of Flange for Brick, ..	15 x 10	24 x 19	31 1/2 x 11 1/2 "	" of Flange for Brick, ..	35 x 14 x 16	—	26 1/2 x 15 1/2 x 17 1/2 "
Prices, Black for Wood, ..	12/6	21/-	20/- each.	Prices, for Woodwork, ..	30/-	27/6	25/- each
" " for Brickwork, ..	16/6	25/-	24/- "	" for Brickwork, ..	32/6	—	27/6 "

# Door Step Risers and Ventilating Panels and Air Gratings



No. C1181. In stock lengths, 2 to 6 feet.  
 $\frac{1}{2}$  inch thick  $\times$  3 inches wide.  
 Prices, 3d. 6d. 7d. 8d. 9d. 10d. per lineal foot.



No. C3809. In 42 and 48 inch lengths.  
 $\frac{1}{2}$  inch thick  $\times$  3 inches wide.  
 Prices, 9d. 10d. 11d. 12d. 13d. 14d. per lineal foot.



No. C3808. In stock lengths, 2 to 4 feet.  
 $\frac{1}{2}$  inch thick  $\times$  2 inches wide. Price, 8d. per lineal foot.



No. C6405. Any length up to 40 inches.  
 $\frac{1}{2}$  inch thick  $\times$  6 inches wide. Price, 39 each.


## GATE AND DOOR PANELS



No. C3810.  
 $34 \times 7\frac{1}{2}$  ins.,  
 3/9 each.



No. C3806.  
 $29\frac{1}{2} \times 10$  ins., 6/- each.  
 $41\frac{1}{2} \times 13$  " 9/- "



No. C3809.  
 $38 \times 18$  ins.,  
 9/- each.




No. C3811.  
 $24 \times 12$  ins., 6/- each.  
 $30 \times 12$  " 8/3 "

THE RECTANGULAR DESIGNS CAN BE MADE IN OTHER SIZES.

## No. C1128. GRATING

With Border all round. Fine Cast.




$\frac{1}{2}$  inch thick;  $\frac{1}{2}$  inch mesh.  

6x9	6x12	6x15	6x18	6x20	6x36 ins.
9d.	1-	13	16	19	26 each.
9x9	9x12	9x15	9x18	9x24	9x30 ins.
13	16	19	23	26	36 each.
9x36	12x12	12x15	12x18	12x24 ins.	
43	46	2-	23	29	36 each.
12x30	12x36	18x18	18x18	18x24	24x24 ins.
4-	5-	29	36	5-	7/3 each.

## No. C6403. GRATING

For Continuous Stretches. Fine Cast.



$\frac{1}{2}$  inch thick;  $\frac{1}{2}$  inch mesh.  


6x42	14x38	18x39 ins.
3-	53	6- each.

$\frac{1}{2}$  inch thick;  $\frac{1}{2}$  inch mesh.  

8x40	9x40	10x40	11x37	12x36 ins.
46	49	6-	49	53 each.
12x42	21x36	24x36	27x36 ins.	
56	9-	99	106 each.	

## No. C3792. GRATING

With Border all round. Fine Cast.




$\frac{1}{2}$  inch thick;  $\frac{1}{2}$  inch mesh.  

9x48	12x24	12x36	12x48 ins.
83	53	76	12- each.
21x42	24x36	24x48	27x48 ins.
129	15-	196	219 each.
33x36	36x48 ins.		
226	299 each.		

SPECIAL.—1 inch thick;  $\frac{1}{2}$  inch mesh— $24 \times 48$  ins., 316 each.

## No. C6404. GRATING

For Continuous Stretches. Fine Cast.




$\frac{1}{2}$  inch thick;  $\frac{1}{2}$  inch mesh.  

9x38	12x40	16x42	18x36 ins.
76	99	119	119 each.
20x42	24x38	30x42	45x36 ins.
139	15-	226	226 each.
45x41	48x42 ins.		
24-	226 each.		

SPECIAL. { 1 inch thick } 17x42 18x42 21x42 26x42 ins.  
 {  $\frac{1}{2}$  inch mesh } 18- 18 196 226 each.

## No. C3793. GRATING

For Continuous Stretches. Fine Cast.




$\frac{1}{2}$  inch thick.  

6x41	7x41	9x41	12x41	14x41 ins.
36	4-	5-	6/3	7- each.
16x40	18x40	21x39	24x38 ins.	
8-	93	129	136 each.	

\* The 6-inch wide Grating has plain border.

## No. C3790. GRATING

With Border all round, or for Continuous Stretches. Fine Cast.



$\frac{1}{2}$  inch thick;  $\frac{1}{2}$  inch mesh.  

9x48	12x48	14x48	16x48 ins.
8-	113	129	149 each.

$\frac{1}{2}$  inch thick;  $\frac{1}{2}$  inch mesh.  


21x48	23x72 ins.
12 inch mesh	18-
316 each.	

$\frac{1}{2}$  inch thick; 1-inch mesh.  

11x48	18x48	24x48	24x54	34x41 ins.
129	21-	30-	316	339 each.

## No. C3787. GRATING

With Border all round. Fine Cast.




$\frac{1}{2}$  inch thick;  $\frac{1}{2}$  inch mesh.  

14x29 ins.	...	56 each.
------------	-----	----------

## No. C1132. AREA GRATINGS

With Straight Bars for heavy wear.



Each  

1 ft. 6 ins. $\times$ 1 ft. 6 ins. $\times$ $\frac{1}{2}$ in. thick,	76
2 " 6 " $\times$ 1 " 9 " $\times$ $\frac{1}{2}$ " "	136
2 " 6 " $\times$ 1 " 9 " $\times$ $\frac{1}{2}$ " "	15-
3 " 0 " $\times$ 2 " 0 " $\times$ $\frac{1}{2}$ " "	196
6 " 0 " $\times$ 1 " 6 " $\times$ 1 " "	293

We can make this Grating to suit any opening.

Prices upon application.

# Cantilever and Greenhouse Brackets

No. C 6408. CANTILEVER BRACKET



**LIGHT PATTERN.**—8 to 14 ins., 6 inch Batt.

	16	24	9						
Length, 8	10	12	14	16	18	20	22	24	inches.
Weight, 5½	6½	7½	8½	9	9½	11	11½	13	lbs. each.
Prices, 1/3	1/6	1/9	2/-	2/3	2/6	3/4	3/3	3/6	each.

**HEAVY PATTERN.** 8 to 14 ins., 4½ inch Batt.

	16	24	9						
Length, 8	10	12	14	16	18	20	22	24	inches.
Weight, 7	8½	10	12	14	16	18	20	22	lbs. each.
Prices, 1/6	2/-	2/3	2/9	3/4	3/3	4/6	5/3	6/-	each.

No. C 3754. CANTILEVER BRACKET



53 lbs. each, .. .. . Price, 12/9 each.  
44 " " size as above, with batt not so deep. .. 11/3 "

No. C 3757. CANTILEVER BRACKET



18½ lbs. each, .. .. . Price, 5/3 each.

No. C 4101. SPANDRIL OR BRACKET



11 ins. on side, .. Price, 6/- each.  
14 " " .. " 6/9 "  
18 " " .. " 7/6 "

No. C 4100. **SADDLE**  
For ridge of Greenhouse, prepared for  
tension rods.



11 ins. on side, .. Price, 10/6 each.  
17 " " .. " 12/- "


No. C 4098. **SPANDRIL**  
For ridge of Greenhouse.



18 ins. on side, .. Price, 10/6 each.  
20 " " .. " 12/- "


Any of the designs can be supplied  
Galvanized at **Double** the price of  
Black.

No. C 3756. CANTILEVER BRACKET




Sizes, .. .. 12 14 16 18 24 inches.  
Weight, .. .. 15½ 16 26 27 37 lbs. each  
Prices, .. .. 4/- 4/3 6/6 7/- 9/9 each.

No. C 3755. CANTILEVER BRACKET



49 lbs. each, .. .. . Price, 12/- each.

No. C 3758. CANTILEVER BRACKET



Sizes, .. .. 20½ 20½ inches.  
Weights, .. .. 50 61 lbs. each.  
Prices, .. .. 10/- 15/- each.

No. C 4102. **SPANDRIL**  
For ridge of Greenhouse.



11 ins. on side, .. Price, 7/6 each.


No. C 4103. **BRACKET**  
For foot of Rafter.



17 ins. on one side, .. Price, 9/- each.  
24 " " .. " 12/9 "


## Miscellaneous Castings

No. C 1157. **KITCHEN SINK**, London Pattern.




Sizes, ..	..	..	..	24	30	36 inches.
Painted, ..	..	..	..	Prices, 6/6	8/6	10/- each.
Galvanized, ..	..	..	..	12/-	15/-	18/- "
Enamelled, ..	..	..	..	20/-	26/-	33/- "

No. C 1199. **KITCHEN SINK**, Scotch Pattern.



Sizes, ..	..	..	..	18	21	24	27	30	36 inches.
Painted, ..	..	..	..	Prices, 9/-	9/6	10/9	14/-	15/6	22/- each.
Galvanized, ..	..	..	..	16/6	18/-	19/6	24/-	27/-	35/- "
Enamelled, ..	..	..	..	17/-	20/-	24/-	28/6	36/-	48/- "


No C 4848. **EYE INSPECTION COVERS**  
FOR DRAINS—TO LOCK.



Galvanized, .. 4 6 ins. diam.  
Complete with Key. 4/- 4/- each.


No. C 6398. **FISH FRYERS**, Cast Iron.

18 x 20 x 4 1/2 ins., ..	..	..	..	13/6 each.
20 x 24 x 4 1/2 " ..	..	..	..	16/9 "
18 x 20 x 6 " ..	..	..	..	15/- "
20 x 24 x 6 " ..	..	..	..	20/3 "
24 x 24 x 6 " ..	..	..	..	22/6 "
24 x 30 x 6 " ..	..	..	..	24/- "



No. C 4145. **DECK FLANGE**

Sizes, ..	..	3 1/2	4	4 1/2	5	6	7	8	9 ins.
Prices, ..	..	1/6	2/3	2/9	3/-	3/6	3/9	4/6	5/3 each.



No. C 4156. **THREE-LEGGED POT**


Sizes, ..	..	..	..	..	..	1/2	1	1 1/2	2	3	4 gallons.
Prices, ..	..	..	..	..	..	7d.	8d.	1/-	1/3	1/6	1/9 2/3 3/- each.

Larger sizes, 9d. per gallon.




No. C 4847. **AUTOMATIC DRAIN TRAP**

Excludes all stench, prevents splashing, and protects the wall from damp.



WHEN CLOSED (No Stench).



AS IN ACTION.




THE OLD-FASHIONED PLAN.

Its action is simple, automatic, and effective. Can be fixed to any ordinary drain pipe in a few minutes by using a little cement and driving in nails as supplied with trap. Price, 3/- each.

# Coal Plates and Pavement Gutters

## YOUNG & MARTEN'S PATENT AUTOMATIC - LOCKING COAL PLATE

DESIGN No. C 7101. Patent No. 13403.




SECTION.  
Showing Stud and Automatic Grip in position,  
ready to close and lock.

DESIGN No. C 7101. Patent No. 13403.



SECTION.  
Showing Automatic Grip near Locking Point.

DESIGN No. C 7101. Patent No. 13403.



SECTION.  
Showing Automatic Grip and Eccentric Over-  
balance of Weight, securely locked.

Size of Plate, 12 inches diameter; over rim, 14 inches diameter. Price, including Plate, Rim, Locking Gear, and Chain, 7/6 per set.

EXPLANATORY.—It will be seen from illustration showing the section that on flange at one side is a stout lug cast on, which fits into slot in rim. At other side is locking lever, hung from underside of plate, having an easy movement—one which, as plate is lowered to its position in rim by its own eccentric weight, automatically grips the under portion of outer rim, and thus the plate is secured to the latter by an immovable Lock and Bolt. To open or release plate, a chain is provided, accessible from INSIDE only; a slight pull detaches the grip, and the Coal Plate itself can then be raised from INSIDE.

NOTE.—This Patent Coal Plate is offered to the public as a means of relieving householders and owners of property from responsibilities arising from the removal of an ordinary lift-off coal plate, either by children or unauthorised persons. By the use of this Patent Plate accidents are avoided, also possible litigation necessarily following. The invention being within the legal regulation, according to Act of Parliament, whereby a heavy penalty can be enforced. "If any occupier or occupiers do or shall leave open, or not sufficiently or substantially cover or keep covered and SECURED, to the satisfaction of the local authorities, any coal plate."

ADVANTAGES :—SELF-LOCKING. BURGLAR PROOF. NON-SLIPPING. CANNOT BE OPENED FROM OUTSIDE. STRONGLY MADE.


## ORDINARY AND SELF-LOCKING COAL PLATES



No. C 1129. COAL PLATE

Solid or Ventilating.

12 ins. diam.,	..	..	Price, 1 9 each.
14 " "	..	..	" 2/9 "
16 " "	..	..	" 3/9 "
18 " "	..	..	" 6/- "




No. C 1130. COAL PLATE

Fitted with Glass Discs.

12 ins. diam.,	..	..	Price, 3/6 each
14 " "	..	..	" 5/3 "
16 " "	..	..	" 10/- "
18 " "	..	..	" 13/6 "


SELF-LOCKING ARRANGEMENT EXTRA :— { .. 12 14 16 18 inches diam.  
.. 4/6 5/- 6/6 7/6 each.



No. C 4144.

SQUARE COAL PLATE AND FRAME

Sizes.	Prices.
11 x 11 ins. in the clear opening,	.. 10/- each.
13 x 13 " " "	.. 12/- "
15 x 15 " " "	.. 14/- "
15 x 15 " " self-locking,	15/- "



No. C 4143. COAL PLATE RIMS


For Concrete.

For 12-in. Plate,	..	Price, 1/6 each
" 14-in. " "	..	" 2/- "
" 16-in. " "	..	" 3/9 "
" 18-in. " "	..	" 4/9 "

No. C 4032. PAVEMENT GUTTER



In 2, 3, 4, and 6 ft. lengths, .. Price, 2/- per ft.



No. C 1450.

STOP COCK BOX

Hinged Cover.

Sizes.	Prices.
4 x 4 x 3 ins. deep, ..	.. 1/9 each.
6 x 5 x 3 " " "	.. 2/6 "
11 x 7 x 4 1/2 " " "	.. 9/- "

No. C 6583.

END PIECE

For Round or Square Pipes.



Price, 3/- each.

No. C 6684.

ANGLE



Price, 5/- each.

No. C 6685.

TEE



Price, 7/- each.

# Columns and Shafts

## SHOP, BAY WINDOW, AND CLOTHES POSTS

No. C 2208.  
Plain Cap and Base Columns.  
Cast Iron




No. C 3273.  
Clothes  
Posts



8 ft., 9/- each.

Ornamental  
Bay Window Columns  
No. C 4133. No. C 4080.



5' 5 1/2" 6' 0" 6' 6" 6' 8" 7' 0"

3 ins. diameter.	
Cap, 6 x 6 ins., with	
4 bolt holes.	
Base, 8 x 8 ins., 1/2 in. metal.	
8 ft. 0 ins., .. Price,	18/- each.
8 " 0 " .. ..	19 " "
9 " 0 " .. ..	20 " "
9 " 6 " .. ..	21 6 " "
10 " 0 " .. ..	22 6 " "
4 ins. diameter.	
Cap, 7 x 7 ins., with	
4 bolt holes.	
Base, 8 x 8 ins., 1/2 in. metal.	
8 ft. 0 ins., .. Price,	24/- each.
8 " 0 " .. ..	25 " "
9 " 0 " .. ..	26 6 " "
9 " 6 " .. ..	28 " "
10 " 0 " .. ..	29 6 " "
10 " 6 " .. ..	31 " "
11 " 0 " .. ..	33 6 " "

Length.	Price.
5 ft. 6 ins., ..	11/- each.
5 " 9 " .. ..	11/6 " "
6 " 0 " .. ..	12/- " "
6 " 3 " .. ..	12/6 " "
6 " 6 " .. ..	13/- " "

No. C 3274.

Clothes Post Socket for Wood Post



Price, .. 3/- each.

No. C 6406

Clothes Post Socket for Iron Post




Price, .. 10/- each.

**Rolled Steel Joists, Stanchions, Steel Columns, and any Special Constructional Work. Prices quoted upon receipt of full particulars and specification.**

## SEWER VENTILATING SHAFTS

No. C 6731.









No. C 6732.



CAST-IRON BASE AND FOOT; WROUGHT-IRON TUBE.


PRICES:			
4 ins. Outside Diam. Tube by 20,	25,	30 ft. above ground.	
No. C 6731, .. .. .	150/- 180/-	200/- each.	
6 ins. Outside Diam. Tube by 20,	25,	30 ft. above ground.	
No. C 6731, .. .. .	230/- 250/-	300/- each.	
" C 6732, .. .. .	240/- 280/-	330/- "	

# Iron Hall and School Bench Standards

<p>No. C3305 Bench Standard.</p>  <p>Price, 3/4 each. " 36/- per doz.</p>	<p>No. C3306 Bench and Back Rail Standard.</p>  <p>Price, 4/- each. " 42/- per doz.</p>	<p>No. C3307 Bench Standard.</p>  <p>Price, 2/3 each. " 24/- per doz.</p>	<p>No. C3308 Bench and Back Rail Standard.</p>  <p>Price, 4/- each. " 42/- per doz.</p>	<p>No. C3309 Bench Standard.</p>  <p>Price, 2/3 each. " 24/- per doz.</p>	<p>No. C3310 Bench and Back Rail Standard.</p>  <p>Price, 4/3 each. " 45/- per doz.</p>	<p>No. C3311 Bench and Back Rail Standard.</p>  <p>Price, 2/3 each. " 24/- per doz.</p>	<p>No. C3312 Bench and Reversible Back Rail Standard.</p>  <p>Price, 4/- each. " 42/- per doz.</p>
--	--	--	--	---	--	--	---

## CAST-IRON SEAT AND TABLE STANDARDS

No. C6310.  
TABLE STANDARD




Prices, 4/- each; 42/- per doz.

No. C6318.  
SEAT STANDARD




Price, 3/3 each.  
" 36/- per doz.

No. C4050. SEAT STANDARD



Price, 2/3 each.  
" 24/- per doz.

No. C4057. TABLE STANDARD




Prices, 6/- each; 66/- per doz.

## Design No. C6322. STANDARDS FOR THEATRE SEATS

CASTINGS ONLY,  
GOLD BRONZED, OR OTHER  
FINISH,  
FOR LIFT-UP SEATS.

	Each.	Per Doz.
Price, without } Arm Rest, }	3/-	33/-
With Arm Rest,	3/3	36/-
End Standards,	3/-	33/-



ESTIMATES FOR  
CONTINUOUS STRETCHES OR  
SERIES OF SEATS,  
INCLUDING WOODWORK AND  
UPHOLSTERING,  
Forwarded upon receipt of  
particulars of actual  
requirements.



## Bakers' Oven Apparatus

**REFERENCE TO PARTS.**

- A**— Proving Door.
- B** Top and Slide Plate.
- C** - Outside Door.
- D** - Flat Register.
- E** Stock and Door.
- F** Chimney Bar.
- G** -Oven Plate.
- H** Covings.
- I** - Jamb Plate.
- J** Ashpit Door.
- K** Boiler and Frame.



**SET OF OVEN WORK WHEN FIXED.**

**EXTRAS.**

**UPSETS (P).**

Sizes, 12 18 24 30 ins.  
Prices, 2/- 3/- 4/- 5/- each.

**BOX REGISTER (Q).**

Fitted with Malleable-Iron Uprights.

Price, .. **27/-** each.

**LAMPS (R).**







Price, .. 3/- each.

PROVING DOORS (AA).

7 bushel size, 24/- per pair.

10    "    "    **25/6**    "

14    "    "    27/-    "



	Size Nos.,...	..	..	..	..	..	1	2	3
Oven Mouth, .. ..	.. ..	.. ..	.. ..	.. ..	.. ..	.. ..	16 x 12	18 x 12	20 x 13 inches.
Capacity of Oven, .. ..	.. ..	.. ..	.. ..	.. ..	.. ..	.. ..	7	10	14 bushels.
Prices (details as under), .. ..	.. ..	.. ..	.. ..	.. ..	.. ..	.. ..	£15 0 0	£17 0 0	£18 0 0 per set.

ANY OF THE FOLLOWING PARTS MAY BE HAD SEPARATELY AT PRICES INDICATED:—

	Size Nos.,	..	..	..	..	..	..	1	2	3
<b>E</b> —Stock and Door,	..	..	..	..	..	..	..	<b>£3 16 0</b>	<b>\$4 6 0</b>	<b>£4 12 0</b> each.
<b>H</b> —Pair of Covings,	..	..	..	..	..	..	..	<b>1 1 0</b>	<b>1 8 0</b>	<b>1 12 0</b> per pair.
<b>G</b> —Oven Plate,	..	..	..	..	..	..	..	<b>1 1 0</b>	<b>1 7 0</b>	<b>1 7 0</b> each.
<b>B</b> —Top and Slide Plate,	..	..	..	..	..	..	..	<b>0 15 6</b>	<b>0 17 0</b>	<b>0 19 0</b> „
<b>F</b> —Chimney Bar,	..	..	..	..	..	..	..	<b>0 5 6</b>	<b>0 6 6</b>	<b>0 7 6</b> „
<b>C</b> —Outside Door and Frame,	..	..	..	..	..	..	..	<b>1 4 0</b>	<b>1 7 0</b>	<b>1 8 0</b> „
<b>L</b> —Inside	..	..	..	..	..	..	..	<b>1 4 0</b>	<b>1 5 0</b>	<b>1 5 0</b> „
<b>J</b> —Ashpit	..	..	..	..	..	..	..	<b>1 4 0</b>	<b>1 4 0</b>	<b>1 4 0</b> „
<b>K</b> —Boiler and Frame,	..	..	..	..	..	..	..	<b>1 8 6</b>	<b>1 10 0</b>	<b>1 13 0</b> „
<b>D</b> —Flat Register,	..	..	..	..	..	..	..	<b>1 2 0</b>	<b>1 2 0</b>	<b>1 2 0</b> „
<b>I</b> —Jamb Plate,	..	..	..	..	..	..	..	<b>0 9 6</b>	<b>0 9 6</b>	<b>0 9 6</b> „
<b>M</b> —Stopping Plate,	..	..	..	..	..	..	..	<b>0 6 0</b>	<b>0 8 0</b>	<b>0 18 0</b> „
<b>N</b> —Furnace Bars,	..	..	..	..	..	..	..	<b>1 3 0</b>	<b>1 10 0</b>	<b>1 10 0</b> per set.
<b>O</b> —24-inch Bearers,	..	..	..	..	..	..	..	<b>1 3 0</b>	<b>1 10 0</b>	<b>1 10 0</b> per set.
<b>TOTAL PRICES.</b>								<b>£15 0 0</b>	<b>£17 0 0</b>	<b>£18 0 0</b> per set.

# Hot-Water Expansion Joint Pipes and Connections

No. C 8.  
Common Elbow.



No. C 1. Hot-water Pipe.



No. C 29.  
T Piece.



No. C 40.  
Syphon.




No. C 50.  
Outlet Syphon.




No. C 46.  
Elbow Syphon.




No. C 43.  
Three-way Syphon.




No. C 53.




No. C 20.  
Two-way Branch.




No. C 21.  
Three-way Branch.




No. C 22.  
H Piece.




No. C 24.  
S Pipe.




No. C 56.



No. C 61.  
Throttle Valve.




No. C 66.  
H Piece, with Two Throttle Valves.




No. C 92.  
Pipe Stands.



No. C 106.  
Expansion Box.



No. C 106 T.  
Expansion Box.



No. C 1.	Hot-water Pipe, plain, 9 feet lengths, ..	Diameter, ..	2	3	4
	" " " " 7 1/2 " " ..	..	—	3/3	4/- per yard.
	" " " " 6 " " ..	..	2/3	3/4	4/1 1/2 "
	" " " " 3 " " ..	..	2/6	3/6	4/3 "
" C 8.	Elbow, ordinary, inside, ..	..	1/-	3/8	4/6 "
	" " " " outside, ..	..	2/-	1/6	1/9 each.
" C 40.	Syphon, ..	..	1/6	3/-	4/6 "
" C 50.	Outlet Syphon, ..	..	2/-	3/-	4/6 "
" C 46.	Elbow ..	..	2/-	3/-	4/6 "
" C 43.	Three-way ..	..	2/6	4/-	5/6 "
" C 29.	Tee Piece, ..	..	1/9	2/3	2/9 "
" C 20.	Two-way Branch, ..	..	2/-	3/3	4/6 "
" C 21.	Three-way ..	..	3/-	5/-	7/- "
" C 22.	H Piece, ..	..	2/9	4/-	5/- "
" C 24.	S Pipe, 3 inch projection, ..	..	2/-	2/9	3/6 "
	" " 6 " " ..	..	2/3	3/6	4/- "
	" " 9 " " ..	..	2/6	3/9	4/3 "
	" " 12 " " ..	..	3/-	4/6	5/6 "
" C 53.	Joint, Complete, ..	..	2/-	2/6	3/- "
" C 56.	" Blank, ..	..	2/-	2/6	3/- "
" C 61.	Throttle Valve, ..	..	13/6	15/-	18/- "
" C 66.	H Piece, with Two Valves, ..	..	30/-	33/-	39/- "
" C 92.	Pipe Stand, for Two Pipes, ..	..	6d.	8d.	1/- "
" C 106.	Expansion Box, Square, for Two Pipes, ..	..	24/-	24/-	24/- "
" C 106 T.	" " Rectangular, for Three Pipes, ..	..	28/6	28/6	28/6 "
" C 106 F.	" " " " Four " ..	..	30/-	30/-	30/- "

# Hot-Water Pipes and Connections (Socket and Spigot)

No. C 851.  
Hot-water Pipe.



Sizes :	Diameter,	..	..	..	..	..	..	..	2	3	4	inches.
	Lengths,	..	..	..	..	..	..	..	6	9	9	feet.
Prices :	Full lengths,	..	..	..	..	..	..	..	2/-	3/-	3/6	per yard.
	3-ft. "	..	..	..	..	..	..	..	2/3	3/4	4/-	"



No. C 852. Hot-water Coil Pipe  
Same sizes and prices as No. C 851  
Hot-water Pipe.

No. C 853.  
Hot-water Trough Pipe



Sizes :	Diameter of Pipe,	..	..	3	4	4	3	4	4	inches.
	Length of Pipe,	..	..	6	6	6	9	9	9	feet.
	Trough,	..	..	3	4	6	3	4	6	inches wide.
Prices, ..	..	..	..	14/-	18/-	19/6	21/-	27/-	29/3	each.

No. C 7037. Loose Trough



Sizes, 2 x 27	3 x 30	4 x 30	inches.
Prices, 3/4	4/10	6/-	each.

Pipe Rests

No. C 914.



No. C 7038.



No. C 7040.



For ..	..	2	3	4 in. dia. pipes.
No. C 914, ..	..	3d.	4d.	6d. each.
" C 7038, ..	..	3d.	6d.	8d. "
" C 7040, ..	..	4d.	7d.	10d. "

No. C 7081.  
H.W. Double Socket  
Valves—Fitted.



2	3	4 inches.
13/6	16/6	18/9 each.

No. C 7082.  
H.W. Single Socket  
Valve—Fitted.



2	3	4 inches.
13/6	16/6	18/9 each.

No. C 907.  
H.W. Single Collar



Sizes, 2	3	4 ins. dia.
Short, 1/9	2/3	3/- each.
Long, 2/-	2/9	4/3 "

No. C 7044.  
H.W. Double Collar



Sizes, 2	3	4 ins. dia.
Prices, 2/4	3/6	4/9 each.

No. C 908.  
H.W. Blank Socket



Sizes, 2	3	4 ins. dia.
Prices, 1/4	1/7	2/9 each.

No. C 909.  
H.W. Blank Spigot




Sizes, 2	3	4 ins. dia.
Prices, 6d.	10d.	1/3 each.

No. C 7041.  
H.W. Diminishing Nipple



3 to 2, 4 to 2, 4 to 3 ins. dia.
3/- 3/3 3/6 each.



C 7008. C 7002. C 7001. C 857.

Common Hot-water Bends


Sizes, ..	2	3	4 inches.
No. C 7003, ..	4/4	7/7	11/4 each.
" C 7002, ..	3/7	6/1	9/3 "
" C 7001, ..	2/6	4/6	6/9 "
" C 857, ..	2/-	3/-	4/6 "

Short and Long Socket Bends



Sizes, ..	2	3	4 inches.
No. C 7005, ..	2/6	3/9	5/4 each.
" C 7006, ..	3/1	5/-	7/6 "

Common  
Diminishing  
H.W. Bends



Sizes, ..	4 to 3, 4 to 2, 3 to 2 ins.
No. C 7013, Outer—	
Prices, 6/9	6/9 4/6 each.
No. C 7013, Inner—	
Prices, 4/6	3/- 2/- "

No. C 804. H.W. Close Syphon

Sizes, ..	2	3	4 inches.
Prices, with Sockets, 3/-	4/3	6/6	each.
" " Spigots, 2/10	4/-	6/-	"

No. C 895. H.W. Open Syphon

Sizes, ..	2	3	4 inches.
Prices, with Sockets, 3/-	4/3	6/6	each.
" " Spigots, 2/10	4/-	6/-	"

No. C 7025. H.W. Outlet Syphon

Sizes, ..	2	3	4 inches.
Prices, with Sockets, 4/3	6/4	9/-	each.
" " Spigots, 3/9	6/-	8/3	"

H.W. Tee Pieces

No. C 873.



Sizes, ..	2	3	4 inches.
Prices, ..	3/4	5/-	7/6 each.

No. C 874.




Sizes, ..	2	3	4 inches.
Prices, ..	3/4	5/-	7/6 each.

No. C 875.



Sizes, ..	2	3	4 inches.
Prices, ..	3/4	5/-	7/6 each.

No. C 876.



Sizes, ..	2	3	4 inches.
Prices, ..	3/10	5/9	8/- each.

# Hot-Water Heating Apparatus




No. C 879. H.W. Close H Piece

Sizes, ..	2	3	4 inches.
Prices, ..	4/6	7/-	11/- each.




No. C 880. H.W. Open H Piece

Sizes, ..	2	3	4 inches.
Prices, ..	4/6	7/-	11/- each.




Nos. C 7035 and C 7036. H.W. Swannecks

Sizes, ..	3	4½	6 ins. projection.
Prices, 2 in. dia.,	2/4½	2/6	2/10½ each.
" 3 " "	3/4½	3/9	4/- "
" 4 " "	5/3	5/6	6/- "
Sizes, ..	9	12	14 ins. projection.
Prices, 2 in. dia.,	3/-	3/10½	4/7½ each.
" 3 " "	4/6	5/1½	5/7½ "
" 4 " "	6/4½	7/7½	8/3 "



No. C 7086. Flush Doors and Frame

Sizes.	PRICES.
24 × 15 ins.	15/9 each, fitted.
22 × 17 "	16/6 " "
24 × 17 "	17/3 " "
26 × 17 "	18/- " "
28 × 19 "	22/- " "



No. C 915. Sliding Doors and Frames

Sizes.	PRICES.
32 × 23 ins.	31/6 each, fitted.
31 × 31 "	40/6 " "
36 × 36 "	60/- " "




No. C 922. Quick Draught Furnace Bars

Sizes, 14 16 18 20 22 24 ins. long.
Prices, 10½d. 1/1½ 1/4½ 1/9 2/1½ 2/4½ each.



No. C 921. Slow Draught Furnace Bars

Sizes, 12 14 16 18 20 22 ins. long.
Prices, 7½d. 9d. 10½d. 1/3 1/4½ 1/7½ each.



No. C 924. Dumb Plates

Sizes, ..	9×30	9×24	9×18 ins.
„ ..	6×30	12×30	12×24 „
Price, 18/- per cwt.			


No. C 6990. H.W. Straight Flanged Bend

Sizes, ..	2	3	4 ins. dia.
Prices, ..	2/6	3/10½	5/4½ each.



No. C 6991. H.W. Curved Flanged Bend

Sizes, ..	2	3	4 ins. dia.
Prices, ..	2/6	3/10½	5/4½ each.



No. C 7045. H.W. Straight Flanged Socket

Sizes, ..	2	3	4 ins. dia.
Prices, ..	2/9	3/3	4/1½ each.



No. C 7046. H.W. Curved Flanged Socket

Sizes, ..	2	3	4 ins. dia.
Prices, ..	2/9	3/3	4/1½ each.



No. C 925.

Dampers and Frames

Nos. ..	00	0	1
Sizes, ..	5×4	5½×5	6×5½ ins.
Prices, ..	8½d.	9d.	10½d.



Nos. ..	2	3	4	5	6	7	8
Sizes, ..	7×6	7½×6½	9×7½	10½×9	12×10	14½×11½	16½×12½ ins.
Prices, ..	1/3	1/6	1/7½	2/3	2/6	3/9	5/-

Outside Sizes.

No. C 917. Soot Boxes

Nos. ..	1	2	3
Sizes, ..	4½×3½	6×4	7×5 ins.
Prices, ..	2/4½	2/10½	3/4½ each.
Nos. ..	4	5	6
Sizes, ..	9×4½	9×6	9×9 ins.
Prices, ..	3/9	4/6	6/- each.



No. C 7079. Expansion Box and Cover


Sizes, 18×9×6 inches. With two 4-in. Sockets.

Price, .. 18/- each.



No. C 920. Cistern and Cover

No. 1.	No. 2.	No. 3.
Sizes, 12×6½×10	13×7×10	15×8×11 ins.
Prices, 4/10½	5/9	7/6 each.
No. 4.	No. 5.	
Sizes, ..	18×8×12	21×9×12½ ins.
Prices, ..	9/9	13/6 each.




No. C 3793. Grating

For Continuous Stretches. Fine Cast, ½-in. thick.

*6×41	7×41	9×41 ins.
3/6	4/-	5/3 each.
12×41	14×41	16×40 ins.
6/6	7/6	8/9 each.
18×40	21×39	24×38 ins.
9/6	13/-	13/6 each.

\* The 6-in. wide Grating has plain border.




# Hot-Water Heating Apparatus

## THE "EVE TILL DAWN" BOILER

DESIGN REGISTERED, No. 446945.

RELIABLE, INEXPENSIVE, POWERFUL, ECONOMICAL. For Small Greenhouses, Motor Houses, Dog Kennels, Chicken Rearers, &c.



SIDE VIEW.


In most small boilers the HEATING SURFACE is too large, the FUEL SPACE is too small, the first cost is too heavy, or the RENEWAL OF FITTINGS too costly.

The "EVE TILL DAWN" BOILER has been designed to overcome these defects, it is simple in construction, NEAT in appearance, the parts are few and INEXPENSIVE, and the AIR REGISTERS control the DRAUGHT.

It will HEAT from 12 ft. to 40 ft. of 4-in. pipes, and can be banked to last from 12 to 24 hours. We have banked it up for 44 hours.

We have kept 40 ft. of 4-in. pipes hot day and night for a full week, 168 hours with 168 lbs. of fuel 1 lb. of fuel per hour.

It is RELIABLE and CHEAP, all parts are SUBSTANTIAL, and it has been subjected to EXHAUSTIVE TESTS before being placed on the market.



FRONT VIEW.

The No. C 5718 Boiler being 14 IN. HIGH, does not require a stoke hole.


It is NOT suitable for building in wall, it should be erected in out-house. If fixed outside it should be protected from rain or snow.

Boilers Nos. C 5718 and C 5719 TAPPED at BACK (unless otherwise ordered) for 1½-in. flow and return, or in any other position to order.

Boiler No. C 5732 TAPPED at BACK (unless otherwise ordered) for 1½-in. flow and return, or in any other position to order.

The RING SECTION will SWIVEL round, so that smoke pipe may be fixed in any position.

The magazine is not supplied with No. C 5732 Boiler, the fuel space in body of same being large enough.




SECTION.

No.	Outside Dimensions of Boiler.		Grate Diameter.	Heating Surface.	Heating Power. 4-inch Pipes.	PRICE of Boiler with Fittings illustrated above.
	Height.	Diam.				
C 5718	14 × 13 ins.		8 ins.	2 feet super.	40 feet.	£3 3 0
C 5719	18 × 16 "		10 "	3½ "	80 "	4 4 0
C 5732	24 × 19 "		11½ "	5 "	120 "	5 5 0

## THE "CRESCENT" BOILER

CAST IRON.



ELEVATION.

SECTION.

The "Crescent" Boiler has been designed to obtain the fullest amount of hot-water heating power from a small consumption of fuel. With the exception of the front, the whole internal surface, sides and top comprising the waterway, is exposed to the heat of the fire, thereby ensuring at the minimum of cost the maximum of results.


No.	Outside Dimensions.			Heating Power in 4-in. Pipes.	Size of Socket.	PRICE.
	Height.	Width.	Depth.			
5522C7.	27 × 12½ × 12 ins.			50 ft.	4 ins.	£4 4 0
5523C7.	26 × 14 × 13 "			80 "	4 "	4 8 6
5524C7.	26 × 14 × 15 "			100 "	4 "	5 0 6
5525C7.	26½ × 15 × 17 "			150 "	4 "	6 12 0
5526C7.	27 × 18½ × 21½ "			250 "	4 "	8 8 0

The above Prices of Boilers include 2 Glands and 4 Bolts.

This Boiler has Automatic Draught Regulator and Oscillating Bottom Grate.

## THE "CRESCENT" BOILER SETS

Details of arrangement of Boiler and Pipes with Prices of Complete Sets, requiring no skilled labour in erection.




PLAN OF GREENHOUSE.

A Complete Set comprises:—A "Crescent" Boiler, 4-in. Pipes with Expansion Joints, Bolts and India Rubber Rings, Spanner, Pipe Stands, Expansion Box, 9-ft. length of Smoke Pipe and Cap, Smoke Pipe Stay, Stoking Tools, Brass Cock.

Inside Size of Greenhouse.	Size of Boiler.		PRICES, per Set.		
	Height.	Width. Depth.	No. 1 Plan.	No. 2 Plan.	No. 3 Plan.
9 × 8 ft.	27 × 12½ × 12 ins.		£7 14 6	£9 9 0	—
10 × 6 "	27 × 12½ × 12 "		7 14 6	9 9 0	—
10 × 8 "	27 × 12½ × 12 "		7 14 6	9 9 0	—
12 × 8 "	27 × 12½ × 12 "		8 9 6	10 6 0	—
15 × 10 "	26 × 14 × 13 "		—	11 6 6	—
15 × 10 "	26 × 14 × 15 "		—	—	£15 3 9
18 × 10 "	26 × 14 × 15 "		—	—	15 19 3
24 × 10 "	26½ × 15 × 17 "		—	—	19 17 6
30 × 12 "	27 × 18½ × 21½ "		—	—	24 12 0
50 × 12 "	27 × 18½ × 21½ "		—	—	31 10 0

# Hot-Water Heating Apparatus

No. C 7110. **THE "ASHCROFT" BOILER**  
CAST IRON.



For Heating Motor Houses, Greenhouses, Stables, Coach Houses, Harness Rooms, Conservatories, &c., &c.

No.	Size of Boiler.	To Heat 4-in. Pipe.	Tapping.	Diameter of Smoke Pipe.	PRICE.
1	12 × 8 ins.	40 feet.	1 inch.	4 inch.	£2 2 0
2	12 × 12 "	60 "	1 "	4 "	2 12 6
3	12 × 16 "	80 "	1 "	4 "	3 3 0


For GREENHOUSES.

No. 1 Boiler, .. 11 ft. × 11 ft. × 8 ft.  
" 2 " .. 11 " × 16 " × 8 "  
" 3 " .. 11 " × 21 " × 8 "  
Or same area.

For GARAGE.

20 ft. × 20 ft. × 10 ft.  
25 " × 25 " × 10 "  
28 " × 28 " × 10 "  
Or same area.

No. C 7111. **THE "HERO" BOILER**  
WROUGHT IRON, WELDED.



SECTION OF No. 1 BOILER.

Suitable for Domestic and Bath Supply, or for Heating Radiators.

No.	Total Height.	Width across front.	Front to Back.	Heating Power.		PRICE.
				Square Feet Radiator.	Gallons per hour to 180°.	
1	Ins. 36 1/2	Ins. 13 1/2	Ins. 13 1/2	150	30	£9 9 0
2	40 1/2	13 1/2	16 1/2	250	50	14 5 0


No. 2 Boiler has a Cross Tube in Firebox.

Prices include Cleaning Plugs as shown.


Other sizes in preparation.

No. C 850. **PLAIN WROUGHT WELDED SADDLE BOILER**

PRICE LIST, EXCLUSIVE OF SOCKETS. WIDTH, 2 TO 3 INCH WATERWAY.



ELEVATION.



CROSS SECTION.

Size of Boiler.				Actual Heating Power in 4-in. Pipe.	Price of Boiler, Each.	Price of Boiler, 2 in. Plates, Each.	Price of Furnace Fittings, Per Set.
Length.	Inside Arch.		Outside Size.				
	W.	M.	W. M.	Feet.			
18	10 × 11		14 × 13	150	£2 17 0	£3 12 0	£3 12 0
21	12 × 12		16 × 14	210	3 15 0	4 10 0	4 1 0
24	12 × 12		16 × 14	240	4 1 0	4 19 0	4 9 3
24	14 × 14		18 × 16	280	4 13 0	5 14 0	4 13 9
27	14 × 14		19 × 16 1/2	315	5 2 0	6 9 0	4 17 6
30	14 × 14		19 × 16 1/2	350	5 17 0	7 4 0	5 3 6
33	14 × 14		19 × 16 1/2	385	6 3 0	7 10 0	5 10 3
36	14 × 14		19 × 16 1/2	420	6 9 0	8 2 0	5 14 9
42	14 × 14		20 × 17	490	7 13 0	9 0 0	5 14 9
42	16 × 16		22 × 19	560	9 12 0	11 8 0	5 18 6
42	18 × 18		24 × 21	630	10 16 0	12 18 0	6 7 6
48	18 × 18		24 × 21	720	12 6 0	14 14 0	6 16 6
48	21 × 21		27 × 24	840	13 13 0	16 4 0	7 13 0
54	24 × 18		30 × 21	910	15 0 0	18 0 0	8 18 6
60	24 × 18		30 × 21	1,000	17 14 0	21 6 0	9 15 0
60	24 × 21		30 × 24	1,120	19 1 0	22 16 0	9 15 0

Straight Sockets Fitted.—2 in., 9/-; 3 in., 10/6; 4 in., 12/- each.

Elbow " " 2 in., 12/-; 3 in., 15/-; 4 in., 18/- "

Furnace Fittings consist of One Furnace Front, Fire Bars, Bearers, Dead-plate, Damper, and Three Soot Doors.

No. C 7090. **Stoking Tools for Saddle Boilers**

Sizes,	..	..	..	42	54	60	66	78 inches long.
Prices,	..	..	..	12/-	14/3	16/6	18/-	21/- per set.

If order for above goods reaches 90/- value, Carriage is paid thereon to any Goods Station in England or Wales.



# "Ideal" Domestic Boilers

FOR HOT WATER SUPPLY.



No.	Ratings.*			Capacities.		Height of Boiler. Ins.	Diam. of Boiler. Ins.	Number and Diam. of Tappings in Inches.		PRICES.	
	B.T.U. per Hour.	Gallons of Water per hour heated from		Water. Gals.	Coke. Lbs.			Flows at Top.	Returns at Back.	Boiler only.	Base.
		40° to 80°	40° to 120°								
9 D	23,800	48	30	6	17	28½	19½	2-1½	1-1½	£4 12 6	£0 12 6
10 D	30,100	60	38	8	21	32½	19½	2-1½	1-1½	5 5 0	0 12 6
12 D	54,600	109	68	17.3	36	43	23	1-2	1-1½	10 0 0	0 15 0
16 D	84,000	168	105	25	75	47½	26½	2-2	1-2	14 0 0	1 5 0

The Nos. 9 D and 10 D Boilers are provided with four clean-out openings at top and two handholes at bottom. Nos. 12 D and 16 D are fitted with three handholes at top and two at bottom.


Stoking Tools (supplied unless otherwise ordered), .. .. . £0 5 6  
 Cleaning Chisel, .. .. . 0 5 6  
 Magazine (for Nos. 9 D and 10 D, increasing capacity, 17 lbs. of coke), .. .. . 1 1 0  
 Summer Grate (for Nos. 12 D and 16 D, decreasing capacity, one-half)—  
 No. 12 D, .. .. . 0 6 6  
 " 16 D, .. .. . 0 14 6

\* These ratings are given as examples; full ratings at various temperature intervals on application.


# "Ideal Premier" Water Boilers

No.	Ratings.		Capacities.		Height of Boiler. Ins.	Diam. of Boiler. Ins.	Number and Diam. of Tappings in Inches.		PRICE.
	H.T.U. per Hour.	Direct Radiation. Sq. Ft.	Water. Gals.	Coke. Lbs.			Flows.	Returns.	
101	26,400	180	3.3	23	39	17½	1—1½	1—1½	£4 12 0
121	36,000	250	7.7	34	42½	20½	3—1½	3—1½	6 7 6
151	52,800	365	9.9	51	49½	22½	3—2	3—2	8 5 0
181	76,800	535	14.2	82	52½	26½	3—2	3—2	10 10 0
182	103,200	715	18.8	82	58½	26½	3—2	3—2	13 0 0
H 211	127,200	885	21.8	126	60½	31½	2—3	3—3	15 15 0
H 212	158,400	1,100	24.2	126	65	31½	2—3	3—3	18 10 0
H 241	144,000	1,000	28.2	170	61	35½	2—3	3—3	17 15 0
H 242	182,400	1,265	31.5	170	65½	35½	2—3	3—3	21 0 0

Stoking Tools (supplied unless otherwise ordered), Nos. 101—182, .. .. . 5/6  
 " " " " " " " " H 211—H 242, .. .. . 7/-



# "Ideal" Sectional Water Boilers



No.	Number of Sections.	Ratings.			Capacities.		Length of Boiler. Ins.	Number and Diam. of Tappings in Inches.		PRICE.
		B.T.U. per Hour.	Direct Radiation. Sq. Ft.	Lineal Feet of 4-in. Pipe.	Water. Gals.	Coke. Lbs.		Flows at Top.	Returns at Bottom, either side.	
0-B-3	3	48,000	335	260	7	42	16½	1-2*	1-2*	\$8 0 0
0-B-4	4	64,800	450	350	9	60	23	1-2*	1-2*	9 12 6
0-B-5	5	81,600	565	440	10	78	29½	2-2*	2-2*	11 5 0
0-B-6	6	98,400	680	530	12	96	35½	2-2*	2-2*	12 17 6
0-B-7	7	115,200	795	620	14	114	41½	3-2*	3-2*	14 10 0
0-B-8	8	132,000	910	710	16	132	48	3-2*	3-2*	16 2 6
1-B-5	5	132,000	910	710	17	116	29½	1-3 or 2-2†	1-3 or 2-2†	17 0 0
1-B-6	6	158,400	1,095	855	20	139	35½	1-3 " 2-2†	1-3 " 2-2†	19 10 0
1-B-7	7	184,800	1,280	1,000	22	162	41½	1-3 " 2-2†	1-3 " 2-2†	22 0 0
1-B-8	8	211,200	1,465	1,145	25	185	48	2-3 " 3-2†	2-3 " 3-2†	24 10 0
1-B-9	9	237,600	1,650	1,290	28	208	54½	2-3 " 3-2†	2-3 " 3-2†	27 0 0
1-B-10	10	264,000	1,835	1,435	31	231	60½	2-3 " 3-2†	2-3 " 3-2†	29 10 0

Height to flow outlet, Nos. 0-B-3 to 0-B-8, 35½ inches; Nos. 1-B-5 to 1-B-10, 44 inches.  
 Width of Boiler, " " 20½ " " 26 "

These Boilers can be supplied with smokehood at back or front; unless otherwise ordered, back smokehood will be furnished.


Stoking Tools (supplied unless otherwise ordered), No. 0 B, 9/9; No. 1 B, 13/3

\* One 2½-inch flow and return can be supplied on face of back section, if specially ordered, in place of tappings on middle sections; distance from floor to centre of flow, 32½ inches; return, 11½ inches.


† If specially ordered, these Boilers can be furnished with a 4-inch return socket on face of back section; distance from floor to centre, 13½ inches. Boilers with front smokehood can also be supplied with 2½-in. flow outlet on face of back section; distance from floor to centre, 39½ inches. No extra charge will be made for these tappings if they are to replace openings in the middle sections.

# "Ideal" Radiators


FOR LOW PRESSURE HOT-WATER AND STEAM HEATING.



1-Column, Ornamental.



4-Column, Plain.



2-Column, Ornamental.


Pattern of Radiator.	1-Column. Plain or Ornamental.				2-Column. Plain or Ornamental.					3-Column. Plain or Ornamental.					4-Column. Plain only.			
Height, .. .. . ins.	38	32	26	23	45	38	32	26	20	46	38	32	26	18	38	32	26	18
Heating Surface, per section, .. sq. ft.	3	2½	2	1½	5	4	3½	2½	2	6	5	4½	3½	2½	8	6½	5	3
Price, per square foot, .. ..	1/3	1/5	1/7	1/11	1/2	1/3	1/5	1/7	1/11	1/2	1/2	1/4½	1/6½	1/10½	1/2	1/4½	1/6½	1/10½
*Length of Sections, .. .. ins.	3	3	3	3	3	3	3	3	3	3†	3†	3†	3†	3†	3	3	3	3
Width " " " " " "	4½	4½	4½	4½	7½	7½	7½	7½	7½	9	9	9	9	9	10½	10½	10½	10½
" " " " " " at feet, .. .. . "	5½	5½	5½	5½	8½	8½	8½	8½	8½	10½	10½	10½	10½	10½	11	11	11	11
Height to centre of Bottom Opening, " " " " " "	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½	4½
" " " " " " Top " " " "	35½	29½	24½	21½	43½	35½	29½	24½	18½	43½	35½	29½	24½	15½	35½	29½	24½	15½

\* In estimating length of Radiator, allow half an inch at each end for bushing.

† The end sections of the 3-column Radiators measure 2½ inches in length.

These Radiators can be supplied in all heights without feet. The plain 2 and 3 column pattern can also be supplied with detachable high legs, giving a space between floor and centre of bottom opening of 6, 8, 10 or 12 inches, as desired.

## "IDEAL" WINDOW RADIATORS



Height, .. .. .	inches, 13
Heating Surface, per section, .. .. .	sq. ft., 3
Price, per square foot, .. .. .	1/8
*Length of Sections, .. .. .	inches, 3
Width " " " " " "	12½
" " " " " " at feet, .. .. .	12½
Height to centre of Bottom Opening, .. .. .	3
" " " " " " Top " " " "	11½


\* In estimating length of Radiator, allow half an inch at each end for bushing.



# Boilers for Heating Apparatus

## No. C.7112. IMPROVED INDEPENDENT "SAVILE" BOILER

SPECIALLY DESIGNED FOR HEATING WATER FOR DOMESTIC SUPPLY IN HOTELS, CLUBS AND COUNTRY HOUSES.



No.	Size of Boiler overall.	Actual Heating Power, 4 inch Pipes.	Heating Power to 212° F. per hour.	Heating Power to 180° F. per hour.	Outside Diameter of Smoke Pipe.	PRICE, each, 3/4-inch Plate.	PRICE, each, 5/8 inch Plate.
1	H. 30 x 13 inches.	110 feet.	22 gallons.	44 gallons.	5 inches.	£12 0 0	£13 17 6
2	32 x 13 "	130 "	26 "	52 "	5 "	12 15 0	14 16 3
3	32 x 15 "	160 "	32 "	64 "	6 "	15 0 0	17 8 9
4	40 x 15 "	195 "	39 "	78 "	6 "	16 17 6	19 13 9
5	46 x 15 "	230 "	46 "	92 "	6 "	18 15 9	21 15 0
6	40 x 18 "	275 "	55 "	110 "	7 "	23 5 0	27 0 0
7	46 x 18 "	320 "	64 "	128 "	7 "	24 0 0	27 18 9
8	52 x 18 "	365 "	73 "	146 "	7 "	26 8 9	30 15 0
9	46 x 21 "	420 "	84 "	168 "	7 "	29 8 9	34 10 0
10	52 x 21 "	475 "	95 "	190 "	7 "	31 10 0	36 15 0
11	58 x 21 "	525 "	105 "	210 "	7 "	35 5 0	40 17 6
12	64 x 21 "	585 "	117 "	234 "	7 "	38 12 6	44 16 3
13	48 x 24 "	520 "	104 "	208 "	7 "	36 0 0	42 0 0
14	54 x 24 "	565 "	113 "	226 "	7 "	41 1 3	48 0 0
15	60 x 24 "	610 "	122 "	244 "	7 "	46 2 6	53 5 0
16	66 x 24 "	665 "	133 "	266 "	7 "	48 15 0	56 12 6
17	72 x 24 "	720 "	144 "	288 "	7 "	51 0 0	59 5 0
18	60 x 30 "	810 "	162 "	324 "	8 "	56 5 0	65 5 0
19	72 x 30 "	940 "	188 "	376 "	8 "	67 10 0	78 0 0

Above prices include two 2-inch Flanges and three Mudholes and Covers.

# Boilers for Heating Apparatus

HOT-WATER SERVICE BOILER.

No. C 7113.

## THE IMPROVED "GOLIATH"

WITH 4-INCH WATERWAY.




ELEVATION.

Outer Shell Riveted.  
Fire Box and Cross Tubes Welded.

Cast-iron Front  
the same as  
Improved Dome-top Boiler.

Water-way Bottom if required.

Cleaning Doors are fitted  
opposite  
each Cross Tube and round the Bottom.



SECTION.

This is a very powerful Boiler and capable of dealing with large quantities of water, as in the case of Swimming Baths.

No.	Sizes overall.		Diam. Smoke Flue.	Grate area.	Cross Tubes.		Heating Power, 4 inch pipe.	Gallons per hour, 80° to 180°.	Price, ½ Plates.	Price, ¾ Plates.	Waterway Bottom, extra.
	Ins.	Ins.	Ins.	Sq. Ft.	No.	Diam. Ins.	Feet.				
1	40	24	7	1.5	2	5	560	90	£33 15 0	£39 7 6	£3 7 6
2	46	24	7	1.5	2	5	630	100	37 2 6	43 17 6	3 7 6
3	52	24	7	1.5	3	5	775	125	40 2 6	46 17 6	3 7 6
4	48	30	8	2.75	2	5	840	135	46 10 0	54 15 0	4 10 0
5	54	30	8	2.75	3	5	1,025	165	53 5 0	61 5 6	4 10 0
6	60	30	8	2.75	4	5	1,125	180	59 5 0	64 0 0	4 10 0
7	48	36	8	4.25	2	6	1,150	186	57 15 0	67 10 0	6 0 0
8	54	36	8	4.25	4	6	1,475	235	69 15 0	79 10 0	6 0 0
9	60	36	8	4.25	4	6	1,575	250	72 15 0	84 0 0	6 0 0
10	66	36	8	4.25	4	6	1,675	265	77 5 6	87 15 0	6 0 0
11	54	42	9	6.25	4	6	1,800	290	84 0 0	94 10 0	7 10 0
12	60	42	9	6.25	4	6	1,950	315	87 15 0	97 5 6	7 10 0
13	66	42	9	6.25	4	6	2,100	340	92 5 0	102 0 0	7 10 0
14	72	42	9	6.25	4	6	2,250	365	96 0 0	106 15 0	7 10 0
15	60	48	10	8.5	4	6	2,300	370	—	108 15 0	9 0 0
16	66	48	10	8.5	4	6	2,475	400	—	112 10 0	9 0 0
17	72	48	10	8.5	4	6	2,650	430	—	116 15 0	9 0 0
18	66	54	10	11.5	4	7	3,000	480	—	129 15 0	10 10 0
19	72	54	10	11.5	4	7	3,200	510	—	134 5 0	10 10 0
20	78	54	10	11.5	6	7	3,750	600	—	142 10 0	10 10 0
21	84	54	10	11.5	6	7	3,950	630	—	147 0 0	10 10 0
22	72	60	12	15.0	4	8	3,700	615	—	150 0 0	12 0 0
23	78	60	12	15.0	6	8	4,500	720	—	172 10 0	12 0 0
24	84	60	12	15.0	6	8	5,000	800	—	180 0 0	12 0 0

Above prices include Smoke Nozzle with Damper, Furnace Work and two Connections. Extras may be fitted as follows :—


	Sizes,	1	1½	1½	2	2½	3	4	5	6 inches.
Wrought Flanges,	..	3/-	3/6	3/6	3/9	5/3	9/-	10/6	13/6	16/6
Cast Sockets,	..	..	..	..	..	9/-	10/6	13/6	16/6	21/-

Stoking Tools, 12/- to 20/- per set. nett extra.  
Especially suitable for warming Swimming Baths.


Note.—Waterway bottom adds 4 inches to total height.

# Improved Stable Fittings

No. C 6830. **SUITE**—INTERIOR ELEVATION



No. C 6830. **SUITE**—PLAN




Comprises :—Improved fittings for 2 loose boxes and 2 stalls, loose box divisions, doors, partition, with bosses to panel bars ; corner and straight mangers, with hay racks, stable gutters and pots, full and half posts, ventilators, exclusive of tiling and wood.

Suitable for 1½ inch wood, and with 4 inch posts, .. .. .	£90 15 0 per set.
" " 1½ " " " " 4 " " " " " " " " " " " "	93 0 0 "
" " 2 " " " " " 4 " " " " " " " " " " " "	94 1 0 "
If above fitted with 4½ inch diameter posts, .. .. .	extra, 2 8 0 "
" " " " 5 " " " " " " " " " " " " " " " "	4 10 0 "

# Improved Stable Fittings

Set No. C 4863. STALL DIVISION




SPECIFICATION :—Plain Ramp, Stall Post, and Sill fitted.

	Ramp, 24	30 ins. high.
9 ft. 6 in. Set, with 4 in. Post for 1½ in. Wood,	66 -	69/- per set.
9 " 6 " " " 4 " " " 1½ " " "	69/-	72/- "
9 " 6 " " " 4 " " " 2 " " "	72/-	75/- "

If Wrought Bar Ramp supplied with Bosses as shown below,

	4	4½	5 ins. diam.
Extra if with Post, .. .. .	—	6/-	12/- each.
" " " Head or Wall Post, .. .. .	33/-	37/6	39/- "


Set No. C 4871. STALL DIVISION



SPECIFICATION :—Wrought-bar Ramp, Stall Post, and Sill fitted.

	Ramp, 24	30 ins. high.
9 ft. 6 in. Set, with 4 in. Post for 1½ in. Wood,	102/-	111/- per set.
9 " 6 " " " 4 " " " 1½ " " "	111/-	117/- "
9 " 6 " " " 4 " " " 2 " " "	117/-	123/- "

.. .. . 10/6 per set extra.



Set No. C 4877. LOOSE BOX DIVISIONS

SPECIFICATION :— Plain Division, Stall Post, and Sill fitted.

	Divisions, 24	30 inches.
9 ft. 6 in. Set, with 4 in. Post for 1½ in. Wood,	114/-	120/- per set.
9 " 6 " " " 4 " " " 1½ " " "	123/-	126/- "
9 " 6 " " " 4 " " " 2 " " "	126/-	129/- "

With Bosses to Upright Bars, as shown, 10/6 per set extra.

	4	4½	5 ins. diam.
Extra if with Post, .. .. .	—	6/-	12/- each.
" " " Head or Wall Post, .. .. .	33/-	37/6	39/- "

# Improved Stable Fittings

## MANGERS, HAY RACKS, AND GRUEL POTS

No. C 1042. **STRAIGHT SET**, 6 ft. long, including Manger and Hay Rack, fitted to Top Plate, Rack either Right or Left Hand.




Black, .. .. .	Price, £2 12 6 per set.
Galvanized, .. .. .	3 15 0 "
Black, with Enamelled Manger (to order), .. .. .	3 15 0 "

No. C 4860. **STRAIGHT SET**, 6 ft. long, including Two Mangers fitted to Top Plate



Black, .. .. .	Price, £2 16 3 per set.
Galvanized, .. .. .	4 11 6 "
Black, with Enamelled Manger and Pot (to order), .. .. .	4 17 6 "

No. C 1046. **CORNER SET**, 3 ft. 6 ins. x 2 ft. 4 ins., including Manger and Hay Rack fitted to Top Plate, Rack either Right or Left Hand.




Black, .. .. .	Price, £2 12 6 per set.
Galvanized, .. .. .	3 15 0 "
Black, with Enamelled Manger (to order), .. .. .	3 15 0 "

No. C 1051. **STRAIGHT MANGER**




		30	33	36	42	48 ins. long.
Black, .. .. .	13/9	14/3	15/-	22/6	25/6	each.
Galvanized, .. .. .	21/9	23/3	25/6	36/-	39/9	"
Enamelled, .. .. .	36/-	38/3	41/3	57/-	63/9	"

No. C 1041. **STRAIGHT SET**, 6 ft. long, including Manger, Hay Rack and Gruel Pot fitted to Top Plate, Rack either Right or Left Hand.




Black, .. .. .	Price, £2 18 6 per set.
Galvanized, .. .. .	4 4 0 "
Black, with Enamelled Manger and Pot (to order), .. .. .	4 10 0 "

No. C 1040. **STRAIGHT SET**, 5 ft. 6 ins. and 6 ft. long, including large Manger fitted to Top Plate.




		Black.	Galvanized.	Black, with Enamelled Manger.
With Manger, 36 ins., .. .. .	45	71/6	78/-	per set.
" " 42 " .. .. .	45/9	75/-	85/6	"
" " 48 " .. .. .	47/3	78/-	88/6	"
" " 54 " .. .. .	48/9	81/9	93/9	"
" " 60 " .. .. .	51/-	88/6	101/3	"

No. C 1045. **CORNER SET**, 4 ft. 2 ins. x 4 ft. 2 ins., including Manger, Hay Rack and Gruel Pot fitted to Top Plate, Rack either Right or Left Hand.



Black, .. .. .	Price, £2 18 6 per set.
Galvanized, .. .. .	4 4 0 "
Black, with Enamelled Manger and Pot (to order), .. .. .	4 10 0 "

No. C 1050. **CORNER MANGER**




		30	33	36	42 ins. across front.
Black, .. .. .	13/9	14/3	15/-	18/-	each
Galvanized, .. .. .	21/9	23/3	25/6	28/6	"
Enamelled, .. .. .	36/-	38/3	41/3	47/3	"

Brass Plugs to Gruel Pots, .. .. . 3/9 each extra.

# Improved Stable Fittings


## HAY RACKS, STALL AND LOOSE BOX DIVISIONS

No. C 1052. **FLAT HAY RACK**—Cast Iron




			30	33	36 inches across.
Painted, .. .. .	..	..	8/3	10/-	12/- each.
Galvanized,.. .. .	..	..	13/9	16/9	20/- ..

No. C 1053. **CORNER HAY RACK**—Cast Iron




			30	33	36 inches across.
Painted, .. .. .	..	..	8/3	10/-	12/- each.
Galvanized,.. .. .	..	..	13/9	16/9	20/- ..

No. C 1064. **HORSE POT**



No. C 1066. **MARE POT**



Sizes, .. .. .	..	..	8	9	10	11	12 ins.
No. C 1064. Horse Pot, ..	..	..	4/6	5/6	6/9	8/9	10/6 each.
„ C 1066. Mare „ ..	..	..	4/6	5/6	6/9	8/9	10/6 ..


Gutter Inlets cast on, 1/9 each.

No. C 1071. **STABLE GUTTER, with Loose Cover**




Size, 4½ ins. wide.  
In 3, 4, and 6 ft. lengths, .. .. 2/9 per foot.

No. C 1069. **ANGLE PIECE**




Price, .. 4/9 each.

No. C 1070. **TEE PIECE**




Price, .. 6/6 each.



No. C 1065. **STABLE GRATE AND FRAME**

Sizes, .. .. .	..	..	6	7	8	9	10	12	14	16 ins.
Prices, .. .. .	..	..	2/-	2/6	3/6	4/9	6/-	8/6	13/6	15/- each.

## COWHOUSE FITTINGS—Cast Iron



No. C 4166. With Fodder Rack.

No. C 4167. With Fodder Rack and Dwarf Division.


Sizes of Stalls, 6 ft. 6 ins., 7 ft. wide, or 7 ft. 6 ins., 8 ft. wide, each to hold two Cows.

No. C 4166. Set, 6 ft. 6 ins., .. .. .	£12 0 0	No. C 4167. Set, 6 ft. 6 ins., .. .. .	£12 6 0
„ 7 „ 0 „ .. .. .	12 6 0	„ 7 „ 0 „ .. .. .	12 12 0
„ 7 „ 6 „ .. .. .	12 12 0	„ 7 „ 6 „ .. .. .	12 18 0
„ 8 „ 0 „ .. .. .	12 18 0	„ 8 „ 0 „ .. .. .	13 4 0

If Self-fixing Bases for Posts supplied, .. 12/- each extra.


# Harness-Room and Stable Fittings

**No. C4883. SET OF GENTLEMEN'S RIDING HARNESS BRACKETS**



Japanned Black, five pieces, .. 9/- per set.  
Colored or Galvanized, five pieces, .. 10/6 "

**No. C4884. SET OF LADIES' RIDING HARNESS BRACKETS**



Japanned Black, five pieces, .. 10/6 per set.  
Colored or Galvanized, five pieces, .. 12/- "

**No. C3214. RIDING BRIDLE BRACKET**



Sizes, .. 6x4 10x6 1/2 ins.  
Japanned, .. 2/6 4/6 each.  
Colored or Galvanized, .. 3/- 5/6 "

**No. C4920. STRONG SWING HARNESS BRACKET**



Sizes, .. 9 12 16 ins.  
Japanned, .. 4/6 5/6 6/6 each.  
Colored or Galvanized, .. 5/6 6/6 7/6 "

**No. C4885. SET OF SINGLE-DRIVING HARNESS BRACKETS**



Japanned Black, six pieces, .. 12/6 per set.  
Colored or Galvanized, six pieces, .. 15 "

**No. C3211. TELESCOPE HARNESS HOOK**



Japanned, .. 12/- each.  
Colored or Galvanized, .. 13/6 "  
Leather Covered Hooks,  
8/- extra per set.

**No. C3201. MANGER RING**




Inside Ring, .. 1 1/2 2 2 1/2 ins.  
Japanned, .. 3d. 4d. 7d. each.  
Colored or Galvanized, .. 3 1/2d. 6d. 9d. "

**No. C4302. BRIDLE HOOK AND RING**



Japanned, .. 7d. each.  
Colored or Galvanized, .. 9d. "

**No. C4886. SET OF DOUBLE-DRIVING HARNESS BRACKETS**



Japanned Black, twelve pieces, .. 27/- per set.  
Colored or Galvanized, twelve pieces, .. 30/- "

**No. C4911. HARNESS BRACKET**



Sizes, .. 4 5 6 7 8 ins.  
Japanned, .. 6d. 7d. 8d. 10d. 1/- each.  
Colored or Galvanized, 7d. 9d. 10d. 1/- 1 1/2 "

**No. C3212. SINGLE HARNESS SADDLE BRACKET**



Projection, 7 1/2 ins.  
Black, .. 2/- each.  
Colored or Galvanized, .. 4/6 "

**No. C3204. HARNESS BRACKET**



Sizes, .. 5 6 7 8 9 10 12 ins.  
Japanned, .. 1/6 1/6 2/6 2/6 2/6 2/6 2/6 each.  
Colored or Galvanized, 1/6 1/6 2/6 2/6 2/6 2/6 2/6 "

**HARNESS BRACKET**



**No. C3203.**

Sizes, .. 8 10 12 15 18 ins.  
Light Japanned, .. 1/6 2/6 2/6 3/6 4/6 each.  
Colored or Galvanized, 2/6 2/6 2/6 2/6 2/6 "

**No. C4919.**


Sizes, .. 8 10 12 15 18 ins.  
Strong Japanned, .. 2/6 2/6 2/6 4/6 4/6 each.  
Colored or Galvanized, 2/6 2/6 2/6 4/6 4/6 "

**No. C4912. HARNESS BRACKET**



5 1/2 ins.  
Japanned, .. 9d. each. | Colored or Galvanized, 1/- each

**No. C4890. LADY'S SADDLE BRACKET**



Projection, 21 ins.  
Black, .. 6/6 each.  
Colored or Galvanized, 7/6 "

**No. C3203. BRIDLE HOOK**



Sizes, .. 2 3 4 5 6 8 ins.  
Japanned, .. 4d. 5d. 7d. 10d. 1 1/2 2 each.  
Colored or Galvanized, 5d. 7d. 10d. 1 1/2 1 1/2 2 "   
Brass, .. 1/6 1/6 2/6 4/6 4/6 "


**No. C3213. GENTLEMAN'S SADDLE BRACKET**



Projection, 20 ins.  
Black, .. 6/- each.  
Colored or Galvanized, .. 6/6 "

# Cast-Iron Feeding Troughs

No. C 3718. CATTLE TROUGH



With Round Corners. Width, 18 ins.; depth, 14 ins.

Sizes, .. 24 30 36 42 48 54 60 72 84 96 ins. long.  
Painted, 21/9 27/9 31/6 41/3 48/- 55/6 63/- 76/- 91/6 103/6 each.

No. C 3710. PIG TROUGH



Round Ends, with Wrought Divisions, from 2 ft. to 6 ft. long, varying 6 ins.

Width, .. .. 8 10 12 ins.  
Painted, .. .. 2/6 3/6 4/3 per ft.


No. C 3712. SINGLE NORFOLK PIG TROUGH



With Wrought-iron Divisions. Size, 11 ins. wide.

Sizes, .. 2 ft. 2 ft. 6 ins. 3 ft. 3 ft. 6 ins. 4 ft. 5 ft. 6 ft.  
Painted, 12/9 14/6 16/3 20/- 21/9 24/6 30/- each.


No. C 3719. CATTLE TROUGH (Strong)



With Square Corners and Rings at ends.

Sizes, .. 24×18×12 30×18×12 36×18×14 48×18×14 ins.  
Painted, .. 28/6 32/3 38/3 46/6 each.  
Sizes, .. 60×18×14 72×18×14 84×18×14 96×18×14 ins.  
Painted, .. 57/- 73/6 92/3 115/6 each.


No. C 3711. PIG TROUGH



Square Ends, with Wrought Divisions, from 1 ft. to 10 ft. long, varying 6 ins.


Width, .. .. 8 10 12 ins.  
Painted, .. .. 2/6 3/6 4/3 per ft.

No. C 3713. DOUBLE NORFOLK PIG TROUGH



Width, .. 11 ins. 12 ins. 16 ins.  
Length, .. 2 ft. 6 ins. 3 ft. 3 ft. 6 ins. 3 ft. 3 ft. 6 ins. 4 ft.  
Painted, .. 12/9 15/- 16/6 18/- 24/- 26/3 27/9 each.


No. C 3714. CIRCULAR PIG TROUGH



With Revolving Divisions.

Sizes, .. 22 26 34 ins. diam.  
Divisions, 4 or 8 5 or 7 8 or 11  
Painted, 16/6 22/6 33/- each.

No. C 3715. CIRCULAR PIG TROUGH




Hopper.

Sizes, .. 24 30 ins. diam.  
Divisions, .. 7 8  
Painted, .. 19/6 31/6 each.


## CATTLE PANS

No. C 3716. Cake Pan



15½ ins. diam., 8 ins. deep.  
Painted, 8/3 each.

No. C 3717. Cake Pan




20 ins. diameter, 8 ins. deep.  
Painted, 9/9 each.



# Cast-Iron Letters, Numerals, Index Hands, and Name Plates

## No. C6741. ORNAMENTAL LETTERS



## No. C6742. PLAIN BLOCK LETTERS




												Block.		
Height, .. .. .	1	2	3	4	6	7	9	12	16	20	24	ins.		
Nos. C6741 and C6742 Letters and Numerals, ..	Prices, 6d.	7d.	8d.	10d.	1/3	1/8	2/3	2/9	4/9	8/3	9/9	each.		

Commas and Periods to suit, 4½d. each.

Prepared with Screwholes for fixing to Wood or Iron. Special fixings charged extra.

## No. C6743. INDEX HANDS



Right or Left, .. .. . 3/9 each.

To Screw on Signboards.

## No. C6744. NAME PLATES FOR STREETS



Size, 21 × 7 ins., with	Seven	3-in. Letters, .. ..	Prices,	1	2	6 or more.	each.
				3/6	3/3	3/-	
" 21 × 7 "	" Eight	3-in. " .. ..	"	4/9	4/6	3/9	"
" 21 × 7 "	" Nine	3-in. " .. ..	"	5/-	4/9	4/6	"
" 27 × 7 "	" Ten	3-in. " .. ..	"	5/9	5/6	5/-	"
" 27 × 7 "	" Eleven	3-in. " .. ..	"	6/-	5/9	5/6	"
" 27 × 7 "	" Twelve	3-in. " .. ..	"	6/3	6/-	5/9	"
" 32½ × 7 "	" Thirteen	3-in. " .. ..	"	7/-	6/6	6/3	"
" 32½ × 7 "	" Fourteen	3-in. " .. ..	"	7/6	6/9	6/6	"
" 32½ × 7 "	" Fifteen	3-in. " .. ..	"	7/9	7/3	7/-	"

No. Y 1920.


# Garden City Thumb Latch

Registered Design.

ESPECIALLY SUITABLE FOR ESTATE WORK.  
HIGHLY FINISHED IN ART BLACK.

No. Y 1921.



No. Y 1920/1.



ILLUSTRATIONS HALF SIZE.

Price, with either pattern Handle, . . . . 2/3 per set.

## No. Y 1924. COUNTY COUNCIL'S PATTERN ESTATE LOCKING LATCH (Patent).



Size of Latch without the fancy portion,  
3 1/2 x 2 1/2 ins.


Size of Handle, 11 x 2 ins.

The Handle is cranked as in illustration, and is supplied either right or left hand. The Latch can be locked from either side of the door, and the latch fall is fitted with roller, which causes the door to close smoothly and without jar.

Price, . . . . 5/3 per set.

No. Y 4763.

## BRASS LOCK SET.



A Set consists of one Upright Mortice Lock and two Lock Plates.

Size of Lock, 2 ins. to 3 ins. in width.

Size of Lock Plates, 7 ins. x 2 1/2 ins.


No. Y 4763, Polished Brass, . . . .	Price, 6/- per set.
" Y 4764, Antique Bronzed, . . . .	7/6 "
" Y 4765, Oxidized Silver, . . . .	10/- "

# Expanded Metal Lathings for Plaster Work

All Lathing is dipped once in Asphaltum Paint unless specially ordered otherwise.  
All Prices are for Lathings per yard super, Free on Rail at Works. For Exceptions, see Footnote.

## "B B" EXPANDED METAL LATHING

Supplied only in Standard Size Sheets, 9 ft. 0 ins. × 2 ft. 0 ins.




Actual Size of Meshes.

Reference Number and Gauge of Metal.	Approximate Weight per yard super.	Quantities of under 300 yards super.	Quantities of 300 and under 700 yards super.	Quantities of 700 and under 1400 yards super.	Quantities of 1400 yards super and upwards.
BB 26 G	Lbs. 3	Per yard super. 8½d.	Per yard super. 7½d.	Per yard super. 7d.	Per yard super. 6d.
BB 24 G	3½	9½d.	8½d.	8d.	7d.
BB 22 G	4½	1/-	11d.	10d.	9d.

## EXPANDED METAL DIAMOND MESH LATHING

NOTE. Sheets 8 ft. 0 ins. long × under 2 ft. 3 ins. wide, and Sheets 6 ft. 0 ins. or 7 ft. 0 ins. long × under 2 ft. 0 ins. wide, are cut and charged as Standard Sizes. Other sizes can be cut for special requirements, and quotations for such Sheets will be furnished on application.




Actual Size of Meshes in Nos. 1, 91, and 92.

Price List No.	Size of Mesh (Short way).	Gauge of Metal.	Size of Sheets kept in Stock.	Approx. Weight per yard super.	Quantities of under 300 yards super.	Quantities of 300 and under 700 yards super.	Quantities of 700 and under 1400 yards super.	Quantities of 1400 yards super and upwards.
1	1½	24	Long way of Mesh. 8' 0" × 2' 3"	Lbs. 3½	Per yard super. 10d.	Per yard super. 9½d.	Per yard super. 9d.	Per yard super. 8d.
91	1½	22	Short way of Mesh. 6' 0" × 2' 0"	4½	1/3½	1/1½	1/0½	11½d.
92	1½	20	6' 0" × 2' 0"	5	1/5½	1/3½	1/2½	1/1½
26	1½	24	Also 7' 6" × 2' 0"	3½	10½d.	10d.	9½d.	8½d.
93	1½	22	in Nos. 1 and 26 only.	4½	1/4½	1/2½	1/1½	1/0½
94	1½	20		5	1/6½	1/4½	1/3½	1/2½

## EXPANDED METAL CUP MESH LATHING

NOTE.—Supplied only in Standard Size Sheets.



Actual Size of Meshes in Nos. 82 and 84.

	In.	Gauge	Size of Sheets	Lbs.	Per yard super.	Per yard super.	Per yard super.	Per yard super.
81	1½	27	8' 0" × 1' 3"	3½	9d.	8d.	7½d.	6½d.
82	1½	27	7' 8" × 1' 8"	2½	8d.	7d.	6½d.	5½d.
83	1½	24	8' 0" × 1' 3"	4½	10d.	9½d.	9d.	8d.
84	1½	24	7' 8" × 1' 8"	3½	9½d.	8½d.	8d.	7d.

## EXPANDED METAL SQUARE MESH LATHING

NOTE.—Supplied only in Standard Size Sheets.



Actual Size of Meshes in Nos. 200 and 201.

	Sq. In.	Gauge	Size of Sheets	Lbs.	Per yard super.	Per yard super.	Per yard super.	Per yard super.
200	16	27	8' 0" × 2' 0"	2½	7½d.	6½d.	6d.	5d.
201	16	24	8' 0" × 2' 0"	3½	8½d.	7½d.	7d.	6d.
202	16	27	8' 0" × 2' 0"	2½	7½d.	6½d.	6d.	5½d.
203	16	24	8' 0" × 2' 0"	3½	9d.	8d.	7½d.	6½d.

Stock Sizes (Free Delivery within our Van Delivery radius).—Nos. 1, 26, 82, 200 and 26 Gauge "BB" Expanded Metal Lathing.

# New Type of Expanded Metal

(Patented)

FOR REINFORCING BRICKWORK, SLAB PARTITIONS,  
CONCRETE BLOCK CONSTRUCTIONS, &c., &c.

This material is made in three strengths, from 24 Gauge, 22 Gauge and 20 Gauge best mild hoop steel, and can be supplied in coils of practically any length, or flat in bundles cut to any desired length up to 16 feet. The standard coil is 270 feet long and  $2\frac{1}{2}$  inches wide, but shorter or longer coils can be supplied, and coiled material is to be preferred in most instances, not only for convenience in handling on the job, but also because coils occupy less space for storing and transhipment.

## "Exmet" Brickwork Reinforcement $2\frac{1}{2}$ inches wide,

in coils, or in bundles of flat strips of any length up to 16 feet, containing approximately 270 feet lineal :


24 Gauge, weighing approximately 14 lbs.,	.. ..	5s. 0d. per coil or bundle.
22 Gauge, weighing approximately 18 lbs.,	.. ..	6s. 6d. per coil or bundle.
20 Gauge, weighing approximately 23 lbs.,	.. ..	8s. 6d. per coil or bundle.

Other quantities, either coiled or bundled, are supplied at the proportionate price per foot run, and no extra charge is made for cutting to special length either in coils or in flat strips.

All material is dipped one coat of paint before leaving the Works.

## DELIVERY.

Orders of the net value of £2 and over are delivered carriage paid to nearest Railway Station in Great Britain or F.O.W. Dublin, Belfast or Cork, unless specially quoted otherwise. Carriage is not paid on orders of a less net value than £2.



Made in lengths of 270 feet.


Actual Size of Meshes of "Exmet" Brickwork Reinforcement.

No. 24 Gauge Stocked. Other Gauges direct from WORKS.

# Manure Bowls, Barn Shovels, &c.

## No. Y 1438. SOLID SOCKET GULLY BOWL

72-inch Handle.




Sizes, .. 6 7 8 9 10 11 12 ins. diam.

No. Y 1438. Strapped, 54 ins. up back and, front of Handle, .. 9/9 10/6 11/3 12/- 13/6 15/- 18/- each.

.. Y 1439. Plain Handle, without Straps, 8/3 8/9 9/- 9/6 9/9 10/- 10/6 ..

## No. Y 1444. WOOD BARN SHOVEL




Deep, for Seed, &c. 23-inch Plain Eye Handle.

Sizes, .. 12 13 14 15 16 ins.  
Prices, Beech, .. 7/6 8/3 8/9 9/9 10/6 each.


## No. Y 1445. ALL STEEL SOCKET GRAIN SCOOP

28-inch Riveted Eye Handle.



Nos. 1 2 3  
Sizes, .. 12 x 14 13 x 16 14 x 17 ins.  
Prices, 16 W.G., .. 3/9 4/6 5/3 each.  
If Galvanized, 1/- each extra.


## No. Y 1446. BEST CAST STEEL FLAT PRONG MALT FORK



30-inch Riveted Eye Handle.

Sizes, .. 5 6 7 8 9 prong.  
Prices, .. 11 x 14 11 1/2 x 14 12 x 14 12 x 15 12 1/2 x 15 ins.  
10/6 12/- 13/6 15/- each.

## No. Y 1451. PAINTERS' TRESTLES




		Light (for 1 Board at Top).	Stout (for 2 Boards at Top).
6 ft. high.	.. ..	£0 19 6	£1 2 6
8 .. ..	.. ..	1 4 0	1 7 9
9 .. ..	.. ..	1 7 0	1 11 6
10 .. ..	.. ..	1 11 6	1 14 6
12 .. ..	.. ..	1 16 0	2 0 6
14 .. ..	.. ..	2 5 0	2 14 0
16 .. ..	.. ..	2 17 0	3 0 0
18 .. ..	.. ..	3 9 0	3 15 0

These Trestles are made from selected wood, properly mortised, and with best quality wrought-iron joints.

## No. Y1440. STRONG SOCKET MANURE BOWL

Bound round Top.




Sizes, .. 9 9 1/2 10 10 1/2 11 12 ins.

No. Y 1440—  
Japanned Black, 4/6 4/10 5/3 5/6 6/- 6/6 ea.

No. Y 1441—  
Galvanized, .. 5/3 6/- 6/6 6/9 7/3 8/3 ..

## No. Y 1442. SOCKET MANURE BOWL

Plain Top.



Sizes, .. 9 9 1/2 10 10 1/2 11 12 ins.

No. Y 1442. Japanned Black, .. 3/6 3/9 4/3 4/6 4/10 5/3 ea.  
.. Y 1443. Galvanized, .. 4/6 4/9 5/- 5/3 6/- 6/9 ..

## SACK BARROW


No. Y 1250.

Very Strong. Suitable for Heavy Warehouse Work.

Height, 4 ft. 5 ins. Wheels, 7 1/2 ins.

Price, .. .. 22/6

Weight, 54 lbs.



No. Y 1252.

Solid Wrought Iron, Light and Very Strong.

Suitable for

FARMERS, SHOPKEEPERS, and

GENERAL PURPOSES.

Height, 3 ft. 6 ins.

Price, .. .. 16/6

## STEPS

No. Y 1448.

Specially made for Builders' use, with extra strong galvanized corrugated steel hinges, well bolted.

Size of wood, 1 inch, finished.

Sizes, .. 8 9 10 12 treads.  
Prices, .. 12/- 13/6 15/- 18/- per pair.

No. Y 1449.

For Household use.

Sizes, .. 6 7 8 treads.  
Prices, .. 5/3 6/6 7/6 per pair.

# Garden and Stable Forks, Spades and Shovels


No. Y 5001.  
Steel Border Fork.



No. Y 5002.  
Steel Digging Fork.




No. Y 5003.  
Steel Potato Fork.




No. Y 5005.  
Steel Manure Fork.






No. Y 5018.  
Contractor's  
Breaking-up Fork.



No. Y 5019.  
Stable Fork.




Prongs, .. .. 3	4	5	Prongs, .. .. 4	5
No. Y 5001, Steel Border Fork,	3/-	each.	No. Y 5005, Genuine "Batcheller" Steel Manure Fork,	5/6
" Y 5002, " Digging " 2 7/8	3/-	4 6 "	" Y 5018, Extra Strong Contractor's Fork, long	6/-
" Y 5003, " Flat Prong Fork,	5/-	"	strapped handle, double riveted eye,	"
No. Y 5010,	No. Y 5014,	No. Y 5008,	" Y 5019, Stable Fork, 2/-; Hay Fork, 2/6 each.	
Guarded Coal Shovel.	"London" Shovel.	"London" Spade.	No. Y 5011,	No. Y 5012,
			All Steel Shovel.	Locomotive Shovel.
				No. Y 5013,
				Grafting Tool.



Size Nos. .. .. 00	1	2	3	4	Size Nos. 2	3	4	5	6	7	8
No. Y 5008, Garden Spade,	2/-	2/3	2/7 1/2	3/-	3/3	3/9 each.	No. Y 5011,	2/-	2/3	3/-	4/6
" Y 5014, "London" Shovel. --	2/3	2/6	2/7 1/2	3/-	3/9	"	" Y 5013,	4/-	4/3	Best Quality.	"
No. Y 5010, London Pattern Guarded Coal Shovel—Sizes, 15 x 13 ins.							No. Y 5012, Locomotive Stoking Shovel—Sizes, 16 x 9 ins., 3/6 each;				
Price, 96/- per doz.							18 x 9 1/2 ins., 4/6 each.				
No. Y 5015, Ditto, without guard, 60/- per doz.											

# NEPONSET Paroid Roofing



A high grade prepared roofing for factories, car sheds, railroad buildings, and in fact, all kinds of buildings where a good permanent prepared roofing can be used.

**NEPONSET PAROID** has a long record of service on buildings owned by the United States Government, leading railroad systems and manufacturers throughout the United States and Canada, and more recently on British railway, factory, colliery and farm buildings.

**AN EXPERIENCE.**—Galvanized roofing after six years required preservative treatment, and after ten years, replacement. **NEPONSET PAROID** Roofing is sound after 25 years, and has been taken up and re-laid on another structure after 10 years.

**NEPONSET PAROID ROOFING** is made in one and two ply, and is put up in rolls **36 inches wide**, containing 216 square feet (sufficient to cover two squares), and 108 square feet (sufficient to cover one square).

## NEPONSET PAROID ROOFING, Grey, 36 inches wide—

One Ply, Light Quality.				Two Ply, Heavy Quality.			
			Price.				Price.
Rolls of 108 square feet,	..	..	10/6 each.	Rolls of 108 square feet,	..	..	15/- each.
" 216 " "	..	..	21/- "	" 216 " "	..	..	30/- "

Galvanized caps, nails, waterproof cement, and complete directions for laying are packed inside of each roll.

# NEPONSET Proslate Roofing

COLORS EITHER RED OR GREEN.

An attractive prepared roofing, designed especially for cottages and residential work of all kinds. It is made either in rich red or deep green, which makes it an especially attractive roofing for pitch roofs; is a thoroughly tested material, and there is no uncertainty about the durability of **NEPONSET PROSLATE**, for its base is our regular **NEPONSET Paroid Roofing** a time-tested material.

It is particularly suitable for piazza roofs, where shingles cannot be used.

**NEPONSET PROSLATE ROOFING** and **SIDING** is put up in rolls 18 inches wide, containing sufficient roofing to cover 100 square feet of surface. Rust retarding clips, nails and cement of the color of the material, with complete directions for laying, are packed inside of each roll.

## NEPONSET PROSLATE ROOFING, Dark Green or Dark Red, 18 inches wide Heavy Quality, Rolls of 108 square feet, 20/- each.

Can also be supplied showing a hexagonal design and also an ornamental edge, same quality and prices. Carriage paid on all above Roofing on orders of £5 and up. Samples and descriptive literature sent upon application.

# NEPONSET Wall Board


**NEPONSET** Wall Board is supplied in 32-inch widths and 8, 9 and 10 feet lengths. The Cream White finish is also made in lengths of 12 feet, especially for ceilings.

## NEPONSET Wall Board Battens.

### SIZES:

1½-inch wide, and  
8, 9 and 10 feet long.

Cream White finish also  
furnished in 12-foot lengths.



**NEPONSET** Wall Board is packed in bundles containing quantities as follows:

8 feet.

14 panels—about 298 sq. feet.

9 feet.

12 panels—about 288 sq. feet.

10 feet.

10 panels about 320 sq. feet.

12 feet (Cream finish only).

10 panels -about 320 sq. feet.

**NEPONSET** Wall Board is a tough fibre board about one-eighth of an inch in thickness. It requires no decoration. Primarily it is intended for walls and ceilings, to be used in place of laths and plaster, but it is also largely used over old cracked plaster and for partitions. It is therefore of interest not only to the person who is building, but to everybody who owns a house, garage, bungalow, or building of any description. It can make an unfinished or plaster cracked room attractive and liveable.

## ADVANTAGES OVER PLASTER

Its principal advantages over plaster are:

1. It preserves waterproof and washable surface.
2. It is less expensive.
3. Easily fixed with unskilled labor.
4. It requires no further decoration.

5. It can be applied quickly and without dirt and litter incidental to laths and plaster. No waiting for plaster to dry out.

6. It can be applied in winter as well as in summer.

## ADVANTAGES OVER OTHER WALL BOARDS

1. It is the only Wall Board with waterproofed surfaces that requires no further decoration.
2. It is made in a variety of finishes Plain Oak, Cream White, and Burnt Leather.
3. Battens of the same materials are furnished for covering joints.

## HOW IT IS APPLIED

**NEPONSET** is nailed directly to the wall studding and ceiling joists. It can be cut with a sharp knife or saw to fit any space. Anyone who is at all handy with tools can apply it quickly and easily. When applied over plaster a longer nail is used in order to fasten it to the studding joists.

**NEPONSET** Wall Board Battens are used to cover the joints between panels. Wooden battens may be used for this purpose, but of course are more expensive.

Either Finish—Plain Oak, Cream White, or Burnt Leather,

Battens to match, for covering joints, panelling, &c., 1½ ins. wide, 3/- per 100 lineal feet.

Carriage paid to most Stations on orders value £2 and upwards.

In Original Bundles.

1½d. per sq. ft.

Less Quantity.

1½d. per sq. ft.

SAMPLES AND DESCRIPTIVE LITERATURE SENT UPON APPLICATION.



# The "Yemart" Embossed Steel Ceilings

High Relief. Painted one coat, both sides.


**Fire-proof. Saves Lathing and Plastering.**

Easily cut with Tinmen's Shears, and usually fixed with 1-inch Galvanized Wire Nails on 1-inch Battens, spaced to come under each Joint.  
The Joints of the material have a slight lap.

**The cheapest form of Decorative Ceilings.**

## Protection:

In case of fire it checks the spread of flames.




No. PA 480.

Price, 1/6 per yard, 24 ins. wide - 3d. per square foot.

Stocked  
in Sheets  
8 x 2 feet.

Scale:  
One Twelfth.



No. PA 481.

Price, 1/9 per yard, 24 ins. wide - 3½d. per square foot.


## Sanitary.

Non-absorbent and free from microbes and bacteria.

Fixed with the least possible inconvenience, without mess.

Never cracks or falls down.

Has the best effects of relief papers.



No. PA 482.

Price, 2/- per yard, 24 ins. wide - 4d. per square foot.

Joints  
practically  
invisible.

A Ceiling  
16 x 14 feet  
of No. PA 480  
Pattern costs  
only 56/-



No. PA 483.

Price, 2/- per yard, 24 ins. wide - 4d. per square foot.

Not affected by vibration nor the settling of buildings.

Reduces the strain on joists to a minimum.

Is not susceptible to damage from leakage through roof or waterpipes.

## Coves and Cornice Mouldings

Stocked in 8 feet Lengths.



No. PA 490. 2½ x 2½ ins. Price, 3d. per lineal foot.



No. PA 491. 5 x 6 ins. Price, 4½d per lineal foot.



No. PA 492. 12 x 12 ins. Price, 9d. per lineal foot.

The above are representative of patterns stocked at our Stratford Warehouse.  
Samples and Descriptive Catalogue supplied upon application.

